LIANT

Retooling Enterprise Systems

RM/COBOL®

User's Guide

Version 7.0 for 32-Bit Windows®

This manual is a user's guide for Liant Software Corporation's RM/COBOL language. It is assumed that the reader is familiar with programming concepts and with the COBOL language in general.

The information contained herein applies to systems running under Microsoft Windows 95, Microsoft Windows 98, Microsoft Windows NT, and UNIX-based operating systems.

The information in this document is subject to change without prior notice. Liant Software Corporation assumes no responsibility for any errors that may appear in this document. Liant reserves the right to make improvements and/or changes in the products and programs described in this guide at any time without notice. Companies, names, and data used in examples herein are fictitious unless otherwise noted.

No part of this publication may be reproduced, stored in a retrieval system, or transmitted, in any form or by any means, electronic, mechanical, photocopied, recorded, or otherwise, without prior written permission of Liant Software Corporation.

The software described in this document is furnished to the user under a license for a specific number of uses and may be copied (with inclusion of the copyright notice) only in accordance with the terms of such license.

Copyright © 1985, 1986-1999 by Liant Software Corporation. All rights reserved.
Printed in the United States of America.

RM, RM/COBOL, RM/COBOL-85, Relativity, Enterprise CodeBench, RM/InfoExpress, RM/Panels, RM/plusDB, VanGui Interface Builder, CodeWatch, CodeBridge, Liant, and the Liant logo are trademarks or registered trademarks of Liant Software Corporation.
Borland is a registered trademark of Borland International, Inc.
Btrieve is a registered trademark of Pervasive Software.
Cobol-WOW, Cobol-RPC, and Cobol-CGI are trademarks of England Technical Services, Inc.
IBM and Macro Assembler/2 are trademarks or registered trademarks of International Business Machines Corporation.
Microsoft, CodeView, MS, MS-DOS, Visual Basic, Windows 95, Windows 98, and Windows NT are trademarks or registered trademarks of Microsoft Corporation in the USA and other countries.
Novell and NetWare are trademarks or registered trademarks of Novell, Incorporated.
TrueType is a registered trademark of Apple Computer, Incorporated.
UNIX is a registered trademark in the United States and other countries, licensed exclusively through X/Open Company Ltd.
All other products, brand, or trade names used in this publication are the trademarks or registered trademarks of their respective trademark holders, and are used only for explanation purposes.

Document Number 401190-0499

Preface

Welcome to RM/COBOL Version 7.0

RM/COBOL version 7.0 for 32-bit Windows is a significantly enhanced version of Liant's widely used RM/COBOL compilers, designed for new program development and execution of programs created with earlier versions of RM/COBOL. Although modeled on the American National Standard COBOL X3.23-1985, there are areas where RM/COBOL varies from the standard. A complete list of these variances is included in Appendix I, *Extension, Obsolete, and Subset Language Elements*.

The RM/COBOL operating procedures described in this manual are for use on Microsoft 32-bit Windows and UNIX-based systems that support remote file access using Novell NetWare (version 3.11 and above), Client for Microsoft Networks, or Btrieve software.

Note 1 Beginning with version 6.5, the -85 suffix is no longer a part of the RM/COBOL product name. The -85 suffix was used to reflect current technology and to avoid confusion with an earlier product named RM/COBOL, which referred to the 1974 ANSI standard version. Support for RM/COBOL (74) ceased on December 31, 1994.

Note 2 The term "Windows" in this document refers to Windows 95, Windows 98, or Windows NT, unless specifically stated otherwise.

What's New

The following section summarizes the major enhancements available in RM/COBOL version 7.0 for Windows. This summary describes the main features of each enhancement. The *RM/COBOL Language Reference Manual* and this user's guide contain the details regarding these features.

Note For information on the significant enhancements in previous releases of RM/COBOL, see the information beginning page xli.

CodeWatch Debugger Introduced

This release includes CodeWatch, a standalone, source-level debugger for Windows. CodeWatch supports the debugging of any applications without requiring that they be built under the RM/CodeBench or Enterprise CodeBench development environments. CodeWatch uses true 32-bit Windows “look-and-feel” and common Windows controls such as native toolbars, tree lists, progress indicators, and spin buttons. For more information, see the *CodeWatch* manual, which is included in the RM/COBOL development system documentation set for this release. CodeWatch uses the enhanced debugging information that is available when the new debugging options are specified during compilation of a source program. For additional information on the new debugging options, refer to the paragraph Enhanced Debugging Options on page xxx in the “Compiler New Features” section.

CodeBridge Cross-Language Call System Introduced

A new facility that simplifies communication between COBOL programs and non-COBOL subprograms (such as those written in C or C++) is included in RM/COBOL version 7.0 for Windows. Known as CodeBridge, this facility allows COBOL programmers to call external APIs or custom-developed subprograms without introducing “foreign” language and data dependencies into their programs. This means that developers can write C functions using C data types as usual, without worrying about the complex ArgEntry structure or COBOL data types. After the function declaration has been augmented for use as a template, the CodeBridge utility automatically produces a C source file for a bridge DLL. This file contains all the logic to interface to the calling COBOL program, the developer's C functions, and the needed calls to a CodeBridge data conversion library. The developer then compiles this source file, along with the C functions to be called, and links everything together with the conversion library to form the completed non-COBOL DLL. In a similar manner, pre-existing DLL libraries also can be called from RM/COBOL applications.

Refer to the *CodeBridge* manual, included in the RM/COBOL development system documentation set for this release.

Enhanced Windows Printing

The RM/COBOL version 7.0 for Windows runtime contains enhancements to provide more capabilities and flexibility when printing with Windows printer drivers. A new predefined printer device, “PRINTER?”, has been added to the runtime (see the “Windows Printers” section under DEFINE-DEVICE configuration record in Chapter 10, *Configuration*). When this device is opened, a standard Windows Print Setup dialog box is presented to the user to allow dynamic selection of the Windows printer.

A library of P$ subprograms (described in Appendix E, *Windows Printing)* and two Windows registry properties, Printer Dialog Always and Printer Dialog Never (see Chapter 3, *Installation and System Considerations for Microsoft Windows*), have been added to allow developer control of this dialog box. The RM/COBOL for Windows compiler can use this capability to select the printer for the listing file.

The RM/COBOL for Windows runtime also has been enhanced to support raw mode printing, which is useful when printing with escape sequences to a Windows NT network printer. Limited support for Windows printers via escape sequences is provided as well (see also Appendix E).

Additions to the RM/COBOL Subprogram Library

The RM/COBOL subprogram library now includes the following C$ subprograms (for more detail, see Appendix F, *Subprogram Library*):

- **C$ClearDevelopmentMode** disables expanded error information reporting (known as "development mode") in many of the C$ and P$ subprograms.
- **C$Delay** relinquishes the CPU for a specified length of time (in seconds).
- **C$GetEnv** and **C$SetEnv** retrieve and set, respectively, environment variables.
- **C$GetLastFileName** retrieves the last file-name and pathname used in a COBOL I/O statement.
- **C$GetLastFileOp** retrieves information about the last COBOL I/O file operation performed.
- **C$GetRMInfo** retrieves information about the RM/COBOL runtime system.
- **C$GetSyn** and **C$SetSyn** retrieve and set, respectively, the values of RM/COBOL synonyms used in the Windows registry file.
- **C$GetSysInfo** retrieves information about the operating system on which the RM/COBOL runtime system is running.
- **C$MemoryAllocate** allocates dynamic memory.
- **C$MemoryDeallocate** deallocates (frees) dynamically allocated memory.
- **C$PlaySound** plays Windows predefined sound events or sound files.

- **C$SetDevelopmentMode** enables expanded error information reporting (known as “development mode”) in many of the C$ and P$ subprograms.
- **C$Show** sets the show state of the main RM/COBOL window (rmguife.exe).
- **C$ShowArgs** displays a list of the arguments used to call a subprogram.

Ability to Use Btrieve Interface

An additional subprogram, **C$BTRV**, makes raw Btrieve functions, including transactions, accessible from RM/COBOL using Btrieve's normal interface.

Runtime New Features

In addition to the new C$ and P$ subprogram libraries supplied in the runtime, RM/COBOL version 7.0 for Windows runtime system includes the following features:

- **Support for Large Files.** The runtime system allows RM/COBOL 7.0 files to grow past limits imposed in previous versions. On Windows 95 and Windows 98, files up to 4 GB (gigabytes) are supported. Windows NT supports multiple terabyte files on the NT file system. Only files on FAT32 (Windows 95 and Windows 98 file system format) or NTFS (Windows NT file system) may be larger than 2 GB.
- **Enhanced Runtime Performance.** The RM/COBOL version 7.0 for Windows runtime typically runs computational tasks 20 to 30 percent faster than RM/COBOL version 6.51 for Windows.
- **Termination Log Added.** On Windows, a log of termination error messages, including traceback information, can be used to collect information about errors not trapped by declaratives. The ENABLE-LOGGING=TERMINATION and LOG-PATH keywords have been added to the RUN-OPTION configuration record to allow error messages to be collected for later analysis. See Chapter 10, *Configuration*, for more information.
- **New Runtime Behavior.** When the RM/COBOL runtime loads a non-COBOL subprogram library using CodeBridge, it builds a table of entry points into that library. If the sequence “RMDLL” is found at the beginning of any entry name, it is removed. See the CodeBridge documentation for more information.

- **Runtime Registration.** The RM/COBOL version 7.0 for Windows runtime now consists of two components: a client (**runcobol.exe)** and a server (**rmcblrun.dll).** The client component is completely compatible with previous versions of the **runcobol.exe** program—no command line changes are required. The server DLL, however, must be registered with Windows before RM/COBOL programs can be run. This is automatically performed during program installation and is an issue only if the runtime is moved to a different directory without being installed again. In this case, the client can be used to reregister the server. See the installation procedures in Chapter 3, *Installation and System Considerations for Microsoft Windows*.

- **More Flexible Filenames.** Two new options have been added to the RUN-FILES-ATTR configuration record. The ALLOW-EXTENDED-CHARS-IN-FILENAMES keyword allows extended characters in filenames. The ENABLE-OLD-DOS-FILENAME-HANDLING keyword supports the way in which filenames are handled in the old DOS-style 8.3 format. See Chapter 10 for further details.

- **LINAGE Configuration Options.** The PRINT-ATTR configuration record now includes two new configuration keywords to assist in configuring LINAGE for page printers, such as laser printers and ink jet printers. (See Chapter 10.)

  The new LINAGE-INITIAL-FORM-POSITION keyword defines where the form is positioned in the printer when the file is opened. The RM/COBOL implementation of LINAGE has required in the past that the form be aligned in the printer such that the first line printed is line one of the page body of the first logical page. This was a reasonable requirement when COBOL was mainly used with line printers and continuous forms. However, this requirement is not reasonable for page printers. For page printers, the value TOP-OF-FORM would be specified for this new keyword. The value PAGE-BODY-LINE-1 (the default value) would be specified for line printers when the operator adjusts the form to the first line of the logical page.

  The new LINAGE-PAGES-PER-PHYSICAL-PAGE keyword in the PRINT-ATTR configuration record defines the number of logical pages per physical page. LINAGE specifies logical pages, not physical pages. Therefore, the RM/COBOL implementation of LINAGE did not use form feed characters when printing LINAGE files since form feed characters advance the printer to the next physical page. For a page printer, a form feed character is sometimes necessary to advance to the next physical page. When LINAGE-PAGES-PER-PHYSICAL-PAGE is set to a nonzero value, then a physical page break (normally a form feed character) is printed each time that number of logical pages has been printed. When LINAGE-PAGES-PER-PHYSICAL-PAGE is set to 0 (the default value), then physical page breaks are not generated for LINAGE files.

Compiler New Features

While RM/COBOL 6.61 contained numerous changes to the compiler, version 7 features even more capabilities, including the following:

- **Increased Compiler Capacity**. RM/COBOL version 7.0 for Windows compiler allows 65535 identifiers to be defined in a single program (up from the 8192 allowed in version 6.61). The maximum space for user-defined words has been increased such that all 65535 identifiers could have unique names 30-characters in length (up from the 21-character average limit for version 6.61). The changes that support the increased capacity also eliminate the problem that limited consecutive comment lines to around 800. The limit is now about 18,000 consecutive comment lines.

- **New Reserved Words**. To support some of the features described in the following paragraphs, the reserved words list has been extended with the following new words: ADDRESS, CENTURY-DATE, CENTURY-DAY, COUNT-MAX, COUNT-MIN, DATE-AND-TIME, DAY-AND-TIME, NULL, NULLS, and RETURNING.

  Note that if you use these reserved words as user-defined words, you must either change the spelling of these user-defined words or use the DERESERVE keyword in the COMPILER-OPTIONS configuration record.

- **ACCEPT Statement Enhancements**. A number of changes have been made to the ACCEPT statement related to improving the way dates and times are handled. These changes provide additional ways of writing Y2K-compliant COBOL. New phrases include CENTURY-DATE, CENTURY-DAY, DATE-AND-TIME, DATE-COMPILED, and DAY-AND-TIME. See the *RM/COBOL Language Reference Manual* for more information.

- **Constant-Names**. Compile-time constants can now be defined with constant-names declared in level-number 78 data description entries. Once defined, a constant-name can be used in almost all contexts where a literal or integer is required in the language syntax. When properly used, constant-names greatly simplify the maintenance of COBOL programs.

- **POINTER Data Types**. The POINTER data type has been added. Pointer data items can be used to point to other data items in the program or in allocated memory. Support for pointer data items includes the NULL and NULLS figurative constants, which are pointer literals with a null pointer value. There are two new formats of the SET statement to manipulate pointer data items and an ADDRESS OF special register for obtaining the address of a data item as a pointer value. A non-null pointer refers to an area of memory that may be accessed in COBOL by setting the base address of a level-number 01 or 77 data item described in the Linkage Section of the program to the pointer value. Dynamic memory allocation is supported by two new subprograms in the provided library, C$MemoryAllocate and C$MemoryDeallocate.

- **Binary Allocation Configuration**. New configuration options allow binary numeric data items to be allocated in the minimum size necessary to support the specified PICTURE character-string consistent with the configured sizes. RM/COBOL has traditionally allocated binary numeric data items as two, four, eight, or sixteen bytes. The new configuration options allow binary numeric data items described with one or two digits to be allocated as a single byte. For more details on binary numeric data item allocation configuration, see the description of the BINARY-ALLOCATION and BINARY-ALLOCATION-SIGNED keywords in the COMPILER-OPTIONS configuration record section of Chapter 10, *Configuration*.

- **Binary Allocation Override**. In addition to binary allocation configuration, the compiler now supports a binary allocation override specification in the USAGE clause. The binary allocation override specification is an integer, enclosed in parentheses, that follows a binary usage type (COMPUTATIONAL-4, COMP-4, or BINARY). The integer specifies the number of bytes to allocate, overriding the number of bytes that would have been allocated based on the current compiler configuration. The override specification may specify fewer bytes than would be required to support the decimal precision indicated by the PICTURE character-string.

- **COUNT, COUNT-MAX, and COUNT-MIN Special Registers**. The compiler now supports three new special registers, COUNT OF *data-name-1*, COUNT-MIN OF *data-name-1*, and COUNT-MAX OF *data-name-1*, that may be used to obtain the number of occurrences of a table data item. For a fixed occurrence table, COUNT, COUNT-MAX, and COUNT-MIN all return the fixed number of occurrences specified in the OCCURS clause. For a variable occurrence table, COUNT-MIN returns the minimum number of occurrences specified in the OCCURS clause, COUNT returns the current number of occurrences (that is, the current value of the DEPENDING data item specified in the OCCURS clause), and COUNT-MAX returns the maximum number of occurrences specified in the OCCURS clause.

- **LENGTH Special Register**. The compiler now supports a new special register, LENGTH OF *identifier-1*, that may be used to obtain the length in bytes of any data item. The length for most data items is a constant, but the length is a variable for variable size groups and for identifiers that specify reference modification.

- **PROGRAM-ID Special Register**. The compiler now supports a new special register, PROGRAM-ID, which may be used to obtain the program-name of any program that specifies this special register.

- **In-Line Comments**. The compiler now supports the *> symbol as an in-line comment introducer. Any characters on the same source record following *> will be treated as commentary. The *> symbol must be preceded by a space separator.

- **OMITTED Arguments**. The compiler now supports the keyword OMITTED in the USING list of a CALL statement. Since arguments are positional, this feature allows an argument to be omitted from other than the end of the USING list.

- **GIVING/RETURNING Phrase**. The compiler now supports the GIVING/RETURNING phrase in the Procedure Division header and in a CALL statement. This phrase specifies an additional argument intended as the output argument of a called program.

- **Formal Arguments (USING/GIVING)**. The compiler now handles as a special case the specification of a formal argument as an actual argument in a CALL statement or in a reference modified identifier reference. In these two cases, the reference is evaluated according to the description of the actual argument corresponding to the formal argument rather than using the Linkage Section description of the formal argument. This means that a program that is just an intermediary between two programs need not have a Linkage Section data description entry that accurately describes the size of the actual argument being passed through it. For example, calling C$CARG with a formal argument, which is described as longer than the corresponding actual argument, will no longer result in a data reference error. Instead, C$CARG will return the correct length of the actual argument, and because of the reference modification change described here, this length may be successfully used to reference modify the formal argument.

  This also means that a program can call the supplied subprogram C$CARG with an argument that the calling program omitted without getting a data reference error. In this case, the call to C$CARG will succeed and return an argument descriptor that includes a type of OMITTED and a length of zero. In the case of reference modification, an omitted actual argument would cause a data reference error, but for an argument that is not omitted, the reference modification can use any offset and length combination that is consistent with the actual argument. Previous to this enhancement, reference modification that used variables implied a reference to the item as described in the Linkage Section for the formal argument data item and this

implied reference, if larger than the corresponding actual argument, would cause a data reference error before the reference modification was applied.

- **New Listing Date Formats**. The compilation listing date format can now be configured to include four-digit years with the new format values DDMMYYYY, MMDDYYYY, YYYYMMDD, and YYYYDDD. The default listing date format has been changed to MMDDYYYY so that a four-digit year will be used by default. This change also included making the DATE-COMPILED paragraph use the same date format as the compilation listing header.

- **Enhanced Debugging Options.** The Y Compile Command Option has two new variations that direct the compiler to embed additional debugging information in the program object file. The additional debugging information allows CodeWatch to display the program source during execution without requiring that the program be compiled under Enterprise CodeBench. See the description of the Y compiler command line option in Chapter 6, *Compiling*, and the DEBUG-TABLE-OUTPUT keyword in the COMPILER-OPTIONS configuration record, as detailed in Chapter 10, *Configuration*.

Enhanced File Recovery Performance

For large files, the Indexed File Recovery utility (**recover1**) runs at least twice as fast as previous versions. The -m option has been added to allow the user to specify a larger amount of memory to be used for the recovery. Allocating more memory generally results in much faster recovery. For more information, see Appendix G, *Utilities*.

New Rmpgmcom Utility Option

A new option in the **rmpgmcom** utility, STRIP, can remove COBOL symbol table and debug line table information produced by the Y compilation option from object files. See Appendix G, *Utilities*, for more information.

Who Should Use This Book

This book is intended for commercial application developers who are familiar with programming concepts and with the COBOL language in general, and by persons running COBOL programs developed with RM/COBOL.

Organization of Information

This user's guide is divided into the following parts:

Chapter 1—Introduction describes the general concepts of the RM/COBOL compiler and runtime system and how they are used, lists the add-on development tools that are available to support RM/COBOL programs, and explains file naming conventions.

Chapter 2—Installation and System Considerations for UNIX explains the installation procedures for RM/COBOL and presents information about the implementation on UNIX-based operating systems.

Chapter 3—Installation and System Considerations for Microsoft Windows explains the installation procedures for RM/COBOL and presents information about the implementation on Microsoft Windows 95, Windows 98, or Windows NT operating systems.

Chapter 4—System Considerations for Btrieve presents information about the implementation of RM/COBOL for systems using Btrieve. This chapter also describes the limitations of RM/COBOL indexed files and the Btrieve MicroKernel Database Engine (MKDE).

Chapter 5—System Verification describes the suite of verification programs provided with RM/COBOL.

Chapter 6—Compiling describes RM/COBOL files, details the RM/COBOL Compile Command, **rmcobol**, and its options, defines the types of errors that can be encountered during program compilation and the messages generated as a result, illustrates and defines each section of the program listing, and presents information on RM/COBOL error recovery.

Chapter 7—Running details the RM/COBOL Runtime Command, **runcobol**, and its options, and defines the types of errors that can be encountered during program execution. It also lists the messages generated as a result.

Chapter 8—RM/COBOL Features presents information about the implementation of RM/COBOL with respect to specific COBOL statements.

Chapter 9—Debugging presents general debug concepts and a detailed discussion of the Debug commands.

Chapter 10—Configuration details the methods available for modifying the RM/COBOL default configuration.

Chapter 11—Instrumentation details the data-gathering Instrumentation facility. It also describes a sample data analysis program—provided with Instrumentation—called **analysis**.

Appendix A—Runtime Messages lists and defines the messages that may be generated during program execution.

Appendix B—Limits and Ranges describes RM/COBOL limits and ranges.

Appendix C—Internal Data Formats describes and illustrates the internal representation of the data types.

Appendix D—Customizing RM/COBOL for UNIX provides information on how to customize the runtime system portion of RM/COBOL and how to add C subprograms to the runtime system.

Appendix E—Windows Printing describes the subprograms supplied with the RM/COBOL Windows runtime system that allow access to Windows printing features.

Appendix F—Subprogram Library describes a set of supplied subprograms that can be called by any RM/COBOL program.

Appendix G—Utilities describes the full range of file conversion, management, and manipulation facilities.

Appendix H—Object Versions lists the new object features that are incompatible with earlier releases of RM/COBOL.

Appendix I—Extension, Obsolete, and Subset Language Elements lists the RM/COBOL extensions to and variances from ANSI COBOL 1985. It also lists obsolete and subset language elements.

Appendix J—Code-Set Translation Tables lists each ASCII and EBCDIC hexadecimal value and its corresponding numeric, alphabetic or control character.

The *RM/COBOL User's Guide for 32-Bit Windows* also includes an index.

Related Publications

For additional information, refer to the following publications that are available from Liant Software Corporation:

CodeBridge—Calling Non-COBOL Subprograms

CodeWatch User's Guide

RM/COBOL for DOS User's Guide Supplement

RM/COBOL Open File Manager User's Guide

RM/COBOL Language Reference Manual

RM/COBOL Syntax Summary

RM/CodeBench User's Guide

Enterprise CodeBench Getting Started Manual

RM/InfoExpress for TCP/IP User's Guide

RM/InfoExpress for SPX/IPX User's Guide

RM/Panels Reference Manual

Relativity Client/Server Installation Guide

Relativity Data Manager Installation Guide

Relativity DBA Installation Guide

Relativity Designer Installation Guide

Theory of Relativity, A Primer

VanGui Interface Builder User's Guides (Delphi and Visual Basic)

Contact the appropriate vendor for other publications:

Btrieve products are available from Pervasive Software, Inc. (formerly Btrieve Technologies, Inc.).

NetWare products are available from Novell, Incorporated.

Microsoft products are available from Microsoft Corporation.

Conventions and Symbols

The following conventions and symbols are used or followed throughout this guide.

1. Words in all capital letters indicate COBOL reserved words, such as statements, phrases, and clauses; acronyms; configuration keywords; environment variables; and RM/COBOL Compiler and Runtime Command line options.

2. Bold lowercase letters represent names of files, directories, programs, commands, and utilities. RM/COBOL accepts uppercase and lowercase filenames. Within this document, the lowercase version is used. Remember, however, that under UNIX filenames are case sensitive (for example, **TEST4** and **test4** represent different files).

   Bold type style is also used for emphasis on some types of lists.

3. Text that is displayed in a monospaced font indicates user input or system output (according to context as it appears on the screen). This type style is also used for sample command lines, program code and file listing examples, and sample sessions.

4. Italic type identifies the titles of other books and the names of chapters in this guide, and it occasionally is used for emphasis.

   In syntax, italic type denotes a placeholder or variable for information you supply, as described in the following item.

5. The symbols found in the syntax charts are used as follows:

italicized words	indicate items for which you substitute a specific value
UPPERCASE WORDS	indicate items that you enter exactly as shown (although not necessarily in uppercase)
...	indicate indefinite repetition of the last item
|	separate alternatives
[ ]	surround optional items
{ }	surround a set of alternatives, one of which is required
{||}	surround a set of unique alternatives, one or more of which is required, but each alternative may be specified only once; when multiple alternatives are specified, they may be specified in any order.

6. All punctuation must appear exactly as shown.
7. The term “NetWare” refers to the Novell NetWare operating system.
8. The term “window” refers to a delineated area of the screen, normally smaller than the full screen. The term “Windows” refers to the Microsoft Windows 95, Windows 98, or Windows NT operating systems.
9. Examples for UNIX-based systems in this document assume the use of the Bourne Shell (**sh**) command interpreter.
10. Throughout this document, references to a printer refer to the device assigned to PRINTER, in accordance with operating system conventions.
11. RM/COBOL Compile and Runtime Command line options may be specified either with or without a leading hyphen. Examples in this guide do not show a leading hyphen. If any option on a command line is preceded by a hyphen, then a leading hyphen is required for all options. When assigning a value to an option, the equal sign is optional if leading hyphens are used.

    Command line options may be specified in either uppercase or lowercase characters. Examples in this guide are shown in uppercase.

    These capabilities are provided to support the command line syntax of previous versions of RM/COBOL.
12. Any text that applies only to a specific operating system is specified in a **Note** format.
13. Key combinations with a plus sign between key names indicate to press and hold down the first key while pressing the second key. For example, “Press Alt + Esc” means to press and hold down the Alt key and press the Escape key. Then release both keys. A comma between key names means to press and release the keys one after the other.

Registration

Please take a moment to fill out and mail (or fax) the registration card you received with RM/COBOL. You can also complete this process by registering your Liant product online at: **http://www.liant.com**.

Registering your product entitles you to the following benefits:

- **Customer support.** Free 30-day telephone support, including direct access to support personnel and 24-hour message service.
- **Special upgrades.** Free media updates and upgrades within 60 days of purchase.
- **Product information.** Notification of upgrades or revisions to RM/COBOL as soon as they are released.

You can also receive up-to-date information about Liant and all its products via our web site. Check back often for updated content.

Technical Support

Liant Software Corporation is dedicated to helping you achieve the highest possible performance from the RM/COBOL family of products. The technical support staff is committed to providing you prompt and professional service when you have problems or questions about your Liant products.

These technical support services are subject to Liant's prices, terms, and conditions in place at the time the service is requested.

While it is not possible to maintain and support specific releases of all software indefinitely, we offer priority support for the most current release of each product. For customers who elect not to upgrade to the most current release of the products, support is provided on a "limited" basis, as time and resources allow.

Support Guidelines

When you need assistance, you can expedite your call by having the following information available for the technical support representative:

1. Company name, support contract, partner, ADR, or distributor number.
2. Liant product serial number (found on the media label, registration card, or product banner message).

3. Product version number.
4. Operating system and version number.
5. Hardware, related equipment, and terminal type.
6. Exact message appearing on screen.
7. Concise explanation of the problem and process involved when the problem occurred.

Test Cases

You may be asked for an example (test case) that demonstrates the problem. Please remember the following guidelines when submitting a test case:

- The smaller the test case is, the faster we will be able to isolate the cause of the problem.
- Do not send full applications.
- Reduce the test case to one or two programs and as few data files as possible.
- If you have very large data files, write a small program to read in your current data files and to create new data files with as few records as necessary to reproduce the problem.
- Test the test case before sending it to us to ensure that you have included all the necessary components to recompile and run the test case. You may need to include an RM/COBOL configuration file.

When submitting your test case, please include the following items:

1. **README text file that explains the problems.** This file must include information regarding the hardware, operating system, versions of all relevant software (including the operating system and all Liant products). It must also include step-by-step instructions to reproduce the behavior.
2. **Program source files.** We require source for any program that is called during the course of the test case. Be sure to include any copy files necessary for recompilation.
3. **Data files required by the programs.** These files should be as small as possible to reproduce the problem described in the test case.

Version 6.6 Enhancements

Increased Compiler Capacity

The ability to compile large programs has been improved by allowing more identifiers and user-defined words during compilation. The maximum number of identifiers has been increased from 3612 to 8192, while the maximum space available for user-defined words has been doubled. The new user-defined word limit allows for 8192 user-defined words that average 21 characters in length, but these cannot all be identifiers since procedure-names must also fit in this space. The cross reference capability of the compiler was also improved to correctly cross reference source programs up to 65535 lines in length, up from the 16384 lines supported in prior versions.

Improved Compiler Performance for Large Programs

The compiler performance has been improved for large programs by adjustments to the memory allocation algorithms.

New Statistics in Compilation Listing File

The compiler now provides additional statistics regarding how much identifier table space and user-defined word space has been consumed to compile a source program. The messages are intended to help project managers avoid surprises in suddenly having a source program exceed one of the limits. The messages are now part of the Program Summary Statistics portion of the listing. Here is an example of the messages:

```
Source program used 4489 (55%) of 8192 available identifiers
(T28 limit).

Source program used 33004 (50%) of 65536 available user-defined
word space (T48 limit).
```

The new compiler also offers additional statistics regarding the use of memory during compilation. The message helps the user establish a proper setting of the workspace size compiler option (W command line option and WORKSPACE-SIZE keyword of the COMPILER-OPTIONS configuration record). The message is now part of the Program Summary Statistics portion of the listing. Here is an example of the message:

```
Maximum compilation memory used was 487K bytes (2 presses and 0
increases required).
```

Memory presses and increases occur in the compiler to help minimize the amount of memory used, but at the cost of compilation speed. Minimizing the number of presses by increasing the workspace size setting yields the fastest compilation. A small number of presses does not affect compiler speed.

Double-Byte Character Set (DBCS) Support

Double-byte character set (DBCS) characters are now supported by RM/COBOL when running on those versions of UNIX that allow their use. See the description of the DBCS-CHARACTERS keyword in the TERM-ATTR configuration record in Chapter 10, *Configuration*, for more information.

Enhanced Indexed File Recovery Program

The Indexed File Recovery utility (**recover1**) has been enhanced to improve its ability to repair damaged indexed files. **recover1** is now able to repair not only those problems that, in previous versions, required the use of the **recover2** utility, but other problems as well. The enhancements to **recover1** have made the **recovery** and **recover2** utilities obsolete. However, **recovery** and **recover2** are still included on the distribution media for backward compatibility. See Appendix G, *Utilities*, for more information on the **recover1** program.

Masked Input and Output

The RM/COBOL runtime now allows dynamic input based on a template supplied with a new keyword, MASK, that can be specified in the CONTROL phrase in ACCEPT and DISPLAY statements. This capability applies to UNIX only. (For more details, see Chapter 8, *RM/COBOL Features*.)

Support For Large Files

When running under operating systems that support files larger than 2 GB (gigabytes), the runtime system will now allow RM/COBOL files to grow past limits imposed in previous versions. This support is provided by the LARGE-FILE-LOCK-LIMIT keyword of the RUN-FILES-ATTR configuration record. In order to use this new limit on relative or sequential files, you must use the USE-LARGE-FILE-LOCK-LIMIT keyword in a RUN-REL-FILES or RUN-SEQ-FILES configuration record. For more information, see Chapter 10, *Configuration*. In order to use this new limit on indexed files, you must use an indexed file version of 3 (see Chapter 8, *RM/COBOL Features*, for more information).

Version 6.5 Enhancements

The following section summarizes the major enhancements available in version 6 of RM/COBOL. This summary describes the main features of each enhancement. The *RM/COBOL Language Reference Manual* and this user's guide contain the details regarding these features.

Full 32-bit Implementation

RM/COBOL is now implemented in 32-bit code across all platforms (UNIX and Windows). One common RM/COBOL runtime system or compiler will execute under either Windows 95 or Windows NT. On Windows 95, the COBOL programs can make calls to non-COBOL subprograms in either 16-bit or 32-bit dynamic link libraries (DLLs). On Windows NT, COBOL programs can make calls only to non-COBOL subprograms in 32-bit DLLs.

Windows Registry Support

RM/COBOL for Windows makes use of the Windows registry to maintain program properties. This feature eliminates the need for initialization (**.ini**) files. The tabs in the Properties dialog box for the COBOL object program can be used to set values in the registry. See "Windows Registry" in Chapter 3, *Installation and System Considerations for Microsoft Windows*, for more information. A new utility, RM/COBOL Configuration, **rmconfig.exe**, also can be used to set these properties by displaying the Properties dialog box. For more details, see Appendix G, *Utilities*.

Note The Initialization File to Windows Registry utility (**ini2reg.exe**), available only in Windows, converts an RM/COBOL for Windows initialization file and places its contents into the registry database.

Windows 95 and Windows NT Extensions

RM/COBOL for Windows now supports extensions to Windows 95 and Windows NT. These extensions include long filenames and 3D controls.

Automated System Installation and Removal

An automated system installation and removal capability is now a part of RM/COBOL for Windows. This feature greatly simplifies the loading and unloading of RM/COBOL. It is especially useful in ensuring that the appropriate programs are included or removed when upgrading to new versions. See the "System Installation" and "System Removal" sections in Chapter 3, *Installation and System Considerations for Microsoft Windows*, for more information.

Right Mouse Button Pop-Up Menu

RM/COBOL now provides the ability to define a pop-up menu that displays when the right mouse button is clicked in the client area of the RM/COBOL window. For more information about setting pop-up menu properties, see the section "Setting Pop-up Menu Properties" in Chapter 3, *Installation and System Considerations for Microsoft Windows*. A new subprogram, C$RBMenu, also can be used to define such a pop-up menu temporarily. For details, see Appendix F, *Subprogram Library*.

New Subprograms for Windows

Several other new subprograms, which are supported only under Windows, have been added in version 6.5. The C$GUICFG subprogram temporarily changes the RM/COBOL graphical user interface. C$TBarEn enables and disables the toolbar buttons in the RM/COBOL window. C$TBarSeq sets the bitmap sequence of a toolbar button in the RM/COBOL window. For further details on these subprograms, see Appendix F, *Subprogram Library*.

Window Style and the SYSTEM Non-COBOL Subprogram

The Windows version of RM/COBOL now allows you to set the style of the window created when you use the SYSTEM non-COBOL subprogram. For more information, see the SYSTEM Window Type property in Chapter 3, *Installation and System Considerations for Microsoft Windows*.

Btrieve Adapter Enhancements

RM/COBOL version 6.5 for Windows 95 and Windows NT includes an **rmbtrv32.dll**, which is the 32-bit version of the 16-bit **rbadaptr.dll** that was shipped with RM/COBOL version 6.08 for Windows 3.1.

rmbtrv32 supports the following RM/COBOL version 6 features: split keys, duplicate prime keys, multiple record locks, record lock timeouts, and START with FIRST or LAST. In addition, **rmbtrv32** supports the RUN-INDEX-FILES DATA-COMPRESSION and BLOCK-SIZE keywords, and **rmbtrv32** returns expanded error codes for better error reporting. **rmbtrv32** also supports selected features of Btrieve version 6 and 6.1 files as well as Btrieve version 6.15 MicroKernel Database Engines. **rmbtrv32** supports the Btrieve maximum of 119 key segments, repeating duplicates, and the no currency change (NCC) option on insert and update operations.

Using repeating duplicates along with the NCC option should eliminate the possible position-lost errors that could occur when a second user deleted records as the first user was reading through them.

rmbtrv32 allows pre-created Btrieve files that have multiple alternate collating sequences (ACS) defined, although all Btrieve keys that map to RM/COBOL keys must use ACS number zero since COBOL defines one ACS per file.

Setting RUN-INDEX-FILES DATA-COMPRESSION=NO allows the user to have **rmbtrv32** create uncompressed Btrieve files (earlier versions of **rbadaptr** always created compressed Btrieve files, which forced some users to pre-create uncompressed files).

See Chapter 4, *System Considerations for Btrieve*, for further information on these features.

Attached Configuration Files on Windows

The Attach Configuration utility (**rmattach.exe**) now allows configuration files to be physically attached to **rmcobol.exe**, **runcobol.exe**, and **recover1.exe** under Windows. When attached, a configuration file will be processed prior to any configuration file specified with a command line option. For more information, see "Attach Configuration Utility (rmattach)" in Appendix G, *Utilities*.

Built-In Configuration File under UNIX

The UNIX version of RM/COBOL allows a configuration file to be linked in to the runtime system and compiler system. For more information, see "Built-In and Attached Configuration Files" in Chapter 10, *Configuration*.

Year 2000 Subprogram

In order to facilitate updating RM/COBOL programs to handle the year 2000 issue, this release provides a non-COBOL subprogram called C$Century. This subprogram retrieves the first two digits of the current year. For example, for the year 1999, it will return 19; for the year 2000, it will return 20. See Appendix F, *Subprogram Library*, for more details.

C$RERR Eleven-Character Extended Status

The C$RERR subprogram has been enhanced to return an eleven-character extended status when called with an eleven-character data item. The four-character extended status returned in a four-character data item remains unchanged from previous versions of RM/COBOL. See Appendix F, *Subprogram Library*, for details.

Improved recover1 Utility Program

The Indexed File Recovery utility program (**recover1.exe**) has several new enhancements, including:

- Displaying information on why recovery may be required.
- The ability to display the last 98 or 30 error received when accessing the file, and the date and time it occurred.
- Several options to control the amount of user interaction required.
- An option that allows the Open For Modify Count to be reset without performing a full recovery.

For more information, see Appendix G, *Utilities*.

Enhanced rmmapinx Utility Program

The Map Indexed File utility program (**rmmapinx.exe**) includes two significant improvements. It now displays the Open for Modify Count for an indexed file, and it also displays the value of the last 98 or 30 error received while accessing the file. The date and time that the error occurred is also available. In addition, this utility reports split keys correctly.

Dynamically Configurable Prompt Character

ACCEPT statements may now specify a prompt character in the CONTROL phrase. The specified character is used for that ACCEPT statement only; the default prompt character is not changed. The PROMPT keyword is described under "CONTROL Phrase" in Chapter 8, *RM/COBOL Features*.

Building Custom Products Using the customiz Shell Script

The User Makefile that was included in previous versions of the RM/COBOL development system for UNIX has been replaced with a UNIX Bourne Shell script. When executed, this script interactively obtains information about the product to be built from the user and generates the appropriate **Makefile**. The user can then use this **Makefile** to build the product. See Appendix D, *Customizing RM/COBOL for UNIX*, for more information.

Indexed File Block Sizes After OPEN OUTPUT

The manner in which a block size is chosen for an indexed file when OPEN OUTPUT is performed may differ from previous releases. See the description of the BLOCK CONTAINS clause under "Indexed Files" in Chapter 8, *RM/COBOL Features*, for more information.

DELETE FILE under UNIX

The DELETE FILE operation will now fail if the user does not have write permission for both the file to be deleted and the directory containing the file.

Resolution of Program Names

The method used to resolve program names from environment variables has been changed to the method used in earlier versions. The environment is now searched for a matching name only after appending the extensions. This procedure is described in steps 5 through 7 in the section entitled "Subprogram Loading" in Chapter 8, *RM/COBOL Features*.

Compiler Support for External Access Methods

The RM/COBOL compiler now supports the use of external access methods (such as RM/InfoExpress) to locate source files and copy files. See "EXTERNAL-ACCESS-METHOD Record" in Chapter 10, *Configuration*.

Deficiencies

When this user's guide was printed, RM/COBOL for UNIX, Windows 95, Windows 98, and Windows NT had the following deficiencies:

- RM/COBOL implements file and record locks through region locks. The algorithm for computing the region to be locked is unique to RM/COBOL. This means that the OPEN and READ statements only lock out other RM/COBOL applications; an application not using the RM/COBOL file system can still access data in locked files. This may cause inconsistent data when a file is shared between RM/COBOL applications and other applications.

- RM/COBOL implements the WITH LOCK phrase of the OPEN statement and the WITH NO LOCK phrase of the READ statement by applying region locks to segments of the file. To ensure consistent results and to improve performance when the WITH LOCK phrase is specified, the runtime system must recognize when two distinct filenames identify the same file. This is accomplished under Windows by resolving the user filename into a fully specified filename, including the remote machine name when the file is remote. If a remote file resides on a UNIX server accessed by Network File System (NFS), however, two very different filenames can be associated with a single file through the **ln** command. This can cause a Windows client program to read invalid data from the file or to diagnose file integrity errors.

Deficiencies that are version-specific or are discovered after printing are described in the README files contained on the delivered media.

Chapter 1: Introduction

This introductory section of the *RM/COBOL User's Guide* provides an overview of the RM/COBOL product. It explains the general concepts of the RM/COBOL compiler and runtime system and how they are used, lists the additional add-on development tools that are available to support RM/COBOL programs, describes how to rename program executables, and explains file naming conventions.

RM/COBOL Software

RM/COBOL, delivered on appropriate media, contains a large number of individual files and programs. The actual number of files and programs depends on the specific version of the product you purchased and whether you purchased a development or a runtime-only system. The delivered media contains one or more README files, which list the actual files and programs delivered. Please check these README files after you have installed the product to make sure that you have received all of the appropriate files and programs.

RM/COBOL Compiler

The RM/COBOL compiler reads COBOL source code and produces object files that can be executed using the runtime system. These object files are portable, and they can be executed by an RM/COBOL runtime system on many computer configurations—even computer configurations that are different from the one used to compile the object files. For more information on compiling COBOL programs, see Chapter 6, *Compiling*.

RM/COBOL Runtime System

The RM/COBOL runtime system is used to execute compiled COBOL programs. Liant Software Corporation provides a different runtime system for each supported computer, and they help to insulate the COBOL programmer from the differences between computers. The runtime system also includes a debugger to assist in developing COBOL programs. For more information on running COBOL programs, see Chapter 7, *Running*.

CodeWatch

CodeWatch is a standalone, source-level debugger for Windows that is included with the RM/COBOL development system. CodeWatch supports easy debugging of any applications without requiring that they be built under the RM/CodeBench or Enterprise CodeBench development environments. CodeWatch uses true 32-bit Windows "look-and-feel" and common Windows controls such as native toolbars, tree lists, progress indicators, and spin buttons. For more information, see the *CodeWatch* manual.

CodeBridge

CodeBridge is a cross-language call system included with the RM/COBOL development system. This facility simplifies communication between COBOL programs and non-COBOL subprograms (such as those written in C or C++). CodeBridge allows COBOL programmers to call external APIs or custom-developed subprograms without introducing "foreign" language and data dependencies into their programs. For more information, see the *CodeBridge* manual.

Internal Libraries and Utility Programs

The RM/COBOL runtime system also includes several built-in library routines to perform functions not described in the COBOL standard. Among other things, these routines can be used to determine information about program arguments, control the display screen, and execute other (non-COBOL) programs. For more information, see Appendix F, *Subprogram Library*.

There are several utility programs delivered with RM/COBOL. These utility programs are used to manage and manipulate both data files and RM/COBOL object files. For more information on the utility programs, see Appendix G, *Utilities*.

Add-On Packages

Several add-on packages are available from Liant Software Corporation to support RM/COBOL programs. They include the following:

- **Relativity**. An integrated tool set that provides relational database functionality for COBOL data without any application modifications or data conversions. It also provides a full-featured, Microsoft Windows Open Database Connectivity (ODBC)-compliant relational database engine that allows SQL-based access to COBOL application data.

- **Enterprise CodeBench.** An integrated, graphical development environment for developing RM/COBOL applications on UNIX within the Windows 95 and Windows 98 environment.

- **RM/InfoExpress.** A file management system designed to optimize RM/COBOL data file access on various local area networks (LANs) and wide area networks (WANs). Implementations are available for TCP/IP (Transmission Control Protocol/Internet Protocol) and Novell SPX/IPX (Sequenced Packet Exchange/Internetwork Packet Exchange).

- **VanGui Interface Builder.** An interface builder that allows Visual Basic and Delphi to serve as graphical user interface (GUI) front-ends to COBOL programs running across a network.

- **RM/Panels.** A portable screen I/O package that allows WYSIWYG development of RM/COBOL displays.

- **Cobol-WOW (Windows Object Workshop).** A visual tool for developing full-featured Windows applications completely in RM/COBOL.

- **Cobol-RPC (Remote Procedure Call).** A tool for building distributed RM/COBOL applications for LANs, WANs, and the Internet.

- **Cobol-CGI (Common Gateway Interface).** A tool for integrating RM/COBOL applications with the Internet's World Wide Web.

Renaming Executables

Some users may wish to rename one of the RM/COBOL executable programs (**runcobol**, **rmcobol**, and **recover1**) after they have been installed. Some error and warning messages for these executables are stored in corresponding message files. The default names for these files are **RUN.MSG, RMC.MSG**, and **REC.MSG**, respectively.

In order to more gracefully handle renamed executables, the message filename may be the same as the root name of the executable or the default name. In a standard installation, for example, the RM/COBOL runtime will first search for a **runcobol.msg** file. If one can not be found, the runtime system will search for a **RUN.MSG** file. If the runtime executable were renamed to **myapp** (**myapp.exe** for DOS and Windows), the RM/COBOL runtime would first search for **myapp.msg**.

File Naming Conventions

On those operating systems that support case-sensitive filenames, RM/COBOL filenames can contain any combination of uppercase and lowercase letters, and numerals.

The Windows version of RM/COBOL, like Windows 95, Windows 98, and Windows NT, supports long filenames and filenames containing embedded spaces. RM/COBOL filenames can be enclosed in quotation marks (ASCII code 22 hex). RM/COBOL filenames containing embedding spaces must be enclosed in quotation marks to avoid having the embedded spaces interpreted as separators. For example:

```
"c:\My Source Directory\My COBOL Program.cbl"
```

Note Although Windows 95, Windows 98, and Windows NT store long filenames with case preserved, filenames are always compared and searched for in a case-insensitive manner (that is, filenames that differ only in whether letters are uppercase or lowercase refer to the same physical file).

RM/COBOL uses the extensions .**cbl**, .**cob**, and .**lst** to designate the source, object and listing files of a program. This allows all three files to reside in the same directory. These extension names may be changed with the EXTENSION-NAMES configuration record (see page 10-19).

Source files do not need to have an extension of .**cbl**; in fact, they do not need an extension at all. If the compiler cannot locate the source file with the name given and the name does not have an extension, it will try to locate the file again, using first .**cbl** as an extension to the filename and then .**CBL**.

The RM/COBOL compiler always creates object and listing files with extensions. It will either replace the current extension of the source file, or append an extension if the source filename does not have one. The case of the extension will match the case of the first character of the source file's extension, or the first character in the source file's name if there is no extension. If there is no extension and the first character of the source filename is not a letter, the extension will be lowercase.

The RM/COBOL runtime system does not require object files to have an extension of .**cob**. However, since the compiler generates objects with the .**cob** extension, the runtime system will try to locate object files by adding first .**cob** and then .**COB**, but only if the original filename does not already have an extension. Table 1-1 contains sample filenames.

Table 1-1 Sample Filenames

Source Filename	Resulting Object Filename
TESTFILE	TESTFILE.COB
Testfile	Testfile.COB
Test	Test.COB
Test.Cbl	Test.COB
Test.cbl	Test.cob
test.xyz	test.cob
test.XYZ	test.COB
tESTFILE	tESTFILE.cob
test	test.cob
test.CBL	test.COB
test.cbl	test.cob
2TESTFIL	2TESTFIL.cob

Chapter 2: Installation and System Considerations for UNIX

This chapter lists the hardware and software required to install the RM/COBOL product, describes how to install RM/COBOL, and provides information specific to using RM/COBOL for UNIX-based operating systems.

Your computer configuration is the assembled set of hardware and software that makes up your system. Before you can develop or run RM/COBOL programs, your configuration must meet or exceed the requirements set forth in this chapter.

System Requirements

The version of RM/COBOL that you have purchased is for a particular combination of hardware and operating system. Several items listed below vary depending on the actual version of the product that you have purchased.

Required Hardware

- **Memory.** The amount of memory depends on the specific version of the product that you have purchased.
- **Hard Disk.** A hard disk drive is required for installing this product. The amount of space required is version-specific. The average minimum disk space required to install this product is 3 megabytes (3 MB) for a development system and 2.5 megabytes (2.5 MB) for a runtime system.
- **Removable Media.** Some form of removable media (magnetic tape or floppy disk) is required for installing this product. The type of media is version-specific.
- **Terminal.** A terminal with a minimum capacity of 80 columns.

System Installation

RM/COBOL is delivered on media suitable for your configuration. In order to use this product, you must install the contents of the distribution media onto your hard disk.

The delivered media contains compressed files. This allows Liant to use fewer floppies in a distribution set and also speeds up the install time. The files are compressed or decompressed using the GNU **gzip** and **gunzip** programs. A copy of these programs or the source is available from the Free Software Foundation (FSF), which can be accessed from CompuServe (using GO UNIXFORUM) or from the Internet (using "anonymous ftp" from prep.ai.mit.edu). The **COPYING.gnu** file is a copy of the GNU General Public License. Use the **cat** or **pg** commands to review the file contents. If you do not have access to these online services, FSF provides a copy of the source for a minimum media handling charge. A copy of the source also may be obtained from Liant Software Corporation.

Note Installation information specific to your UNIX system can be found on the media label.

To install RM/COBOL on your operating system, take the following steps.

1. Log in as root.

2. The amount of disk space required to install this product is noted on the media envelope label. You can check the availability of space on your system by executing the following command:

   ```
   df
   ```

3. Create an empty directory in which you want to install RM/COBOL. For example:

   ```
   mkdir /usr/rmcobol
   cd /usr/rmcobol
   ```

4. Copy the contents of the distribution media (all volumes) onto your hard disk. Use the **cpio** command on the distribution media to copy the files.

5. Issue the following command to install RM/COBOL. This command performs the necessary steps to copy the proper files into the system command directory (/usr/bin) and to decompress the data files.

   ```
   ./rminstall
   ```

During the execution of this command, you are asked whether you want to install the termcap or terminfo version of **runcobol** and **recover1** (see "Terminal Interfaces" on page 2-9 for more information). Messages appear periodically indicating the status of the installation.

RM/COBOL is distributed with a default configuration that will satisfy your system requirements. Configuration options for your system are found in Chapter 10, *Configuration*.

Locating RM/COBOL Files

File Locations Within Operating System Pathnames

File locations are determined by the pathname of the file, according to operating system rules and conventions. A fully qualified pathname consists of an optional directory path with slash separators followed by a filename. The directory path may begin with a leading slash, tilde (~), or period (.) character. A directory path with a leading slash or tilde is fully specified and identifies a filename relative to the root file system. A directory path without a leading slash or tilde character specifies a filename relative to the current directory.

If a pathname is specified without a directory path, RM/COBOL searches the current directory.

Specifying a directory path with a leading slash or tilde indicates to RM/COBOL that an exact filename has been specified. If RM/COBOL cannot find the file in the specified location, it will not look elsewhere. If you do not specify a directory path, and RM/COBOL cannot find the file relative to the current directory, it will search for the file according to the directory search sequence. If a directory path is specified, but there is no leading slash or tilde, then the EXPANDED-PATH-SEARCH keyword of the RUN-FILES-ATTR configuration record determines whether the directory search sequence will be used. When the configuration keyword is set to its default value of NO, the directory search sequence will not be used (see page 10-27). If the value is set to YES, then the entire name, including the directory path, will be appended to each entry in the directory search sequence in an attempt to locate the file.

The tilde (~) character at the beginning of a pathname is used to refer to home directories. Standing alone, it expands to the user's home directory as reflected in the environment variable HOME. When followed by a name consisting of letter and digit characters, the name identifies the user whose home directory should be used.

Directory Search Sequences

You can direct RM/COBOL to search for a file not found in the current working directory by using a predefined directory search sequence. There are two directory search sequences: one for the compiler and one for the runtime system.

To direct the RM/COBOL compiler to use the directory search sequence, set the environment variable RMPATH as follows:

```
RMPATH=path[:path] ... ; export RMPATH
```

To direct the RM/COBOL runtime system to use the directory search sequence, set the environment variable RUNPATH as follows:

```
RUNPATH=path[:path] ... ; export RUNPATH
```

In both commands, *path* indicates the directory that is to be searched for the file and has the form:

```
[/]directory[/directory ] ...
```

directory is the name of an existing directory.

If multiple *path*s are specified, they must be separated with colons. If the file is not located in the current directory or the explicitly defined paths and if the file should be created, then the file is created in the current directory. Figure 2-1 and Figure 2-2 illustrate the compiler and runtime system search sequences, respectively.

Figure 2-1 Compiler Search Sequence



Figure 2-2 Runtime System Search Sequence



The compiler and runtime system may be executed from a directory other than the current directory if a complete pathname is specified in the command line, or if the PATH directory search feature is used. If a complete pathname is not specified, the list of directories specified by PATH are searched. Note that the current directory is not implicitly searched with the PATH environment variable.

The compiler, runtime system, and recovery utility (**recover1.exe**) require access to other files in order to operate. These include the message files (**RMC.MSG**, **RUN.MSG**, and **REC.MSG**), and, for the compiler, the compiler overlay file **rmcobol.ovy**. RM/COBOL looks for these files first in the directory containing the executable file, then in the current directory, and finally in the directories specified in the PATH environment variable.

The compiler overlay file is located by the compiler, not by the operating system. The compiler will attempt to locate the overlay file first in the directory containing the compiler executable, then in the current directory, and finally in the directories specified in the PATH environment variable. After locating the overlay file, the compiler will use the compiler directory search sequence to locate all other files.

Note On some versions of UNIX, it is impossible to determine the directory that contains the executable file when that directory is specified on the command line.

File Access Names

The file access name you specify in the COBOL source program specifies the physical file or device to which input or output is directed. For information on specifying the file access name in a COBOL source program, see the discussion of the ASSIGN clause (file control entry) in Chapter 3, *Environment Division*, and the discussion of the VALUE OF clause in Chapter 4, *Data Division*, of the *RM/COBOL Language Reference Manual*.

To establish synonymity between a file access name specified in your source program and another name specified when the program is run, use environment variables that are set before starting the runtime system.

If you specified a generic file access name for program input-output and wish to direct it to a specific device or file, enter:

```
file-access-name = file-access-name-2;
   export file-access-name-1
```

A generic file access name is one that does not specify a directory path. Since the format of physical pathnames, including conventions of directory names, varies from one operating system to another, for maximum portability it is recommended that source programs specify generic file access names, preferably with eight or fewer letters. This recommendation applies only when the file access name is hard coded into the program as a literal.

For example, if the file control entry specifies:

```
SELECT REPORT-FILE ASSIGN TO PRINT, "report"
```

and no environment variable named “report” exists, RM/COBOL will create a file named **report** in the current directory.

If, prior to running the program, you enter the command:

```
REPORT=/dev/lp; export report
```

all program output written to REPORT-FILE will be written to **/dev/lp**.

If—again prior to execution—you enter the command:

```
REPORT=/output/audit.lst; export report
```

RM/COBOL will create a file **audit.lst** in the directory **/output** without any need to modify or recompile the source program.

The RESOLVE-LEADING-NAME and RESOLVE-SUBSEQUENT-NAMES keywords of the RUN-FILES-ATTR configuration record can be used to force resolution of one or more of the directory names from the environment. For more information, see the discussion of the RUN-FILES-ATTR record beginning on page 10-26.

When environment variables are not used, the file access name in the COBOL program specifies the UNIX filename. The effect of a prior environment variable assignment may be canceled by the command:

Whether or not an environment variable is used to modify the file access name, if the resulting file access name does not include a directory path, RUNPATH will be used by the runtime system to obtain the fully qualified pathname (see “File Locations Within Operating System Pathnames” on page 2-3 for additional information).

When the resulting file access name is PRINTER or PRINTER1, then the default configuration writes the file to the print spooler. See “Printer Support” on page 8-46 for additional information on printing.

When the resulting file access name is TAPE, then the default configuration writes the file to the default tape device. See “Tape Support” on page 8-47 for additional information on tape devices.

The DEFINE-DEVICE configuration record may define other file access names that are to be treated as devices and also may change the default treatment of PRINTER and TAPE. See “DEFINE-DEVICE Record” on page 10-16 for additional information on configuring file access names that are to be treated as devices.

The resulting file access name should follow the operating system rules for valid filenames and pathnames.

Other System Considerations

Memory Available for a COBOL Run Unit

The memory available for a run unit in the operating system environment is implementation specific. If the total memory required by a run unit exceeds the amount of available memory, runtime system errors will occur. These errors indicate the inability to obtain enough memory to perform a desired operation. The RM/COBOL runtime system does not provide a virtual memory scheme, although your system may.

Segmentation and subprograms should be used to manage the dynamic memory requirements of very large run units.

Most modern UNIX systems (for example, BSD, System V, Sun OS) are supplied with built-in virtual memory systems. These systems make it appear as though there is always sufficient memory for the runtime system, regardless of how much physical RAM is installed in the machine.

A small number of UNIX machines (for example, the NCR Tower systems), are configured by the manufacturer to limit the maximum size of a program to less than 10 MB (2 MB in the case of the NCR Tower range). This limitation is enforced regardless of the availability of physical RAM. Execution of the runtime system on such machines can lead to unpredictable results. Moreover, it is not uncommon for the runtime system to terminate with the following message:

```
Segmentation fault:  core dumped
```

There is no known solution to this problem except to adjust the UNIX kernel parameter MAXUMEM to a more reasonable value (for example, 16 MB or 32 MB) and then rebuild the kernel. The method of performing this task varies among different UNIX systems. Contact your UNIX system supplier for details.

Number of Files

The operating system determines the number of files a run unit is allowed to open. The maximum number of files that may be opened is three fewer than the maximum number of open files per process. Most UNIX systems allow this maximum to be changed by reconfiguring the kernel.

Number of Region Locks

The runtime system uses the operating system region lock facility to provide file level locking and to control file sharing, as well as to support record locking. To implement file locking, the runtime system applies one region lock to each open file in addition to the locks applied for record locks. During an I/O statement, one or two additional region locks may be applied to a single file. If the program employs multiple record locking, these region locks remain until the program unlocks the records.

Network File Access

It is possible to receive a 98,27 error when accessing an indexed file through the network file system (NFS) when logged in as super-user (or root). If the file permissions do not include write permission for “other”, an open operation may inadvertently succeed for modes other than input mode. This is misleading because writes to the file will appear to succeed, even though the data is not updated. This problem is undetectable and will appear as a 98,27 error on the next access of the file after writing or deleting a record.

Terminal Input and Output

This section describes how terminal input and output is handled by the RM/COBOL runtime system.

Terminal Interfaces

The runtime system uses one of two terminal interface mechanisms, termcap or terminfo, to control cursor positioning, video display attributes, and function key mapping.

The termcap version of the runtime system uses the older termcap database, which has a description of the user's terminal in it. See "Termcap Database" on page 2-10 for more information.

The terminfo version of the runtime system uses the terminal description in the terminfo database for both input and output control of the terminal. See "Terminfo Database" on page 2-11 for more information.

Both the termcap and terminfo versions of the runtime system are present on the distribution media. During the installation process you will be asked which version to install. To switch to the other interface, you must either install RM/COBOL again or use the **customiz** utility as described in Appendix D, *Customizing RM/COBOL for UNIX*.

Cursor Types

The termcap and terminfo versions of the runtime system support two types of cursors, each of which indicates a different edit mode during ACCEPT operations.

1. The attribute cursor_normal (or cursor-on) indicates that standard overtype mode is active.

2. The attribute cursor_visible (or cursor-blink) indicates that insert mode is active.

Terminal Attributes

Some terminals under UNIX require that special characters appear on the screen just before the start of an attribute and right after the end of it. Characters in between these special characters take on the specified attribute. To accommodate these terminals, the **oV** capability for termcap specifies the number of screen positions to be used by the **nM**, **nB**, **nR**, **nS**, **aL**, **aB**, **aR**, **aS** and **rS** capabilities. The **xmc** capability is used for the terminfo runtime system. RM/COBOL places the attribute characters at the position specified by the ACCEPT or DISPLAY operation, and moves the actual start of the field by the number of positions specified by **oV** or **xmc**. If you want, you can use the keyword MOVE-ATTR with the TERM-UNIT configuration record to specify moving the

attributes back the number of positions specified by **oV** or **xmc**. However, if MOVE-ATTR causes the attribute character to move back to the next line, and such a move is prohibited by the **lA** (do not cross lines) capability described in the next paragraph, the attribute will appear on the same line that is being displayed or accepted.

The **lA** is a Boolean termcap capability and is used with terminals that require screen positions to implement attributes, as described in the preceding paragraph. The standard RM/COBOL model is to keep an attribute in effect—without regard to the number of screen lines to which it applies—until it encounters the special character that signals the end of the attribute. Some terminals, however, recognize the end of a line as the end of the attribute, without regard to the presence or absence of the ending special character. In this case, the presence of **lA** will tell RM/COBOL that a new attribute character must be placed at the start of every new line in a multiline ACCEPT or DISPLAY operation.

The **sA** is a Boolean termcap capability that is also used with terminals that require screen positions to implement attributes. The RM/COBOL model is to assume that attributes will not wrap from the bottom to the top of the screen. If your terminal behaves differently, and if you have specified the MOVE-ATTR configuration keyword, use **sA**. This allows fields placed at the home position (line 1, position 1) to have their attributes placed at the last line of the screen.

Termcap Database

The runtime system locates the termcap database by first looking for the environment variable TERMCAP. If the TERMCAP environment variable is found and contains a valid pathname, that value is used as the pathname to the database. If the environment variable is found but it contains a valid termcap entry, that entry will be used as the terminal description. Otherwise, the filename **/etc/termcap** will be used as the name of the database.

The TERMCAP environment variable can be set as follows:

```
TERMCAP=pathname ; export TERMCAP
```

pathname is a pathname of the termcap file.

For example:

```
TERMCAP=/usr/sales/mytermcapfile; export TERMCAP
```

Terminfo Database

The runtime system locates the terminfo database by first looking for the environment variable TERMINFO. If the TERMINFO environment variable is found, that value is used as the pathname to the database subdirectories. Otherwise, the path /usr/lib/terminfo will be used.

The TERMINFO environment variable can be set as follows:

```
TERMINFO=pathname ; export TERMINFO
```

pathname is a pathname of the terminfo file.

For example:

```
TERMINFO=/usr/sales/myterminfo; export TERMINFO
```

Termcap and Terminfo

The name of the database entry that describes the behavior of your terminal is obtained from the environment variable TERM. This variable should be set to the appropriate terminal name before invoking the runtime system. The TERM environment variable can be set as follows:

```
TERM=term-name ; export TERM
```

term-name is the name of your terminal as it appears in the termcap or terminfo database. The termcap or terminfo capabilities used by the runtime system (if present) are listed in the tables that follow.

Table 2-1 describes the information from the terminfo and termcap databases that the runtime system uses.

Table 2-1 Terminfo and Termcap Names for the Runtime System

Terminfo Name	Termcap Name	Description
Booleans		
am	am	Terminal has automatic margins.
bce	be	Screen erased with background color.
xenl	xn	Newline ignored after 80 columns. Also used to signify that the terminal's cursor will not automatically advance to the next line after column 80 is reached, but will instead wait for the next character.
Numbers		
cols	co	Number of columns in a line.
lines	li	Number of lines on screen or page.
pb	pb	Lowest baud where padding is needed.
xmc	sg	Number of blank characters left by smso or rmso.
Output Strings		
acsc	ac	Graphic charset pairs.
batt1		Attributes for box characters—primary set (AIX systems only).
batt2		Attributes for box characters—alternate set (AIX systems only).
box1		Box characters—primary set (AIX systems only).
box2		Box characters—alternate set (AIX systems only).
bel	bl	Audible signal (bell).
blink		Turn on blinking.
civis	vi	Make cursor invisible.
clear	cl	Clear screen and home cursor.
cnorm	ve	Make cursor appear normal (undo vs/vi).
cr	cr	Carriage return.

Table 2-1 Terminfo and Termcap Names for the Runtime System *(Cont.)*

Terminfo Name	Termcap Name	Description
Output Strings		
cub1	le	Move cursor left one space.
cud1	do	Down one line.
cuf1	nd	Nondestructive space (cursor right).
cup	cm	Cursor motion.
cuu1	up	Upline (cursor up).
cvvis	vs	Make cursor very visible—insert mode.
dim		Turn on half-bright mode.
ed	cd	Clear to end of display.
el	ce	Clear to end of line.
enacs	eA	Enable alternate character set.
home	ho	Home cursor.
	ko	Termcap entries for other non-function keys.
ind	sf	Scroll text up.
pad	pc	Pad character (rather than null).
op	op	Set all colors to the original color pairs.
rev		Turn on reverse video mode.
rmacs	ae	End alternate character set.
rmcup	te	String to end programs that use cup.
rmso	se	End of standout mode (if no nM or sgr0).
	is	Terminal initialization string.
rs1	r1	Terminal reset/initialization string 1.
rs2	r2	Terminal reset/initialization string 2.
rs3	r3	Terminal reset/initialization string 3.
setb	Sb	Set current background color.
setf	Sf	Set current foreground color.
sgr		Define video attributes, 1 through 9.
sgr0	me	Turn off all attributes.
smacs	as	Start alternate character set.
smcup	ti	String to begin programs that use cup.
	tc	Entry of similar terminal.
xenl	xn	Newline ignored after 80 columns.

Table 2-2 describes the input sequences that may be handled by the terminfo package. For convenience, the corresponding termcap name is also given. These terminfo names are also the only names that will be recognized when using the TERM-INPUT configuration feature of the runtime system. Termcap names other than the ones listed in the table can be used.

Table 2-2 Input Sequences for Terminfo and Termcap

Terminfo Name	Termcap Name	Description
Input Strings		
ka1	K1	Upper-left of keypad.
Ka3	K3	Upper-right of keypad.
Kb2	K2	Center of keypad.
Kbeg	@1	Sent by beginning key.
Kbs	kb	Sent by backspace key.
Kc1	K4	Lower-left of keypad.
Kc3	K5	Lower-right of keypad.
Kcan	@2	Sent by cancel key.
Kclo	@3	Sent by close key.
Kclr	kC	Sent by clear screen or erase key.
Kcmd	@4	Sent by command key.
Kcpy	@5	Sent by copy key.
Kcrt	@6	Sent by create key.
Kctab	kt	Sent by clear-tab key.
Kcub1	kl	Sent by terminal left arrow key.
Kcud1	kd	Sent by terminal down arrow key.
Kcuf1	kr	Sent by terminal right arrow key.
Kcuu1	ku	Sent by terminal up arrow key.
Kdch1	kD	Sent by delete character key.
Kdl1	kL	Sent by delete line key.
Ked	kS	Sent by clear-to-end-of-screen key.
Kel	kE	Sent by clear-to-end-of-line key.
Kend	@7	Sent by end key.
Kent	@8	Sent by enter/send key.
Kext	@9	Sent by exit key.
Kf0	k0	Sent by function key f0.
Kf1	k1	Sent by function key f1.
Kf2	k2	Sent by function key f2
kf3	k3	Sent by function key f3.
Kf4	k4	Sent by function key f4.

Table 2-2 Input Sequences for Terminfo and Termcap *(Cont.)*

Terminfo Name	Termcap Name	Description
Input Strings		
kf5	k5	Sent by function key f5.
kf6	k6	Sent by function key f6.
kf7	k7	Sent by function key f7.
kf8	k8	Sent by function key f8.
kf9	k9	Sent by function key f9.
kf10	k;	Sent by function key f10.
kf11	F1	Sent by function key f11.
kf12	F2	Sent by function key f12.
kf13	F3	Sent by function key f13.
kf14	F4	Sent by function key f14.
kf15	F5	Sent by function key f15.
kf16	F6	Sent by function key f16.
kf17	F7	Sent by function key f17.
kf18	F8	Sent by function key f18.
kf19	F9	Sent by function key f19.
kf20	FA	Sent by function key f20.
kf21	FB	Sent by function key f21.
kf22	FC	Sent by function key f22.
kf23	FD	Sent by function key f23.
kf24	FE	Sent by function key f24.
kf25	FF	Sent by function key f25.
kf26	FG	Sent by function key f26.
kf27	FH	Sent by function key f27.
kf28	FI	Sent by function key f28.
kf29	FJ	Sent by function key f29.
kf30	FK	Sent by function key f30.
kf31	FL	Sent by function key f31.
kf32	FM	Sent by function key f32.
kf33	FN	Sent by function key f33.
kf34	FO	Sent by function key f34.
kf35	FP	Sent by function key f35.
kf36	FQ	Sent by function key f36.
kf37	FR	Sent by function key f37.
kf38	FS	Sent by function key f38.

Table 2-2 Input Sequences for Terminfo and Termcap *(Cont.)*

Terminfo Name	Termcap Name	Description
Input Strings		
kf39	FT	Sent by function key f39.
kf40	FU	Sent by function key f40.
kf41	FV	Sent by function key f41.
kf42	FW	Sent by function key f42.
kf43	FX	Sent by function key f43.
kf44	FY	Sent by function key f44.
kf45	FZ	Sent by function key f45.
kf46	Fa	Sent by function key f46.
kf47	Fb	Sent by function key f47.
kf48	Fc	Sent by function key f48.
kf49	Fd	Sent by function key f49.
kf50	Fe	Sent by function key f50.
kf51	Ff	Sent by function key f51.
kf52	Fg	Sent by function key f52.
kf53	Fh	Sent by function key f53.
kf54	Fi	Sent by function key f54.
kf55	Fj	Sent by function key f55.
kf56	Fk	Sent by function key f56.
kf57	Fl	Sent by function key f57.
kf58	Fm	Sent by function key f58.
kf59	Fn	Sent by function key f59.
kf60	Fo	Sent by function key f60.
kf61	Fp	Sent by function key f61.
kf62	Fq	Sent by function key f62.
kf63	Fr	Sent by function key f63.
kfnd	@0	Sent by find key.
khlp	%1	Sent by help key.
khome	kh	Sent by home key.
khts	kT	Sent by set-tab key.
kich1	kI	Sent by insert character/enter insert mode key.
kil1	kA	Sent by insert line.
kind	kF	Sent by scroll-forward/down key.
kll	kH	Sent by home-down key.
kmov	%4	Sent by move key.
kmrk	%2	Sent by mark key.

Table 2-2 Input Sequences for Terminfo and Termcap *(Cont.)*

Terminfo Name	Termcap Name	Description
Input Strings		
kmsg	%3	Sent by message key.
knp	kN	Sent by next-page key.
knxt	%5	Sent by next-object key.
kopn	%6	Sent by open key.
kopt	%7	Sent by options key.
kpp	kP	Sent by previous-page key.
kprt	%9	Sent by print key.
kprv	%8	Sent by previous-object key.
krdo	%0	Sent by redo key.
kref	&1	Sent by reference key.
kres	&5	Sent by resume key.
krfr	&2	Sent by refresh key.
kri	kR	Sent by scroll-backward/up key.
krmir	kM	Sent by exit insert mode key.
krpl	&3	Sent by replace key.
krst	&4	Sent by restart key.
ksav	&6	Sent by save key.
kslt	*6	Sent by select key.
kspd	&7	Sent by suspend key.
ktbc	ka	Sent by clear-all-tabs key.
kund	&8	Sent by undo key.
kBEG	&9	Sent by shifted beginning key.
kCAN	&0	Sent by shifted cancel key.
kCMD	*1	Sent by shifted command key.
kCPY	*2	Sent by shifted copy key.
kCRT	*3	Sent by shifted create key.
kDC	*4	Sent by shifted delete-char key.
kDL	*5	Sent by shifted delete-line key.
kEND	*7	Sent by shifted end key.
kEOL	*8	Sent by shifted clear-line key.
kEXT	*9	Sent by shifted exit key.
kFND	*0	Sent by shifted find key.
kHLP	#1	Sent by shifted help key.
kHOM	#2	Sent by shifted home key.
kIC	#3	Sent by shifted input key.

Table 2-2 Input Sequences for Terminfo and Termcap *(Cont.)*

Terminfo Name	Termcap Name	Description
Input Strings		
kLFT	#4	Sent by shifted left arrow key.
kSAV	!1	Sent by shifted save key.
kSPD	!2	Sent by shifted suspend key.
kUND	!3	Sent by shifted undo key.
kMSG	%a	Sent by shifted message key.
kMOV	%b	Sent by shifted move key.
kNXT	%c	Sent by shifted next key.
kOPT	%d	Sent by shifted options key.
kPRV	%e	Sent by shifted prev key.
kPRT	%f	Sent by shifted print key.
kRDO	%g	Sent by shifted redo key.
kRPL	%h	Sent by shifted replace key.
kRIT	%i	Sent by shifted right arrow key.
kRES	%j	Sent by shifted resume key.
lf0	l0	Labels on function key f0 if not f0.
lf1	l1	Labels on function key f1 if not f1.
lf2	l2	Labels on function key f2 if not f2.
lf3	l3	Labels on function key f3 if not f3.
lf4	l4	Labels on function key f4 if not f4.
lf5	l5	Labels on function key f5 if not f5.
lf6	l6	Labels on function key f6 if not f6.
lf7	l7	Labels on function key f7 if not f7.
lf8	l8	Labels on function key f8 if not f8.
lf9	l9	Labels on function key f9 if not f9.
lf10	la	Labels on function key f10 if not f10.
nel	nw	Sent by newline key.

Table 2-3 describes the additional Boolean capabilities used by RM/COBOL when accessing the termcap database.

Table 2-3 Additional Boolean Capabilities

Termcap Name	Description
lA	Attributes will not wrap lines.
sA	Attributes will wrap screen.

Table 2-4 describes the additional output string capabilities used by RM/COBOL when accessing the termcap database.

Table 2-4 Additional Output String Capabilities

Termcap Name	Description
aB	Low intensity blink.
Ab	Low intensity underline and blink.
aL	Low intensity.
Al	Low intensity underline.
aR	Low intensity reverse.
aS	Low intensity blink and reverse.
nB	High intensity blink.
Nb	High intensity underline and blink.
nM	High intensity.
Nm	High intensity underline.
nR	High intensity reverse.
nS	High intensity blink and reverse.
vr	End of field.

Table 2-5 describes the additional numeric capabilities used by RM/COBOL when accessing the termcap database.

Table 2-5 Additional Numeric Capabilities

Termcap Name	Description
oV	Number of blank characters left by additional RM/COBOL attribute capabilities.

The Boolean capabilities **sA** and **lA** cannot be added to the terminfo database since it is a closed system; these capabilities are not used by the terminfo runtime system. Under runtime systems that use terminfo for output, the **xmc** numeric capability determines the width of attribute characters and the starting position of fields. Specifying **xmc#0** indicates a physical attribute terminal for which the attributes do not occupy a screen position but still must be written at the physical start and end of each field.

Runtime systems that use the terminfo database directly for output sequences will use the set_attributes or **sgr** string for all field attributes, if it is available. The terminfo set_attributes string has nine parameters or attributes that can be set. RM/COBOL makes use of six of these parameters. The second parameter is set if the underline attribute is requested. The third parameter is set if the reverse attribute is requested. The fourth parameter is set if the blinking attribute is requested. The fifth parameter is set if the low-intensity attribute is used. The sixth parameter is set if the high-intensity attribute is used. The ninth parameter may be used when line draw characters are requested for pop-up window borders. The only exception to requesting line draw characters in this manner is in terminals where **xmc** and **sgr** are specified (for example, physical attribute terminals). On these terminals the alternate character set attribute can either be a field attribute or a single character attribute. Because the terminfo database does not indicate how to determine this behavior for a terminal, RM/COBOL will infer that the terminal has the alternate character set as a single character attribute, if the **smac** definition is in the terminfo database for the terminal. In this case, the **smacs** and **rmacs** sequence will be used for the writing of graphics or alternate character set data and the ninth parameter will always be specified as off.

Each of the **sgr** parameters is set to one if an ACCEPT or DISPLAY requests the corresponding attribute. Otherwise, a zero is set for the parameter. A zero is also set for all other parameters.

Attributes are reset by using the **sgr0** string if it is defined. Otherwise, they are reset using all zeroes as parameters to the set_attributes string.

If the set_attributes string is not available, the standard terminfo strings listed in Table 2-6 will be used.

Table 2-6 Standard Terminfo Strings

Terminfo Name	Description
blink	High intensity blink.
dim	Low intensity.
rev	High intensity reverse video.
rmacs	End alternate character set.
rmso	Reset attributes (also used for high intensity if no sgr0).
sgr0	High intensity.
smacs	Start alternate character set.
smso	High intensity (if no sgr0 or rmso).

If color keywords are specified in the CONTROL phrase, the terminfo **setf** or **setb** sequence will be used to set the foreground or background color. These sequences accept a single numeric parameter indicating the desired color. If these sequences are not already defined for your terminal and you wish to define them, the association of colors to color numbers is normally defined in the C include file, **curses.h**.

If line draw characters are requested for either pop-up window borders, or because the GRAPHICS keyword in the CONTROL phrase was specified in an ACCEPT or DISPLAY statement, the terminfo database is examined for the **acsc** sequence or the **box1** and **box2** sequences. UNIX systems provide the **acsc** string to map generic (vt100) line draw characters to the correct characters for your terminal. These characters are then enabled through the ninth **sgr** parameter (see page 2-20). To support double-line draw characters, RM/COBOL has extended the **acsc** string to include six more mappings. These mappings extend the generic (vt100) characters by describing the double-line graphic characters with the corresponding uppercase letters, as shown in Table 2-7.

AIX systems describe line draw graphic characters through the **box1** and **box2** sequences in the terminfo file. In addition, if the first character of **batt1** or **batt2** is f, the ninth **sgr** parameter will be set when writing the **box1** or **box2** line draw characters, respectively.

Table 2-7 vt100 Line Graphic Characters

Description	Single-Line Character	Double-Line Character
lower-right corner	j (┘)	J (╝)
upper-right corner	k (┐)	K (╗)
upper-left corner	l (┌)	L (╔)
lower-left corner	m (└)	M (╚)
horizontal line	q (─)	Q (═)
vertical line	x (│)	X (║)

Redirection of Input and Output

RM/COBOL supports standard piping and standard redirection of input and output.

The use of the redirection and piping operators (>, >> , < and |) on the Runtime Command line affects the operation of ACCEPT and DISPLAY statements in several ways. Piping is a means of chaining the standard output (DISPLAY statements) of one run unit to the standard input (ACCEPT statements) of a second run unit; therefore, piping appears identical to redirection at the program level. Note that a Format 1 ACCEPT or DISPLAY statement that includes the FROM/UPON CONSOLE phrase or FROM/UPON *mnemonic-name* phrase where *mnemonic-name* is defined as CONSOLE IS *mnemonic-name*, is not redirected or piped unless it is configured to come from standard input or go to standard output. If this is not the case, you must use either 2> or 2>> for redirection. Note also that if an ACCEPT or DISPLAY statement contains a UNIT phrase, it will not be redirected.

Standard Input

The standard input device is defined by default to be the keyboard of the terminal that started the run unit. Standard input may be redirected to a file or other device by the operating system conventions for standard input redirection and piping on the command line that starts the run unit.

For example:

```
runcobol getdata <inputfile
```

redirects standard input to the file **inputfile** and

```
runcobol putdata | runcobol getdata
```

pipes the standard output from program **putdata** to the standard input of program **getdata**.

ACCEPT statements that do not specify the FROM CONSOLE phrase read from the standard input device.

When standard input is redirected, the ACCEPT statement (Formats 1 and 3) operation is modified. Only the SIZE, CURSOR, ECHO, CONVERT and ON EXCEPTION phrases of Format 3 are used; all other phrases are ignored. Note that Format 1 ACCEPT statements with numeric operands are treated as Format 3 ACCEPT statements unless the program containing the ACCEPT statements was compiled with the M Compile Command Option (see page 6-11).

At the beginning of each ACCEPT statement, the next record is read from standard input into the ACCEPT buffer. The following operations take place for each of the receiving data items in the ACCEPT statement:

1. If there are no characters in the ACCEPT buffer, the next record is read from standard input into the ACCEPT buffer.

2. If the number of characters in the ACCEPT buffer does not exceed the size of the current receiving item, those characters are transferred to the receiving item in the appropriate format (that is, left justified, space fill for all Format 1 and for alphanumeric Format 3, and with appropriate conversion for numeric Format 3).

3. If the number of characters in the ACCEPT buffer exceeds the size of the current receiving item, only the leftmost “size” characters are transferred, as described in the previous operation. The characters that remain in the ACCEPT buffer are used for the next receiving item or are discarded if the current receiving item is the last receiving item in the ACCEPT statement.

Note Where numeric sending and receiving data items are used with piping, the use of the CONVERT phrase with DISPLAY and ACCEPT statements is strongly recommended.

The M Runtime Command Option (see page 7-4) modifies the operation of Format 1 ACCEPT statements to conform to Level 2 ANSI semantics. The actions described above are modified as follows:

1. If the number of characters in the ACCEPT buffer does not equal or exceed the size of the current receiving item, one or more records are read from standard input and are concatenated until there are enough characters.

2. The leftmost "size" characters are transferred as described in steps 2 and 3 on the preceding page. The characters that remain in the ACCEPT buffer are discarded.

Note that the use of the M Runtime Command Option requires close matching of ACCEPT and DISPLAY statements when used with piping.

Also note that the M Runtime Command Option affects the operation of Format 1 ACCEPT statements which are not redirected; the console operator is required to enter enough characters to fill the receiving item. If the Enter key is pressed before enough characters have been entered, the request will be reissued until the concatenation of the characters entered is sufficient to fill the receiving item.

The M Runtime Command Option does not affect the operation of Format 3 ACCEPT statements.

An end-of-file condition is reported to Format 3 ACCEPT statements as an exception variable of 64 (Send). If an end-of-file condition occurs and there is no ON EXCEPTION phrase, a runtime system error is reported and execution ends.

Standard Output

The standard output device is defined by default to be the monitor of the terminal that started the run unit. Standard output may be redirected to a file or other device by the operating system conventions for standard output redirection and piping on the command line that starts the run unit.

For example:

```
runcobol putdata >outputfile
```

redirects standard output to the file **outputfile** and

```
runcobol putdata | runcobol getdata
```

pipes the standard output from program **putdata** to the standard input of program **getdata**.

DISPLAY statements that do not specify the UPON or UPON CONSOLE phrase write to the standard output device.

When standard output is redirected, all phrases, except SIZE and CONVERT, of the Format 2 DISPLAY statement are ignored. All sending operands are concatenated (within the limits of the ACCEPT/DISPLAY buffer as described in the following paragraphs) and are transferred to standard output as one or more records.

A Format 1 DISPLAY statement generates one record and may generate more than one record, depending on the presence or absence of the M Runtime Command Option (see page 7-4). If the M Option is not present in the Runtime Command, all sending operands are concatenated, the resulting operand is truncated to the DISPLAY buffer size, and a single record is written. If the M Option is present, all sending operands are concatenated and the resulting operand is split into zero or more records equal in length to the DISPLAY buffer size, along with a final record no longer than the DISPLAY buffer size.

If a Format 2 DISPLAY statement is redirected, one or more records are generated, depending on the size of the discrete sending items. If the size of the sending operand does not exceed the space remaining in the DISPLAY buffer, the sending operand is appended to the current buffer and the DISPLAY buffer is written if the sending operand is the last operand. If the size of the sending operand exceeds the space remaining in the DISPLAY buffer, the current DISPLAY buffer is written and the sending operand is truncated to the size of the DISPLAY buffer. The new DISPLAY buffer contents are written if the sending operand is the last operand.

Standard Error

The standard error device is defined by default to be the monitor and keyboard. Interactive debug input and output, STOP *literal* statements, and runtime system messages are directed to the standard error device. These operations can be redirected by a configuration option; see the discussion of the ERROR-MESSAGE-DESTINATION keyword that begins on page 10-25.

These operations also can be redirected using the operating system standard-error redirection convention on the command line that starts the run unit.

For example:

```
runcobol putdata 2>error.out
```

To direct standard output and standard error to the same destination, specify:

```
runcobol putdata >all.out 2>&1
```

Chapter 3: Installation and System Considerations for Microsoft Windows

This chapter lists the hardware and software required to install the RM/COBOL product, describes how to install RM/COBOL, and provides information specific to using RM/COBOL with Microsoft Windows 95, Windows 98, and Windows NT operating systems.

Your computer configuration is the assembled set of hardware and software that makes up your system. Before you can develop or run RM/COBOL programs, your configuration must meet or exceed the requirements set forth in this chapter.

System Requirements

RM/COBOL runs on the IBM PC and full compatibles. Appropriately licensed versions run in conjunction with Client for Microsoft Networks or Novell NetWare software to provide support for multiuser file access.

Required Hardware

- IBM PC or compatible machine with an 80486-class processor or higher.
- A mouse or other pointing device.
- Eight megabytes of random-access memory (RAM). (Sixteen megabytes are recommended.)
- VGA (640x480) or compatible display. (An 800x600 or better super-VGA display is recommended.)
- A double-sided, high-density 3.5-inch floppy disk drive for program installation.
- Network adapter (for multiuser configurations)

Required Software

One of the following operating systems is required:

- Microsoft Windows 95
- Microsoft Windows 98
- Microsoft Windows NT version 4.0

Local Area Network (LAN) Software

To provide multiuser access, one or both of the following network programs is required:

- Novell NetWare version 3.11 or later
- Client for Microsoft Networks for Windows 95, Windows 98, or Windows NT version 4.0

Btrieve Software

To access local Btrieve files, the following software is required:

- Btrieve for Windows NT/Windows 95/Windows 98 version 6.15 or later

To access remote Btrieve files, both of the following software components are required:

- Btrieve MicroKernel Database Engine for NetWare or Windows NT Servers version 6.15 or later
- Btrieve Requester for Windows 95/Windows 98/Windows NT version 6.15 or later

Note Btrieve components are available from Pervasive Software Inc.

System Installation

To install RM/COBOL, take the following steps:

1. Start the Windows 95, Windows 98, or Windows NT operating system.
2. Insert your RM/COBOL for 32-bit Windows diskette into a disk drive.
3. Click on the Start button and select the Run command.
4. In the Open text box in the Run dialog box, type the following:

   ```
   A:setup
   ```

   where "A" is the letter assigned to the drive where you inserted the diskette.
5. Click the OK command button and follow the prompts on your screen to complete the installation process.

After installation is complete, you can display the RM/COBOL Program Folder, which is illustrated in Figure 3-1. The programs are described in Table 3-1.

Figure 3-1 RM/COBOL Program Folder



Note Depending upon which RM/COBOL package you purchased, not all of the program icons in Figure 3-1 will appear on your system.

Table 3-1 RM/COBOL Program Icons

Program Icon Name	Description
CodeWatch	Starts CodeWatch, a standalone, source-level debugger for Windows.
Compiler (rmcobol)	Starts the RM/COBOL compiler and prompts for a source filename.
doverify	Starts the RM/COBOL verification suite.
INI to Registry (ini2reg.exe)	Takes a Windows initialization (.ini) file and inserts its entries into the Windows registry used by RM/COBOL.
ixverify	Starts the RM/InfoExpress verification suite.
Read Me	Starts notepad with the README file.
Recover1	Starts the Indexed File Recovery utility program (recover1.exe). This program is used to recover damaged indexed files.
Registry Configuration (rmconfig.exe)	Sets the runtime system, compiler, and Indexed File Recovery utility program (recover1.exe) options for RM/COBOL programs and data files.
rmdefinx	Starts the Define Indexed File utility program (rmdefinx.cob).
rmmapinx	Starts the Map Indexed File utility program (rmmapinx.cob).
rmmappgm	Starts the Map Program File utility (rmmappgm.cob) program.
rmpgmcom	Starts the Combine Program File utility program (rmpgmcom.cob).
Runtime (runcobol)	Starts the RM/COBOL runtime system and prompts for a program name.
Toolbar Editor	Starts the toolbar button editor.

Registering the RM/COBOL Runtime

The RM/COBOL version 7.0 for Windows runtime system consists of two components:

- A client, called **runcobol.exe**
- A server, called **rmcblrun.dll**

The runtime server DLL, which must be registered with Windows before RM/COBOL programs can be run, is automatically registered by the Setup program when the runtime system is installed. If the runtime is moved to a directory other than the installation directory without a re-installation, the error message shown in Figure 3-2 is displayed indicating that there is a registration problem.

Figure 3-2 RM/COBOL Runtime Server Error Message



There are two ways to resolve this problem. You can do either of the following:

- Repeat the installation.
- Use the /REGSERVER command line option.

To register the Windows runtime in a directory other than the installation directory, first make sure that **runcobol.exe** and **rmcblrun.dll** are in the same directory. Then, click the Windows Start button and select Run from the menu, or open a DOS window. Enter the following command:

```
path\RUNCOBOL /REGSERVER
```

where *path* is the drive and directory or the UNC location of these two files.

For example:

```
"c:\program files\rmcobol v7\runcobol" /regserver
```

Note The quotes are necessary only if the pathname contains spaces.

If the registration process is successful, the message box illustrated in Figure 3-3 is displayed.

Figure 3-3 Successful RM/COBOL Server Registration Message



Once registration is complete, the **runcobol.exe** program is no longer required to be in the same directory as the **rmcblrun.dll** server.

The RM/COBOL runtime also provides the /UNREGSERVER command line option to unregister the runtime from Windows. Although the uninstallation program automatically unregisters the runtime, this can be done manually with the following command:

```
path\RUNCOBOL /UNREGSERVER
```

It is not necessary to unregister the runtime before re-registering the runtime from a different location.

Finally, the following option will display the location of the currently registered runtime server:

```
path\RUNCOBOL /SHOWSERVER
```

Figure 3-4 illustrates the message box that is displayed when the server has been properly registered:

Figure 3-4 RM/COBOL Show Server Registration Message



Otherwise, a detailed error message is displayed. Note that “Class not registered” in the this error message indicates that the server is not registered.

System Removal

To remove RM/COBOL from your system, take the following steps:

1. Click Start button, point to Settings, and then click Control Panel.
2. Double-click Add/Remove Programs.
3. From the Install/Uninstall tab in the Add/Remove Programs Properties dialog box, select “RM/COBOL” from the list of installed program packages.
4. Click the Add/Remove button.
5. Follow the prompts on your screen to complete the removal process.

All installed RM/COBOL system programs, files, shortcuts, and Windows registry entries are now removed. Customer files are not affected.

System Configuration

As mentioned, RM/COBOL supports IBM PCs, full PC compatibles, and Windows systems. This section sets forth information required to configure RM/COBOL with each type of system.

Creating a Windows Shortcut

When you create a shortcut in Windows, you must also specify the properties of the item. Properties include a description of the item (the application name) and the working directory where the application files are stored.

To create a shortcut for an application under Windows, take the following steps:

1. Open the folder to which you want the item added. (Note that you can also add an item directly to the desktop.)
2. Click the right mouse button to open a pop-up menu. Point to the New option and click Shortcut. The Create Shortcut dialog box opens.

3. In the Target text box, type in a runtime system command, as described in Chapter 7, *Running*. Click the Next button.

4. When prompted to name the shortcut, choose a name that uniquely identifies the application program. This name becomes the label that appears under the shortcut icon.

5. After Windows creates the shortcut, you must modify the properties of the shortcut in order for it to work properly. Right-click the shortcut icon and choose Properties. The Shortcut Properties dialog box opens.

6. Select the Shortcut tab in the dialog box. (Figure 3-5 illustrates the Shortcut Properties Tab used in this example.) In the Start in text box, enter the name of the directory where the program files for this application are located and where new files will be placed. The directory you specify here becomes the current directory while the application program is running.

Figure 3-5 Shortcut Properties Tab



Using Associations With Filename Extensions

During installation, RM/COBOL for Windows automatically sets up filename extension associations for **.cbl** and **.cob** files. These associations allow the user to compile or run source or object files by double-clicking these files when running the Windows File Manager or Windows Explorer.

Normally, you cannot pass command line options to Windows programs executed using a filename extension association. However, using the Windows registry (described on page 3-16), it is possible to inform the RM/COBOL compiler or runtime system of command line options for all programs or for specific programs. (See page 3-20 for a discussion of the Command Line Options property in the RM/COBOL configuration.)

Under Windows, it is also possible to drag and drop **.cbl** and **.cob** files to the RM/COBOL compiler or runtime system for execution. Dropping a **.cbl** file on a printer icon will print that source file.

Prompting for a Filename

If the command line specified for the compiler or the runtime system has a ? character for the source or object filename, the Select an RM/COBOL Object File dialog box appears, as shown in Figure 3-6.

Figure 3-6 Select an RM/COBOL Object File Dialog Box



When the user selects the file from the list available in the space below the Look in drop-down list box, the filename in the File name text box replaces the ? character on the command line. To open (or start) the source or runtime system file, click the Open button. Double-clicking the name of the file also opens (or starts) the selected object file.

Locating RM/COBOL Files

File Locations Within Operating System Pathnames

File locations are determined by the pathname of the file, according to operating system rules and conventions. A fully qualified pathname contains the drive specifier, a directory path, the filename, and the filename extension. A filename that begins with a universal naming convention (UNC) specifier (*server*) is also treated as a fully qualified pathname.

Note Novell NetWare syntax (*server**volume:filename*) is no longer supported. Use of UNC filename is now required (*server**volume**filename*).

If a pathname appears without a drive specifier, the current drive is assumed. If a pathname is specified without a directory path, RM/COBOL searches the current directory of the specified or assumed drive.

Specifying a directory path with a leading slash, a drive letter, or a volume name indicates to RM/COBOL that an exact filename has been specified. If RM/COBOL cannot find the file in the specified location, it will not look elsewhere. If you do not specify a directory path, and RM/COBOL cannot find the file in the assumed location, it will search for the file according to the directory search sequence. If a directory path is specified, but there is no leading slash, drive letter, or volume name, then the EXPANDED-PATH-SEARCH keyword of the RUN-FILES-ATTR configuration record determines whether the directory search sequence will be used (see page 10-27). When the configuration keyword is set to its default value of NO, the directory search sequence will not be used. If the value is set to YES, then the entire name, including the directory path, will be appended to each entry in the directory search sequence in an attempt to locate the file.

Directory Search Sequences

You can direct RM/COBOL to search for a file not found in the current working directory by using a predefined directory search sequence. There are two directory search sequences: one for the compiler and one for the runtime system.

To direct the RM/COBOL compiler to use the directory search sequence, set the RMPATH synonym. You do this by using the RM/COBOL Configuration utility (**rmconfig.exe**), as explained in Appendix G, *Utilities*. Alternatively, you can right-click the mouse button on a **.cbl** file, select the Synonyms Properties tab, and set the RMPATH synonym with the following syntax (see page 3-29 for a discussion of setting synonyms):

```
path [;path] ...
```

To direct the RM/COBOL runtime system to use the directory search sequence, set the RUNPATH synonym. To do this, use the RM/COBOL Configuration utility (**rmconfig.exe**), as discussed in Appendix G. You may also right-click the mouse button on a **.cob** file, select the Synonyms Properties tab, and set the RUNPATH synonym with the following syntax (see page 3-29 for a discussion of setting synonyms):

```
path [;path] ...
```

In both commands, *path* indicates the directory that is to be searched for the file, and has the form:

```
[d:] [\] directory [\directory] ...
```

d is the drive specifier.

directory is the location of an existing file, or the location of a file that will be created.

If multiple *path*s are specified, they must be separated with semicolons. Figure 3-7 and Figure 3-8 illustrate the compiler and runtime system search sequences, respectively.

Figure 3-7 Compiler Search Sequence



Figure 3-8 Runtime System Search Sequence



Files made to appear in the current directory by using Novell search directories when the Novell Search Mode is set to a value other than 2 will not be accessed. If a file to be accessed resides in a directory other than the current directory, that directory must be included in the RMPATH or RUNPATH directory list. This requirement also applies to files located in Novell search directories when the Novell Search Mode is set to a value other than 2.

The compiler, runtime system, and Indexed File Recovery utility program require access to other files in order to operate. These include the message files (**RMC.MSG**, **RUN.MSG**, and **REC.MSG**), dynamic link library files (with an extension of **.dll**), and, for the compiler, the compiler overlay file, **rmcobol.ovy**. RM/COBOL looks for these files first in the directory containing the executable file, then in the current directory, and finally in the directories specified in the PATH environment variable. For the dynamic link library files, the default Windows system directory and then the default Windows directory will be searched prior to searching the directories specified in the PATH environment variable.

The compiler and runtime system may be executed from a directory other than the current directory if a complete pathname is specified in the command line, or if either the search directory of Novell NetWare or the DOS PATH directory search feature is used. If a complete pathname is not specified and the compiler or runtime system is not located in the current directory, the directories specified by PATH are searched.

Novell NetWare Search Paths

Novell NetWare defines a search path for locating command files. RM/COBOL defines a search path for locating compiler files (RMPATH) and for locating runtime system files (RUNPATH). Both Novell NetWare and RM/COBOL search paths consist of a list of directories from which attempts are made to open files.

With RM/COBOL search paths, if any one of the directories in a user's path does not have search permission for the user, then the searching sequence stops for all remaining directories and a security violation is reported. This security violation indicates that the runtime system has been prevented from examining the directory for a file. If a security violation occurs, and the file is located in a directory for which the user has permission, examine the permissions for other directories in the RUNPATH sequence.

To prevent this security violation, take one of the following actions:

- Give the user search permission for all directories in RUNPATH, RMPATH, and the Novell NetWare search path.
- Alternatively, remove the directory from the search path.

Note This same security violation can occur when creating a new file, even if it is with OPEN OUTPUT. The RM/COBOL runtime system still searches RUNPATH to locate a file that needs to be replaced.

File Access Names

The file access name you specify in the COBOL source program specifies the physical file or device to which input or output is directed. For information on specifying the file access name in a COBOL source program, see the discussion of the ASSIGN clause (file control entry) in Chapter 3, *Environment Division*, and the discussion of the VALUE OF clause in Chapter 4, *Data Division*, of the *RM/COBOL Language Reference Manual*.

To establish synonymity between a file access name specified in your source program and another name specified when the program is run, use the Synonyms tab of the Properties dialog box, as illustrated in Figure 3-9. The Synonyms Properties tab is described on page 3-29.

Figure 3-9 Synonyms Tab of the Properties Dialog Box



For example, let us say that you specified a generic file access name for program input-output and wish to direct it to a specific device or file. A generic file access name is one that does not specify a directory path or drive letter. Since the format of physical pathnames, including conventions of specifying drive letters and directory names, varies from one operating system to another, for maximum portability it is recommended that source programs specify generic file access names, preferably with eight or fewer letters. This recommendation only applies when the file access name is hard coded into the program as a literal.

For example, if the file control entry specifies:

```
SELECT REPORT-FILE ASSIGN TO PRINT, "report"
```

and no synonym is assigned, RM/COBOL will create a file named **report** in the current directory on the current drive.

If, prior to running the program, you set the synonym "report" to a value of LPT1, all program output written to REPORT-FILE will be written to **LPT1**.

If—again prior to execution—you set the synonym "report" to a value of "A:\output\audit.lst", RM/COBOL will create a file named **audit.lst** in the subdirectory **\output** on drive A without any need to modify or recompile the source program.

When a synonym is not set, the file access name in the COBOL program specifies the actual filename. Synonym values can be canceled by highlighting the entry on the Synonyms tab of the Properties dialog box, clicking the Remove button, and restarting **runcobol.exe**.

Whether or not a synonym is used to modify the file access name, if the resulting file access name does not include either a drive letter or a directory path, RUNPATH will be used by the runtime system to obtain the fully qualified pathname (see “File Locations Within Operating System Pathnames” on page 3-10 for additional information).

The RESOLVE-LEADING-NAME and RESOLVE-SUBSEQUENT-NAMES keywords of the RUN-FILES-ATTR configuration record can be used to force resolution of one or more of the directory names from the environment. For more information, see the discussion of the RUN-FILES-ATTR record beginning on page 10-26.

The resulting file access name should follow the operating system rules for valid filenames and pathnames.

Windows System Print Jobs

When the resulting file access name is PRINTER or PRINTER*n*, where *n* is a decimal digit from 1 to 9, RM/COBOL refers to the Windows printer device attached to **LPT1:** or **LPT*n*:** respectively, provided that **LPT1:** or **LPT*n*:** has a Windows printer attached to it. This method causes the Windows printer device driver to be used, which does not allow the use of raw escape sequences.

When the resulting file access name is "PRINTER?" (see 10-19), RM/COBOL displays the standard Windows Print dialog box when the file is opened. This allows the user to select the destination Windows printer in a dynamic manner (that is, at execution). Once the "PRINTER?" device has been opened, the selected printer is remembered by the runtime, and subsequent opens do not display the standard Windows Print dialog box. The program may call the P$EnableDialog subprogram (see page E-16) to force a standard Windows Print dialog box on the next open of "PRINTER?". The user may also set the Printer Dialog Always registry property to TRUE (see page 3-25) to force the dialog box on every open of "PRINTER?". The program may also call P$DisplayDialog (see page E-16) at any time, to force the standard Windows Print dialog box to be displayed.

In order to send raw escape sequences to a printer, the printer must be opened directly by using the name “LPT1”. The name “LPT*n*”, where *n* is a decimal digit, also can be used.

The DEFINE-DEVICE configuration record may define other file access names that are to be treated as devices and also change the default treatment of PRINTER and PRINTER*n*. See “DEFINE-DEVICE Record” on page 10-16 for additional information on configuring file access names that are to be treated as devices.

Windows Registry

RM/COBOL version 6.5 and later stores configuration information for the runtime system, compiler, and Indexed File Recovery utility program in the Windows registry. The registry is a hierarchical database of configuration information maintained by Windows.

Previous versions of RM/COBOL for Windows stored configuration information in separate initialization files located in the main Windows directory. These initialization files are no longer used. However, when distributing configuration information to end-users, initialization files can still be shipped with your product. To merge your program's configuration information into the Windows registry, include a call to the supplied Initialization File to Windows Registry Conversion utility (**ini2reg.exe**), described on page G-40, in your application's installation procedure.

The Windows registry is organized much like a disk drive's directory structure. All of RM/COBOL's configuration information is stored under the "directory" path "HKEY_LOCAL_MACHINE\SOFTWARE\Liant Software Corporation\RM/COBOL\CurrentVersion". Three subdirectories underneath that path (rmcobol, runcobol, and recover1) correspond with information previously stored in the separate initialization files **rmcobol.ini, runcobol.ini,** and **recover1.ini**.

You are not required to know the inner details of the Windows registry structure in order to change the properties of your programs. RM/COBOL for Windows includes Windows shell extensions that allow the manipulation of configuration information for default values as well as individual program settings without having to navigate through the Windows registry editor. Configuration information for a specific COBOL program may be edited by right-clicking a source or object file and choosing Properties. If a source file is chosen, the properties used when compiling that program can be modified. If an object file is chosen, the properties used when running that program can be modified. The configuration options available in the Properties dialog box are described in the following section "Setting Properties." Configuration information for programs and generic default values may also be edited by running the supplied RM/COBOL Configuration utility (**rmconfig.exe**), as described on page G-41.

Users may migrate the complete RM/COBOL registry information from one machine to another by using the **regedit.exe** utility supplied with Windows. This utility allows entire sections of the Windows registry to be exported to a **.reg** text file, which can then be imported into the Windows registry of another machine. Consult the Microsoft Windows help documentation for more information on **regedit.exe**.

Setting Properties

This section describes the configuration options that can be set using the Properties dialog box.

The following definitions explain terms used throughout this section.

Term	Meaning
Boolean	Indicates a value of TRUE or FALSE. A value of 1 or 0 may also be used to indicate TRUE or FALSE.
number	Indicates a positive integer value. Valid example: "12". Invalid example: "=5".
string	Indicates alphanumeric characters.
filename	Indicates the operating system filename.

Selecting a File to Configure

The Select File tab, illustrated in Figure 3-10, allows you to select the source file or object file that you want to configure.

Note If you have opened the Properties dialog box by right-clicking the mouse button on an RM/COBOL source or object file and then selecting Properties, this tab will not be available. You are only able to configure options for the current file.

Figure 3-10 Select File Tab



The Select File tab contains the following options:

- **Default Properties.** When selected, the Default Properties option enables the other Properties tabs (Miscellaneous, Synonyms, Colors, Toolbar, Menu Bar, and Pop-up Menu) to set system defaults for all files.
- **Individual File.** When selected, the Individual File option enables the other Properties tabs to change the properties for the selected file.
- **Configure for.** The three options provided in this area determine the activity for which the Properties tabs will configure a file.
  - **Running.** If this option is selected, the settings for the **.cob** file will be shown and used when running the file.
  - **Compiling.** If this option is selected, the settings for the **.cbl** file are affected.
  - **Recovery.** If this option is selected, the settings used for recovering a data file with the Indexed File Recovery utility program (**recover1.exe**) are affected.
- **Browse.** Use this button to open a dialog box that allows you to look for a file for which you want to set properties.
- **Use Defaults.** The behavior of the Use Defaults button is dependent upon whether the Default Properties or the Individual File option is in effect.

  If the Default Properties option is selected, choosing the Use Defaults button causes the system defaults to be reset to the values that were in place when the product was originally installed. Note, however, that any property values set for an individual file will not be reset.

  If the Individual File option is selected, choosing the Use Defaults button causes property values that have been overridden for the selected file to be reset to use the system defaults.

Setting Miscellaneous Properties

The Miscellaneous Properties tab, illustrated in Figure 3-11, allows you to set various properties for the file that was specified using the Select File tab.

Figure 3-11 Miscellaneous Properties Tab



The Miscellaneous Properties tab contains the following options:

- **Property.** This list box presents an alphabetical listing of the properties that are used to configure the physical appearance of the RM/COBOL program. (Each of these properties is discussed below.)
- **Use Default Settings.** Select this button to use the selected property's default value. That default value will be shown in the Value area (described below). See the Default Properties option on the Select File tab for information on configuring default values (for more information, see the discussion of "Selecting a File to Configure" that begins on page 3-17).
- **Use Custom Settings.** Select this button to override the default value for the selected property.
- **Value.** This area displays the value associated with the property selected in the Property list box and allows you to change it. Note that this area is disabled unless the Use Custom Settings button is selected.

The following properties can be set or modified.

Auto Paste

The Auto Paste property specifies a *Boolean* value that enables or disables the Auto Paste function. Setting Auto Paste to TRUE enables the Auto Paste feature and double-clicking the mouse button transfers the marked data to a pending ACCEPT field. If Auto Paste is set to FALSE, double-clicking the mouse button marks a word of text. The default value is TRUE.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Auto Paste property in order to manipulate the graphical user interface.

Auto Scale

The Auto Scale property specifies a *Boolean* value that determines whether to implement auto scaling of fonts when the window is resized. Setting Auto Scale to TRUE automatically changes the font size when the window is resized. Setting Auto Scale to FALSE turns off this capability. The default value is TRUE. See also the Sizing Priority property on page 3-27.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Auto Scale property in order to manipulate the graphical user interface.

Command Line Options

The Command Line Options property defines a series of command line options to be passed to the runtime system. Processing of options on the actual command line occurs last and replaces any options specified using this property.

Enable Close

The Enable Close property specifies a *Boolean* value that enables or disables the Close menu item on the Control menu as well as the Close button in the upper-right corner of the window. Setting Enable Close to TRUE enables the Close menu item and the Close button. Setting Enable Close to FALSE dims and disables the Close menu item and the Close button. The default value is TRUE.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Enable Close property in order to manipulate the graphical user interface.

Enable Properties Dialog

The Enable Properties Dialog property specifies a *Boolean* value that enables or disables the Properties menu item on the Control menu. Setting Enable Properties Dialog to

TRUE enables the Properties menu item. Setting Enable Properties Dialog to FALSE dims and disables the Properties menu item. The default is TRUE.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Enable Properties Dialog property in order to manipulate the graphical user interface.

Font

The Font property specifies the typeface to use as well as point size and style. The typeface must be a fixed-width (or monospaced) font, such as Courier. Clicking the Select Fonts button opens the Fonts dialog box, which provides a list of available fonts, styles, and sizes.

Full OEM To ANSI Conversions

The Full OEM To ANSI Conversions property specifies a *Boolean* value that determines whether or not to convert a character from OEM to ANSI or from ANSI to OEM. This property affects titles, menus, and other Windows objects. Because Windows uses the ANSI character set, the default setting (TRUE) causes all output to be converted from the OEM character set to the ANSI character set and all input from these controls to be converted from ANSI to OEM. If, however, the user wants to avoid these conversions, this property should be set to FALSE in order to suppress the conversion. Setting this value to FALSE causes the runtime system to behave as it did prior to the RM/COBOL 6.5 release.

Note The European "Latin-1" character set is the same as the Windows native ANSI character set.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Full OEM to ANSI Conversions property in order to manipulate the graphical user interface.

Icon File

The Icon File property specifies the icon *filename* from which to load icons for the toolbar (see the Name option of the Toolbar Properties tab, described beginning on page 3-32). This property is used only if the Toolbar property is set to TRUE (see page 3-28). The default value is **rmtbar.vrf** (see Table 3-3 on page 3-38 for more information).

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Icon File property in order to manipulate the graphical user interface.

Load Registry On CALL

The Load Registry On CALL property specifies a *Boolean* value that enables or disables additional processing of the Windows registry file. If set to TRUE, the registry is re-examined whenever a COBOL subprogram is called. The subprogram name is treated as if it were a *filename* and causes corresponding registry entries to be processed. If set to FALSE, the registry is not re-examined. The default value is FALSE.

Note Use caution when setting the value of the Load Registry On CALL property to TRUE as a system default. Doing so can affect the performance of your application. This behavior can occur when using RM/Panels because an RM/Panels application uses many subprogram calls. Alternatively, you can use the C$TBar (see page F-37), C$MBar (see page F-17), or C$GUICFG (see page F-16) subprograms to manipulate the toolbar and menu bar instead of using the Windows registry file and the Load Registry on CALL property.

Load Registry On RETURN

The Load Registry On RETURN property specifies a *Boolean* value that enables or disables additional processing of the Windows registry file. If set to TRUE, the registry is re-examined whenever a COBOL subprogram is exited. The calling program's name is treated as if it were a *filename* and causes corresponding registry entries to be processed. If set to FALSE, the registry is not re-examined. The default value is FALSE.

Note Use caution when setting the value of the Load Registry On RETURN property to TRUE as a system default. Doing so can affect the performance of your application. This behavior can occur when using RM/Panels because an RM/Panels application uses many subprogram calls. Alternatively, you can use the C$TBar (see page F-37), C$MBar (see page F-17), or C$GUICFG (see page F-16) subprograms to manipulate the toolbar and menu bar instead of using the Windows registry file and the Load Registry on RETURN property.

Logo Bitmap

The Logo Bitmap property specifies a *Boolean* value that determines whether a Logo Bitmap is displayed. If set to TRUE, the file specified by the Logo Bitmap File property (described below) is displayed. If set to FALSE, it is not displayed. The default value is TRUE.

Logo Bitmap File

The Logo Bitmap File property specifies the bitmap (**.bmp**) *filename* that may be displayed in the COBOL window when an application is started. The bitmap is centered in the main window until an erase screen operation is encountered (DISPLAY ERASE). You can build a simple COBOL program that displays a bitmap, responds to keyboard sequences (such as function keys that could be generated from the menus or toolbar), and dispatches the appropriate code. The default value is **run.bmp**, **rmc.bmp,** or **rec.bmp** for the runtime system, compiler, and Indexed File Recovery utility program, respectively. If the bitmap file is not found, or if Logo Bitmap (described above) is set to FALSE, this property is ignored.

Main Window Type

The Main Window Type property determines the style of the Main window (the window that is activated when the COBOL application begins execution).

The following values are valid:

Value	Meaning
HIDDEN	The window is not activated and is hidden.
MINIMIZED	The window is activated and is displayed as an icon.
MAXIMIZED	The window is activated and is displayed in its maximized state.
SHOW	The window is activated and is displayed in its current size and position.

Mark Alphanumeric

The Mark Alphanumeric property specifies a *Boolean* value that determines the terminating conditions for selecting a word from the application window. If Mark Alphanumeric is set to TRUE, double-clicking the mouse button to mark a word selects characters until a non-alphanumeric character is encountered. If Mark Alphanumeric is set to FALSE, selection occurs when a blank is encountered. The default value is TRUE.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Mark Alphanumeric property in order to manipulate the graphical user interface.

Offset X

The Offset X property specifies a *number* that identifies the leftmost location (as a pixel offset from the left edge of the screen) of the COBOL window. The default value is 0.

Offset Y

The Offset Y property specifies a *number* that identifies the uppermost location (as a pixel offset from the top edge of the screen) of the COBOL window. The default value is 0.

Panels Controls 3D

The Panels Controls 3D property specifies a *Boolean* value that causes certain RM/Panels for Windows controls (date, time, alpha, and numeric fields) to take on a three-dimensional appearance. This capability was not available in prior versions of RM/Panels for Windows. The default value, FALSE, causes existing applications to appear the same as they did under previous versions of RM/COBOL.

Panels Static Controls Border

The Panels Static Controls Border property specifies a *Boolean* value that cause the Static Text Control (a new Panels control type) to have a border. The default value, FALSE, causes these controls to be drawn without a border.

Paste Termination

The Paste Termination property specifies a *Boolean* value that affects automatic termination of fields pasted into a pending ACCEPT statement, using either the Paste (see page 3-44) or Auto Paste (see page 3-20) function. If Paste Termination is set to TRUE, data transfer will continue until the data is exhausted, including all tabs and carriage returns. If Paste Termination is set to FALSE, data transfer stops when a tab or carriage return is encountered. There is a carriage return at the end of each line of text in the Windows Clipboard. The default value is TRUE.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Paste Termination property in order to manipulate the graphical user interface.

Persistent

The Persistent property specifies a *Boolean* value that affects the behavior of the RM/COBOL window when the COBOL program, compiler, or Indexed File Recovery utility program terminates. If Persistent is set to TRUE, the window will not close until dismissed by the user. If Persistent is set to FALSE, the window will close immediately upon completion. The default value is FALSE.

If any RM/COBOL window disappears upon completion before the user is able to read the final text displayed in that window, then set Persistent to TRUE and close the window manually after reading the final text.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Persistent property in order to manipulate the graphical user interface.

Printer Dialog Always

The Printer Dialog Always property specifies a *Boolean* value that affects the behavior of the RM/COBOL runtime when opening the "PRINTER?" (dynamic printer selection) device (see page 10-19). If Printer Dialog Always is set to TRUE, the standard Windows Print dialog box will appear when the dynamic printer device is opened. If Printer Dialog Always is set to FALSE, the dialog box will appear only the first time the dynamic printer is opened. The P$EnableDialog subprogram (see page E-16) may be called to cause the dialog to appear on the next open of the dynamic printer). The default value is FALSE.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Printer Dialog Always property.

Printer Dialog Never

The Printer Dialog Never property specifies a *Boolean* value that affects the behavior of the RM/COBOL runtime when opening the "PRINTER?" (dynamic printer selection) device (see page 10-19). If Printer Dialog Never is set to TRUE, the standard Windows Print dialog box will never appear when the dynamic printer device is opened. In this case, the "PRINTER?" device behaves like the Printer (default) printer device. If Printer Dialog Never is set to FALSE, the appearance of the dialog box is controlled by the setting of the Printer Dialog Always property. The default value is FALSE.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Printer Dialog Never property.

Note If the Printer Dialog Never property is set to TRUE, the standard Windows Print dialog box will never appear, regardless of the state of the Printer Dialog Always property.

Printer Enable Escape Sequences

The Printer Enable Escape Sequences property specifies a *Boolean* value that determines whether printing will allow embedded RM/COBOL-specific escape sequences. See “RM/COBOL-Specific Escape Sequences" in Appendix E, *Windows Printing,* for a more complete description. If the value is set to TRUE, the RM/COBOL runtime system will

recognize the sequences. If the value is set to FALSE, the runtime system will ignore those escape sequences. The default value is FALSE.

Note Setting the Printer Enable Escape Sequences property to TRUE affects all Windows printers that the COBOL program uses. To allow embedded RM/COBOL-specific escape sequences for only specific printers, use the P$EnableEscapeSequences subprogram (see page E-38).

Printer Enable Raw Mode

The Printer Enable Raw Mode property specifies a *Boolean* value that determines whether or not Windows printers will be opened in raw mode. If the value is set to TRUE, the runtime system will open printers in raw mode. This allows certain Windows NT networked printers to respond to embedded escape sequences. See P$SetRawMode subprogram on page E-43 for a more complete description of raw mode. Most P$ subprograms are not available if RAW mode is used. If the value is set to FALSE, the runtime system will treat the printer as a normal Windows printer. The default value is FALSE.

Note Setting the Printer Enable Raw Mode property to TRUE affects all Windows printers that the COBOL program uses. To allow raw mode printing for only specific printers, use the P$SetRawMode subprogram. For more information, refer to Appendix E.

Remove Trailing Blanks

The Remove Trailing Blanks property defines a *Boolean* value that specifies whether trailing blanks will be removed from the Toolbar (see page 3-32) and Menu Bar strings (see page 3-34) before they are sent to the COBOL program's ACCEPT statement for processing. The default value is TRUE.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Remove Trailing Blanks property in order to manipulate the graphical user interface.

Scroll Buffer Size

The Scroll Buffer Size property specifies a *number* that affects the virtual size of the RM/COBOL window. The number of rows initially displayed in the window is determined by the ROWS keyword in the TERM-ATTR configuration record (see page 10-39). The Scroll Buffer Size property determines the number of rows that can be scrolled off the screen using the vertical scroll bar. Setting the Scroll Buffer Size to a non-zero value overrides the Auto Scale property (described on page 3-20) and automatically turns on the vertical scroll bar. The default value is 0.

Show Return Code Dialog

The Show Return Code Dialog property specifies a *Boolean* value that determines whether the Return Code message box (see page 3-44) indicating the program exit code, described on page 7-8, should be displayed when an error occurs. Automated systems, which handle such errors and do not require operator assistance, may wish to suppress the message box and continue processing. The default value is TRUE, which causes the message box to be displayed.

Show Through Borders

The Show Through Borders property specifies a *Boolean* value that determines whether the border of an overlayed pop-up window is shown when overlayed by a pop-up window without a FILL character. When Show Through Borders is set to TRUE, the border is visible. When Show Through Borders is set to FALSE, the border is not visible. The default value is FALSE.

Sizing Priority

The Sizing Priority property specifies whether to make the width or height a priority when auto scaling fonts. If the user resizes the window and auto scaling is on, the system will select a font to match the new size of the window. The new size will be based on the width or height of the window. The default value is WIDTH. (See also the Auto Scale property on page 3-20.)

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Sizing Priority property in order to manipulate the graphical user interface.

Status Bar

The Status Bar property specifies a Boolean value that determines whether the status bar is initially visible. Setting Status Bar to TRUE turns on the status bar. Setting Status Bar to FALSE turns off the status bar. The default value is FALSE.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Status Bar property in order to manipulate the graphical user interface.

Status Bar Text

The Status Bar Text property specifies the initial *string* of text to be placed in the status bar. The default value is an empty string. This text is displayed in the status bar whenever the mouse is in the client area of the window.

Note The C$SBar subprogram (see page F-25) also can be used to display a status bar in the RM/COBOL window.

SYSTEM Window Type

The SYSTEM Window Type property determines the style of the window shown by a program run using the SYSTEM non-COBOL subprogram (see page F-41).

The following values are valid:

Value	Meaning
HIDDEN	The window is not activated and is hidden.
MINIMIZED	The window is activated and is displayed as an icon.
MAXIMIZED	The window is activated and is displayed in its maximized state.
SHOW	The window is activated and is displayed in its current size and position.

Title Text

The Title Text property specifies the *string* of text to be placed in the main window of the COBOL program that is currently running. The default title is "RM/COBOL" if no program name is specified on the **runcobol** command line. Otherwise, it is the initial program name.

Note The C$Title subprogram (see page F-39) also can be used to specify the text to be placed in the RM/COBOL window.

Toolbar

The Toolbar property specifies a *Boolean* value that determines whether the toolbar is visible initially. Setting Toolbar to TRUE turns on the toolbar. Setting Toolbar to FALSE turns off the toolbar. The default value is FALSE.

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Toolbar property in order to manipulate the graphical user interface.

Update Timeout

The Update Timeout property specifies a *number* that represents a delay before a screen refresh occurs. The value of *number* is specified in milliseconds. A larger number causes DISPLAY statements to occur less frequently, potentially improving screen display performance (especially when multiple DISPLAY statements of short records occur in a short period of time). This property may also be used to force DISPLAY statements to occur more frequently. The default value is 500 milliseconds (half of a second).

The C$GUICFG subprogram (see page F-16) can be used to temporarily change the Update Timeout property in order to manipulate the graphical user interface.

Use Windows Colors

The Use Windows Colors property defines a *Boolean* value that specifies whether the standard Windows colors, as set in the Windows Control Panel (Display Properties dialog box, Appearance tab), are used as the RM/COBOL default foreground and background colors. If Use Windows Colors is set to TRUE, the standard Windows colors will be used. If Use Windows Colors is set to FALSE, BLACK will be used for the background and WHITE for the foreground. A value of FALSE allows the same behavior as that found in versions of RM/COBOL prior to 6.0. The default value is TRUE.

Setting Synonym Properties

The Synonyms Properties tab, illustrated in Figure 3-12, allows you to establish synonym *name(s)* and their *values* for the file that was specified using the Select File tab (see page 3-17). The *name* is a string that is the name of a variable placed in the program's environment. The *value* is a string that is the value of *name* in the environment. A synonym can be used to specify the actual file access name for a COBOL program, or to specify other environment variables such as the RMPATH and RUNPATH directory search sequences (see page 3-11).

Figure 3-12 Synonyms Properties Tab



The Synonyms Properties tab contains the following options:

- **Name.** The value entered in this list box is the name of the synonym to which you are assigning a value.
- **Value.** The value in this text box is the value assigned to the synonym selected in the Name list box.
- **Remove.** Use this button to clear the value for the currently selected synonym name and remove it from the list.
- **Remove All.** Use this button to clear all synonym values for the currently selected program.

These synonyms override any environment variables established with the DOS SET command. As a result, these synonyms may be used to establish a connection between the open name of the file, *literal-1* or *data-name-1* (see "Input-Output Section" in Chapter 3, *Environment Division*, of the *RM/COBOL Language Reference Manual* for more information), and the actual file access name.

If either the Load Registry On CALL property or Load Registry On RETURN property (see page 3-22) is set to TRUE, synonyms will be reprocessed whenever a subprogram is called or exited. Synonym assignments are cumulative. For example, if a synonym is assigned for a called subprogram, its value is unchanged when the subprogram exits unless Load Registry On RETURN is set to TRUE and the synonym is defined for the calling program.

Setting Color Properties

The Colors Properties tab, illustrated in Figure 3-13, allows you to control color mapping for the file that was specified using the Select File tab (as described beginning on page 3-17).

Figure 3-13 Colors Properties Tab



The Colors Properties tab contains the following options:

- **Color.** Use this list box to select the color you want to change. The first eight colors in this list box correspond to the *color-names* for the keywords (FCOLOR and BCOLOR) allowed in a CONTROL phrase of an ACCEPT or DISPLAY statement (see page 8-11). These colors are displayed if low intensity is selected. The remaining eight colors correspond to the same *color-names* if high intensity is selected. Note that GRAY is “HIGH BLACK” and YELLOW is “HIGH BROWN.” The current color setting is displayed to the right of each name.

  Note An asterisk (*) after the name indicates that the default color should not be overridden. If the Change button (see the following item) is used to override the default, the overriding color is displayed on the right.

- **Change.** Use this button to display a Color Selection dialog box that allows you to select a color to override the selected color name.

- **Use Default.** Use this button to clear the overriding color for the currently selected color name, thereby using the default color.

Setting Toolbar Properties

The Toolbar Properties tab, illustrated in Figure 3-14, allows you to define the string that is to be sent to the program through the COBOL ACCEPT statement when the corresponding toolbar button is pressed.

The C$TBar subprogram (see page F-37) also can be used to display a toolbar in the RM/COBOL window.

Figure 3-14 Toolbar Properties Tab



The Toolbar Properties tab contains the following options:

- **Name.** The value entered in this text box is the name of the icon stored in the filename specified by the Icon File property (see page 3-21).
- **Prompt.** The value entered in this text box is an optional text string that is displayed whenever the cursor is placed on the toolbar icon that is specified by the icon name.
- **String.** Although the value entered in this text box is an ASCII text string, it also can contain special characters for the Return, Tab, Escape, or Function keys. If the first character is a greater than character (>), the characters that follow are executed as a command. The special characters are described in Table 3-2. (These characters are interpreted by the COBOL ACCEPT statement, as described in Table 8-2 beginning on page 8-6.)

Table 3-2 Special Characters for the Button Character-String

Special Character	Description
>*commandline*	execute *commandline*:
\a	Alt
\b	Backspace
\\	Backslash character
\c	Control
\d	Delete
\e	Escape
\f0	Function key 10
\f1	Function key 1
\f2	Function key 2
\f3	Function key 3
\f4	Function key 4
\f5	Function key 5
\f6	Function key 6
\f7	Function key 7
\f8	Function key 8
\f9	Function key 9
\fa	Function key 10
\fb	Function key 11
\fc	Function key 12
\i	Insert
\n	Newline
\s	Shift
\t	Tab
\x	Exit program
\zb	Begin
\zc	Clear
\zd	Down Arrow
\ze	End
\zh	Home
\zl	Left Arrow
\zn	Next (Page Down)
\zp	Prior (Page Up)
\zr	Right Arrow
\zu	Up Arrow

- **Move Up and Move Down.** Use these buttons to control the order of the buttons shown in the toolbar. This order is determined by the order of the names in the Name list box. When you choose Move Up, the currently selected name moves up one position in the list. Choosing the Move Down button moves the selected name down one position.

- **Remove.** Use this button to clear the value for the currently selected toolbar button name and remove it from the list.

- **Remove All.** Use this button to clear all toolbar button values for the currently selected program.

Setting Menu Bar Properties

The Menu Bar Properties tab, illustrated in Figure 3-15, allows you to identify a list of pulldown menu names and their associated values for the file that was specified using the Select File tab (as described beginning on page 3-17).

The C$MBar subprogram (see page F-17) also can be used to display a menu bar in the RM/COBOL window.

Figure 3-15 Menu Bar Properties Tab



The Menu Bar Properties tab contains the following options:

- **Name.** The value entered in this text box is the string that appears in the menu bar. If the first character is a tilde (~), the name is disabled. An ampersand (&) character causes the next character to be underlined and used as an accelerator.

- **Prompt.** The value entered in this text box is an optional text string that is displayed when the cursor is placed on the menu bar item.

- **String.** The value entered in this text box defines the items in the pulldown menu along with the strings that are returned to the COBOL program when an item is selected. Using the following syntax, it can specify either a value to be returned or additional sub-menu items:

  ```
  pulldownname["prompt"]=menu
  ```

  pulldownname is the string that appears in the menu bar.

  prompt is an optional text string that is displayed on the status bar when the cursor is placed on the menu bar item specified by *pulldownname*.

  menu defines the items in the pulldown menu along with the strings that are returned to the COBOL program when an item is selected. The syntax for *menu* is shown as follows:

  ```
  menu        -> [(]items[)]
  items       -> item name=[string | (menu)][,items]
  item name   -> pulldownname["menu prompt"]
  string      -> string to be sent (see the Toolbar Properties tab)
  ```

  If the first character of *pulldownname* is a ~ (tilde), the *menu* is disabled. An & (ampersand) in *pulldownname* causes the next character to be underlined and used as an accelerator.

- **Move Up and Move Down.** Use these buttons to control the order of the pulldown menu names shown in the menu bar. This order is determined by the order of the names in the Name list box. When you choose Move Up, the currently selected name moves up one position in the list. Choosing the Move Down button moves the selected name down one position.

- **Remove.** Use this button to clear the value for the currently selected pulldown menu name and remove it from the list.

- **Remove All.** Use this button to clear all pulldown menu values for the currently selected program.

Setting Pop-Up Menu Properties

The Pop-up Menu Properties tab, illustrated in Figure 3-16, allows you to identify a list of pop-up menu names and their associated values that will be displayed when right-clicking the mouse button on an RM/COBOL program in the client area of the screen.

The C$RBMenu subprogram (see page F-22) also can be used to display a pop-up menu in the RM/COBOL window when the right mouse button is pressed.

Note If you are using RM/Panels, a pop-up menu defined by RM/Panels will override a pop-up menu defined by setting mouse menu properties.

Figure 3-16 Pop-up Menu Properties Tab



The Pop-up Menu Properties tab contains the following options:

- **Name.** The value entered in this text box is the string that appears in the pop-up menu. If the first character is a tilde (~), the name is disabled. An ampersand (&) causes the next character to be underlined and used as an accelerator.
- **Prompt.** The value entered in this text box is an optional text string that is displayed when the cursor is placed on the pop-up menu item.

- **String.** The value entered in this text box defines the items in the pop-up menu along with the strings that are returned to the COBOL program when an item is selected. It can specify either a value to be returned or additional sub-menu items by using the following syntax:

  ```
  pop-upname["prompt"]=menu
  ```

  pop-upname is the string that appears in the pop-up menu.

  prompt is an optional text string that is displayed on the status bar when the cursor is placed on the pop-up menu item specified by *pop-upname*.

  menu defines the items in the pop-up menu along with the strings that are returned to the COBOL program when an item is selected. The syntax for *menu* is shown as follows:

  ```
  menu        -> [(]items[)]
  items       -> item name=[string | (menu)][,items]
  item name   -> pop-upname["menu prompt"]
  string      -> string to be sent (see the Toolbar Properties tab)
  ```

  If the first character of *pop-upname* is a ~ (tilde), the *menu* is disabled. An & (ampersand) in *pop-upname* causes the next character to be underlined and used as an accelerator.

- **Move Up and Move Down.** Use these buttons to control the order of the names shown in the pop-up menu. This order is determined by the order of the names in the Name list box. When you choose Move Up, the currently selected name moves up one position in the list. Choosing the Move Down button moves the selected name down one position.

- **Remove.** Use this button to clear the value for the currently selected pop-up menu name and remove it from the list.

- **Remove All.** Use this button to clear all pop-up menu values for the currently selected program.

Toolbar Editor

RM/COBOL provides a default toolbar in the file, **rmtbar.vrf**. This toolbar is the default value specified in the Icon File property (see page 3-21). The buttons provided in the default toolbar are documented in Table 3-3. A bitmap editor (**rmtbedit.exe**), provided with your RM/COBOL runtime system, allows you to create or edit the buttons on the toolbar.

Table 3-3 Default rmtbar.vrf File Button Icons

Button	Description
A – Z	Letters A through Z (useful for menu picks)
1 – 20	Numbers 1 through 20 (useful for menu picks)
AF1 – AF12	Alt Function keys 1 through 12
AP	Accounts Payable
AR	Accounts Receivable
BREAK	Hammer smashing object (Break key)
CF1 – CF12	Control Function keys 1 through 12
COMPANION	Two buddies (Companion for RM/COBOL)
DISK	Hard disk drive
DISKETTE	Floppy disk
DOWN	Down Arrow key
END	Curtains closing (End key)
ENTER	Enter key
ESCAPE	Escape key
EXIT	Door with exit sign
F1 – F12	Function keys 1 through 12
FILE	File cabinet
GL	General Ledger
GO	GO sign
GRAPH	Three-dimensional graph (Grafsman)
GREEN	Green traffic light
HELP	Question mark
HOME	Little house (Home key)
INFO	Italic lowercase i
LEFT	Left Arrow key
LINELEFT	Left Arrow key pointing at margin bar (Tab left)
LINERIGHT	Right Arrow key pointing at margin bar (Tab right)
MAIL	Bundle of letters
MENU	Menu

Table 3-3 Default rmtbar.vrf File Button Icons *(Cont.)*

Button	Description
PAGEDOWN	Down Arrow key pointing at margin bar
PAGEUP	Up Arrow key pointing at margin bar
PHONE	Telephone
PR	Payroll
PRINTER	Printer
RED	Red traffic light
REPORT	Text on computer paper
RIGHT	Right Arrow key
SAFE	Archive (Safe)
SEARCH	Flashlight
SF1 – SF12	Shift Function keys 1 through 12
STOP	Stop sign
TERMINAL	Display and keyboard (Data terminal or PC)
UP	Up Arrow key
WRITE	Pencil writing on paper
YELLOW	Yellow traffic light
YIELD	Yield sign

Running the Toolbar Editor

To run the Toolbar editor, choose the Toolbar Editor icon. The application presents you with a menu bar. Under the File menu, you can open a toolbar file or create a new one. (The file created by the Toolbar editor is a resource file that is composed of bitmap buttons, each of which has a name. It is that name that you reference in the Toolbar Properties tab when defining character actions, as described on page 3-32.) A Resource dialog box then displays the bitmap buttons available in the toolbar file.

When the Resource dialog box is active, a Resource menu is available. You can edit, delete, copy, and save the bitmap buttons presented in the Resource dialog box. Opening or creating a bitmap Resource dialog box opens a bitmap editor.

Editing a Bitmap

When you start the bitmap editor, you are in draw mode. When you move the cursor into the editor's grid area, it changes to a pen. You can use the left and right mouse buttons to modify your bitmap. Each button can hold in memory a color that you choose from the color palette. For example, if you click red with the left mouse button and blue with the right mouse button, these colors are stored until you click on another color. By default, when you start the bitmap editor, the left button is black and the right button is gray until you change the color.

In the bottom portion of the color palette, the center square contains the mouse's left button color and the background color is in the mouse's right button color. For example, the color palette in Figure 3-17 shows the center square to be black (indicating that the color stored in the left mouse button is black) and the background is gray (indicating that the color stored in the right mouse button is gray).

Figure 3-17 Color Palette Showing Right and Left Mouse Colors



Buttons are shown in a pair of frames. The first frame represents the up image of the button. The second frame in the sequence represents the down image of the button.

Testing the Bitmap

To test a button, choose the Bitmap->Test Button command from the menu bar.

A dialog box appears that shows the bitmap as a button.

Transferring the Image Up

The bitmap that you create can be duplicated to the down image of the button. Select Bitmap->Transfer Up Image command from the menu bar. At the prompt, choose the Yes button to transfer the image or choose the No button to terminate the transfer.

Importing and Exporting Bitmaps

You may import a bitmap by choosing the Resource->Import command from the menu bar. This command opens the Import Bitmap dialog box. Enter the name of the **.bmp** file you want to import and choose the OK button.

You may export a bitmap by choosing the Resource->Export command from the menu bar. This command opens the Save Bitmap As dialog. Enter the name of the file you want to export and choose the OK button.

Other System Considerations

This section describes special system considerations for using RM/COBOL under the Windows operating system.

Memory Available for a COBOL Run Unit

The memory available for a run unit depends on the configuration of your PC. If the total memory required by a run unit exceeds the amount of available memory, runtime system errors will occur. These errors indicate an inability to obtain enough memory to perform a desired operation. This is unlikely to occur under Windows because Windows 95, Windows 98, and Windows NT provide virtual memory. However, it is still possible to use segmentation and subprograms to manage the dynamic memory requirements of very large run units.

Portable Line Draw Characters

The GRAPHICS keyword of the ACCEPT and/or DISPLAY CONTROL phrase translates the characters described in Table 8-5 on page 8-13 to system-specific line draw characters. Characters that are not listed in this table are output unchanged.

It is not required that the current font contain line draw characters because the runtime system dynamically creates these characters as required.

Blinking Attribute

The blinking attribute (see page 10-24) is not supported in the Windows environment.

Runtime System Screen

Figure 3-18 illustrates a sample screen of an RM/COBOL program running under Windows.

Figure 3-18 Sample Screen of an RM/COBOL Program Running Under Windows



The runtime system screen is a typical Windows operating system window with the following areas:

- **Client area.** Used by the RM/COBOL program input and output.
- **Menu bar.** Configurable by the developer. Menu bar can be different for each program. COBOL programs can also display a menu bar by using the C$MBar subprogram (see page F-17 for more information).
- **Status bar.** Displays prompt text when the user moves the mouse in the client area, through a menu pick or over a toolbar button. It is configurable by the developer. Status bar can be different for each program. COBOL programs can also display text in the status bar by using the C$SBar subprogram (see page F-25 for more information). It can be turned on or off by the user.
- **Control menu button.** Opens the Control menu.

- **Title bar.** Identifies the program name currently running the COBOL program and displays the Minimize, Maximize, and Close buttons. It is configurable by the developer. Title bar can be different for each program. COBOL programs can also display a title by using the C$Title subprogram (see page F-39 for more information).
- **Toolbar.** Configurable by the developer. Toolbar can be different for each program. It can be turned on or off by the user. COBOL programs can also display a toolbar by using the C$TBar subprogram (see page F-37 for more information).
- **Pop-up menu.** Configurable by the developer. Pop-up menu can be different for each program. RM/COBOL programs can also change the contents of a pop-up menu by using the C$RBMenu subprogram (see page F-22 for more information).

Cursor Types

Under default conditions, there are three types of cursors, each of which indicates a different edit mode during ACCEPT operations.

_ The underscore cursor indicates that standard overtype mode is active.

▌ The full-height cursor indicates that you have typed to the end of the field and that the TAB phrase has been specified in the ACCEPT statement. A backspace key or field termination key are the only valid keystrokes in this mode.

▄ The half-height cursor indicates that insert mode is active.

Control Menu Icon

The upper-left corner of the title bar has a button that enables the Control menu (sometimes referred to as System menu). Although the Control menu is standard in the Windows operating system, RM/COBOL for Windows has added functions to this menu. Figure 3-19 illustrates the RM/COBOL for Windows Control menu.

Figure 3-19 RM/COBOL for Windows Control Menu



The Restore, Move, Size, Minimize, Maximize, and Close commands are standard Control menu functions for the Windows operating system. (For more information, see the Microsoft Windows documentation that accompanied the operating system.) The Copy, Copy table, Paste, and Properties commands have been added to the Control menu by RM/COBOL for Windows. Each of these commands is described in the following sections.

Copy

Choosing the Copy command from the Control menu copies the text selected in the client area of the window to the Windows Clipboard. To select text, hold down the mouse button and drag the mouse to the target area. Double-clicking the mouse button selects text in the same manner, as described in the Mark Alphanumeric property (see page 3-23).

Copy table

Choosing the Copy table command from the Control menu copies the text selected in the client area of the window to the Windows Clipboard, and also replaces multiple spaces with a tab. This feature is useful in copying a table of numbers to a spreadsheet, since spreadsheets require that number fields be separated by the tab character.

Paste

Choosing the Paste command from the Control menu copies the text in the Windows Clipboard to the currently running RM/COBOL program through the COBOL ACCEPT statement. If more data is pasted than can be accepted by the ACCEPT command, the data is buffered.

Properties

Choosing the Properties command from the Control menu opens the Properties dialog box, which is illustrated in Figure 3-11 on page 3-19.

Return Code Message Box

When **runcobol.exe** terminates with an exit code other than 0, a Return Code message box appears displaying the status code, as shown in Figure 3-20. (See page 7-8 for more information on program exit codes.) If a COBOL error occurred, that error message is displayed as well. The Show Return Code Dialog property can be used to suppress the display of this message box (see page 3-27).

The message box contains two command buttons. The OK button dismisses the message box and closes the application. The Cancel button dismisses the message box only. The application window remains open until you select the Close option from the Control menu. To close the message box, you can click the Close button in the upper-right corner of the window.

Figure 3-20 Return Code Message Box

CALL "SYSTEM"

When using the SYSTEM non-COBOL subprogram (CALL "SYSTEM") with DOS programs and batch files (see page F-41), you can customize how these programs run by modifying the MS-DOS Prompt properties. This can be done by right-clicking the mouse on the MS-DOS Prompt icon and selecting Properties from the pop-up menu.

Performance

For increased file system performance in single-user mode, set the RUN-FILES-ATTR configuration record option to FORCE-USER-MODE=SINGLE (see page 10-28).

Chapter 4: System Considerations for Btrieve

This chapter describes special considerations for using RM/COBOL to access Btrieve files. Btrieve files are an alternative indexed file format to the RM/COBOL indexed file format. Btrieve files can reside on the local machine, in which case they are accessed via client-based Btrieve, or they can reside on a remote machine, in which case they are accessed via server-based Btrieve. The RM/COBOL-to-Btrieve Adapter program (**rmbtrv32**) provides the communication between the RM/COBOL runtime and Btrieve runtime, translating COBOL requests to Btrieve requests.

RM/COBOL-to-Btrieve Adapter Program (rmbtrv32) Concepts

The RM/COBOL-to-Btrieve Adapter program, **rmbtrv32**, improves performance by providing a mechanism to reduce the overhead required to transmit requests for records in an indexed file across a local area network (LAN).

The goal of the **rmbtrv32** program is to use the local area network for passing general requests to other machines and for receiving completed requests back from the other machines. As a result, significant increases may occur in the performance of the application program, the cost-effectiveness of the local area network, and the productivity of the user.

Note See "RM/COBOL versus Btrieve Indexed File Performance" on page 4-8 for a situation in which the performance of Btrieve index files may not exceed that of RM/COBOL indexed files.

Indexed Files

The application program can request a specific record of information in an indexed file. The location of the specified record within the indexed file is determined by means of an identifier known as a key. Indexed files use a much more efficient method of locating the record than simply searching through all the records in the file until the requested record is found. Instead, indexed files build overhead tables into the file that are similar to indexes in a book. These overhead tables enable the indexed files to quickly look up the

desired location and then read the desired data. Figure 4-1 illustrates this process on a single-user system.

Note In Figure 4-1, Figure 4-2, and Figure 4-3, each line represents a separate event that happens at a separate time. The lighter lines represent a small transfer of information, and the heavier lines represent a large transfer.

Figure 4-1 Indexed File Requests on a Single-User System



When this process happens over a network, the situation is very similar, as shown in Figure 4-2.

Figure 4-2 Indexed File Requests on a Local Area Network



In Figure 4-2, Computer 2 acts as a conduit, called a server, through which the requests of Computer 1, called a client, are routed. (The server routes requests for more than one client computer, which is an advantage of local area networks.) A more effective way to route requests, however, is shown in Figure 4-3.

Figure 4-3 Indexed File Requests on a Local Area Network by the Btrieve MicroKernel Database Engine (MKDE)



Figure 4-3 illustrates the way in which a Btrieve requester (running on the client, Computer 1) and a Btrieve MicroKernel Database Engine (running on the server, Computer 2), makes the processing of messages even more efficient. (Note that the Btrieve MicroKernel Database Engine is a key external component of the **rmbtrv32** program.) Although the interactions between Computer 2 and the disk drive are exactly the same as shown in Figure 4-2, the interactions between Computer 1 and Computer 2 are significantly different. Instead of Computer 1 giving Computer 2 many small instructions to carry out, Computer 1 now gives Computer 2 a single, general request. Computer 2 searches the overhead table for the indexed files to locate the desired record and then returns only the requested record.

There are several advantages to this method, but the following two are the most significant:

1. The overall operation may be quicker because the number of transfers between the two computers is reduced.

2. Because there are fewer transfers between the Computer 1 and Computer 2, the local area network can use the time that it is not performing transfers between the two computers to make transfers between other computers on the network. It allows the network to handle more computers, which makes it more cost effective.

Required Software Components

The following components, described in the following sections, are required when using RM/COBOL to access Btrieve files:

- Novell NetWare version 3.11 or later
- Btrieve MicroKernel Database Engine (MKDE) for NetWare Server, version 6.15 or later
- Btrieve Requester for Windows 95/Windows 98/Windows NT
- RM/COBOL compiler (development system) for Windows
- RM/COBOL runtime system for Windows
- RM/COBOL-to-Btrieve Adapter program (**rmbtrv32**) for Windows

Note NetWare products are available from Novell, Incorporated. Btrieve products are available from Pervasive Software, Inc. (formerly Btrieve Technologies, Inc.).

Novell NetWare

NetWare is the software that communicates between computers on the local area network. These NetWare products are responsible for handling the actual hardware connections, recovering from transmission errors detected by the hardware, and routing the messages from one program executing on one computer to another program executing on another computer.

NetWare augments the operating system by providing access to files on file servers.

Btrieve MicroKernel Database Engine (MKDE)

The MKDE component consists of two types. The first type, a client-based Btrieve MKDE, provides access to files that are located on the same machine as the application program. The second type, NetWare Btrieve MKDE, provides access to files that are located on a remote machine in a multiuser environment.

The NetWare Btrieve MKDE is a record management system similar to the indexed files built into the RM/COBOL runtime system. Because the NetWare Btrieve MKDE is not built into the RM/COBOL runtime system, it can run on a separate computer using NetWare, thus providing access to files in the manner illustrated in Figure 4-3 (see page 4-3).

There are also versions of the Btrieve MKDE that run on other types of networks and on a single machine (client-based Btrieve MKDE), without network support. The client-based Btrieve MKDE, however, no longer has the speed advantage over the RM/COBOL file management system, since both systems have the same access to the disk drive.

Btrieve Requester for Windows NT, Windows 98, and Windows 95

The Windows NT, Windows 98, or Windows 95 requester, a dynamic link library (DLL) program, runs on the client computer and communicates with either the server-based or the client-based Btrieve MKDE.

RM/COBOL Compiler for Windows

The RM/COBOL compiler (development system) is a GSA-certified high implementation of the American National Standard COBOL X3.23-1985 with extensions and support for most optional features of the language.

RM/COBOL Runtime System for Windows

The RM/COBOL runtime system executes the application program and carries out its instructions. The runtime system has an internal file management system that accepts input from the user, processes data, produces data in the form of output to the user, and, most importantly, generates requests for records to be written to and read from files.

The runtime system has been designed so that any existing RM/COBOL application may be run in many different environments without changes either to the source of the program or to the actual executable object. Furthermore, any existing RM/COBOL runtime system that executes on Windows can also use the RM/COBOL-to-Btrieve Adapter (**rmbtrv32**) program.

RM/COBOL-to-Btrieve Adapter (rmbtrv32) Program for Windows

The **rmbtrv32** program acts as an interpreter between either of the two types of Btrieve MKDEs (described on page 4-4) and COBOL application programs. In order to understand how this transparent interface is achieved, it is necessary to briefly describe the different ways in which the Btrieve MKDE and the COBOL language provide access to indexed files.

The Btrieve MKDE lets an application program access records stored in indexed files, and provides the necessary functions for storing, retrieving, and updating the information.

The Btrieve MKDE's method of accessing indexed files is an efficient system that provides significant increases in functionality to the user in certain cases. However, because the Btrieve MKDE does not use COBOL language features that provide access to indexed files, a COBOL application program cannot communicate directly with the Btrieve MKDE.

A COBOL application program uses American National Standard COBOL 1985 language features, such as OPEN, READ, WRITE, REWRITE, and CLOSE, to access indexed files. The RM/COBOL runtime system contains a file management system that provides the runtime system with support for these features. The RM/COBOL runtime system communicates with the file management system by means of requests and responses that are called messages. These messages are processed outside of the file management system by any one of a variety of external file access methods.

The **rmbtrv32** program, in effect, is one such external file access method for the RM/COBOL runtime system. **rmbtrv32** receives messages from the RM/COBOL file management system. Then, acting as an application program for the Btrieve MKDE, **rmbtrv32** translates the messages into Btrieve requests, enabling the Btrieve MKDE to carry out the action originally requested by the COBOL application program. The Btrieve MKDE performs the action either on the user's computer system or acts with NetWare on a remote system using the local area network. (The drive letter in the pathname of the file indicates the machine on which the file resides.) After the Btrieve MKDE has completed the requests, **rmbtrv32** constructs an appropriate response message, which is sent to the RM/COBOL file management system, and, finally, back to the COBOL application program. Figure 4-4 illustrates this process.

Figure 4-4 RM/COBOL-to-Btrieve Adapter Program (rmbtrv32) Acting as an External File Access Method



See page 4-9 for the RM/COBOL-to-Btrieve Adapter program (**rmbtrv32**) options.

Configuration for Btrieve

The installation and configuration of client-based Btrieve (also called Workstation Btrieve) for Windows 95, Windows 98, and Windows NT are fully described in the *Btrieve for Windows NT/Windows 95/Windows 98 Installation and Operation* manual supplied by Pervasive Software with your Btrieve system. The client-based Btrieve is the MicroKernel Database Engine (MKDE) that is used to access local files (that is, Btrieve files residing on the computer where the RM/COBOL runtime system is run). A number of configuration settings can be modified using the Btrieve Setup utility. After configuring Btrieve, use the Btrieve File Manager utility (or other Btrieve software) to verify that Btrieve is working properly before using Btrieve with RM/COBOL.

Similarly, the installation and configuration of server-based Btrieve (for NetWare or for the Windows NT Server) are fully described in the *Btrieve for NetWare Installation and Operation* manual or the *Btrieve for Windows NT Server Edition Installation and Operation* manual, whichever is appropriate, that was supplied by Pervasive Software with your Btrieve system. These manuals also describe the installation and configuration of the requesters used to communicate with server-based Btrieve. The server-based Btrieve is the MKDE that is used to access remote files (that is, Btrieve files residing on the NetWare or Windows NT Server computer). A number of configuration settings for both the MKDE and the requesters can be modified by using the appropriate Btrieve Setup utility.

The *Btrieve Programmer's Guide*, supplied by Pervasive Software with your Btrieve Developer Kit, is an excellent source of information for help in setting the Btrieve configuration options properly. In addition, several books on Btrieve are available commercially, and the *Btrieve Developer's Journal* is published quarterly by Smithware, Inc.

System Considerations for Btrieve Files

The RM/COBOL-to-Btrieve Adapter program (**rmbtrv32**) creates Btrieve files when necessary or if requested. Btrieve files created by **rmbtrv32** have a computed page size based on one of the following methods that produces the largest value:

1. The size of the block requested by the COBOL application.

2. The size necessary for the length of the longest key, times eight.

3. The size of the largest record requested by the application, plus eight times the number of linked duplicate keys, plus six (for overhead information), plus four if the file specifies variable-length records (again for overhead information). See "Variable-Length Records" on page 4-23 for more information.

Furthermore, if the record size is greater than the maximum page size and the keys of the file all fit into that maximum, the **rmbtrv32** program creates a variable-length file. (The Btrieve MKDE restricts the fixed-length part of records to less than the page size.)

Finally, **rmbtrv32** creates the file with the following characteristics:

- Data compression
- Blank truncation
- Five-percent, free-space threshold
- No page preallocation

To create Btrieve files with characteristics other than those previously listed, use the Btrieve File Manager utility, the filename, and the Btrieve description-file that contains the characteristics for the new file. For more information, see the chapter about using the File Manager utility in the appropriate Btrieve installation and operation manual. Characteristics established using the Btrieve File Manager utility can have a direct impact on performance, including the following:

- The page preallocation value can be used to reserve pages for use by the file. This has the advantage of ensuring, in advance, that the file has the disk space it needs. It can also improve performance by concentrating the location of the file on the disk media (assuming that the disk space is not already fragmented).
- The free-space threshold value can be set to 10, 20, or 30 percent to allow for growth of variable-length records.
- Keys can be created that are binary or have any of the extended key types.
- Null keys can be created.
- More keys can be defined than can be used by the COBOL program. These keys must be defined either at starting locations that are different from the COBOL keys or after the COBOL key description for the same location. Such keys can have any Btrieve attribute and can be split.

RM/COBOL versus Btrieve Indexed File Performance

In general, when used across the network, Btrieve indexed files have better performance than RM/COBOL indexed files because less network activity has to occur to access a record.

However, there is a case in which this may not be true. When a COBOL program opens an indexed file WITH LOCK, the COBOL program then has exclusive access to that file.

This has an important consequence for RM/COBOL indexed files. In this case, the RM/COBOL runtime system knows that no other user is able to change the indexed file overhead tables on the server, and it keeps the overhead tables on the local machine. This results in fewer requests across the network for the overhead tables and may result in better performance than the same program using Btrieve indexed files.

This effect is most pronounced when the indexed file is being read sequentially (for example, producing a report).

RM/COBOL-to-Btrieve Adapter Program (rmbtrv32) Options

The **rmbtrv32** program has options that are specified on the EXTERNAL-ACCESS-METHOD or on the RUN-INDEX-FILES configuration record in the RM/COBOL configuration file. (See pages 10-20 and 10-31, respectively.) These configuration file options, described in the following sections, give **rmbtrv32** information that the Btrieve MKDE requires, but which is not contained in RM/COBOL file management system messages.

Note Typically when configuring the Btrieve MKDE, it is often sufficient to specify only the "Largest Compressed Record Size" Btrieve configuration option if you are using compression (see the appropriate Btrieve installation and operation manual for more details).

EXTERNAL-ACCESS-METHOD Configuration Record Options

Most of the information that the **rmbtrv32** program needs to operate can be obtained through requests received from the RM/COBOL file management system. However, when **rmbtrv32** needs information required by the Btrieve MKDE, which the RM/COBOL file management system cannot supply, it is possible to provide this information directly to **rmbtrv32** with the following options in the EXTERNAL-ACCESS-METHOD configuration record:

- B (**rmbtrv32** Btrieve MKDE page size option)
- Create option
- D (Duplicates option)
- I (Initial display option)
- L (Lock option)

- M (Mode option)
- O (Owner option)
- P (**rmbtrv32** page size option)
- T (Diagnostic trace filename)

These options are described in the following sections.

Note The create option is specified by the CREATE-FILES keyword in the EXTERNAL-ACCESS-METHOD configuration record. The other options (B, D, I, L, M, O, P, and T) are specified by the OPTIONS keyword in the EXTERNAL-ACCESS-METHOD configuration record. (For more information, see page 10-20.)

B (rmbtrv32 Btrieve MKDE Page Size Option)

This option is obsolete and should not be specified. The "Maximum Page Size" is no longer a configurable parameter of the Btrieve engine, which always assumes the Btrieve limit of 4096 bytes. If this value is inadvertently specified as an amount smaller than 4096, **rmbtrv32** may create a Btrieve file with variable-length records when such records would not be needed.

Create Option

The create option, for creating a new file, has the following values:

- Yes Create new files as Btrieve indexed files (the default).
- No Do not create new files.

See the description of the CREATE-FILES keyword in the EXTERNAL-ACCESS-METHOD configuration record on page 10-20.

The create option is the determinant parameter supplied to the **rmbtrv32** program, because it determines the system that will be responsible for creating a new indexed file. Depending on the value specified in this parameter, the new file can be created by **rmbtrv32**, by another external file access method, or by the RM/COBOL file management system. In order to understand how this process works, it is helpful to know more about the way in which the RM/COBOL file management system searches for a file.

Before an application program creates a file, the RM/COBOL file management system first tries to locate an existing file having the same name as the one specified in the create attempt. The file management system searches the current directory first, and then all the other directories located in the environment variable, RUNPATH. (See

"Directory Search Sequences" on page 3-11 for more information on setting the RUNPATH variable.)

In addition to the **rmbtrv32** program, other external file access methods can be running on the computer or network at the same time. In searching for a file, the RM/COBOL file management system also communicates with all other known external file access methods.

The search for the filename occurs in the following sequence:

1. Any external file access methods currently running (including **rmbtrv32**) search the current directory.
2. The RM/COBOL file management system searches the current directory.
3. The external file access methods search the first directory in the RUNPATH list.
4. The RM/COBOL file management system searches the first directory in the RUNPATH list.

The search continues until all pertinent directories have been checked. If a file having the same name as the one specified in the create attempt is found, it will be opened. If such a file cannot be found, and the application program wants to create one, then a designated external file access method can create the file.

The **rmbtrv32** program create option value is a yes or no indicator that specifies whether you want **rmbtrv32** to create any new indexed files as Btrieve files. Regardless of the value specified, any new file is created in the first directory possible, usually the current directory. Valid values are Yes and No. The default value is Yes.

A value of Yes causes any new indexed files to be created as Btrieve files:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 CREATE-FILES=YES
```

A value of No causes **rmbtrv32** not to create the file and enables another external file access method or the RM/COBOL file management system to create new indexed files:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 CREATE-FILES=NO
```

D (Duplicates Option)

The duplicates option is used to specify whether linked or repeating duplicatable keys are used for files created by **rmbtrv32**.

The duplicates option has the following values:

- L Create linked duplicatable keys. Linked duplicates mean that only one copy of the duplicated key value is stored in index pages. The data records with the duplicated key value are linked together with pointers in a doubly-linked list.

- R Create repeating duplicatable keys. Repeating duplicates mean that the duplicated key value is repeated in the index pages for each data record with that value. The data records are not linked together. Using repeating duplicates uses more space in index pages, but saves space in data pages and also helps avoid position lost errors when files are shared.

The default value is L. Refer to the *Btrieve Programmer's Guide* for more information.

The following example tells **rmbtrv32** to create files with repeating duplicatable keys:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='D=R'
```

I (Initial Display Option)

The initial display option is used to specify whether or not **rmbtrv32** should display an initial message box when it is first invoked.

The initial display option has the following values:

- Y (Yes) Display the message box. The message box shows the **rmbtrv32** version number and the OPTIONS parameter string that was passed to it from the EXTERNAL-ACCESS-METHOD configuration record. The user must click the OK button to acknowledge and continue. This option is most useful the first time the user attempts to use **rmbtrv32** with RM/COBOL and Btrieve.

  Note I=Y should not be used in a production environment.

- N (No) Do not display the message box.

The default value is N.

Example

The following example tells **rmbtrv32** to display the informative message box:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='I=Y'
```

L (Lock Option)

The lock option is used to specify the manner in which the **rmbtrv32** program is to handle the WITH LOCK phrase on OPEN statements.

The lock option has the following values:

- I Ignore the WITH LOCK phrase. Use the Btrieve MKDE open mode indicated with the M option (see page 4-14).
- D Deny the WITH LOCK phrase.
- A Accept the WITH LOCK phrase. If OPEN WITH LOCK is requested by the application, ignore the open mode indicated with the M (mode) option described on page 4-14.

The default value is A.

Examples

The following example tells **rmbtrv32** to ignore the WITH LOCK phrase on OPEN statements:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='L=I'
```

The following example tells **rmbtrv32** to deny the WITH LOCK phrase on OPEN statements:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='L=D'
```

The following example tells **rmbtrv32** to accept the WITH LOCK phrase on OPEN statements:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='L=A'
```

M (Mode Option)

The mode option is used to specify a value to **rmbtrv32** at the time a Btrieve file is opened. The following values are used only if the file is not OPENed WITH LOCK. See the L (lock) option, described previously. The mode option has the following values:

- N Normal
- A Accelerated
- R Read-only
- V Verify
- E Exclusive

The default value is N.

Note The ability of **rmbtrv32** to specify a mode value is dependent on whether the application program requests the WITH LOCK phrase on OPEN statements. See the lock option on page 4-13 for more information.

Examples

In normal mode, the Btrieve MKDE behaves as it normally does with its recovery option enabled, allowing update requests and performing normal writes to the disk drive. The following example specifies a value of normal when the file is opened:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='M=N'
```

In accelerated mode, the data recovery capability of the Btrieve MKDE is disabled to increase the speed at which records are updated. The following example specifies a value of accelerated when the file is opened:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='M=A'
```

In read-only mode, no updates can be performed. The following example specifies a value of read-only when the file is opened:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='M=R'
```

Verify mode is now disregarded and the MKDE assumes normal mode instead.

In exclusive mode, the user has exclusive access to the file until the user closes it. This is the same as specifying EXCLUSIVE or WITH LOCK on the OPEN statement in the COBOL program.

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='M=E'
```

O (Owner Option)

The owner option specifies the "owner" ID (actually a security password) for new files and open requests for existing files. The value is a string of up to a maximum of eight characters delimited by a trailing space. The value cannot contain spaces. The following example specifies an owner ID of YELLOW:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='O=YELLOW'
```

P (rmbtrv32 Page Size Option)

The **rmbtrv32** page size option is the default minimum page size for the files created by **rmbtrv32**. Btrieve files are physically accessed in fixed-length pieces called pages. When **rmbtrv32** creates a new file, the Btrieve MKDE requires the specification of a page size. The size of a page is determined from either the page size option or a computation based on the size of the record. See "Variable-Length Records" on page 4-23 for more information. A larger page size transfers more data in a single disk request, requires more time to transfer, and requires more memory to contain the pages. A smaller page size allows more blocks in memory for a fixed amount of memory, but requires more time to randomly access a record by increasing the tree depth of each index for the file.

If specified, the value must be a multiple of 512 in the range of 512 to 4096, inclusive. When creating a file, the page size used will be the smallest multiple of 512 sufficient to hold the file overhead, eight keys, the fixed part of the record, or, if specified, the default page size, whichever is greater.

The following example sets the value of the page size option to 1024:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='P=1024'
```

T (Diagnostic Trace Filename Option)

This option is used to specify the pathname of a file to which **rmbtrv32** will write a trace of open requests. This feature is used when there is a problem with a Btrieve file not being successfully opened by a COBOL program. It is not to be used in a production environment, because it degrades performance and the trace file can become quite large, which might exhaust disk space. To turn on the trace feature, edit the RM/COBOL configuration file for the COBOL program in question and add a T=*trace-file-name* parameter to the OPTIONS keyword in the EXTERNAL-ACCESS-METHOD configuration record (see page 10-20). For example, the following record writes trace information to the file **c:\test\trace.fil**:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32 OPTIONS='T=C:\test\trace.fil'
```

The trace file contains a “Begin open” and “End open” pair of records for every open request that **rmbtrv32** receives. This includes all opens that **runcobol** does for files, such as its message file and the COBOL program file, as well as every OPEN statement executed by the COBOL program. The “End open” line shows the COBOL status code returned to the RM/COBOL file management system. Between the “Begin” and “End” lines, zero or more “BTRV Create” or “BTRV Open” lines show the full pathname of the file, the exact Btrieve status code returned by the name of the file, and the exact Btrieve status code returned by the Windows Btrieve DLLs. The following is a sample trace file:

```
Trace Initialized
Begin open, Not indexed
End open, Code=35
Begin open, Not indexed
End open, Code=35
Begin open, Not indexed
End open, Code=35
Begin open, Flags=0x4900 (file must exist)
 UFN=INX1
  BTRV Open status 0 on file C:\TEST\INX1
End open, Code=0
Begin open, Flags=0xe100 (file must exist)
 UFN=INX2
  BTRV Open status 12 on file C:\TEST\INX2
End open, Code=35
Begin open, Flags=0xe000
 UFN=INX2
  BTRV Open status 12 on file C:\TEST\INX2
  BTRV Create status 0 on file C:\TEST\INX2
End open, Code=0
```

When you are finished diagnosing the problem, be sure to edit the configuration file again and remove the T=*trace-file-name* parameter from the OPTIONS keyword in the EXTERNAL-ACCESS-METHOD configuration record.

RUN-INDEX-FILES Configuration Record Options

In addition to the options specified on the EXTERNAL-ACCESS-METHOD, two RUN-INDEX-FILES keywords have meaning for **rmbtrv32**: DATA-COMPRESSION and BLOCK-SIZE. (For more information, see page 10-31.)

Specifying DATA-COMPRESSION=NO causes **rmbtrv32** to create uncompressed Btrieve files. The default is to create compressed Btrieve files. (Note that Btrieve does not support key compression.)

Specifying BLOCK-SIZE=*nnnn* causes **rmbtrv32** to create files with a page size of *nnnn*. **rmbtrv32** first computes the minimum allowable page size for the file based on the record size, number of key segments, type of duplicates, and so forth. It then uses the first value greater than or equal to the computed minimum value in the following order:

1. From the BLOCK CONTAINS clause in the program's file description entry.
2. From the P=<page size> option parameter on the OPTIONS keyword in the EXTERNAL-ACCESS-METHOD record (see page 10-20).
3. From the RUN-INDEX-FILES BLOCK-SIZE=<size> configuration record.

If none of these three values is present or acceptable, **rmbtrv32** uses the computed minimum value.

Example

The following example represents a typical command line invoking **runcobol** using **rmbtrv32**:

```
runcobol userprog x=config.cfg
```

where the **config.cfg** file contains the following records:

```
RUN-INDEX-FILES DATA-COMPRESSION=NO
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32
& CREATE-FILES=YES
& OPTIONS='P=1024, D=R, O=XyZzY'
```

The ampersand (&), which begins the third and fourth lines in this example, is the configuration file record continuation character. Note that different RM/COBOL applications can specify different **rmbtrv32** option parameters by using different RM/COBOL configuration files.

Starting the RM/COBOL-to-Btrieve Adapter Program (rmbtrv32) for Windows

The RM/COBOL-to-Btrieve Adapter (**rmbtrv32**) program and either the client-based Btrieve MKDE or the Windows 95/Windows 98/Windows NT Btrieve requester programs are all started automatically. This process is initiated by the user placing the following configuration record in the RM/COBOL configuration file and starting the RM/COBOL runtime system:

```
EXTERNAL-ACCESS-METHOD NAME=RMBTRV32
```

The only requirement is that Windows must be able to locate the various executable files that are required.

Note The server-based Btrieve MKDE (running on a NetWare server or on a Windows NT Server) must be started separately. Refer to the appropriate Btrieve installation and operation manual for information on starting server-based Btrieve.

The **rmbtrv32** program, **rmbtrv32.dll**, is a dynamic link library (DLL) that can be loaded by the Windows 95, Windows 98, and Windows NT version of RM/COBOL. **rmbtrv32.dll** communicates directly with **wbtrv32.dll**, which is the Btrieve interface DLL supplied with your Btrieve system. The **wbtrv32.dll** file is normally installed, along with a number of other DLL, EXE, and other Btrieve files, in a separate Btrieve executable subdirectory.

Since RM/COBOL and Btrieve are separate products supplied by separate vendors, the executable files required by each are normally installed in the separate directory structures. Therefore, the recommended way of ensuring that Windows can locate the files is to place the directory names containing the files into the Windows PATH environment variable. For RM/COBOL, this is the directory containing **rmbtrv32.dll** (and also containing **runcobol.exe**, and so forth). For Btrieve, this is the directory containing **wbtrv32.dll** (and other DLLs and EXEs). Add these two directory names to your Windows PATH (which is often done in the **autoexec.bat** file).

Although it is not the recommended method, Windows will find the executable files if they reside in any combination of the following:

1. The directory that contains the **runcobol.exe** that is started.
2. The current directory.
3. The Windows system directory (normally **c:\windows\system**).

4. The main Windows directory (normally **c:\windows**).

5. Any directory in the PATH environment variable

Note Both the Btrieve MKDEs and **rmbtrv32.dll** have keywords that can be passed to them when they are started. If no parameters are specified, the programs use default values.

For information on specifying keywords in the EXTERNAL-ACCESS-METHOD configuration record, see page 10-20. For more information on **rmbtrv32** options, see page 4-9.

The **rmbtrv32** program, the Windows 95/Windows 98/Windows NT Btrieve requester, and the client-based Btrieve MKDE all terminate automatically when the final RM/COBOL runtime system using them terminates. Server-based Btrieve (running on a NetWare or Windows NT Server) must be terminated separately; however, server-based Btrieve normally remains running as long as the server computer remains running.

RM/COBOL Indexed Files and Btrieve MicroKernel Database Engine (MKDE) Limitations

This section describes the limitations of the Btrieve MicroKernel Database Engine (MKDE), and the way in which these limitations affect RM/COBOL indexed files. Although these two systems perform the same functions, they do not operate in the same manner.

Note For more information on the RM/COBOL limits and ranges, see Appendix B, *Limits and Ranges*.

Current Record Position Limitations

A COBOL application program can sequentially read through all the records in an indexed file. The manner in which a requested record is presented to the application program for the READ operation varies, depending on how the file was created. The Btrieve MicroKernel Database Engine (MKDE) behaves according to ANSI COBOL 1985 for simple READ statements.

However, for READ NEXT statements, the behavior of the Btrieve MKDE can vary from ANSI COBOL 1985. According to ANSI COBOL 1985, the determination of the next record to be read is not affected by subsequent non-READ operations. As long as the

COBOL application program does not perform any non-READ operations to the indexed file, the Btrieve MKDE behaves according to ANSI COBOL 1985. If non-READ operations are performed to the file, however, the Btrieve MKDE defines the next record as being the one after the non-READ operation.

The RM/COBOL-to-Btrieve Adapter program, **rmbtrv32**, compensates for this variation by remembering the location of the record that was last read, and the surrounding records, in order to set the position indicator back to the correct place following the non-READ operation. This compensation works completely when a single-user is accessing the file, but can fail in a shared file environment.

In a Btrieve shared file environment, **rmbtrv32** can become lost when reading records via a key containing duplicate key values. If the COBOL application program performs a non-READ operation between a READ and a READ NEXT statement, and an application program running on the same or another computer deletes the current record and the records around it (and all these records contain duplicate key values), then **rmbtrv32** becomes lost and returns an error message 46,02 to the application program (see page A-20 for more information).

This position-lost problem can be avoided when the shared Btrieve file is accessed via a version 6.1 or later Btrieve MKDE. **rmbtrv32** sets the new No Currency Change (NCC) option on Insert and Update operations so that Btrieve will not change the current record position. In addition, the user can specify the use of repeating duplicatable keys (see the D (Duplicates Option) on page 4-11 of this guide and the discussion of Linked versus Repeating Duplicatable keys in the *Btrieve Programmer's Guide*). Using both of these features avoids the position lost problem and retrieves the correct record.

File Position Indicator Limitations

The file position indicator specifies the next record to access within a file during certain sequences of input-output operations.

If the COBOL program executes a START LESS THAN statement and there are multiple records in the file that contain duplicate keys (for example, multiple records having the same key value that satisfy the START LESS THAN condition), then the file position indicator will be positioned to the last record in the sequence of duplicate key values. The same result occurs if you execute a START LESS THAN OR EQUAL statement where the equal condition is not met.

If no new records containing duplicates for a key value are added to the file, then **rmbtrv32** behaves identically to the RM/COBOL file management system for the succeeding READ NEXT or READ PREVIOUS statements. The RM/COBOL file management system does not move the file position indicator from the record originally

located by the START statement. This position is the record returned for succeeding READ NEXT or READ PREVIOUS statements.

The Btrieve MKDE does not allow **rmbtrv32** to emulate this behavior if new records are added that contain duplicates for a key value. **rmbtrv32** moves the file position indicator to the last record added at the time of the succeeding READ NEXT or READ PREVIOUS statement.

Note Once the READ statement has been executed, the position is known, and the RM/COBOL file management system and the Btrieve MKDE again behave the same.

Permission Error Detection Limitations

When you attempt to open an RM/COBOL indexed file and **rmbtrv32** is active, **rmbtrv32** may open the file before the RM/COBOL file management system opens the file. If the indexed file is already opened by the RM/COBOL file management system on another computer, the Btrieve MKDE returns a Permission Error to **rmbtrv32** instead of a Not a Btrieve File error. **rmbtrv32** assumes that the file is an already-opened RM/COBOL indexed file and reports an Invalid Organization error to the file management system, which then attempts to open the file. If the file is an RM/COBOL indexed file, the open succeeds. If the problem was one with permissions, then the RM/COBOL file management system encounters it also and returns the correct error code.

Using Existing Btrieve Files with RM/COBOL

RM/COBOL and ANSI COBOL 1985 define some limitations on indexed files that are not imposed by the Btrieve MKDE.

rmbtrv32 creates new Btrieve files that are compatible with the COBOL concept of indexed files. Existing Btrieve files can be used also, providing they have the following characteristics:

- The primary key cannot have a null value.
- Alternate keys can be modified, can use either the native or alternate collating sequence (ACS), can be binary, and can have a null value.
- Keys cannot have the following Btrieve key flags: descending, supplemental, and any-segment null. Keys must use ACS number zero, if any.

- Keys do not have to be created in the file in any particular order. However, within the file, there must be at least one key residing at the correct position for each COBOL key. That key must be of the correct length, contain the correct duplicates flag, and cannot contain any of the restrictions on keys as described above. Furthermore, this key must be defined within the Btrieve file before any other keys that start at the same position. Subsequent keys may have forbidden characteristics.

- There can be more keys in the Btrieve file than in the COBOL description and they can have characteristics that are not legal for COBOL keys. However, they must either have a starting position that does not match the starting position for any COBOL key, or they must occur in the Btrieve definition after the COBOL key description for that position.

- Within the record there should not be any multiple-byte integer data fields. **rmbtrv32** will not reject any files with fields of this type. Because of byte ordering, however, there are no COBOL data types that can directly manipulate the integer data in the field.

If an OPEN OUTPUT is performed on an existing Btrieve file, all characteristics of the original file are preserved. This includes any compression (or lack of it) and any extra keys. The file is simply made empty.

Btrieve MicroKernel Database Engine (MKDE) Limitations Affecting RM/COBOL Applications

The Btrieve MKDE has limitations that may affect existing COBOL applications:

- Version 5 Btrieve files have a maximum record size of 55296 bytes. Version 6 Btrieve files support record sizes of 64 KB or more using "chunk" operations. **rmbtrv32** does not use any Btrieve "chunk" operations; therefore, the maximum record size is limited by the communication environment in which Btrieve runs. When accessing server-based Btrieve (remote files), the maximum record size is 57000 bytes. When accessing client-based Btrieve (local files), the maximum record size is 64512 bytes. The largest possible record size without using variable-length records is 4088 bytes. RM/COBOL files have a maximum record size of 65280 bytes.

- Btrieve files have a minimum record length of four bytes. RM/COBOL files have a minimum record length of one byte. **rmbtrv32** supports files whose record size is less than four bytes by using a zero-filled, four-byte record.

- Btrieve files must have all keys located within the first 4096 bytes of a record. RM/COBOL files may have keys located anywhere within the record.

- Btrieve files have a limit of 119 key segments. RM/COBOL files have a limit of 255 key segments.
- Btrieve files have a maximum key size of 255 bytes. The RM/COBOL runtime system (including **rmbtrv32**), however, supports a maximum key size of 254 bytes.

Variable-Length Records

RM/COBOL will support variable-length records using the Btrieve MKDE's variable-length record files. The size of the Btrieve data page will be either the minimum record length or the maximum Btrieve MKDE page size, whichever is smaller.

For more details, refer to the discussion of variable-length records, logical and physical record lengths, and page sizes in the *Btrieve Programmer's Guide*.

Key Placement

The Btrieve MKDE restricts placement of keys within the first data page of a record. If a file has variable-length records, the keys must fit within the minimum record length of the file or the maximum Btrieve MKDE page size, whichever is smaller.

Automatic Creation of Variable-Length Record Files

If a COBOL program creates a file with a record size greater than the maximum Btrieve page size, and the keys of that file fit within the maximum Btrieve page size, then the file will be created with a record size equal to the maximum Btrieve page size, with the remainder of the record in the variable-length portion of the Btrieve record. (The Btrieve MKDE allows the portion of the record past the fixed length to be considerably longer.)

Verification of Maximum Record and Block Length

Btrieve files do not have a mechanism for storing the maximum record length and maximum block length for a file. If a Btrieve file is opened with a maximum length for its RECORD CONTAINS or BLOCK CONTAINS clause that does not match the maximum length at the time the file was created, the mismatch will not be detected.

Support for RM/COBOL Internal Data Formats

The Btrieve MKDE internally stores integers in Intel binary integer format, with the most significant byte at the highest address and the least significant byte at the lowest address. Therefore, applications that access Btrieve files written outside of RM/COBOL cannot directly access the following three RM/COBOL internal data formats since they store

numbers in the opposite manner (as binary integers with the most significant byte at the lowest address and the least significant byte at the highest address):

- BINARY data
- COMPUTATIONAL-1 data
- COMPUTATIONAL-4 data

For more information about RM/COBOL internal data formats, refer to Appendix C, *Internal Data Formats*.

Support for Btrieve Internal Data Formats

RM/COBOL programs can directly access the following Btrieve internal data formats:

- Decimal
- Money
- Numeric Signed ASCII
- Numeric Signed Trailing Separate
- String

All other Btrieve internal data formats can be interpreted by an RM/COBOL program on a byte-by-byte basis. For more information about Btrieve internal data formats, refer to "Extended Key Types" in the *Btrieve Programmer's Guide*.

Input/Output Errors

Input/output errors that you would expect to occur for an RM/COBOL indexed file may not occur for a Btrieve file. Because of its file structure and organization, information in Btrieve files is stored differently than in RM/COBOL indexed files, or it is not recorded at all. Thus, the RM/COBOL runtime system is unable to check or verify certain values in these files.

For example, the error message 39,01, which normally occurs if an error is encountered when the runtime system is trying to open an RM/COBOL indexed file, may not occur if the file is a Btrieve file. Appendix A, *Runtime Messages*, provides more information on this and other specific input/output error codes where this behavior can occur.

Chapter 5: System Verification

A suite of verification programs is provided with RM/COBOL. These programs ensure that your delivered diskettes are undamaged and that you have installed the required software correctly.

System Verification for UNIX

To invoke compilation and execution of the verification suite, enter:

```
doverify
```

For runtime-only systems, the compilation step is ignored.

The verification suite is designed to be self-explanatory. Follow the prompts on the screen for instructions on selecting and running individual tests.

Note 1 If a problem occurs with the display features of the verification suite, make sure you have properly set and exported the environment variable TERM for your terminal type. If you have done this and a problem exists, verify that your terminal type has an entry in the system terminal database (termcap or terminfo) and check the accuracy of the cursor motion sequence. This can be accomplished by running the system visual editor (vi).

Note 2 If any of the menu selections within the terminal configuration test work incorrectly, refer to Chapter 8, *RM/COBOL Features*, for details on the terminal attributes required by the runtime system for complete ACCEPT and DISPLAY functionality.

Single-User Tests

Six sets of tests are provided in the verification suite for single-user versions. They are as follows:

1. **Terminal Configuration Test.** This consists of individual tests that verify the functionality of ACCEPT and DISPLAY statements and defaults, screen editing functions and color functions (for appropriately configured terminals).

2. **File System Test.** This tests the sequential, relative, and indexed file system. It reads and writes records to each of the three file types.

3. **Nucleus Test.** This tests the modules of the RM/COBOL nucleus.

4. **Printer Test.** This tests that the printer configuration is correct and that communication from RM/COBOL to the printer is successful. If no printer is attached, preserve the test result in the **prntst.out** file by entering:

   ```
   PRINTER=prntst.out; export PRINTER
   ```

   before running this test.

5. **Sort-Merge Test.** This tests the sort-merge function of RM/COBOL.

6. **Pop-Up Window Manager Test.** This test ensures that the RM/COBOL Pop-Up Window Manager feature is installed correctly. The program displays a self-explanatory menu that allows you to test the various features of the Pop-Up Window Manager system. If the runtime system has been linked to not include the Pop-Up Window Manager, the program displays an appropriate message (see Appendix D, *Customizing RM/COBOL for UNIX*).

Multiuser Test

An additional verification program is provided with an appropriately licensed, multiuser version of RM/COBOL. This test ensures that RM/COBOL is interacting correctly with the file protection mechanisms employed by your system.

The program **pacetest** needs to be run simultaneously from at least two terminals that use the RM/COBOL runtime system on the computer. This test creates and uses two indexed files: **pinx** and **pinxfl**. **pinx** is a file that contains a single control record which contains the next available record in **pinxfl**. **pinxfl** is the working data file.

pacetest reads the control record, saves it, increments the control record, and writes it back to **pinx**. The original number read is used as the primary key for the record written to the growing **pinxfl** file. This scenario is repeated 100 times for each user running the test. With two users running, 200 records would be written to **pinxfl**. The directions for running **pacetest** are as follows:

1. Invoke **pacetest** at each terminal as follows:

   ```
   runcobol pacetest
   ```

2. At one terminal only, choose function 1 to create the initial files. Wait for this operation to complete.

3. At each terminal, choose function 2 to do simultaneous write operations. You will be required to enter a unique station ID (1, 2, and so forth). Then, all stations should try to press the Enter key simultaneously.

4. At any of the terminals, choose function 3 to read the file. Make sure all the records are shown in order and are all there (100 records are written by each station).

If **pacetest** encounters any errors while reading the file, it will sound an alarm and display an error message next to the record in question. Should this occur, double-check your software installation. If everything appears to be set up correctly and you are still having problems, contact Liant technical support services.

System Verification for Windows

To invoke compilation and execution of the verification suite, choose the icon named doverify. The **doverify** program allows the user to select compilation and/or execution. For runtime-only systems, the program detects that the compiler is not present and informs the user. The user may still select the execution option.

The verification suite is designed to be self-explanatory. Follow the prompts on the screen for instructions on selecting and running individual tests.

Single-User Tests

Six sets of tests are provided in the verification suite for single-user versions. They are as follows:

1. **Terminal Configuration Test.** This consists of individual tests that verify the functionality of ACCEPT and DISPLAY statements and defaults, screen editing functions and color functions (for appropriately configured terminals).

2. **File System Test.** This tests the sequential, relative and indexed file system. It reads and writes records to each of the three file types.

3. **Nucleus Test.** This tests the modules of the RM/COBOL nucleus.

4. **Printer Test.** This tests that the printer configuration is correct and that communication from RM/COBOL to the printer is successful. If no printer is attached, preserve the test result in the **prntst.out** file by setting a synonym before running this test. Using the Synonyms Properties tab (see page 3-29 for more information), type PRINTER in the Name text box and type **prntst.out** in the Value text box.

5. **Sort-Merge Test.** This tests the sort-merge function of RM/COBOL.

6. **The Pop-Up Window Manager Test.** This program displays a self-explanatory menu that allows you to test the various features of the Pop-Up Window Manager.

Multiuser Test

An additional verification program is provided with an appropriately licensed, multiuser version of RM/COBOL. This test ensures that RM/COBOL is interacting correctly with the Novell NetWare software. Before using RM/COBOL on the network, you need to install the Novell NetWare software and be familiar with its operation.

The program **pacetest** needs to be run simultaneously from each computer that uses the RM/COBOL runtime system on the network. This test creates and uses two indexed files: **pinx** and **pinxfl**. **pinx** is a file that contains a single control record which contains the next available record in **pinxfl**. **pinxfl** is the working data file.

pacetest reads the control record, saves it, increments the control record, and rewrites it back to **pinx**. The original number read is used as the primary key for the record written to the growing **pinxfl** file. This scenario is repeated 100 times for each user running the test. With two users running, 200 records would be written to **pinxfl**. The directions for running **pacetest** are as follows:

1. Compile **pacetest** by choosing the RMCOBOL icon and selecting **pacetest.cbl** as the source file.
2. Invoke **pacetest** at each computer by choosing the RUNCOBOL icon and selecting **pacetest.cob** as the object file.
3. At one computer only, choose function 1 to create the initial files. Wait for this to complete.
4. At each computer, choose function 2 to do simultaneous write operations. You will be required to enter a unique station ID (1, 2, and so forth). Then, all stations should try to press the Enter key simultaneously.
5. At any of the computers, choose function 3 to read the file. Make sure all the records are shown in order and are all there (100 records are written by each station).

If **pacetest** encounters any errors while reading the file, it will sound an alarm and display an error message next to the record in question. Should this occur, double check your network installation. If everything appears to be set up correctly and you are still having problems, contact Liant technical support services.

Chapter 6: Compiling

RM/COBOL programs are compiled with a single pass of the RM/COBOL compiler. Specifically, the compiler performs the following actions on the contents of the source programs:

- Verifies syntactic accuracy.
- Creates object programs for execution with the RM/COBOL runtime system. Liant's use of this technique provides compactness and machine-independence.
- Creates program listings, the contents of which are chosen by entering the appropriate Compile Command options.

This chapter presents complete information about the RM/COBOL compiler.

Compilation Process

The RM/COBOL compiler is invoked when you enter the Compile Command, **rmcobol**. Once invoked, the compiler makes one pass through the specified source file. During this pass, both object files and listing files are generated. The object file contains the machine-independent object code, executed at runtime, for the RM/COBOL program. The listing file contains a source image, which may be printed at the end of each compilation. Using the available Compile Command options, you can alter, augment, and suppress portions of the information contained in the listing.

RM/COBOL provides standard COBOL subprogram structure, but no intermediate linkage process stands between program compilation and execution. It is also possible to define sections of code within your program as overlay segments to the fixed permanent segment, as explained in the discussion of segmentation in Chapter 5, *Procedure Division*, of the *RM/COBOL Language Reference Manual*.

Note By default, the RM/COBOL compiler window disappears immediately when a successful compilation completes. If you want the window to remain visible, set the Persistent property to TRUE (see page 3-24).

System Files

RM/COBOL takes its input from a source file, and creates an object file and a listing file.

Source Files

RM/COBOL source files contain the RM/COBOL source code. Source lines are made up of variable-length records. Source text is ASCII, with either a line feed (LF) character or a carriage return (CR) and line feed (LF) character paired as the line separator. Embedded tab characters are expanded to one or more spaces, according to the default tab column position, which is every fourth column, starting with column 8 and ending with column 72, or according to the value of the TAB-STOPS keyword in the RUN-SEQ-FILES configuration record (see page 10-35).

Object Files

An object file is created on disk as a purely binary file. Its filename is identical to the filename of the source file, with the filename extension **.cob** or **.COB** (or the extension specified in the EXTENSION-NAMES configuration record described on page 10-19).

You can direct the object file to a directory other than the one on which the source file resides. To do this, use the O Compile Command Option. The object file may be suppressed by the use of the N Option.

Listing Files

The contents of RM/COBOL listings are detailed later in this chapter, beginning on page 6-18. Listings can be directed to a disk file, the printer, the screen, or any combination thereof, depending on the options selected in the Compile Command. Listing files are given the filename of the source program, with the filename extension **.lst** or **.LST** (or the extension specified in the EXTENSION-NAMES configuration record described on page 10-19). The listing file is a printer file and therefore may be configured using the PRINT-ATTR configuration record (see page 10-20).

Libraries

A source file can contain more than one source program. Files containing a sequence of two or more programs are referred to in this manual as libraries. With libraries, the generated object file contains a distinct object module for each source program in the source file, excluding contained programs. The object for a contained program is considered part of the object of the program that contains it. The listing file contains a complete listing of each source program in the source file.

Each noncontained program in a source file or library is compiled strictly independent of the other programs: there need be no relationship between them. However, this capability to concatenate multiple source programs into a single library is used most effectively when there is some logical relationship among the programs. This might be a main program and the called subprograms, or all the programs that include a specific copy file or group of copy files. In the latter case, recompilation of all the source programs affected by a change in one of the copy files can be accomplished with a single invocation of the Compile Command.

Note RM/COBOL versions 1 and 2 did not require END PROGRAM headers to separate a sequence of source programs. Versions 3 and later support nested programs, which makes END PROGRAM headers necessary. If you have a source file with a sequence of programs and no END PROGRAM headers, you can either add the headers or specify the Z=2 Compile Command Option (described on page 6-14).

Use the Combine Program utility (**rmpgmcom**), detailed in the discussion that begins on page G-9, to combine multiple object files into a single library when the source modules are contained in separate files.

Compile Command

Use the Compile Command (**rmcobol**) to request program compilation and to specify options.

Under UNIX, the Compile Command is entered at a shell prompt. After typing the desired command and options, press Enter to begin compilation.

Under Windows, the Compile Command can be entered in the Command Line text box of the Shortcut dialog box. See page 3-7 for instructions on creating a Shortcut. Choose the RMCOBOL icon to begin compilation. Programs also may be executed by dragging the **.cbl** source file to the RMCOBOL object or by double-clicking the source file.

The format of the Compile Command is as follows:

```
rmcobol filename [[(]  [[~]option ] …  [)comment]]
```

filename is the name of the source file to be compiled. It may be any valid operating system pathname, and may by partially or fully qualified. Specifying an extension is optional, but that extension must not be the same as the object file extension (**.cob** or **.COB** unless configured otherwise). If you do not enter a filename extension with the pathname, the compiler begins its search for the source file by looking first for the file exactly as specified. If it cannot find such a file, it looks for a file with the supplied name and an extension **.cbl**. If the file is still not found when running under UNIX, it looks for a file with an extension of **.CBL**. For all attempts to open the source file, if neither a drive designator nor a directory path is specified, the directory search sequence is used. If a directory path is specified, a directory search sequence may be used if configured properly. See the discussions that begin on page 2-4 for UNIX and page 3-11 for Windows, and the EXPANDED-PATH-SEARCH configuration keyword discussed on page 10-27.

~ (tilde) can be used as a negation character. Its purpose is to negate the presence of attributes in a COMPILER-OPTIONS configuration record (see page 10-6). Its use is fully described in Step 2 on page 6-5.

option specifies the RM/COBOL compiler options, described in the next section. Spaces or commas must separate options. Options may be entered in either uppercase or lowercase letters. If an option is repeated in a command, the last occurrence of the option is used. Each option may be preceded by a hyphen. If any option is preceded by a hyphen, then a leading hyphen must precede all options. When a value is assigned to an option, the equal sign is optional if leading hyphens are used.

comment is used to annotate the command. The comment is ignored by the compiler and has no effect on the compilation. The left parenthesis is always optional. The right parenthesis is a required separator if comments are entered.

Up to 83 characters of the Compile Command—including the pathname—are copied into the option list field within the listing header, so that they are reproduced at the top of each listing page.

Compile Command Options

Compile Command options can be specified in the following two ways:

1. They can be placed into a configuration file, which is processed by the RM/COBOL compiler when the appropriate command line option is specified. (See the discussion of the COMPILER-OPTIONS configuration record that begins on page 10-6.)

2. They can be specified in the Compile Command itself.

Options read from the configuration file are processed before options in the Compile Command. This means that options specified in a Compile Command will always override conflicting or contradictory options in a configuration file. The configured options, together with the options that appear in a Compile Command, apply to every source program in the source file referred to in that Compile Command.

You can override specific options in a configuration file by negating the option in the Compile Command. To do this, enter a tilde (~) and the option in the Compile Command. For example, the following configuration file, possibly named **config.cfg**:

```
COMPILER-OPTIONS     FLAGGING=HIGH,COM2,OBSOLETE
&          OBJECT-VERSION=2
&          LISTING-PATHNAME=LISTINGS
```

directs RM/COBOL to flag HIGH, COM2 and OBSOLETE language elements, to restrict the object version level to 2, and to write the listing file to the directory named LISTINGS.

For a particular compilation, you may want to suppress some or all configured options. For example, to suppress the flagging of COM2 elements and the creation of the listing file (here, assuming the program name is PAYROLL), enter the following Compile Command:

```
rmcobol payroll G=config.cfg F=~COM2 ~L
```

This negates the flagging of COM2 elements and suppresses the creation of the listing file (L option) for the compilation. The next time you use this configuration file in a compilation, the configured options will be in effect again.

To disable all flagging, and to write the listing to the current directory, enter the following Compile Command:

```
rmcobol payroll G=config.cfg ~F, L=.
```

This negates the flagging of HIGH, COM2 and OBSOLETE elements, and writes the listing to the current directory instead of to LISTINGS as specified in the configuration file.

A negated option calls up the default value for that option; that is, it behaves exactly as if no option were configured.

There are six groups of Compile Command options:

1. Compiler configuration options
2. Data item options
3. File type options
4. Listing options
5. Object program options
6. Source program options

The following sections contain a complete description of the Compile Command options.

Compiler Configuration Options

The following compiler options designate a file to be used as the complete compiler configuration or as a supplement to it and allow suppression of the compiler banner message.

G Use the G Option to designate a file to be used as the compiler configuration. The G Option has the following format:

```
G=path
```

See the discussion of the COMPILER-OPTIONS configuration record that begins on page 10-6. See also the H Compile Command Option.

By default, a configuration file is not designated.

H Use the H Option to designate a file as a supplement to the compiler configuration. The H Option has the following format:

```
H=path
```

If no configuration exists (specified with the G Option), the specified file serves as the complete configuration. See Chapter 10, *Configuration*.

By default, a supplemental file is not designated.

K Use the K Option to suppress the banner message and the terminal error listing. This is useful when you are running under batch files or shell scripts.

By default, this information is displayed on the standard output device.

W Use the W Option to specify the amount of memory (in kilobytes) that the compiler should use for its internal table storage. The W Option has the following format:

```
W=n
```

n is a decimal number from 32 to 16384.

The default value is 1024 kilobytes (1024 KB).

Data Item Options

The following compiler options direct the compiler to assume a certain usage for data items.

S Use the S Option to direct the compiler to assume a separate sign when the SIGN clause is not specified for a DISPLAY usage, signed numeric data item (that is, for a data item whose PICTURE character-string clause begins with S) . The S Option also allows a BLANK WHEN ZERO clause to be specified in the data description entry of a signed numeric data item for compatibility with RM/COBOL 2.*n*. In such cases, a trailing fixed insertion plus symbol (+) is assumed for the PICTURE character-string.

Note This option should be used only when compiling existing source programs written with an earlier version of RM/COBOL, and then only with caution. The use of this option creates inconsistencies between RM/COBOL and ANSI COBOL 1974 and 1985.

The default is to assume a trailing combined (zoned) sign unless the SIGN clause is present and to disallow the BLANK WHEN ZERO clause for signed numeric data items. For more information about trailing combined (zoned) signs, see Table C-1 on page C-2.

U Use the U Option to direct the compiler to assume an alternative usage for data items described as COMP or COMPUTATIONAL. The U Option has the following format:

```
U[=B|D|P]
```

The U Option specified alone or as U=B directs the compiler to assume BINARY usage for data items described as COMP or COMPUTATIONAL. This option causes COMP data items to be compatible with IBM OS/VS COBOL COMP data items and may result in improved computational speed at runtime.

The U=D Option directs the compiler to assume DISPLAY usage for items described as COMP or COMPUTATIONAL.

The U=P Option directs the compiler to assume PACKED-DECIMAL usage for items described as COMP or COMPUTATIONAL.

The U[=B] and 2 Options are mutually exclusive; they may not appear in the same Compile Command.

The default is to assume unpacked decimal format for data items described as COMP or COMPUTATIONAL.

File Type Options

The following compiler options determine whether a sequential file is declared as a binary sequential or a line sequential file.

B Use the B Option to define as binary sequential those sequential files not explicitly declared to be line sequential in their file control entries. (See page 8-40 for a discussion of file types and structure.)

V Use the V Option to direct that any sequential file not declared to be binary sequential be considered line sequential.

Note The B and V Options are mutually exclusive; they may not appear in the same Compile Command. If neither the B nor the V Option is used, the decision on whether the file is binary sequential or line sequential is deferred to program execution. The choice is then controlled by the configured DEFAULT-TYPE keyword (see page 10-35).

Listing Options

The following compiler options generate a listing and control the destination and contents of the listing.

Note The L, P, and T Options direct the listing to different destinations; any or all of these options may appear in the same Compile Command. If neither the T nor the K Option is selected, an error-only listing is written to standard output.

A Use the A Option to direct the compiler to generate the allocation map in the listing (see the discussion that begins on page 6-22).

This is useful during program development for use with the RM/COBOL Interactive Debugger.

The A Option may not be specified if none of the L, P, T, or Y=3 Options are specified or configured.

By default, the allocation map is not created as part of the listing or debugging information in the object file.

C Use the C Option to suppress the inclusion of copied text in the listing.

Copied text is source text brought into the program as a result of encountering a COPY statement. (The COPY statement is described in more detail in the discussion that begins on page 8-31 of this user's guide, and in Chapter 1, *Language Structure*, of the *RM/COBOL Language Reference Manual*.)

The C Option suppresses only the inclusion of the copied text in the listing; the copied text is always compiled. Even though the C Option is selected, erroneous lines encountered in the copied text during compilation are written to the listing along with the associated diagnostic message.

Text to the right of the COPY statement in the source line that contains that statement appears on a line by itself, immediately following the copied text.

The C Option may not be specified if none of the L, P, T, Y=2, or Y=3 Options are specified or configured.

By default, copied text is included in the source listing. Copied text immediately follows the line that contains the COPY statement.

E Use the E Option to suppress the inclusion of the source program component in the listing. However, if errors are encountered during compilation, the listing will include the erroneous lines and their associated diagnostic messages.

The E Option may not be specified if none of the L, P, or T Options are specified or configured. The E Option is ignored if the Y=2 or Y=3 Options are specified.

By default, the source program component is included in the listing.

L Use the L Option to direct that a listing file be written to disk. The L Option has the following format:

```
L[=path]
```

The L Option specified above directs the compiler to write the listing to the default directory.

path specifies a directory into which the listing file is to be written.

The listing file will always have the same name as the source file; its extension will be the listing file extension (**.lst** or **.LST** unless configured otherwise). On those operating systems that have case-sensitive filenames, the case of the extension will match the case of the first character of the source file's extension, or the first character in the source file's name if there is no extension. If there is no extension and the first character of the source filename is not a letter, then the extension **.lst** will be used. (See Table 1-1 on page 1-5 for examples of valid filenames.)

The default directory, when *path* is not specified, depends on whether the source filename was specified with a drive or directory in its value.

If the source filename was specified with a drive or directory in its value, the default directory is the one containing the source file.

Otherwise, the default directory is determined by using the compiler directory search sequence. If an existing file with the same name as the source file and the listing file extension is found using the compiler directory search sequence (see page 2-4 for UNIX and page 3-11 for Windows), the default directory is the one in which that file is found. If such a file is not found using the compiler directory search sequence, the default directory is the current directory.

If a file already exists with the specified name and extension in the specified or default directory, it is overwritten.

By default, the listing is not written to disk.

P Use the P Option to direct the compiler to write a copy of the listing to the printer.

Without a print spooler, the P Option cannot be used when the printer is busy.

By default, a copy of the listing is not written to the printer. See the discussion of the listing that begins on page 6-18.

R Use the R Option to direct the compiler to generate a sequential number in the first six columns of source records as they appear on the listing. The source file itself is not affected.

If selected, this option numbers records beginning with 1 for each source or copy input file. The number can be helpful when editing the source file. This line number cannot be used with the RM/COBOL Interactive Debugger.

The default is to print the source record exactly as read, including any commentary information present in columns 1 through 6.

T Use the T Option to direct the compiler to write a copy of the listing to the standard output device. Generally, the standard output device is the screen, but this can be controlled through redirection.

By default, a copy of the listing is not written to the standard output device. However, the last two lines of the summary listing—as well as all erroneous lines and associated diagnostic messages—are written to the standard output device regardless of the T Option. This display can be suppressed with the K Option (see page 6-7).

X Use the X Option to direct the compiler to generate a cross reference map in the listing. The cross reference map contains an alphabetic list of all user-defined words that appear in the source program. For each user-defined word, the line number of each appearance is listed. Each line number is marked to indicate that the word is being used as a declaration, a source operand or a possible destination operand. (See Figure 6-10 on page 6-28 for a sample of the cross reference map.)

The X Option may not be specified if none of the L, P, T, or Y=3 Options are specified or configured.

By default, the cross reference map is not included in the listing or in the debugging information in the object file.

Object Program Options

The following compiler options generate or suppress an object program and control the destination and features of the object program.

M Use the M Option to direct the compiler to suppress automatic conversions in certain ACCEPT and DISPLAY statements. In Format 1 and 3 ACCEPT statements, this option suppresses automatic input conversion for numeric operands and suppresses right justification for justified operands. For Format 3 DISPLAY statements (DISPLAY *screen-name*), this option suppresses automatic output conversion for numeric fields within the screen description entry.

Note This option must be used if Format 1 ACCEPT statements with numeric operands are to be treated in compliance with ANSI COBOL 1985 and 1974.

The default is to provide input conversion for numeric operands of Format 1 and 3 ACCEPT statements, right justification for justified operands of Format 1 and 3 ACCEPT statements, and output conversion for numeric fields of Format 3 DISPLAY statements.

N Use the N Option to suppress the generation of an object program.

The default is to generate object code according to the rules for the O Option, described in the following section.

O Use the O Option to specify the directory pathname where the object file will be placed. The O Option has the following format:

```
O=path
```

path specifies a directory into which the object file is to be written.

The object file will always have the same name as the source file. Its extension will be the object file extension (**.cob** or **.COB** unless configured otherwise). On those operating systems that have case-sensitive filenames, the case of the extension will match the case of the first character of the source file's extension, or the first character in the source file's name if there is no extension. If there is no extension and the first character of the source filename is not a letter, then the extension **.cob** will be used. (See Table 1-1 on page 1-5 for examples of valid filenames.)

The O and N Options may appear together in a single compilation. For example, the OBJECT-PATHNAME keyword in the COMPILER-OPTIONS configuration record (see page 10-14) specifies the directory for the object file. Entering the N Option on the Compile Command suppresses the generation of the object file (and as a result negates the OBJECT-PATHNAME keyword in the configuration file).

The default directory depends on whether or not the source filename was specified with a drive or directory in its value.

If the source filename was specified with a drive or directory in its value, the default directory is the one containing the source file.

Otherwise, the default directory is determined by using the directory search sequence. If an existing file with the same name as the source file and the object file extension is found using the compiler directory search sequence, the default directory is the one in which that file is found. If such a file is not found using the compiler directory search sequence (see the appropriate installation and systems considerations chapter in this user's guide for your specific operating system), the default directory is the current directory.

If a file already exists with the specified name and extension in the specified or default directory, it is overwritten.

Q Use the Q Option to direct the compiler to eliminate debugging information from generated object programs. Programs compiled with this option will appear invisible to the Interactive Debugger and Instrumentation. A statement address consisting of an optional segment number and segment offset will be substituted for line numbers in Normal Termination, Error Termination and Traceback runtime system messages. A segment number and segment offset replace line number references when this option is selected.

Note This option may be used to both reduce the memory requirements and increase the execution speed of most programs.

The default is to generate debugging information in object programs.

Y Use the Y Option to direct the compiler to output debugging information in the object file. The Y Option has the following variations:

Option	Action
Y=0 or ~Y	Omits the symbol and debug line table from the object program file. This is also the default behavior if Y is not specified.
Y=1 or Y	Places the symbol table but not the debug line table in the object file. When the symbol table is included in the object program file, the source program data-names and index-names may be used in Debug commands during execution (see Chapter 9, *Debugging*).
Y=2	Places both the symbol table and the debug line table in the object file. The line table is used by CodeWatch to display the source program.
Y=3	Same as Y=2, except that the debug line table also includes allocation map and cross-reference information if the A and/or X option are also specified. This information can then be viewed within CodeWatch, but may lead to large object program files.

Object program files created with Y=2 and Y=3 are fully compatible with all versions of the RM/COBOL runtime (note that previous versions will ignore these tables). This option does increase the size of the object program files, but has no effect on runtime performance or memory requirements.

Note A new option in the **rmpgmcom** utility (see Appendix G, *Utilities*), STRIP, may be used to remove symbol table and debug line table information from object files that were created with Y=1 or Y=2. For source code security, object program files that contain line table information should be reduced in size with this option or recompiled without the Y option before they are redistributed.

Z Use the Z Option to indicate the highest allowed object version of the generated code. The Z Option has the following format:

```
Z=version
```

version must be an integer in the range 1 through 8.

Statements that require a higher object version level than the value specified will be flagged in error (see page 6-33 and the description of the COMPUTATIONAL-VERSION keyword for the COMPILER-OPTIONS configuration record that begins on page 10-10). This option forces the generation of code accepted by earlier versions of the RM/COBOL runtime system.

Appendix H, *Object Versions*, lists the changes between object versions.

The default is to use the current object version number (8).

For source programs created with versions 1 or 2 that contain a sequence of programs without an END PROGRAM header, this option can prevent the compiler from treating the second or subsequent programs as contained programs. Since version 3 is the first version supporting nested source programs, setting Z=1 or Z=2 forces the compiler to treat the source file as a sequence of programs even in the absence of an END PROGRAM header.

7 Use the 7 Option to specify the semantic rules under which the program is to be compiled.

7 specifies that the source program is to be compiled with ANSI COBOL 1974 semantics. ANSI COBOL 1974 semantics affect the I-O status values, PERFORM . . . VARYING statements, ALPHABETIC class conditions, and alphabetic-edited data items. A more specific discussion of these semantic differences can be obtained by contacting Liant technical support services.

The 7 Option is implied if the 2 Option is specified.

The default is to compile the source program using ANSI COBOL 1985 semantics.

Source Program Options

The following compiler options affect the analysis of the source program and cause flagging of certain source features.

D Use the D Option to direct RM/COBOL to compile all source programs as if the WITH DEBUGGING MODE clause appeared in each compiled program. This option causes all source lines with the letter D in the indicator area to be compiled as if they had a space in the indicator area.

This option is independent of the RM/COBOL Interactive Debugger, described in Chapter 9, *Debugging*.

The default is to treat source lines with the letter D in the indicator area as commentary information unless the WITH DEBUGGING MODE clause is specified in the source program.

F Use the F Option to direct the compiler to flag occurrences of these language elements:

COM1	INTERMEDIATE
COM2	OBSOLETE
EXTENSION	SEG1
HIGH	SEG2

The F Option has the following format:

```
[F=(keyword-list)]
[F=keyword       ]
```

keyword-list specifies multiple elements to be flagged. Enclose the list in parentheses, and if the *keyword-list* contains more than one item, separate them with a space or comma. If leading hyphens are being used, the parentheses are optional. You can negate an individual keyword by preceding it with a tilde (~).

keyword specifies a single element to be flagged.

The names of elements can be abbreviated, as long as they remain unique. If the abbreviation is not unique, the keyword that occurs first alphabetically is chosen. For example, C, CO and COM are valid abbreviations of COM1 but not of COM2.

Certain keywords cause more than one element of the language to be flagged:

1. Selecting INTERMEDIATE flags both HIGH and INTERMEDIATE elements.
2. Selecting COM1 flags both COM1 and COM2 elements.
3. Selecting SEG1 flags both SEG1 and SEG2 elements.

See Appendix I, *Extension, Obsolete, and Subset Language Elements*, for a complete list of elements flagged.

By default, no elements of the language are flagged.

2 Use the 2 Option to direct the compiler to accept source programs created for the RM/COBOL (74) 2.*n* compiler.

If the programs were compiled (or designed to be compiled) without the RM/COBOL (74)2.*n* compiler ANSI Option, the separate sign (S) and line sequential (V) Options (described on pages 6-7 and 6-8, respectively) may also need to be selected.

The 2 Option removes certain words from the list of RM/COBOL reserved words. The removed words are those that are RM/COBOL additions to RM/COBOL (74) 2.*n*; thus, all words used in the earlier version as user-defined words are still valid. Note carefully that if RM/COBOL language features are added to the program, the 2 Option can no longer be used, and the program must be changed accordingly. There is also a technique for removing individual words from the list of reserved words. See the discussion of the COMPILER-OPTIONS configuration record on page 10-6.

The 2 Option directs that COMP-3 data items always be signed, irrespective of the presence or absence of an S in the associated PICTURE character-string.

The 2 Option directs that COMP-1 data items behave as in RM/COBOL (74) 2.*n*. This causes the number of digits in the PICTURE character-string describing a COMP-1 item to be ignored in three situations: when the item is the receiving item in a MOVE statement, in an arithmetic statement that specifies ON SIZE ERROR, and in an ACCEPT statement that specifies, explicitly or implicitly, input conversion. In these situations, the COMP-1 item may contain any value in the range –32768 through 32767.

The 2 Option directs that OPEN EXTEND create a new file when the file is not present, even when OPTIONAL was not specified in the file control entry.

The 2 Option directs that equality and inequality relation conditions, where the subject and object are similar signed packed-decimal (COMP-3 or PACKED-DECIMAL usage) or signed unpacked-decimal (COMP usage) operands, should not be optimized to use string comparison operations. The string comparison optimization prevents detection of equality when the only difference between the subject and object of the relation results from the change in positive sign convention for such items.

The 2 Option directs that the size of index data items be two bytes in length.

The 2 Option directs that the implied EXIT PROGRAM required by ANSI COBOL 1985 at the end of the Procedure Division be omitted. RM/COBOL (74) 2.*n* had only an implied STOP RUN at the end of the Procedure Division.

The 2 and U[=B] Options are mutually exclusive; they may not appear in the same Compile Command.

The 2 Option implies the 7 Option.

The default is to recognize all RM/COBOL reserved words, treat COMP-3 data items without an S in their PICTURE character-string as unsigned data items, treat COMP-1 data items the same as two-byte COMP-4 data items, return a file not present error for OPEN EXTEND of a nonexistent file not described with the OPTIONAL phrase in its file control entry, use the string comparison optimization for conditional relations of similar signed COMP-3 and COMP data items, use a size of four bytes for index data items, and include the implied EXIT PROGRAM at the end of the Procedure Division.

Sample Compile Commands

Here are examples of valid and invalid RM/COBOL Compile Commands.

Valid Compile Commands

```
rmcobol payroll.con P, V R
```

This command compiles the program named **payroll.con**; it directs the listing to the system printer (the P Option); declares all sequential files not defined as binary sequential in the source program to be line sequential files (the V Option); and sequentially numbers the printed listing, starting with 1 for each copy level, in the first six columns of the listing (the R Option).

```
rmcobol demo.prg (D,L=COBOL,S X) 3RD COMPILE
```

This command compiles the program **demo.prg**; the program is compiled as if the WITH DEBUGGING clause were present (the D Option); the listing is written to the directory named COBOL (the L Option); a separate sign is assumed in the absence of a SIGN clause (the S Option); and the cross reference map is generated (the X Option). A comment—3RD COMPILE—is reproduced in the listing header, but is ignored by the compiler.

Note Under UNIX, the parenthesis must be preceded with a backslash (\) character in order to be protected from the shell.

Invalid Compile Command

```
rmcobol payroll.cob B V
```

Here, the extension to the filename (**.cob**) is illegal, since **.cob** is the default extension for the object file. The B and V Options are entered together: B treats all sequential files not specified as either binary sequential or line sequential in the file control entry as binary sequential, but V treats all such files as line sequential.

Listing

Depending on the options specified in the Compile Command, the compiler generates a detailed listing. The T Option (see page 6-11) directs the listing to standard output. The listing can be directed to the printer with the P Option (see page 6-10) and to a file with the L Option (see page 6-9). All three of these options—or any combination thereof—may be specified. However, keep in mind that in certain circumstances the listing may contain lines as long as 118 characters. If the device to which the listing is sent cannot accommodate lines of that width, characters at the right end of the long lines will be truncated.

Note Error lines are always listed to standard output unless suppressed by the K Option (see page 6-7).

The components of the listing (in order of appearance) are as follows:

1. **Program listing**, which contains the source image of the program.
2. **Allocation map**, which defines and locates each identifier used in the program.
3. **Called program summary**, which lists the names of all programs called or canceled by the program being compiled.
4. **Cross reference listing**, which lists the names of all identifiers used in the program, along with the source line numbers at which they are declared and used.
5. **Summary listing**, which provides status information on the compilation itself.

When the listing is written to a printer (either because the P Option is selected or because a disk file that was generated as a result of the L Option is printed), each component starts a new page.

Program Listing

At the top of each page of the program listing, a header appears, a sample of which appears in Figure 6-1.

Figure 6-1 Program Listing Header

```
 RM/COBOL (Version 7.0n.00) for operating-system 03/15/1999 08:52:03 Page 1
0 Source file: ALLOCMAP        Options: L A X                              0
```

Note The date and time formats are configurable (see the discussion of the COMPILER-OPTIONS configuration record that begins on page 10-6).

Each page of the program listing also contains a subheader, illustrated in Figure 6-2.

Figure 6-2 Program Listing Subheader

```
  LINE   DEBUG     PG/LN -A 1 B..+....2....+....3....+....4....+....5....+....6....7..IDENTFCN
0                                                                                              0
```

This subheader sets a scale against which material on each page can be measured. The column of numbers under the "LINE" heading contains sequential line numbers assigned by the compiler to each line read from the source file or from a copy file; these line numbers are used in the cross reference listing and in Debug. The numbers under the "DEBUG" heading are used with the Interactive Debugger or for interpreting error messages when the compiler Q Option is used; this column is used only when listing the Procedure Division. The remaining headings locate the regions of the source line images: the internal six-column line number field, area A, area B, the main body of the source image (subdivided into ten-column subregions) and the eight-column identification field.

If the R Option was present in the Compile Command, the program listing contains a compiler-generated line number in the PG/LN column.

The subheading is sometimes useful in determining when the text of a source line has inadvertently extended beyond column 72, and is therefore not seen by the compiler.

The program listing itself contains the sequential line number, statement address, copy level indicator (described in the next paragraph) and the source record. If errors were detected during compilation, the appropriate error message diagnostic appears. The error message marker and diagnostics are detailed on page 6-31.

The copy level indicator is a character-string of the following form:



n is a decimal digit in the range 1 through 9. The copy level indicator appears between the sentence address (DEBUG heading) and source record in the listing whenever the source record has been copied at level *n*.

A sample of a program listing is shown in Figure 6-3.

Statement addresses are listed in decimal notation. For overlay segments, the segment number is printed as part of the statement address. A slash separates the segment number from the offset within the segment. For example:

```
50/000100
```

refers to location 100 within segment 50. Segment numbers and the slash are suppressed for the fixed permanent segment.

The generation of the program listing may be suppressed by specifying the E Option (page 6-9) in the Compile Command. Copied source text can be suppressed with the C Option (page 6-9). Error messages (if any) and their associated undermarks and source text are not suppressed, even when the C or E Option has been selected.

Figure 6-3 Sample Program Listing



```
 1                IDENTIFICATION DIVISION.
 2                PROGRAM-ID.    ALLOCMAP.
 3                ENVIRONMENT DIVISION.
 4                CONFIGURATION SECTION.
 5                SOURCE-COMPUTER. IBM-PC-XT.
 6                OBJECT-COMPUTER. IBM-PC-XT,
 7                                      PROGRAM COLLATING SEQUENCE EBCDIC-CODE.
 8                SPECIAL-NAMES.
 9                     SWITCH-1 IS REPORT-MODE,
10                         ON STATUS IS REPORT-LIST,
11                         OFF STATUS IS REPORT-NOLIST;
12                     SWITCH-3 IS DISPLAY-MODE,
13                         ON STATUS IS DISPLAY-LIST,
14                         OFF STATUS IS DISPLAY-NOLIST;
15                     CO1 IS TOP-OF-FORM;
16                     CO5 IS AMOUNT-LINE;
17                     CONSOLE IS PC-DISPLAY;
18                     SYSIN IS STANDARD-IN;
19                     SYSIN IS STANDARD-OUT;
20                     ALPHABET ASCII-1 IS STANDARD-1;
21                     ALPHABET ASCII-2 IS STANDARD-2;
22                     ALPHABET NATIVE-1 IS NATIVE;
23                     ALPHABET EBCDIC-CODE IS EBCDIC;
24                     ALPHABET BACKWARDS IS "ZYXWVUTSRQPONMLKJIHGFEDCBA";
25                     SYMBOLIC CHARACTERS QUESTION-MARK, ASTERISK ARE 64, 43;
26                     CLASS PUNCTUATION IS ";", ",", ".", "!", "?".
27                INPUT-OUTPUT SECTION.
28                FILE-CONTROL.
29                     SELECT REPORT-FILE1   ASSIGN TO PRINTER;
30                                           ORGANIZATION IS SEQUENTIAL;
31                                           ACCESS IS SEQUENTIAL.
32                     SELECT LOOKUP-FILE1   ASSIGN TO DISC;
33                                           ORGANIZATION IS RELATIVE;
34                                           ACCESS IS SEQUENTIAL.
                          .
                          .
                          .
151               PROCEDURE DIVISION USING ARG1-GROUP, ARG2-GROUP.
152  000002       A.
153  000005           CALL "CHRRTN" USING NW5-MDATE, NW5-MTIME.
154  000016           CALL MATHRTN USING NBS-1, NBU-1, NCS-1, NCU-1,
155                        NLC-1, NPS-1.
156  000035       STOP RUN.
157               END PROGRAM ALLOCMAP.
```

Allocation Map

The allocation map provides information on each user-defined word from the source program, listed in the order declared. The type of user-defined word (described in the following section) determines the allocation map format. The allocation map is generated in the listing when the A Option is specified in the Compile Command (see page 6-9) or the LISTING-ATTRIBUTES keyword is configured with the ALLOCATION-MAP value (see page 10-12).

Alphabet-Names, Symbolic-Characters, Mnemonic-Names and Class-Names

User-defined words declared in the SPECIAL-NAMES paragraph are listed in the allocation map with the following information:

1. **Association**, which is the value for a figurative or symbolic-character; the code-name for an alphabet-name; the switch-name for a mnemonic-name or condition-name associated with a switch-name; the channel-name for a mnemonic-name associated with a channel-name; the low-volume-I-O-name for a mnemonic-name associated with a low-volume-I-O-name; or blank for a class-name. The value of a figurative or symbolic-character is listed as the hexadecimal value in the native character set. If that value represents a printable character, the printable character is listed in quotation marks.

2. **Status**, which is On or Off for a condition-name associated with a switch-name. The letters PCS appear with an alphabet-name declared as the program collating sequence. Otherwise, the column is blank.

3. **Type**, which indicates whether the user-defined word is: an alphabet-name; a mnemonic-name associated with a switch-name; a condition-name; a mnemonic-name associated with a channel-name; a mnemonic-name associated with a low-volume-I-O-name; a class-name; or a symbolic-character.

4. **Name**, which is the actual user-defined word declared with the indicated attributes or the figurative constant LOW-VALUE or HIGH-VALUE. These particular figurative constants are listed since their value depends on the program collating sequence declared in the source program.

Figure 6-4 is an example of this part of the allocation map.

Figure 6-4 Allocation Map (Part 1 of 5)

```
Special-Names
 Association              Status  Type                  Name
  X"00"                           Figurative constant   LOW-VALUE
  X"FF"                           Figurative constant   HIGH-VALUE
  SWITCH-1                        Switch-name           REPORT-MODE
  SWITCH-1                  On    Condition-name        REPORT-LIST
  SWITCH-1                  Off   Condition-name        REPORT-NOLIST
  SWITCH-3                        Switch-name           REPORT-MODE
  SWITCH-3                  On    Condition-name        REPORT-LIST
  SWITCH-3                  Off   Condition-name        REPORT-NOLIST
  C01                             Channel-name          TOP-OF-FORM
  C05                             Channel-name          AMOUNT-LINE
  CONSOLE                         Low-volume-I-O-name   PC-DISPLAY
  SYSIN                           Low-volume-I-O-name   STANDARD-IN
  SYSOUT                          Low-volume-I-O-name   STANDARD-OUT
  STANDARD-1                      Alphabet-name         ASCII-1
  STANDARD-2                      Alphabet-name         ASCII-2
  NATIVE                          Alphabet-name         NATIVE-1
  EBCDIC                    PCS   Alphabet-name         EBCDIC-CODE
  Literal                         Alphabet-name         BACKWARDS
  X"3F" = "?"                     Symbolic-character    QUESTION-MARK
  X"2A" = "*"                     Symbolic-character    ASTERISK
                                  Class-name            PUNCTUATION
```

alphabet-names, symbolic-characters, mnemonic-names, and class-names

Split Key Names

User-defined words, declared as part of a RECORD KEY clause in an indexed file control entry of the Environment Division that defines a split key, are listed in the allocation map with the following information:

1. **File-Name** is the name of the file from the indexed file control entry.
2. **Key-Number** specifies the number of the key that has a split key defined. A value of zero indicates the prime record key. Alternate keys are numbered from 1 to 254.
3. **Type** indicates that the entry is a split-key-name.
4. **Name** is the name associated with the split key.

Figure 6-5 illustrates a section of the allocation map for a file that defines split keys for the primary key and the second alternate key in the file control entry.

Figure 6-5 Allocation Map (Part 2 of 5)

```
Split Key Names for program SPLITKEY
File-Name              Key-Number   Type                Name
FILE-1                          0   Split-key-name      KEY-1
                                2   Split-key-name      KEY-2
```

split-key-names

Data-Names, Condition-Names, File-Names and Cd-Names

User-defined words declared in the Data Division, other than index-names, are listed in the allocation map with the following information:

1. **Address**, which is the decimal address for data-names. The "Address" column is blank for file-names, cd-names and condition-names.

   For data items declared with the external attribute in the File Section or Working-Storage Section, the compiler-generated external number is printed on a line preceding the file or level 01 item description.

   For data-names declared in the Linkage Section, each level 01 or 77 item is preceded by an indication of how it is addressable:

   - If it is listed in the USING phrase of the Procedure Division header, "U*n*:" and "Using argument *n*" are printed to indicate the formal argument umber is *n* within the USING argument list.
   - If it is listed in the GIVING (RETURNING) phrase of the Procedure Division header, "G:" and Giving argument" are printed to indicate that the item is the formal GIVING argument.
   - If it is a based linkage record and is not a formal argument, "B*n*:" and "Based linkage record *n*" are printed to indicate that the compiler assigned based linkage record number is *n*.
   - If none of the preceding descriptions apply, "Not addressable" is printed to indicate that the Linkage Section data item is not available to the program.

2. **Size**, which is the decimal number of character positions required to store the value of a data-name, or the maximum block size—in characters or records—for a file-name declared with a non-zero block size. The "Size" column is blank for cd-names and condition-names.

3. **Debug**, which contains an abbreviated type indicator used in the Interactive Debugger to describe the format of the data item. The "Debug" column contains "Fixed" or "Variable" for file-names to indicate that records of the file are fixed or variable length, respectively. The "Debug" column is blank for cd-names and condition-names.

   Note These first three columns (Address, Size, and Debug) are used with the Interactive Debugger to display and modify the values of data-names. See Chapter 9, *Debugging*.

4. **Order**, which indicates the number of subscripts required when referencing the data-name or condition-name. The “Order” column is blank for data-names not requiring subscripting and also for file-names and cd-names. When one or more subscripts are required, the order is indicated with a decimal number enclosed in parentheses.

5. **Type**, which is a brief description of the item associated with the user-defined word. For files, the organization and access are listed, in that order, separated by a slash.

6. **Name**, which is the actual user-defined word declared with the listed attributes. The name is indented one column to the right for each increase in level-number.

Figure 6-6 is an example of this part of the allocation map.

Figure 6-6 Allocation Map (Part 3 of 5)

```
File Section for program ALLOCMAP
 Address    Size     Debug    Order     Type                Name
                     Variable           File Seq/Seq        REPORT-FILE1
       8      80     ANS                Alphanumeric         REPORT-RECORD-1
       8      40     ANS                Alphanumeric         REPORT-RECORD-2
                     .
                     .
                     .
Working-Storage Section for program ALLOCMAP
  Address   Size     Debug    Order     Type                Name
      532   112      GRP                Group               G1
      532     8      ABS                Alphabetic           ABS-1
      540     8      ANSE               Alphanumeric edited  ANSE-1
      548     8      ABS                Alphabetic, just     ABSR-1
                     .
                     .
                     .
Linkage Section for program ALLOCMAP
  Address   Size     Debug    Order     Type                Name
   U1:                                 Using argument 1
        0     44     GRP                Group               ARG-GROUP
        0      4     NSU                Numeric unsigned     ARG-COUNT
        4      8     ANS      (1)       Alphanumeric         ARG-AREA
                     .
                     .
                     .
Communication Section for program ALLOCMAP
  Address   Size     Debug    Order     Type                Name
                                        Cd for Input        NET-WORK-1
      734     12     ANS                Alphanumeric         NW1-SYM-Q
      746     12     ANS                Alphanumeric         NW1-SQ1
      758     12     ANS                Alphanumeric         NW1-SQ2
      770     12     ANS                Alphanumeric         NW1-SQ3
      782      6     NSU                Numeric unsigned     NW1-MDATE
```

data-names, condition-names, file-names and cd-names

Index-Names

User-defined words declared as index-names in the Data Division are listed in the allocation map with the following information:

1. **Address**, which is the decimal address of the index-name within the index-name table for the program. For index-names with the external attribute, the compiler-generated external number is printed on a line preceding the index-name description.

2. **Span**, which is the decimal number of character positions of the table entry associated with the index-name. This value is needed in order to convert index-name values to occurrence number values and vice versa.

3. **Debug**, which contains an abbreviated type indicator used in the Interactive Debugger to describe the format of the index-name. For all index-names, the type indicator is IXN.

   Note These first three columns (Address, Span, and Debug) are used with the Interactive Debugger to display and modify the values of index-names. See Chapter 9, *Debugging*.

4. **Type**, which is a description of the item associated with the user-defined word. It is Index-name for all index-names.

5. **Name**, which is the actual user-defined word declared as the index-name.

Figure 6-7 is an example of this part of the allocation map.

Figure 6-7 Allocation Map (Part 4 of 5)

```
  Index-names for program ALLOCMAP
    Address       Span      Debug        Type          Name
0          0          5       IXN        Index-name    G2-I1          0
           4          5       IXN        Index-name    G2-I2
           8         13       IXN        Index-name    NW3-I1
          12         13       IXN        Index-name    NW3-I2
```

index-names

Constant-Names

User-defined words declared as constant-names in the Data Division are listed in the allocation map with the following information:

1. **Constant Value**, which is the value associated with the constant-name. If the constant-name value was specified with a constant-expression, then the result value is shown. Otherwise, the literal associated with the constant-name is shown.

2. **Type,** which is a brief description of the type of the value associated with the constant-name. If the constant-name value was specified with a constant-expression, then the type is always Numeric unsigned. Otherwise, the type is the type of the literal specified as the value for the constant-name.

3. **Name**, which is the actual user-defined word declared as the constant-name.

Figure 6-8 is an example of this part of the allocation map.

Figure 6-8 Allocation Map (Part 5 of 5)

```
Constant-names for program ALLOCMAP
   Constant Value                  Type                Name
2                                  Numeric unsigned    TWO
"STRING1"                          Alphanumeric        STRING1
QUOTE (QUOTES)                     Alphanumeric        MY-QUOTES
-256.357                           Numeric signed      CONSTANT1
X"454647"                          Alphanumeric        HEX1
ALL "ABC"                          Alphanumeric        STRING2
ZERO (ZEROS, ZEROES)               Numeric unsigned    MY-ZEROS
SPACE (SPACES)                     Alphabetic          MY-SPACES
```

constant-names

Called Program Summary

The called program summary lists the names of all called and canceled programs and the using count associated with each. Figure 6-9 illustrates this listing.

Figure 6-9 Called Program Summary

```
Called Program Summary
Program-name required          Using count
MATHRTN                              6
"CHARRTN"                            2
```

The program-name appears without quotation marks for dynamic (identifier) references and inside quotation marks for static (literal) references. The “Using count” field lists the maximum number of arguments used in any CALL reference to the listed literal or identifier.

Cross Reference Listing

The cross reference alphabetically lists all user-defined words used in the program, and provides the line number of each declaration, source and possible destination reference. The line number is enclosed in slashes if the reference is a declaration or in asterisks if the reference is a possible receiving item. The line number is not marked for sending items. Procedure-names specified as the first operand of an ALTER statement and data-names that are specified as receiving operands of Procedure Division statements are considered destination references and are thus marked with asterisks in the cross reference listing. The cross reference is generated in the listing when the X Option is specified in the Compile Command (see page 6-11) or the LISTING-ATTRIBUTES keyword is configured with the CROSS-REFERENCE value (see page 10-12). Figure 6-10 illustrates the cross reference listing.

Note The method used to mark possible destination references with surrounding asterisks errs on the conservative side, particularly in arithmetic statements. The compiler marks the second operand of an arithmetic statement as a possible destination even though it may be followed by the GIVING phrase, which causes the second operand to be only a sending item. The operands in the USING phrase of a CALL statement are always considered to be possible destination references unless they are subject to a BY CONTENT phrase.

Figure 6-10 Cross Reference Listing

```
   Cross reference       /Declaration/     *Destination*
   A                   /0152/
0  ABSE-1              /0082/                                    0
   ABSR-1              /0083/
   ABS-1               /0081/
   AMOUNT-LINE         /0016/
0  ANSE-1              /0085                                     0
   ANSR-1              /0086/
   ANS-1               /0084/
   ARG1-AREA           /0113/
0  ARG1-COUNT          /0112/                                    0
   ARG1-GROUP          /0111/  0151
   ARG2-AREA           /0116/
   ARG2-COUNT          /0115/
0  ARG2-GROUP          /0114/  0151                              0
   ARG3-AREA           /0119/
   ARG3-COUNT          /0118/
   ARG3-GROUP          /0117/
0  ASCII-1             /0020/                                    0
   ASCII-2             /0021/
   ASTERISK            /0025/
   BACKWARDS           /0024/
0  DB1-DATA            /0070/                                    0
   DB1-KEY              0047  /0069/
```

Summary Listing

The summary listing shows the sizes of the regions of the generated object program. Figure 6-11 illustrates this listing.

Figure 6-11 Summary Listing

```
   Program Summary Statistics
   Read only size:                   266 (X"0000010A") bytes
0  Read/write size:                  532 (X"00000214") bytes
0  Overlayable segment size:           0 (X"00000000") bytes                0
   Total generated object size:      798 (X"0000031E") bytes
   Maximum EXTERNAL size:             88 (X"00000058") bytes
0  Total EXTERNAL size:               92 (X"0000005C") bytes
0  Errors: 1, Warnings: 0, Lines: 157 for program ALLOCMAP                  0
   Source program used 4489 (7%) of 65534 available identifiers
   (T1C limit).
0  Source program used 33004 (6%) of 588800 available user-defined
   word space (T2B limit).                                                  0
   Maximum compilation memory used was 487K bytes (2 presses and 0
   increases required).
0  Previous diagnostic message occurred at line 151.
   Object version level = 3                                                 0
   Options in effect:
   A - Allocation map listing
0  X - Cross reference listing
                                                                            0
```

The line labeled “Read only size” lists the size of that region of the object program that contains values that do not change during program execution. It consists primarily of the instructions generated for the resident (or fixed) portion of the Procedure Division, representations of the literals mentioned in the Procedure Division, and descriptors of the operands referred to in the Procedure Division.

The line labeled “Read/write size” lists the size of that region of the object program that contains values that might change during the course of execution. It consists primarily of a current record area and a control block for each of the files specified, an area for the Working-Storage Section and other internal control information.

The line labeled “Overlayable segment size” lists the size of the region of the object program that is reserved for the independent and fixed overlayable segments of the Procedure Division. Its length is the length of the longest independent or fixed overlayable segment. All such segments are loaded into this common region on an as-needed basis.

The line labeled “Total generated object size” lists the sum of the preceding values, and is therefore the amount of memory needed to load the object program. It is not the total size needed to execute that program. To execute the program there must be memory available to accommodate not only the total size (as shown on the fourth line) but the operating system, the runtime system, any external data items and the I/O buffers as well. Although you have no control over the size of the operating system or runtime system, you can exercise some control over the memory requirement for the I/O buffers by use of the

RESERVE and BLOCK CONTAINS clauses, described in detail in Chapter 8, *RM/COBOL Features*.

The line labeled “Maximum EXTERNAL size” indicates the size of the single largest record area with the external attribute declared in the source program. This number is useful because the maximum allowed value varies depending on the environment in which the program is run. See the section “Memory Available for a COBOL Run Unit” on page 2-7 for these limitations.

The line labeled “Total EXTERNAL size” indicates the sum of the sizes of all record areas with the external attribute declared in the source program. This number provides information needed in estimating the runtime system memory requirements of the program, but is not a direct measure since the memory requirements depend on the use of matching external records in other programs of the run unit.

Note The two lines regarding EXTERNAL size are omitted in the listing file when the program does not specify the EXTERNAL clause for any item.

The line labeled "Source program used ... of 65534 available identifiers ..." indicates the amount of the identifier table limit consumed. Identifiers are the individual items (classes, symbolic-characters, data items, conditions, and so forth) declared in the program. Each data item and condition defined in the program requires its own identifier entry even if the data-name or condition-name for the data item or condition is the same, since qualification can be used to distinguish between the data items or conditions. The T1C in the message refers to the compiler limit listed in Table 6-1 beginning on page 6-36.

The line labeled "Source program used ... of 588800 available user-defined word space ..." indicates the amount of the user-defined word space consumed. User-defined words are the unique spellings of words used as alphabet-names, cd-names, class-names, condition-names, data-names, file-names, index-names, key-names, mnemonic-names, paragraph-names, section-names, and symbolic-characters in the source program. Any particular spelling consumes space only once in the user-defined word table. The T2B in the message refers to the compiler limit listed in Table 6-1 beginning on page 6-36. The limit of 98133 shown in that table assumes 30-character names, which use six words each in the user-defined word space. If names averaged 24-characters in length (5 words average use of word space), the limit would be 117760 names.

The line labeled "Maximum compilation memory ..." indicates the amount of memory required to compile the source program. Setting the workspace size for the compiler to a value at least this size or slightly larger results in the best compilation speed with the minimum amount of memory consumption. The workspace size can be set using the W command line option or the WORKSPACE-SIZE keyword of the COMPILER-OPTIONS configuration record (see page 10-6). The number of presses indicates how many times the compiler attempted to recover unused memory. Minimizing the number of presses by

increasing the workspace size provides improved compilation speed. If the number of presses is zero, then the compilation speed cannot be improved by increasing the workspace size. The number of increases indicates the number of times the compiler had to request more memory because the original workspace size was too small.

The lines labeled “Errors: . . .” and “Previous diagnostic message . . .” summarize the number of diagnostic messages issued during compilation and the location of the last diagnostic message, respectively.

The line labeled “Object version level” indicates the object version level of the object program associated with the program being compiled. See Appendix H, *Object Versions*, for complete information on the object version levels accepted by RM/COBOL.

The line labeled “Options in effect” and the lines that follow list the options selected for the compilation. The listed options may have been specified in the Compile Command or be part of a configuration file (see the discussion of the COMPILER-OPTIONS record that begins on page 10-6). Those options that have no direct affect on the compilation (such as list directing options) are not listed; if no options were specified, these lines will not appear.

Error Marker and Diagnostics

Violations of syntactical or semantic rules are detected during the compiler’s pass through the source program. If an error is detected, it is undermarked by a dollar sign. Figure 6-12 illustrates the RM/COBOL diagnostic message format.

Figure 6-12 Error Marker and Diagnostics

```
      1            IDENTIFICATION DIVISION.
      2            PROGRAM-ID.  ALLOCMAP.
      3            ENVIRONMENT DIVISION
      4            CONFIGURATION SECTION.
                   $
*****   1) 0319: E Period space separator expected.
      5            SOURCE-COMPUTER. RMCOBOL.
      6            OBJECT-COMPUTER. same.
                                    $
*****   1) 0382: E Computer-name must be user-defined word instead of
                    reserved word. (scan suppressed).
*****Previous diagnostic message occurred at line 4.
      7                   PROGRAM COLLATING SEQUENCE EBCDIC-CODE.
                          $
*****   1) 0005: I Scan resumed.
*****Previous diagnostic message occurred at line 6.
      8            SPECIAL-NAMES.
      9                SWITCH-1 IS REPORT-MODE,
```

The first number on the line following the line with the undermark refers to the undermark number. Multiple errors on the same line are numbered in ascending order, reading left to right. The next number is the error number. This corresponds to the appropriate message

listed in Appendix B, *Compiler Messages*, of the *RM/COBOL Language Reference Manual*.

Following the error number is a single letter that indicates the severity of the error. There are three classes:

1. **I** indicates the message is informational only.
2. **E** indicates a severe error.
3. **W** indicates a warning.

Error Recovery

The RM/COBOL compiler may display a recovery message along with the error diagnostic. This recovery message is generated if—as often happens—a compilation error interrupts scanning. In this case, the source text is ignored until the compiler finds a recovery point. This minimizes the amount of code you need to examine if an error occurs. See Figure 6-13 for an illustration.

Figure 6-13 Error Recovery Display

```
   10                 ON STATUS IS REPORT-LIST,
   11                 OFF STATUS IS REPORT-NOLIST;
0  12                 C21 IS TOP-OF-FORM;                                  0
                         $
   *****  1) 0088: E Wrong code-name in ALPHABET clause. (scan suppressed).
   *****Previous diagnostic message occurred at line 7.
0  13                 CONSOLE IS CRT-DISPLAY;                              0
   14               PROCEDURE DIVISION.
                         $
   *****  1) 0005: I Scan resumed.
```

The undermark indicates that the compiler did not recognize the alphabet code-name given.

When the compiler encounters an error, it first attempts to make an assumption about what was actually meant. When it can do so, it continues compiling from the point of error, without displaying the “(scan suppressed)” portion of the message.

If it cannot do so, the compiler suppresses scanning until it finds a point where it can begin again. In this case, an undermark indicates where it restarted scanning, and the informational “Scan resumed” message is written. No source text between the undermark associated with the “(scan suppressed)” message and the “Scan resumed” message is compiled. This may result in data-names being undefined if the message occurs in the Data Division.

The diagnostic information described previously is always contained in the listing regardless of the setting of the compiler options. If the L, P, and T Options are all absent (meaning that the listing is not being written to any device), the diagnostic information is written to the standard output device.

Error Threading

RM/COBOL provides error-threading facilities. By reading the "Previous diagnostic message occurred at line" message, you can trace back through every error encountered during compilation. This message may also appear after the summary listing, to point to the last error in the program.

Compilation always proceeds to the end of the program regardless of the number of errors found, unless an error causes abnormal termination. Global errors, such as undefined paragraph names and illegal control transfers, are listed at the end of the listing file allocation map.

Compile Command Messages

The banner appears when you first invoke the compiler:

```
RM/COBOL Compiler - Version 7.0nn.nn for operating system
Copyright(c) 1985, 1986-1999 by Liant Software Corp.  All rights reserved.
Configured Options: option list

Registration Number:  xx-nnnn-nnnnn-nnnn
```

The third line of the compiler banner appears only when options have been specified in a configuration file or in the Compile Command. Options displayed as a single character appear first. If flagging is configured, the configured keywords appear next; long keywords are abbreviated. If an object pathname or a listing pathname is configured, it appears in the form O=*pathname* or L=*pathname*. If the object version level number is configured, it appears in the form Z=*nnnn* (where *nnnn* is a four-digit decimal number).

If you enter an invalid Compile Command, you will see:

```
Usage:      RMCOBOL name [options]
Options: [(] [A] [B] [C] [D] [E] [F=(keyword list)] [G=configfile]
     [H=configmod] [K] [L[=path]] [M] [N] [O=path] [P] [Q] [R] [S] [T]
     [U[=B|D|P]] [V] [W=workspace] [X] [Y[=n]] [Z=version] [2] [7]
     [)comments]
```

In addition, the following may appear:

```
Command line error: file name is missing from command line.
Conflict error: COMPUTATIONAL-VERSION conflicts with OBJECT-VERSION.
Conflict error: option U conflicts with 2.
Conflict error: option V conflicts with B.
Mismatch error: options A and X require option L, P, T, or Y=3.
Mismatch error: option C requires option L, P, T, Y=2, or Y=3.
Mismatch error: option E requires option L, P, or T.
Syntax error: flag keyword is incorrect.
Syntax error: option characters must be followed by space or comma.
Syntax error: option O requires path specification.
Syntax error: option G or H requires path specification.
Syntax error: option U specifies invalid type character.
Syntax error: option Z requires numeric version specification.
Syntax error: symbol n is incorrect option letter.
Syntax error: option W requires numeric workspace specification.
Syntax error: option U describes incorrect type character.
Syntax error: option Y specifies an invalid numeric debug level.
Version error: value must be non-zero and less than or equal to 8.
Error invoking unauthorized copy of compiler.
```

Compiler Status Messages

The RM/COBOL compiler displays messages that tell you it has completed normally, or that it has terminated abnormally.

One of these messages—Compilation complete—appears every time the compilation is finished, regardless of the number of errors that appear. This message has the following form:

```
Compilation complete--Programs: p, Errors: e, Warnings: w
```

p is the number of programs in the source file, excluding contained programs.

e is the number of errors found.

w is the number of warnings issued.

The other messages appear under specific circumstances. They are listed in Appendix B, *Compiler Messages*, of the *RM/COBOL Language Reference Manual*.

During initialization, the compiler locates and reads its message file. If it cannot find its message file or the message file is corrupt, one of the following messages appears:

```
Unable to find the system message file
Unable to format the system message file
Unable to read the system message file
```

The compiler compares its version number and product code with those in the message file. If they do not match, one or both of the following messages appears:

```
RM/COBOL:  Message file version mismatch, expected 7.0n.nn, found n.nn.nn
RM/COBOL:  Message file product mismatch, expected XX, found YY
```

When any of the above messages appear, the compilation terminates with the following message:

```
Error invoking mismatched compiler and message file.
```

The compiler message file may have the wrong name or be in the wrong directory. The compiler message file must have the name **rmc.msg** (**RMC.MSG** under UNIX). The compiler attempts to find the message file in the directory that contains the **rmcobol** executable file, the current directory, or through the PATH directory search sequence (see page 2-4 for UNIX or page 3-11 for Windows).

Note On some versions of UNIX, it is impossible to determine which directory contains the executable file when that directory is specified on the command line.

If a compilation error results in an abnormal termination, a message appears in the following general form:

```
Compiler error n:  text
```

n is a compiler error number.

text is any of the first sentences in the following definitions.

The numbers and their definitions are listed in Table 6-1.

In addition to these errors, unnumbered error messages may appear as a result of configuration or I/O errors. These unnumbered error messages are described beginning on page 6-41.

Table 6-1 Abnormal Termination Messages

<table>
<tr><th>Error Number</th><th colspan="3">Message Text</th></tr>
<tr><td>1</td><td colspan="3">Compiler limit exceeded, Tnn message.</td></tr>
<tr><td></td><td colspan="3">The program has exceeded an internal compiler limit. This can be remedied by dividing the program into a main program with multiple subprograms. The table number and table usage are included in the message to provide additional information to help keep the program in conformance with compiler limits. If this error continues to occur even in a small program, it suggests an internal compiler malfunction. Provide a source copy and the table number as it appears in this message to Liant technical support services.

The values of nn are listed as table numbers, and the values for message are listed as table usage in the following table. Limits are provided only where meaningful; all compiler tables are listed since error number 2 also displays this information.</td></tr>
<tr><td></td><td>Table Number</td><td>Table Usage</td><td>Limit</td></tr>
<tr><td></td><td>T00</td><td>Source (input source records, contiguous comments)</td><td>28000</td></tr>
<tr><td></td><td>T01</td><td>AliasID (aliased identifiers)</td><td>65534</td></tr>
<tr><td></td><td>T02</td><td>Alter (ALTER statements)</td><td>65534</td></tr>
<tr><td></td><td>T03</td><td>BackPatchPsect (object back patches)</td><td></td></tr>
<tr><td></td><td>T04</td><td>Cfd (COBOL file definers)</td><td>65534</td></tr>
<tr><td></td><td>T05</td><td>Code (object code buffer)</td><td></td></tr>
<tr><td></td><td>T06</td><td>Condition (condition-names)</td><td>65534</td></tr>
<tr><td></td><td>T07</td><td>Corresponding (CORRESPONDING items for MOVE, ADD, or SUBTRACT)</td><td></td></tr>
<tr><td></td><td>T08</td><td>CrossRef (cross reference entries)</td><td>290000</td></tr>
<tr><td></td><td>T09</td><td>DataParameter (forward data references, for example, FILE STATUS)</td><td>65534</td></tr>
<tr><td></td><td>T0A</td><td>DataRecord (DATA RECORDS clause references)</td><td></td></tr>
<tr><td></td><td>T0B</td><td>DeclarativeRefError (declarative reference errors)</td><td></td></tr>
<tr><td></td><td>T0C</td><td>DeferredScript (deferred subscripting in Screen Section)</td><td>65534</td></tr>
<tr><td></td><td>T0D</td><td>DimensionTemp (table dimensions in subscripting)</td><td></td></tr>
<tr><td></td><td>T0E</td><td>Dsect (data descriptions for data references)</td><td>65534</td></tr>
<tr><td></td><td>T0F</td><td>ErrorID (identifier errors discovered after the definition)</td><td></td></tr>
<tr><td></td><td>T10</td><td>ErrorMessage (diagnostic messages for current line)</td><td></td></tr>
<tr><td></td><td>T11</td><td>ErrorProcedure (procedure errors)</td><td></td></tr>
<tr><td></td><td>T12</td><td>Error (diagnostic message entries)</td><td></td></tr>
<tr><td></td><td>T13</td><td>ErrorTemp (diagnostic message temporaries)</td><td></td></tr>
</table>

Table 6-1 Abnormal Termination Messages (*Cont.*)

Error Number	Message Text		
	Table Number	Table Usage	Limit
	T14	Exit (stacked internal exit locations)	
	T15	External (external data items or files)	
	T16	Fail (stacked recovery information for parsing errors)	
	T17	FileArea (file areas for SAME [RECORD] AREA clauses)	65534
	T18	FileAreaTemp (file area temporaries)	
	T19	Fsect (file references)	65534
	T1A	Global (global data items or files)	65534
	T1B	Group (group data items stack for a record)	
	T1C	ID (identifier definitions)	65534
	T1D	IndexTempHold (held index temporaries)	
	T1E	IndexTemp (index temporaries)	
	T1F	InspectTempHold (held INSPECT temporaries)	
	T20	InspectTemp (INSPECT temporaries)	
	T21	IntegerConstant (integer constants)	65534
	T22	Jsect (procedure references)	65534
	T23	Label (made intra-statement labels)	65534
	T24	LiteralCharacter (literal characters)	65534
	T25	LiteralRef (literal references)	65534
	T26	Literal (literal descriptors)	65534
	T27	LiteralTemp (literal temporaries)	
	T28	LiteralValue (literal values)	65534
	T29	LocalSymbol (local symbol information for object symbol table)	
	T2A	NameLink (user-defined word links)	98133
	T2B	Name (user-defined words)	98133
	T2C	NextSentenceLabel (NEXT SENTENCE labels)	
	T2D	NumericTemp (numeric temporaries)	65534
	T2E	Operand (statement operands)	
	T2F	PackTemp (character packing temporaries)	

Table 6-1 Abnormal Termination Messages (*Cont.*)

Error Number	Message Text		
	Table Number	Table Usage	Limit
	T30	ParameterText (diagnostic message parameter text)	
	T31	Partial (partial segments)	65534
	T32	Perform (PERFORM statements)	65534
	T33	PictureTemp (PICTURE character-string temporaries)	
	T34	PointerTemp (pointer temporaries stack)	
	T35	PointerTempHold (pointer temporaries save)	
	T36	Polish (expression evaluation Polish)	
	T37	PolishTemp (expression evaluation Polish temporary)	
	T38	PrecomputeRef (precomputed subscripting or reference modification)	65534
	T39	Preset (initial VALUE clause values)	
	T3A	ProcedureRef (procedure references)	65534
	T3B	Procedure (procedure definitions)	65534
	T3C	ProgramName (program-names)	
	T3D	ProgramNest (contained programs)	
	T3E	Program (programs referenced by CALL statements)	65534
	T3F	Qualifier (qualifiers in identifiers)	
	T40	QualifierTemp (qualifier temporaries)	
	T41	RecordKey (record keys)	65534
	T42	RecordKeyTemp (record key temporaries)	
	T43	RefMod (reference modifiers)	65534
	T44	ReplaceKey (REPLACE statement keys)	65534
	T45	ReplaceText (REPLACE statement text)	65534
	T46	ReplacingKey (REPLACING phrase keys in COPY statements)	65534
	T47	ReplacingText (REPLACING phrase text in COPY statements)	65534
	T48	SameSortArea (SAME SORT AREA list)	
	T49	ScreenAttributes (Screen Section data item attributes)	65534
	T4A	ScreenGroup (Screen Section groups)	

Table 6-1 Abnormal Termination Messages (*Cont.*)

<table>
<tr><th>Error Number</th><th colspan="3">Message Text</th></tr>
<tr><td></td><td>Table Number</td><td>Table Usage</td><td>Limit</td></tr>
<tr><td></td><td>T4B</td><td>ScriptPlex (subscripted reference entries)</td><td>65534</td></tr>
<tr><td></td><td>T4C</td><td>ScriptRef (subscripted references)</td><td>65534</td></tr>
<tr><td></td><td>T4D</td><td>ScriptTemp (subscript temporaries)</td><td></td></tr>
<tr><td></td><td>T4E</td><td>Segment (Procedure Division segments)</td><td>65534</td></tr>
<tr><td></td><td>T4F</td><td>SortMergeBlock (SORT and MERGE statements)</td><td></td></tr>
<tr><td></td><td>T50</td><td>SourceTemp (input source character temporaries)</td><td></td></tr>
<tr><td></td><td>T51</td><td>SpecialRegister (special register references)</td><td>65534</td></tr>
<tr><td></td><td>T52</td><td>Symbol (user-defined word temporaries)</td><td></td></tr>
<tr><td></td><td>T53</td><td>SystemNames (implementor-names)</td><td>65534</td></tr>
<tr><td></td><td>T54</td><td>TableIndex (INDEXED BY phrases of OCCURS clauses)</td><td></td></tr>
<tr><td></td><td>T55</td><td>TableKey (KEY phrases of OCCURS clauses)</td><td>65534</td></tr>
<tr><td></td><td>T56</td><td>Table (OCCURS clauses)</td><td>65534</td></tr>
<tr><td></td><td>T57</td><td>UndefinedProcedure (undefined procedure references)</td><td></td></tr>
<tr><td></td><td>T58</td><td>UsingID (Procedure Division header USING list)</td><td>256</td></tr>
<tr><td></td><td>T59</td><td>Work (compiler data stack)</td><td>65534</td></tr>
<tr><td>2</td><td colspan="3">Table memory overflow, Tnn message.</td></tr>
<tr><td></td><td colspan="3">The program has exceeded the available workspace when adding information to the indicated compiler table. Increase the amount of user space available to the compiler with the W Option, reduce the program size by dividing the program into a main program with multiple subprograms or by using segmentation, or use shorter data-names.

The values of nn are listed as table numbers, and the values for message are listed as table usage in the table provided above for error number 1. Note that the table listed is not necessarily one of the tables causing the problem; it may simply be the table being increased in size when the operating system refuses to provide more memory to the compiler.</td></tr>
<tr><td>3</td><td colspan="3">Program data or code overflow.</td></tr>
<tr><td></td><td colspan="3">The program exceeded an internal compiler limit. The listing file shows whether a data or procedure overflow occurred.

One of the object sections has run out of space. Segmenting the program or dividing it into a main program with multiple subprograms may solve a procedure overflow. Reducing the size of data items described in the Data Division may solve a data overflow condition.</td></tr>
</table>

Table 6-1 Abnormal Termination Messages (*Cont.*)

Error Number	Message Text
4	**Internal logic error, <*error location information*>**
	An internal compiler error has been encountered. If this problem arises, call Liant technical support services for assistance. The <*error location information*> included in this message may help determine the cause of this malfunction and should be recorded for reference.
5	**Fatal syntax error.**
	The compiler has encountered a syntax error from which it cannot recover. Fix the syntax error in the source program and then compile the program again.
6	**Object file overflow.**
	The object file has become too large for the compiler to produce a correct object file. Break the program into two or more smaller programs that communicate using the CALL statement.
7	**Internal logic error, <*error location information*>**
	An internal compiler error has been encountered: an invalid compiler table number (roll) has been referenced. If this problem arises, call Liant technical support services for assistance. The <*error location information*> included in this message may help determine the cause of this malfunction and should be recorded for reference.
8	**Internal logic error, <*error location information*>**
	An internal compiler error has been encountered: an erroneous compiler table entry number (group) has been referenced. If this problem arises, call Liant technical support services for assistance. The <*error location information*> included in this message may help determine the cause of this malfunction and should be recorded for reference.
9	**Internal logic error, <*error location information*>**
	An internal compiler error has been encountered: an erroneous compiler table entry offset (rung) has been referenced. If this problem arises, call Liant technical support services for assistance. The <*error location information*> included in this message may help determine the cause of this malfunction and should be recorded for reference.
n	**Unknown error number.**
	The value of *n* was not 1 through 9, inclusive. If this occurs, call Liant technical support services for assistance.

In the unnumbered error messages described below, *pathname* may be one of the following: a valid pathname, PRINTER if the P Option is used, or the standard output device if the T Option is used.

Open error for file *pathname*

This message may occur for overlay files, program listings or object files. There are a number of reasons this message may appear:

- A write-protected file was opened for output.
- The system is out of disk space.
- An invalid pathname was specified.
- A file exists, but RM/COBOL could not locate it because the directory search sequence was not specified or was specified incorrectly.
- The system has reached its limit for the number of files that can be open at one time.

If the open error occurs on the compiler overlay file, the file may have the wrong name or be in the wrong directory. The compiler overlay file must have the name **rmcobol.ovy**. The compiler attempts to find the overlay file in the current directory and then in the same directory as the compiler executable file. If unable to find the file there, the compiler finds the overlay file through the PATH directory search sequence (see page 2-4 for UNIX or page 3-11 for Windows).

Note On some versions of UNIX, it is impossible to determine the directory that contains the executable file when that directory is specified on the command line.

Write error for file *pathname*

This message can occur for both listing and object files. Generally, it means space is not available to perform the write operation.

Read error for file *pathname*

This message can occur for source, overlay, and object files. Generally, it indicates a corrupted file. The error will also occur on source files that contain a NULL character. Restore the file from its backup copy, or, for object files, restart the compilation.

Load error for file *pathname*

This message can occur only for overlay files. It indicates that the overlay file is not the same version as the resident compiler which loaded it. The overlay file may be corrupted, in which case the problem can be corrected by restoring it from its backup. The problem can also be caused by multiple versions of the compiler existing on the disk and an incorrect establishment of the search sequence for overlay files. Such cases can be corrected either by deleting the undesired version of the compiler or by resetting the PATH environment variable such that the overlays associated with the resident compiler will be found.

Compiler Configuration Errors

Compiler configuration errors include all errors that occur because of an error in the configuration. The formats are as follows:

```
Error code at record number in file.

Error code in configuration.
```

code is the compiler configuration error number listed in Table 6-2 (see also the "Configuration Errors" section that begins on page A-37), or it is an input/output error (see the "Input/Output Errors" section beginning on page A-11).

number is the logical record in the configuration file where the error occurred. When using *number* to determine which record is in error, count lines combined with their continuation lines as one record, and do not count comment lines or blank lines.

file identifies one of the following sources of configuration records:

1. Attached configuration file
2. Overriding configuration file
3. Supplemental configuration file

The format with the record number and filename appears if an error is detected during the processing of a configuration record. The text of the configuration record in error follows the message. The other format is used if an error is detected after all configuration records have been processed or if an error is detected without an associated record.

Table 6-2 Compiler Configuration Errors

Code	Description
E002	An invalid delimiter was found.
E004	A keyword has not been provided where one was expected or the keyword is invalid.
E007	Syntax error.
E009	A value has not been provided where one was expected or the value is invalid.
E00B	A logical configuration record exceeds the maximum length.
E00C	Token requested to dereserve was not found.

Compiler Initialization Errors

If the compiler encounters difficulties initializing the RM/COBOL file management system, the following error message will appear:

```
Error initializing file manager.
```

This error generally occurs because a buffer pool has been configured that is too large to be allocated. See the BUFFER-POOL-SIZE keyword of the RUN-FILES-ATTR configuration record (page 10-26) for instructions on changing the buffer pool size.

Compiler Exit Codes

Compiler exit codes indicate the status of the compilation (either successful or unsuccessful). These codes and their associated definitions are listed in Table 6-3.

Under UNIX, the exit code can be interrogated from the shell. See shell (**sh**) in your UNIX documentation for details.

Under Windows, a non-zero exit code is displayed in a message box titled “Return Code”. Selecting the OK button closes the compiler window. The message box also will contain the COBOL error code, if one occurred. Display of the Return Code message box may be disabled by setting the RM/COBOL Windows registry value “Show Return Code Dialog” to FALSE. For more information, see the section “Setting Miscellaneous Properties” in Chapter 3, *Installation and System Considerations for Microsoft Windows*.

If the compiler was invoked from a COBOL program using the SYSTEM non-COBOL subprogram (CALL “SYSTEM”), the exit code can be retrieved by passing an exit code variable in the USING list. See page F-41 for more information on the SYSTEM subprogram.

Table 6-3 Compiler Exit Codes

Code	Description
0	Normal termination.
249	Warnings in program.
250	System initialization error.
251	Incorrect Compile Command.
252	Errors in program.
253	Reserved.
254	Compilation canceled (by pressing the CTRL and BREAK keys or the system Interrupt key).
255	Compiler error.

Chapter 7: Running

One of the immediate results of compilation is the creation of the object file. Object files contain the object version of the program that can be executed with the runtime command. To execute the object program, use the RM/COBOL Runtime Command described in the following section.

If your program uses segmentation, the segments are loaded and executed—as they are referenced—by the RM/COBOL runtime system. The runtime system also allocates memory for file buffers, external data items, and called RM/COBOL and non-COBOL subprograms.

This chapter contains information on the RM/COBOL Runtime Command, **runcobol**, and its options, examples of valid and invalid runtime commands, runtime messages, and program exit codes.

Runtime Command

The RM/COBOL Runtime Command (**runcobol**) loads and executes RM/COBOL programs.

Under UNIX, the Runtime Command is entered at a shell prompt. After typing the desired command and options, press Enter to begin execution.

Under Windows, the Runtime Command can be entered in the Command Line text box of the Shortcut dialog box. See page 3-7 for instructions on creating a Shortcut. Choose the RUNCOBOL icon to begin execution. Programs also may be executed by dragging the **.cob** object file to the RUNCOBOL object or by double-clicking on the object file.

The format of the Runtime Command is as follows:

```
runcobol filename [ option ] …
```

filename is the name of the main program of the run unit. If the L Option (described in the next paragraph) is not specified, *filename* must be a valid pathname. If a filename extension is not specified, RM/COBOL uses first .**cob**, and then .**COB** unless configured otherwise.

The L Option allows you to invoke execution of a program contained in a library by entering the name of the library only. (See the discussion of libraries that begins on page 6-3.) The rules for invocation of libraries are as follows:

1. If the main program is not in a library, you must enter the appropriately qualified pathname for *filename*.

2. If the main program is in a library, you must enter the L Option and the library name containing the main program. The main program name specified by *filename* must have been specified in the PROGRAM-ID paragraph of the program.

option specifies the available RM/COBOL Runtime Command options, described in the next section. Spaces or commas must separate options. Options may be entered in uppercase or lowercase letters. If an option is repeated in a command, the last occurrence of the option is used. Each option may be preceded by a hyphen. If any option is preceded by a hyphen, then a leading hyphen must precede all options. When a value is assigned to an option, the equal sign is optional if leading hyphens are used.

In addition, the RM/COBOL runtime system also supports three OLE server registration commands, which do not follow the command format described earlier in this section:

```
runcobol /regserver
runcobol /unregserver
runcobol /showserver
```

These options are described in the topic “Registering the RM/COBOLRuntime" in Chapter 3, *Installation and System Considerations for Microsoft Windows*.

Runtime Command Options

A single RM/COBOL Runtime Command may include all of the options. There are no rules of exclusivity. However, as is mentioned with the appropriate option, some options override others.

There are four groups of Runtime Command options:

1. Configuration options

2. Debug and test options

3. Environment options

4. Program options

The following sections contain a complete description of the Runtime Command options.

Configuration Options

The following options designate a file to be used as the complete runtime configuration or as a supplement to it and allow suppression of the banner and STOP RUN messages.

C Use the C Option to designate a file to be used as the runtime configuration. The specified file replaces any attached configuration for the run of the program only. The C Option has the following format:

```
C=pathname
```

See the discussion of the RUN-OPTION configuration record that begins on page 10-33. See also the X Option, described in this section.

The default is to use the default configuration options described in Chapter 10, *Configuration*.

K Use the K Option to suppress the banner message and the STOP RUN message. This option is most useful when running under batch command files or shell scripts.

The default is to display the banner and STOP RUN messages.

X Use the X Option to designate a file as a supplement to the runtime configuration. The X Option has the following format:

```
X=pathname
```

If no configuration exists (either attached or specified with the C Option, described previously), the specified file serves as the complete configuration. See Chapter 10, *Configuration*.

Debug and Test Options

The following options invoke the RM/COBOL Interactive Debugger and collect program instrumentation data.

D Use the D Option to invoke the RM/COBOL Interactive Debugger (called Debug). Complete details on program debugging are contained in Chapter 9, *Debugging*.

By default, the Interactive Debugger is not invoked.

I Use the I Option to collect RM/COBOL program instrumentation data. Complete details on program instrumentation are contained in Chapter 11, *Instrumentation*.

By default, instrumentation data is not collected.

Environment Options

The following options specify the runtime environment.

B Use the B Option to specify a maximum buffer size for use with the ACCEPT and DISPLAY statements. The B Option has the following format:

B=*n*

The maximum buffer size is 65280 characters. The default size is 264 characters.

See page 2-23 for information about ACCEPT and DISPLAY buffers.

M Use the M Option to direct that level 2 ANSI semantics are to be used for Format 1 ACCEPT and DISPLAY statements.

The default is to use level 1 ANSI semantics in these situations (see the discussion that begins on page 2-24).

S Use the S Option to set (or reset) the initial value of switches in the RM/COBOL program. The S Option has the following format:

S=*n . . . n*

Switches are numbered left to right from 1 to 8, without trailing zeroes. Each *n* indicates a switch value: 0 indicates OFF and 1 indicates ON.

The default is to initialize all switches to OFF at the start of the run unit.

T Use the T Option to specify the amount of memory (*n* bytes) to be used for a sort operation. The T Option has the following format:

T=*n*

There are a number of reasons to use the T Option in association with a sort operation:

- To increase the amount of memory available for the sort operation, thereby increasing the efficiency of the sort operation.
- To reduce the default memory allocation. This provides more room for loading other data or called subprograms into memory during an input procedure.

If no SORT or MERGE statement is used in the run unit, using a value of 0 will allow the runtime system to allocate the memory generally used to contain the sort-merge logic for other purposes.

The default is 256000 bytes. The maximum allowed value is 2147483647 bytes.

Program Options

The following options define an argument to be passed to the main program and the object libraries to be used for the run unit.

A Use the A Option to pass an argument to the main program. The A Option has the following format:

A=[*delim*]*string*[*delim*]

string is an alphanumeric series of characters.

The delimiter character specified for *delim* may be either ' or ".

The delimiter character chosen as the opening delimiter must be used as the closing delimiter as well. The closing delimiter must be followed by a space or comma if another option follows the A Option. The delimiter character used cannot appear as part of *string*.

If *string* contains no spaces, delimiter characters are not required.

Under UNIX, it is safer to delimit *string* using single quotation marks '. . .' because characters in the argument might otherwise be meaningful to the shell (sh) command interpreter.

To use the string assigned to the A option, you must have a Linkage Section for the main program with the following form:

```
01 MAIN-PARAMETER.
   02 PARAMETER-LENGTH  PIC S9(4) BINARY (2).
   02 PARAMETER-TEXT.
      03 PARAMETER-CHAR PIC X OCCURS 0 TO 100 TIMES
               DEPENDING ON PARAMETER-LENGTH.
```

The Procedure Division header should have the following form:

```
PROCEDURE DIVISION USING MAIN-PARAMETER.
```

The variable PARAMETER-LENGTH contains the number of characters between delimiter characters. PARAMETER-TEXT contains a copy of the characters between the delimiter characters. If no parameter is passed with the A Option and the main program describes a parameter as shown above, the value of PARAMETER-LENGTH will be zero. When this is the case, PARAMETER-TEXT should not be referenced. In all cases, no part of MAIN-PARAMETER should be modified.

The number of characters between the delimiter characters cannot exceed 100.

The following is an example program using the A Option.

```
 IDENTIFICATION DIVISION.
 PROGRAM-ID.  CPASS.
*  To see a command-line argument string passed to a
*  COBOL main program, run this program as follows:
*     runcobol cpass A="string"
 DATA DIVISION.
 LINKAGE SECTION.
 01  APARAM.
     02  APARAM-SIZE    PIC S9(4) BINARY (2).
     02  APARAM-STRING.
         03 FILLER      PIC X OCCURS 0 TO 100 TIMES
                          DEPENDING ON APARAM-SIZE.
 PROCEDURE DIVISION USING APARAM.
 0010-BEGIN.
     DISPLAY APARAM-STRING(1:) LINE 22 ERASE.
     STOP RUN.
 END PROGRAM CPASS.
```

L Use the L Option to designate RM/COBOL object or non-COBOL subprogram libraries. The L Option has the following format:

L=*pathname*

These libraries allow more than one program to be contained within a file. RM/COBOL imposes no limitation on the number of times the L Option may appear in a single Runtime Command. (See the discussion of libraries that begins on page 6-3.)

Sample Runtime Commands

Following are examples of valid and invalid RM/COBOL Runtime Commands.

Valid Runtime Commands

```
runcobol payroll B=500,K
```

This command executes the program named **payroll.cob.** It establishes a maximum buffer size of 500 bytes for ACCEPT and DISPLAY statements (the B Option) and suppresses banner and STOP RUN messages (the K Option).

```
runcobol FIRSTPRG L=lib1\library.cob,D
```

This command executes the program FIRSTPRG contained in the RM/COBOL library named **lib1\library.cob**.

It informs the runtime system of the name of the library (the L Option) that contains the programs available, and invokes the Interactive Debugger (the D Option).

Invalid Runtime Commands

```
runcobol payroll.sal A='PRINT-RUN"
```

Here, the A Option is invalid, since the opening and closing delimiters are not identical.

```
runcobol lib1\library D T
```

In this example, the library used in the valid example cannot be executed by this command, assuming the library contains more than one program. Also, the T Option is specified without an associated value.

Runtime Messages

Messages of different classes may appear on the screen during program execution. The message types are defined in the following paragraphs.

Diagnostic Messages

Diagnostic messages indicate either that an internal RM/COBOL error occurred or that an I/O error occurred that was not handled by an appropriate USE procedure (see the description of the USE statement in Chapter 5, *Procedure Division*, of the *RM/COBOL Language Reference Manual*). If the D Option (see page 7-3) was entered in the Runtime Command and one of these errors occurs, the Interactive Debugger will be entered to allow examination of program data values. Otherwise, control will return to the operating system.

Execution Messages

Execution messages report the status of the runtime system, or problems within the RM/COBOL program that prevent successful execution.

These messages result from normal program termination, the presence of a STOP *literal* statement, or an incorrectly entered option.

Diagnostic and execution error messages are detailed in Appendix A, *Runtime Messages*.

Program Exit Codes

An appropriate exit code is returned to the operating system when program execution ends. The exit code may indicate that execution was successful or unsuccessful. Users may move (or otherwise assign) any exit code value in the range 0 through 255 to the implicitly defined RETURN-CODE special register. The program exit codes are listed and defined in Table 7-1.

Under UNIX, the exit code can be interrogated from the shell. See shell (sh) in your UNIX documentation for details.

Under Windows, a non-zero exit code is displayed in a message box titled "Return Code". Choosing the OK button closes the runtime window. The message box also will contain the COBOL error code, if one occurred. Display of the Return Code message box may be disabled by setting the RM/COBOL Windows registry value "Show Return Code Dialog" to FALSE. For more information, see the section "Setting Miscellaneous Properties" in Chapter 3, *Installation and System Considerations for Microsoft Windows*.

If the runtime system was invoked from a COBOL program using the SYSTEM non-COBOL subprogram (CALL "SYSTEM"), the exit code can be retrieved by passing an exit code variable in the USING list. See page F-41 for more information on the SYSTEM subprogram.

Note User-defined termination codes in the range 249–255 will be ambiguous if a runtime system error occurs.

Table 7-1 Program Exit Codes

Code	Description
0	Normal termination.
249	Internal library subprogram called with incorrect parameters.
250	System initialization error.
251	Incorrect Runtime Command.
252	Program load failure.
253	Program error.
254	Run unit canceled (by pressing the Ctrl and Break keys or the system Interrupt key).
255	I/O error.

Chapter 8: RM/COBOL Features

This chapter offers operating system-specific information on the use of RM/COBOL statements and on RM/COBOL file types and structure. It is assumed the reader is familiar with RM/COBOL statements.

ACCEPT and DISPLAY Statements

Specific characteristics of your operating system affect the following aspects of RM/COBOL ACCEPT and DISPLAY statement usage:

- The initial contents of a screen field.
- The use of certain edit keys with the ACCEPT statement.
- The use of phrases with ACCEPT and DISPLAY statements.
- Redirection and piping of standard input and standard output (for more information, see Chapter 2, *Installation and System Considerations for UNIX*).

Initial Contents of a Screen Field

Depending on the current configuration and the phrases specified in the ACCEPT statement, the initial contents of a screen field may be the following:

- Unchanged but treated as if the field contained all spaces. This is the default if neither the PROMPT nor UPDATE phrase is specified, and if the ACCEPT-FIELD-FROM-SCREEN keyword of the RUN-ATTR record is not specified or is set to NO in the configuration file (as described on page 10-23).
- Unchanged if neither the PROMPT nor UPDATE phrase is specified and the ACCEPT-FIELD-FROM-SCREEN keyword of the RUN-ATTR record is set to YES in the configuration file (see page 10-23).
- Filled with prompt characters if the PROMPT phrase is specified in the ACCEPT statement.
- Filled with the current value of the associated ACCEPT operand if the UPDATE phrase is specified in the ACCEPT statement.

- Filled with the literal characters specified with the MASK keyword of the CONTROL phrase, if that CONTROL phrase is specified. If UPDATE is also specified, or the ACCEPT-FIELD-FROM-SCREEN keyword of the RUN-ATTR configuration record is set to YES, then the input character positions specified in the mask are replaced by the contents of the ACCEPT operand or the current contents of the screen field, respectively.

You can then modify the contents of the screen field. Except for literal characters specified with the MASK keyword of the CONTROL phrase, all positions of that field can be modified until a field termination key is pressed. This modification of displayed data is called field editing.

Defined Keys

The following sections list and explain the specially defined screen field editing keys and the keys that generate field termination key codes.

Before these keys can function as described under UNIX, you must associate them with the definition in the termcap or terminfo database (described on page 2-9, and detailed in Chapter 10, *Configuration*). For example, the Left Arrow key might be associated with the **k1** termcap attribute.

Edit Keys

Table 8-1 describes the keys used to manipulate the cursor during field editing.

Table 8-1 Edit Keys

Key	CONTROL Phrase	Action
Left Arrow	Default	Moves the cursor left one character without affecting any input characters. If the cursor is already at the leftmost character in the screen field, a beep sounds.
	MASK	Same as above; however, the cursor skips over literal characters that were specified in the mask.
Right Arrow	Default	Moves the cursor right one character without affecting any input characters. If the cursor is already at the rightmost character in the screen field, a beep sounds.
	MASK	Same as above; however, the cursor skips over literal characters that were specified in the mask.
Backspace	Default	Moves the cursor left one character, and deletes the input character in that position. All characters to the right of the deleted characters are shifted to the left. The prompt character (or a space if the PROMPT phrase was not specified) is used to pad the screen field on the right. If the cursor is already at the leftmost character in the screen field, a beep sounds.
	MASK	Same as above; however, if the character to the left of the cursor is a literal character, the cursor is moved left until another input character is encountered, and that character is deleted without altering any subsequent input characters.
Delete Character	Default	Deletes the input character at the cursor position. All screen field characters to the right of the cursor are shifted to the left. The cursor remains stationary. The prompt character (either as specified in the PROMPT phrase, or spaces if the PROMPT phrase was not specified) is used to pad the screen field on the right. If the cursor is positioned at the right margin when this key is pressed, and no characters are deleted, a beep sounds.
	MASK	Same as above; however, only input characters up to the next literal character to the right are shifted to the left.

Table 8-1 Edit Keys (*Cont.*)

Key	CONTROL Phrase	Action
Erase Entire	Default	Places the cursor at the leftmost field position, and fills all input positions with the prompt character, or spaces if the PROMPT phrase was not specified. Note that the Erase Entire key is not a field terminator.
	MASK	Same as above; however, literal characters in the mask are not overwritten.
Erase Remainder	Default	Without moving the cursor, fills all input positions from the current cursor position to the rightmost position of the screen field with the prompt character, or spaces if the PROMPT phrase was not specified. Note that the Erase Remainder key is also a field termination key.
	MASK	Same as above; however, literal characters in the mask are not overwritten.
Insert Character	Default	Initializes insert mode. Subsequent keystrokes insert characters at the cursor position. Screen field characters to the right of the cursor are shifted further to the right to accommodate the inserted characters. If an attempt is made to shift any character except for a space or a prompt character (if the PROMPT phrase was specified) beyond the rightmost input position of the screen field, a beep sounds. Insert mode is canceled when you press a field termination key or any screen field editing key other than Insert Character.
	MASK	Same as above; however, an attempt to shift an input character past a literal character specified in the mask is rejected and results in a beep.

Keys That Generate Field Termination Codes

Table 8-2 lists the keys that generate field termination codes and the corresponding codes. The table lists the default termination codes that the runtime system returns for the indicated PC keyboard keys and for the input sequences from the terminfo and termcap interfaces. The keys may be configured to perform different actions and return different codes (see page 10-49 for information on the TERM-INTERFACE configuration specifications).

An entry in brackets ([ ]) next to a terminfo or termcap entry identifies an alternate actual input sequence that will generate the same termination code under UNIX. These predefined input sequences are implied by the terminfo and termcap databases, as they have no defined terminfo or termcap name.

Note Any key not covered by footnote 1 in Table 8-2 causes the ON EXCEPTION imperative sequence.

The generic key name is described in the "EXCEPTION and NOT EXCEPTION Phrases" section of the ACCEPT statement in Chapter 6, *Procedure Division Statements*, of the *RM/COBOL Language Reference Manual*. See also Table 10-5 on page 10-48 of this guide for more information.

Table 8-2 Keys that Generate Field Termination Codes

PC Keyboard Key	Terminfo Name	Termcap Name	Generic Name	Termination Code
F1	kf1	k1	Function 1	01
F2	kf2	k2	Function 2	02
F3	kf3	k3	Function 3	03
F4	kf4	k4	Function 4	04
F5	kf5	k5	Function 5	05
F6	kf6	k6	Function 6	06
F7	kf7	k7	Function 7	07
F8	kf8	k8	Function 8	08
F9	kf9	k9	Function 9	09
F10	kf10	k;	Function 10	10
F11	kf11	F1	Function 11	11
F12	kf12	F2	Function 12	12
Shift+F1	kf11	F1	Function 11	11
Shift+F2	kf12	F2	Function 12	12
Shift+F3	kf13	F3	Function 13	13
Shift+F4	kf14	F4	Function 14	14
Shift+F5	kf15	F5	Function 15	15
Shift+F6	kf16	F6	Function 16	16
Shift+F7	kf17	F7	Function 17	17
Shift+F8	kf18	F8	Function 18	18
Shift+F9	kf19	F9	Function 19	19
Shift+F10	kf20	FA	Function 20	20
Ctrl+F1	kf21	FB	Function 21	21
Ctrl+F2	kf22	FC	Function 22	22
Ctrl+F3	kf23	FD	Function 23	23

[1] *Causes field termination but does not take the ON EXCEPTION imperative sequence.*

[2] *Performs the Erase Remainder.*

[3] *Normal STTY configuration to terminate the runtime system under UNIX.*

[4] *Terminates the runtime system under Windows. Also, the normal STTY configuration to terminate the runtime system under UNIX.*

Table 8-2 Keys that Generate Field Termination Codes *(Cont.)*

PC Keyboard Key	Terminfo Name	Termcap Name	Generic Name	Termination Code
Ctrl+F4	kf24	FE	Function 24	24
Ctrl+F5	kf25	FF	Function 25	25
Ctrl+F6	kf26	FG	Function 26	26
Ctrl+F7	kf27	FH	Function 27	27
Ctrl+F8	kf28	FI	Function 28	28
Ctrl+F9	kf29	FJ	Function 29	29
Ctrl+F10	kf30	FK	Function 30	30
Ctrl+Shift+F1	kf31	FL	Function 31	31
Ctrl+Shift+F2	kf32	FM	Function 32	32
Ctrl+Shift+F3	kf33	FN	Function 33	33
Ctrl+Shift+F4	kf34	FO	Function 34	34
Ctrl+Shift+F5	kf35	FP	Function 35	35
Ctrl+Shift+F6	kf36	FQ	Function 36	36
Ctrl+Shift+F7	kf37	FR	Function 37	37
Ctrl+Shift+F8	kf38	FS	Function 38	38
Ctrl+Shift+F9	kf39	FT	Function 39	39
Ctrl+Shift+F10	kf40	FU	Function 40	40
	kf41	FV	Function 41	41
	kf42	FW	Function 42	42
	kf43	FX	Function 43	43
	kf44	FY	Function 44	44
	kf45	FZ	Function 45	45
	kf46	Fa	Function 46	46
	kf47	Fb	Function 47	47
	kf48	Fc	Function 48	48
	kf49	Fd	Function 49	49
	kf50	Fe	Function 50	50
	kf51	Ff	Function 51	51
	kf52	Fg	Function 52	52
	kf53	Fh	Function 53	53

Table 8-2 Keys that Generate Field Termination Codes *(Cont.)*

PC Keyboard Key	Terminfo Name	Termcap Name	Generic Name	Termination Code
	kf54	Fi	Function 54	54
	kf55	Fj	Function 55	55
	kf56	Fk	Function 56	56
	kf57	Fl	Function 57	57
	kf58	Fm	Function 58	58
	kf59	Fn	Function 59	59
	kf60	Fo	Function 60	60
	kf61	Fp	Function 61	61
	kf62	Fq	Function 62	62
	kf63	Fr	Function 63	63
Enter [Ctrl+M][1]	cr [Ctrl+M]	cr [Ctrl+M]	Enter	13
Ctrl+Shift+K[1, 2]				13
→|	kc3 [Ctrl+I]	K5 [Ctrl+I]	Tab Right	58
Ctrl+A			Function 1	01
Ctrl+B			Function 2	02
Ctrl+C[4]			Function 3	03
Ctrl+D			Function 4	04
Ctrl+E			Function 5	05
Ctrl+F			Function 6	06
Ctrl+G			Function 7	07
Ctrl+I			Function 9	09 (58 on UNIX)
Ctrl+J			Function 10	10 (55 on UNIX)
Ctrl+K			Function 11	11
Ctrl+L			Function 12	12
Ctrl+N			Function 14	14
Ctrl+O			Function 15	15
Ctrl+P			Function 16	16
Ctrl+Q			Function 17	17

Table 8-2 Keys that Generate Field Termination Codes *(Cont.)*

PC Keyboard Key	Terminfo Name	Termcap Name	Generic Name	Termination Code
Ctrl+R			Function 18	18
Ctrl+S			Function 19	19
Ctrl+T			Function 20	20
Ctrl+U			Function 21	21
Ctrl+V			Function 22	22
Ctrl+W			Function 23	23
Ctrl+X			Function 24	24
Ctrl+Y			Function 25	25
Ctrl+Z			Function 26	26
Esc			Escape	27
Ctrl+[				27
Ctrl+\[3]				28
Ctrl+]				29
Ctrl+6				30
Ctrl+ –				31
Ctrl+Shift+C	kf0	k0	Command	40
Ctrl+Shift+A	ka3	K3	Attention	41
Ctrl+Shift+P	lf0	l0	Print	49
↑	kcuu1	ku	Up Arrow	52
↓	kcud1	kd	Down Arrow	53
Home	khome	kh	Home	54
Ctrl+Shift+N	nel [Ctrl+J]	nw [Ctrl+J]	New Line	55
|←	kc1	K4	Tab Left	56
Ctrl+Shift+E	kel	kE	Erase Remainder	57
Ctrl+Shift+R	kc3	k5	Tab Right	58
Ctrl+Shift+I	kil1	kA	Insert Line	59
Ctrl+Shift+D	kdl1	kL	Delete Line	61
Ctrl+Shift+S	kb2	K2	Send	64
Ctrl+←				65
Ctrl+→				66

Table 8-2 Keys that Generate Field Termination Codes *(Cont.)*

PC Keyboard Key	Terminfo Name	Termcap Name	Generic Name	Termination Code
PgUp	kpp	kP	Page Up	67
PgDn	knp	kN	Page Down	68
Ctrl+PgUp				69
Ctrl+PgDn				70
Ctrl+Shift+1				71
Ctrl+Shift+2				72
Ctrl+Shift+3				73
Ctrl+Shift+4				74
Ctrl+Shift+5				75
Ctrl+Shift+6				76
Ctrl+Shift+7				77
Ctrl+Shift+8				78
Ctrl+Shift+9				79
Ctrl+Shift+0				80
Ctrl+Home				81
End	ka1	K1	End	82
Ctrl+End	khlp	%1	Help	83
N/A	krdo	%0	Redo	84
Ctrl+Shift+ –				85
Ctrl+Shift+=				87

Table 8-3 lists the default semantic actions that the runtime system returns for input sequences from the different terminal interfaces under UNIX.

Table 8-3 Default Semantic Actions

Semantic Action	Terminfo Name	Termcap Name
Left Arrow	kcub1	kl
Right Arrow	kcuf1	kr
Backspace	kbs [Ctrl+H]	kb [Ctrl+H]
Set RM Insertion	kich1	kI
Delete Character	kdch1	kD
Erase Entire	kclr	kC
Erase Remainder[1]	kel	kE

[1] *This action also generates a termination code.*

ACCEPT and DISPLAY Phrases

The CONTROL, ERASE, HIGH, LOW, OFF, and REVERSE phrases affect the use of color attributes with the ACCEPT and DISPLAY statements. The SIZE phrase used with the ACCEPT and DISPLAY statements affects the size of the screen field. The TIME phrase is used to "time-out" the execution of a pending ACCEPT statement. These phrases are defined in the following paragraphs.

CONTROL Phrase

Some of the system dependencies that apply to the CONTROL phrase value concern color-capable terminals. Systems with monochrome terminals ignore color information contained in the CONTROL phrase value. (See the appropriate manufacturer's manual for information on configuring your system with color capability.)

Under UNIX, color requests are processed only if the terminal does not require an attribute byte and if one of the following conditions is met:

1. The terminfo database contains the set_foreground and set_background string sequences. (The back_color_erase and orig_pairs string sequences are not required.) The termcap database contains the **Sb** (set current background color) and **St** (set current foreground color) sequences.

2. A configuration record is present to force the use of ISO Set Graphics Rendition (SGR) sequences when the terminfo information is not available.

The method a terminal uses to process SGR color sequences will vary from one manufacturer to another. When color sequences are sent to monochrome terminals, they are either ignored, processed as shades of gray, or represented as characters on the screen. Color sequences sent to color-capable terminals may or may not conflict with other attributes sent to the terminal. For example, sending a color sequence followed by a blink sequence may result in the loss of the color request. RM/COBOL always sends color sequences after all other requested attributes. This prevents areas of the terminal screen from appearing without the desired color. You will need to refer to the terminal manufacturer and the UNIX terminfo documentation in order to determine the sequences necessary to access color capabilities. See Chapter 10, *Configuration*, for information on the color options of the TERM-ATTR configuration record.

RM/COBOL provides eight system-dependent keywords in the CONTROL phrase that affect an ACCEPT or DISPLAY field: FCOLOR, BCOLOR, GRAPHICS, MASK[1], PASS-THRU[1], PROMPT, REPAINT-SCREEN[1], and SCREEN-COLUMNS[1].

1. **FCOLOR = *color-name***

   When FCOLOR is present, *color-name* specifies the foreground color of the ACCEPT or DISPLAY field. This name is then used as the default value for subsequent ACCEPT and DISPLAY statements in the program.

   See the discussion of the HIGH, LOW and OFF phrases in the following section for information concerning high-intensity colors.

   The initial default for *color-name* is white.

   Note Under Windows, the default colors are determined by the Use Windows Colors property as described on page 3-29.

2. **BCOLOR = *color-name***

   When BCOLOR is present, *color-name* specifies the background color of the ACCEPT or DISPLAY field. This value is then used as the default value for subsequent ACCEPT and DISPLAY statements in the program.

   The initial default for *color-name* is black.

   Table 8-4 contains a list of all the possible names for *color-name*. The left column contains the valid color name. The right column shows the color that appears when high intensity is specified (the default intensity).

   Note Under Windows, the default colors are determined by the Use Windows Colors property as described on page 3-29.

---

[1] These keywords are supported only under RM/COBOL for UNIX.

Table 8-4 Valid COBOL Color Names

Valid Color Names	High-Intensity Color Values (Defaults)
Black	Gray
Blue	Light Blue
Green	Light Green
Cyan	Light Cyan
Red	Light Red
Magenta	Light Magenta
Brown	Yellow
White	High-Intensity White

3. **GRAPHICS**

The GRAPHICS keyword causes the characters in Table 8-5 to be translated to portable, system-specific line draw characters. Characters that are not listed in Table 8-5 are output unchanged.

Table 8-5 System-Specific Line Draw Characters

Description	Single-Line Character	Double-Line Character
lower-right corner	j(┘)	J(╝)
upper-right corner	k(┐)	K(╗)
upper-left corner	l(┌)	L(╔)
lower-left corner	m(└)	M(╚)
plus	n(┼)	N(╬)
horizontal line	q(─)	Q(═)
left tee	t(├)	T(╠)
right tee	u(┤)	U(╣)
bottom tee	v(┴)	V(╩)
top tee	w(┬)	W(╦)
vertical line	x(│)	X(║)

If the requested line draw characters are not available, the runtime system uses the best available characters. If double-line characters are requested and only single-line characters are available, they are used. If no line draw characters are available, then plus-characters, vertical bars, and dashes are used.

See page 2-21 for details on how the runtime system determines whether line draw characters are available for a given terminal under UNIX.

Here is a sample program that demonstrates how boxes are drawn:

```
 IDENTIFICATION DIVISION.
 PROGRAM-ID.  GRAPHXMP.
 PROCEDURE DIVISION.
 GRAPHXMP.
     DISPLAY " ", LINE 5 POSITION 1 ERASE.
* Single-line graphics
     DISPLAY "lqqqqwqqqqk", CONTROL "HIGH, GRAPHICS".
     DISPLAY "x    x    x", CONTROL "HIGH, GRAPHICS".
     DISPLAY "tqqqqnqqqqu", CONTROL "HIGH, GRAPHICS".
     DISPLAY "x    x    x", CONTROL "HIGH, GRAPHICS".
     DISPLAY "mqqqqvqqqqj", CONTROL "HIGH, GRAPHICS".
     DISPLAY " ".
* Double-line graphics
     DISPLAY "LQQQQWQQQQK", CONTROL "HIGH, GRAPHICS".
     DISPLAY "X    X    X", CONTROL "HIGH, GRAPHICS".
     DISPLAY "TQQQQNQQQQU", CONTROL "HIGH, GRAPHICS".
     DISPLAY "X    X    X", CONTROL "HIGH, GRAPHICS".
     DISPLAY "MQQQQVQQQQJ", CONTROL "HIGH, GRAPHICS".
 END PROGRAM GRAPHXMP.
```

4. **MASK**

A new keyword, MASK, has been added to the CONTROL phrase in ACCEPT and DISPLAY statements. Use the following format:

```
MASK = mask
```

Note The MASK keyword is ignored when standard input or standard output is redirected. This keyword is supported only under UNIX.

The MASK keyword in the CONTROL phrase causes a literal mask to be edited into the ACCEPT or DISPLAY screen field. Literal mask characters are inserted into the operand as it is transferred to the screen field if UPDATE is specified, or overlaid onto the screen field if ACCEPT-FIELD-FROM-SCREEN is in effect.

In all cases, the size of the mask determines the size of the actual ACCEPT or DISPLAY screen field. The optional SIZE phrase, or the size of the actual operand, is used only to limit the number of data characters that may be edited and entered into the ACCEPT screen field, or edited into the DISPLAY screen field prior to the screen operation.

The mask is specified in the CONTROL phrase as a literal string with no embedded spaces. If the mask specifies more input positions than are contained in the ACCEPT/DISPLAY operand, then excess mask input positions are replaced by literal spaces. The mask is limited to a total of 80 characters, including escape characters. When a screen field is edited, literal characters specified with the MASK keyword cannot be modified.

Table 8-6 lists the characters and character sequences that have special meanings in the MASK keyword in a CONTROL phrase string. All other characters are treated as literal characters.

Table 8-6 Characters Used with the MASK Keyword of a CONTROL Phrase

Character	Meaning
X	Specifies an input/output position. Characters will be accepted wherever an uppercase "X" appears in the mask. DBCS characters can be entered only into two, adjacent input positions.
_	Specifies a literal space.
\	Forces the following character to be treated as a literal character. The backslash character is the escape character.
\X	Specifies a literal "X".
_	Specifies a literal underscore.
\,	Specifies a literal comma.
\=	Specifies a literal equal sign.
\\	Specifies a literal backslash.

Note 1 The preceding characters are case-sensitive. For example, “x” is not the same as “X”.

Note 2 If a mask character overlays part of a double-byte (DBCS) character, the entire character is replaced by blanks.

When an ACCEPT operation that specifies the MASK keyword in a CONTROL phrase is processed, the RM/COBOL runtime takes the following actions:

a. If the operation is ACCEPT with UPDATE, characters from the operand are copied (from left to right) into mask input positions. Mask literal characters are skipped. If the operand is exhausted while there are still remaining input positions, such positions are changed to literal spaces. If the mask is exhausted before the operand, the remainder of the operand is ignored. The SIZE phrase, if specified, limits the size of the operand, not the size of the mask.

The size of the screen field is then set to the size of the mask, including trailing literal characters.

If PROMPT is also specified, trailing input positions that are initialized with spaces are replaced with the prompt character.

b. If ACCEPT without UPDATE is specified, and ACCEPT-FIELD-FROM-SCREEN is not in effect, mask input positions are initialized with spaces or with the prompt character, if PROMPT is specified. The number of mask input positions is still restricted, based on the SIZE phrase or the size of the operand.

c. If ACCEPT without UPDATE is specified, and ACCEPT-FIELD-FROM-SCREEN is in effect, mask input positions are initialized from the current screen field. In this case, there is a one-for-one correspondence between mask characters and screen characters; that is, the mask is overlaid rather than inserted into the screen field. If PROMPT is specified, trailing input positions that are initialized with spaces are replaced with the prompt character.

When the ACCEPT is terminated, the input field is scanned from left to right. Characters appearing in input positions only are copied into the ACCEPT operand. The operand is then processed by the CONVERT and UPPER phrases as if a regular ACCEPT operation had been performed.

Table 8-7 lists keywords and phrases that, when specified in ACCEPT and/or DISPLAY statements, have an effect on masked input processing.

Table 8-7 Effect of Certain Keywords and Phrases on Masked Input Processing

Keyword or Phrase	Effect
CURSOR	The CURSOR phrase in an ACCEPT statement specifies the input position, rather than the field position where the cursor is placed. It returns the input position occupied by the cursor when the ACCEPT statement is terminated.
GRAPHICS	The GRAPHICS keyword in the CONTROL phrase of an ACCEPT or a DISPLAY statement translates mask characters and input characters.
HIGH, LOW, HIGHLIGHT, LOWLIGHT	The presence of these phrases in an ACCEPT or a DISPLAY statement causes literal mask characters and input characters to be displayed at the specified intensity.
OFF, SECURE	When the OFF (SECURE) phrase is specified in an ACCEPT statement, literal mask characters are displayed, while input characters are not displayed.
PROMPT	When the PROMPT phrase is specified in an ACCEPT statement, trailing input positions are filled with the specified prompt character.
SIZE	When the SIZE phrase is specified in an ACCEPT or a DISPLAY statement, the size of the ACCEPT and DISPLAY operand is limited, but there is no effect on the screen field size.
TAB	If the TAB keyword is not specified in the CONTROL phrase of an ACCEPT statement (or the TAB phrase is not specified in an ACCEPT statement), field termination occurs when the cursor leaves the last input position, which may be followed by literal characters.

5. **PASS-THRU**

The ability to write escape sequences (such as pass-through printing) to the terminal with DISPLAY statements requires an additional keyword in the CONTROL phrase. The keyword, PASS-THRU, indicates that all data specified in the corresponding DISPLAY statement is to be written directly to the unit and not recorded in the in-memory image of the screen. Thus, if the DISPLAY statement causes the screen to change, the runtime system will have no knowledge of the change, and subsequent DISPLAY statements may cause confusion for the terminal operator.

This ability also can be used automatically by specifying a TERM-ATTR PASS-THRU-ESCAPE configuration file record. If used, any DISPLAY statements beginning with one of the escape characters will behave as if PASS-THRU were specified in the statement. See page 10-39 for more information.

Note This keyword is supported only under UNIX.

6. **PROMPT = *prompt-char***

   The PROMPT keyword causes ACCEPT statements to accept data with fill characters in positions from which data is to be accepted. Optionally, the PROMPT keyword may specify *prompt-char*, which causes the ACCEPT operation to use a prompt character different from the system default. *prompt-char* must be a single, literal character. For example:

   ```
   ACCEPT FOO CONTROL "PROMPT=*,TAB".
   ```

   where asterisk (*) is the *prompt-char*.

7. **REPAINT-SCREEN**

   The REPAINT-SCREEN keyword causes the entire screen to be refreshed from the runtime system's in-memory screen image. Any characters that were written directly to the screen, such as from C routines or DISPLAY statements with the PASS-THRU keyword (which are not recorded in the in-memory screen image), are replaced by the last value written to that location by regular DISPLAY statements. This provides the ability to clean up the screen without manually having to redraw the entire display. REPAINT-SCREEN may be used in both ACCEPT and DISPLAY statements. It is also callable from linked C routines (see page D-23 in Appendix D, *Customizing RM/COBOL for UNIX*).

   Note This keyword is supported only under UNIX.

8. **SCREEN-COLUMNS = *screen-width***

   The SCREEN-COLUMNS keyword instructs the runtime system to change the current display state of the user's terminal to accommodate the requested screen size. Screen-width values of 80 and 132 are currently supported.

   Changing the terminal state produces a new, blank screen of the requested screen width. All characters and windows on the original display are erased. In order to maintain valid user-defined window control blocks, programs using pop-up windows must close all pop-up windows before changing the screen size.

   Most terminals support varying screen dimensions through normal and wide terminfo and termcap entries. These normally correspond to 80 and 132 columns, respectively. When a screen dimension change is requested, the runtime system switches the TERM environment variable to the appropriate value and then sends reset or initialization strings that change the terminal's state. For terminfo, the strings are defined with the capabilities **rs1**, **rs2**, and **rs3**. For termcap, the strings are defined with the capabilities **r1**, **r2**, and **r3**. If these termcap capabilities are not defined, the runtime system attempts to use the capability **is**. If these strings are not set correctly, the terminal may be changed to an unpredictable state.

Most UNIX systems append a "–w" to terminal descriptions to indicate a terminal's wide screen mode. For example, the wyse60 terminal description for wide displays is normally referred to as wyse60–w. Because not all UNIX systems follow this standard, the COBOL runtime allows users to use the RMTERM80 and RMTERM132 environment variables. If both variables are set, the runtime system changes the TERM environment variable to the appropriate name, as specified in RMTERM80 or RMTERM132. For example, some systems append "w" to wide terminal descriptions. RMTERM132 can be used to ensure proper behavior by setting it as RMTERM132=wyse60w.

Note This keyword is supported only under UNIX.

ERASE Phrase

All valid ERASE options (that is, ERASE, ERASE EOL, and ERASE EOS) erase the screen with the specified background color, if possible. Under UNIX, if the back_color_erase termcap or terminfo capability is set to false, or the appropriate termcap or terminfo capability to perform the specified ERASE operation is not available, blanks will be used to perform the operation.

HIGH Phrase

HIGH specifies that the foreground color be the corresponding high-intensity color listed in Table 8-4 on page 8-13.

Under UNIX, when the HIGH phrase is present, the termcap capabilities used to set the attributes of the terminal are **nM**, **nB**, **nR** or **nS**. The terminfo capabilities are **sgr0**, **blink**, **rev** or **sgr**. The capability used is determined by the BLINK and REVERSE phrases, and by the definition of termcap or terminfo capabilities in the terminal database.

When used with a color monitor under UNIX, the HIGH phrase specifies that the foreground color be the high-intensity color from Table 8-4 that corresponds to the foreground color name. If the REVERSE phrase is also present in the statement, it takes precedence over the HIGH phrase. That is, any reversal of colors takes place before the intensity is determined.

LOW Phrase

LOW specifies that the foreground color be the default foreground color unless overridden with the FCOLOR keyword.

When the LOW phrase is present under UNIX, the termcap capabilities used to set the attributes of the terminal are **aL**, **aB**, **aR**, or **aS**. The terminfo capabilities are **dim** or **sgr**. The capability used is determined by the BLINK and REVERSE phrases, and by the

definition of termcap or terminfo capabilities in the terminal database. The BLINK and REVERSE phrases are not supported by a terminfo runtime system unless the **sgr** capability is available.

If the REVERSE phrase is also present in the statement, it takes precedence over the LOW phrase, that is, any reversal of colors takes place before the intensity is determined.

OFF Phrase

OFF specifies that the background color be used for the foreground color. During field editing for ACCEPT operations, the cursor is moved as specified, but without character echoing.

If the REVERSE phrase is also present in the statement, it takes precedence over the OFF phrase; that is, any reversal of colors takes place before the background color is determined.

SECURE is a synonym for OFF.

REVERSE Phrase

When the REVERSE phrase is present, the specified (or default) foreground color is used as the background color, and the background color is used as the foreground color. The REVERSE phrase is processed before the HIGH, LOW, and OFF phrases.

SIZE Phrase

The SIZE phrase is used to specify the size of an ACCEPT or DISPLAY field. The runtime system imposes the following restrictions and limitations on the value of the SIZE phrase:

1. The size of an ACCEPT or DISPLAY field must not exceed the number of characters that can appear on the screen at one time, minus the column of the first character of the data item.

2. The ACCEPT or DISPLAY field must not exceed the size of the associated buffer: the default is 264 (see the discussion of the B Runtime Command Option on page 7-4).

3. Fields that extend beyond the physical right margin of the screen wrap around to the next line.

4. Fields that extend beyond the last line of the screen cause the screen to scroll one line.

TIME Phrase

The BEFORE TIME phrase is used to "time-out" the execution of a pending ACCEPT statement. The value of *literal-8* or *identifier-8* in the BEFORE TIME phrase represents the time-out value in hundredths of seconds. The time-out value is limited to 23 hours, 59 minutes, 59.99 seconds (or 8,639,999). A value greater than 8,639,999 and less than or equal to 4,294,967,295 ($2^{**32} - 1$) is set to 8,639,999.

A time-out value of 0 indicates that the ACCEPT operation should terminate immediately if there is no character waiting. A time-out value greater than 4,294,967,295 (a PIC 9(10) data item set to a value of 9999999999 is recommended) indicates that the BEFORE TIME phrase is being overridden and the ACCEPT statement will behave as if the BEFORE TIME phrase were not specified.

When the ACCEPT statement is executed, a target time is calculated as the sum of the current time and the time-out value. The time-out operation runs until the target time is reached or a key is pressed. Once a key has been pressed, the time-out function is disabled.

If the target time is reached before a key has been pressed, the ACCEPT statement is terminated. A termination code of 99 is returned in *identifier-9* if the ON EXCEPTION phrase is specified.

The BEFORE TIME phrase is intended for terminal input and it is not available if input is redirected.

Under UNIX, if the CHARACTER-TIMEOUT keyword of the TERM-ATTR configuration record has a value (see page 10-36), it will affect the BEFORE TIME phrase of the ACCEPT statement. The actual time-out value will be the first integral multiple of the CHARACTER-TIMEOUT value that is greater than or equal to the value specified in the ACCEPT BEFORE TIME phrase.

Pop-Up Windows

A COBOL program can create one or more pop-up windows on the terminal output device. A pop-up window (referred to hereinafter as a window) is a temporary subscreen within the terminal screen to which all terminal output is directed. The rules concerning placement of data and default video attributes that apply to full screen input/output also apply to the window (including wrapping and scrolling). Thus the window performs just like a full screen, except that a window is usually smaller.

A window is used for terminal input/output from the time it is created until the window is removed by the COBOL program or another window is created. When a window is

removed, the contents that occupied the window area before it was created are restored, and the previous window again becomes the active subscreen. All current defaults that are associated with the newly restored window, such as the current video attributes, the current line, and the current position, are restored.

Note Only information written to the screen by the RM/COBOL runtime system can be restored to the screen in the event that it is covered by a window that is later removed.

For examples on using the RM/COBOL Pop-Up Window Manager, see your installation directory and examine the following programs:

- **wintest.cbl**
- **winattrb.cbl**
- **winbordr.cbl**
- **wincolor.cbl**
- **winreltv.cbl**
- **winstat.cbl**
- **wintitle.cbl**

Creating Pop-Up Windows

A window is created by a Format 2 DISPLAY statement containing the WINDOW-CREATE keyword in its CONTROL phrase. See the description of the DISPLAY statement (terminal I-O) in Chapter 6, *Procedure Division Statements*, of the *RM/COBOL Language Reference Manual*. The general format of a DISPLAY statement used to create a window is shown below.

Note The format shown is a subset of the Format 2 DISPLAY Terminal I-O statement because some options of the complete statement are not applicable to window creation.



identifier-1 specifies the window control block for the window creation. See pages 8-24 and 8-27 for more information.

BEEP Phrase

The presence of the BEEP phrase in the DISPLAY statement causes the audio alarm signal to occur at the creation of the window. If the BEEP phrase is omitted, no signal is given.

BELL is a synonym for BEEP.

BLINK Phrase

The presence of the BLINK phrase causes the border, title, and fill characters of the window to appear in a blinking mode. If the BLINK phrase is not specified, the border, title, and fill characters appear in a nonblinking mode.

Note The blinking attribute is not available under Windows.

CONTROL Phrase

A DISPLAY statement with a CONTROL phrase containing the WINDOW-CREATE keyword (see discussion of the CONTROL phrase of the DISPLAY statement in Chapter 6, *Procedure Division Statements*, of the *RM/COBOL Language Reference Manual*) causes *identifier-1* to be treated as a window control block, and this data item must have the structure described in "Pop-Up Window Control Block" on page 8-27. The window is created according to the specifications given in the window control block. The window control block provided must not be that of an active window.

The FCOLOR and BCOLOR keywords can be used to set the colors of the border characters, title characters, and fill characters of the window being created. FCOLOR specifies the foreground color of each character, and BCOLOR defines the background color. FCOLOR and BCOLOR also establish the initial default colors for ACCEPT and DISPLAY statements performed while the window is active. See Table 8-4 on page 8-13 for valid color names. If FCOLOR and BCOLOR are not specified when creating a window, the default colors (if any) in effect when the window creation is requested are carried over to the new window.

Additional keywords that may be specified in the CONTROL phrase and that affect the creation of the window include: HIGH, LOW, BLINK, NO BLINK, REVERSE, NO REVERSE, ERASE, NO ERASE, BEEP, and NO BEEP. The meanings of these keywords when they appear in the value of the CONTROL phrase operand are the same as the corresponding phrases that may be written as static options of the DISPLAY statement, with the addition of the negative forms to allow suppression of statically declared options. The window creation effects of the static phrases and the corresponding CONTROL phrase keywords are described in the following paragraphs.

ERASE Phrase

The presence of the ERASE phrase causes the window area to be erased upon creation of the window.

Note Using the EOS or EOL reserved words with ERASE causes the ERASE phrase to be ignored.

HIGH and LOW Phrases

The presence of the HIGH or LOW phrase causes the border, title, and fill characters of the window to be painted at the specified intensity. When HIGH or LOW is not specified, the default intensity is HIGH.

HIGHLIGHT is a synonym for HIGH and LOWLIGHT is a synonym for LOW.

Note Under Windows, the HIGH and LOW phrases do not affect the border or the title of the window.

LINE and POSITION Phrases

The window is painted on the screen with LINE 1 and POSITION 1 of the window positioned at the LINE and POSITION specified in the DISPLAY statement creating the window. See "Defining the Location of the Pop-Up Window" on page 8-28 for further discussion of the placement of the window. LINE 1, POSITION 1 of the window is limited to the boundaries of the screen.

If requested, the border occupies the lines immediately above and below the window, and the columns immediately to the right and to the left of the window. If a title is requested, it will be painted within the top or bottom border. If a title is requested and a border is not requested, the title will occupy the line either immediately above or immediately below the window.

If the LINE or POSITION phrase is omitted from the DISPLAY statement, the line and position values for the window are determined in the same manner as the line and position values in a non-window Format 2 DISPLAY statement, except that the ERASE phrase and the window dimensions are not considered (see the section "Determining Line and Position" for the DISPLAY statement in Chapter 6, *Procedure Division Statements,* of the *RM/COBOL Language Reference Manual*).

COLUMN and COL are synonyms for POSITION.

REVERSE Phrase

The presence of the REVERSE phrase causes the border, title, and fill characters of the window to appear in a reverse video mode. If the REVERSE phrase is not specified, the border, title, and fill characters appear in the normal video mode.

REVERSED and REVERSE-VIDEO are synonyms for REVERSE.

Note Under Windows, the REVERSE phrase does not affect the border or the title of the window.

UNIT Phrase

The UNIT phrase, if specified, must be written first. The other phrases may be written in any order. If not running under UNIX, the value of *identifier-2* or *literal-2* in the UNIT phrase is ignored. Under UNIX, the value of *identifier-2* or *literal-2* specifies the terminal upon which the window is to be created. If the UNIT phrase is omitted, the terminal that started the run unit is used.

Removing a Pop-Up Window

A window is removed by a Format 2 DISPLAY statement (see the description of the "DISPLAY Statement" in Chapter 6 of the *RM/COBOL Language Reference Manual*) containing the WINDOW-REMOVE keyword in its CONTROL phrase. The general format of a DISPLAY statement used to remove a window is shown below.

Note The format shown is a subset of the Format 2 DISPLAY statement because some options of the complete statement are not applicable to window removal.



identifier-1 specifies the window control block for the window creation. See pages 8-23 and 8-27 for more information.

CONTROL Phrase

A DISPLAY statement with a CONTROL phrase containing the WINDOW-REMOVE keyword (see discussion of the CONTROL phrase of the DISPLAY statement in Chapter 6 of the *RM/COBOL Language Reference Manual*) causes *identifier-1* to be treated as a window control block, and causes the active window to be removed. The window control block should be the same one used to create the window; it must not be that of a different active window.

UNIT Phrase

The UNIT phrase, if specified, must be written first. The other phrases may be written in any order. If not running under UNIX, the value of *identifier-2* or *literal-2* in the UNIT phrase is ignored. Under UNIX, the value of *identifier-2* or *literal-2* specifies the terminal upon which the window is to be created. If the UNIT phrase is omitted, the terminal that started the run unit is used.

Pop-Up Window Control Block

The following is an example of a window control block in a COBOL program. The order of the fields, the PICTURE character-string, and the declared usage in the example are fixed parameters that cannot be changed when defining a window control block. The data-names and contents of the fields in the example are variable and thus may be changed.

```
01 WINDOW-CONTROL-BLOCK.
   03 WCB-HANDLE                   PIC 999 BINARY(2)
                                     VALUE 0.
   03 WCB-NUM-ROWS                 PIC 999 BINARY(2).
   03 WCB-NUM-COLS                 PIC 999 BINARY(2).
   03 WCB-LOCATION-REFERENCE       PIC X.
      88 WCB-SCREEN-RELATIVE         VALUE "S".
      88 WCB-WINDOW-RELATIVE         VALUE "W".
   03 WCB-BORDER-SWITCH            PIC X.
      88 WCB-BORDER-ON               VALUE "Y" FALSE "N".
   03 WCB-BORDER-TYPE              PIC 9.
      88 WCB-BORDER-WCB-CHAR         VALUE 0.
      88 WCB-BORDER-PLUS-MINUS-BAR   VALUE 1.
      88 WCB-BORDER-LINE-DRAW        VALUE 2.
      88 WCB-BORDER-DBL-LINE-DRAW    VALUE 3.
   03 WCB-BORDER-CHAR              PIC X.
   03 WCB-FILL-SWITCH              PIC X.
      88 WCB-FILL-ON                 VALUE "Y" FALSE "N".
   03 WCB-FILL-CHAR                PIC X.
   03 WCB-TITLE-LOCATION           PIC X.
      88 WCB-TITLE-TOP               VALUE "T".
      88 WCB-TITLE-BOTTOM            VALUE "B".
   03 WCB-TITLE-JUSTIFICATION      PIC X.
      88 WCB-TITLE-CENTER            VALUE "C".
      88 WCB-TITLE-LEFT              VALUE "L".
      88 WCB-TITLE-RIGHT             VALUE "R".
   03 WCB-TITLE-LENGTH             PIC 999 BINARY(2).
      88 WCB-TITLE-LENGTH-COMPUTE    VALUE 0.
   03 WCB-TITLE                    PIC X(40).
```

Identifying the Pop-Up Window

The field WCB-HANDLE is initialized by the WINDOW-CREATE DISPLAY operation to contain a value that identifies the window. This field must be set to zero before the WINDOW-CREATE operation. The value that was placed in this field following the WINDOW-CREATE operation must be in the WCB-HANDLE field when the WINDOW-REMOVE DISPLAY operation is performed to remove the window. The only other value that is allowed is zero, which removes the active window.

Note The use of zero is allowed for compatibility with previous versions of the Pop-Up Window Manager, but it is strongly discouraged.

Defining the Size of the Pop-Up Window

The parameters WCB-NUM-ROWS and WCB-NUM-COLS define the number of rows and columns available for ACCEPT and DISPLAY statements within the window. If the window is to have a border, it will occupy two additional rows and two additional columns on the screen. If the window has a title but does not have a border, the window occupies one additional line on the screen.

Defining the Location of the Pop-Up Window

The WCB-LOCATION-REFERENCE parameter determines whether the LINE and POSITION in the DISPLAY statement used to create the window describes a location relative to the physical screen or the active window. A value of S indicates the location is relative to the physical screen. A value of W indicates the location is relative to the active window.

The created window is limited to the boundaries of the screen, not to the boundaries of the active window.

Defining the Border of the Pop-Up Window

The parameter WCB-BORDER-SWITCH determines whether a border should be painted around the window. A value of Y indicates that a border is to be painted. A value of N indicates that a border is not to be painted.

The parameter WCB-BORDER-TYPE determines what characters are used to make up the border. A value of 0 indicates that the character specified by WCB-BORDER-CHAR is used to paint the border. A value of 1 indicates that the plus sign, hyphen, and vertical bar characters (+, –, |) are used to paint the border. A value of 2 in the WCB-BORDER-TYPE field indicates that graphic line draw characters are used to paint the border. A value of 3 in the WCB-BORDER-TYPE field indicates that graphic double-line line draw characters are used to paint the border. If the terminal does not

support line draw graphics characters, the border will be drawn using normal characters (+, –, |). This field is ignored unless WCB-BORDER-SWITCH has a value of Y.

The WCB-BORDER-CHAR parameter determines the character to be used in building the border around the window. This field is ignored unless WCB-BORDER-SWITCH has a value of Y and WCB-BORDER-TYPE has a value of 0.

Note The WCB-BORDER-CHAR and WCB-BORDER-TYPE parameters are ignored under Windows.

Initializing the Pop-Up Window Area

WCB-FILL-SWITCH determines whether the window should be filled with the character defined by WCB-FILL-CHAR when it is created. If the window is not filled, then the contents in the defined window area remain untouched until modified by a subsequent ACCEPT or DISPLAY statement in the window. A value of Y indicates that the window area be filled with the defined character. A value of Y will also cause an ERASE phrase to be ignored. A value of N indicates that the window area is to be left unchanged.

The parameter WCB-FILL-CHAR determines the character to be used to fill the window area. This field is ignored unless WCB-FILL-SWITCH has a value of Y.

Defining the Location of the Title of the Pop-Up Window

The parameter WCB-TITLE-LOCATION determines whether the text in WCB-TITLE should be placed within the location of the top border or bottom border. A value of T indicates that the title is to be painted at the top of the window. A value of B indicates that the title is to be painted at the bottom of the window. This field is ignored if WCB-TITLE-LENGTH has a value of zero and WCB-TITLE is filled with spaces.

The WCB-TITLE-JUSTIFICATION parameter determines whether the text of the title should be centered, left-justified, or right-justified in its location at the top or bottom of the window. A value of C indicates that the title should be centered, L indicates that it should be left justified, and R indicates that the window should be right justified. This field is ignored if WCB-TITLE-LENGTH has a value of zero and WCB-TITLE is filled with spaces.

Note The WCB-TITLE-JUSTIFICATION and WCB-TITLE-LOCATION parameters are ignored under Windows.

Defining the Title of the Pop-Up Window

The length of the title is defined by the value of the WCB-TITLE-LENGTH parameter. If the value of this field is non-zero, WCB-TITLE-LENGTH indicates the number of characters, beginning with the first character of the WCB-TITLE field, that are to be used as the title of the window. If the value of this field is zero, the title string is made up of all characters between the first character of the WCB-TITLE field to the last non-blank character in the field.

The WCB-TITLE parameter defines the text to be placed in the title of the window. This field may be any length sufficient to contain the desired title, and must be the last data item in the window control block. The length of 40 specified in the example is an arbitrary value.

Pop-Up Window Operation Status

The COBOL program can obtain the status of a window operation immediately after a request is made to create or remove a window. The ACCEPT FROM EXCEPTION STATUS statement places the status in the field designated by *identifier-1*. The general format of the ACCEPT FROM EXCEPTION STATUS statement is shown below.

ACCEPT *identifier-1* FROM EXCEPTION STATUS [END - ACCEPT]

The information requested is transferred from EXCEPTION STATUS to *identifier-1* according to the rules of the MOVE statement (see the discussion of the MOVE statement in Chapter 6, *Procedure Division Statements*, of the *RM/COBOL Language Reference Manual*). EXCEPTION STATUS is an implicitly defined data item that behaves as if it had been defined in the Data Division as an unsigned, three-digit, numeric integer data item.

Table 8-8 is a list of the error codes and values returned to the COBOL program after a request is made to create or remove a window.

Table 8-8 Pop-Up Window Error Codes

Code	Description
0	Operation successfully completed.
301[1]	Window border or title does not fit on screen.
302[1]	Title is too long for window or specified title length is longer than the title field in the window control block.
303[1]	Requested window will not fit on screen.
304	No windows are active.
305	Window manager is not available.
306	Out of memory.
307	Too many windows.
308	Buffer I/O error.
309	Requested REMOVE-WINDOW for inactive WCB.
310	CREATE-WINDOW requested with active WCB.
311	Invalid parameter in WCB.

[1] *These error codes are reported differently under Windows than under UNIX, or they are not reported.*

COPY Statement

Use the COPY statement to copy RM/COBOL source text from a specified file into the source program. The text copied may have been created outside RM/COBOL, either through a text editor or through some other process. The file is copied at the point at which the COPY statement appears in the program; the file logically replaces the COPY statement.

A copied file may in turn contain COPY statements, up to the limits of either five (the typical case) or nine (if the last statement in the copy file is a COPY statement).

See the discussion of the COPY statement in Chapter 1, *Language Structure*, of the *RM/COBOL Language Reference Manual*, for a description of the syntax and field definitions.

Filenames that are not reserved words and that are made up of valid RM/COBOL alphabetic, numeric and special characters do not need to be enclosed in quotation marks within the COPY statement. Filenames that are reserved words or contain characters other than the standard set must be specified as a nonnumeric literal (that is, they must be enclosed in quotation marks). A period followed by a space terminates the COPY statement (that is, it is not considered part of a text-name or a library-name).

If a library-name is specified in the COPY statement, it is treated as a pathname for the filename.

If you do not enter a filename extension with the filename, the compiler assumes an extension of **.cbl**. If it cannot find such a file, it then looks for a file with the supplied name with the extension **.CBL**. The assumed extension can be changed with the EXTENSION-NAMES configuration record (see page 10-19). For all attempts to open the copied file, if a directory path or a drive letter is not specified, the directory search sequence is used to try to locate the file (see the discussion of search sequences that begins on either page 2-4 for UNIX or page 3-11 for Windows).

Here are three examples of valid COPY statements.

```
IDENTIFICATION DIVISION.
COPY STDID.
```

The preceding COPY statement copies the file **stdid.cbl** from the path specified by RMPATH.

```
ENVIRONMENT DIVISION.
COPY "cobol".
```

The preceding COPY statement copies the file **cobol.cbl** from the path specified by RMPATH (see the discussion of RMPATH in the appropriate installation and system considerations chapter in this user's guide for your specific operating system).

```
COPY data1 OF lib1.
```

The preceding COPY statement copies the file **lib1/data1.cbl** relative to the current directory.

STOP RUN Numeric Statement and RETURN-CODE Special Register

When a run unit terminates, a numeric value—termed an exit code—is returned to the operating system. The exit code is made up of the low-order eight bits of the binary RETURN-CODE special register.

At the start of the run unit, the RETURN-CODE special register is initialized to zero. The program may change the RETURN-CODE special register value by using it as the destination of a MOVE statement or arithmetic verb, or by using the "STOP RUN numeric" form of the STOP RUN statement. Certain program exit codes (as described on page 7-8) are used by the runtime system to indicate error conditions. Use of these values should be avoided in the program.

CALL Statement

The CALL statement transfers control to a contained RM/COBOL subprogram, to an external RM/COBOL subprogram, or to a non-COBOL subprogram. Called subprograms may themselves call other subprograms during the course of execution.

There are certain regulations that must be observed before RM/COBOL subprograms or non-COBOL subprograms can be called:

1. The RM/COBOL subprogram must have been compiled.

2. Under UNIX, the non-COBOL subprogram must have been compiled and linked with the runtime system and must conform with the rules set forth in Appendix D, *Customizing RM/COBOL for UNIX*. Under Windows, the non-COBOL subprogram must be contained in a dynamic link library (DLL) and the non-COBOL subprogram must conform with the rules set forth in the "Alternate Method of Preparing Non-COBOL Subprograms Under Windows" appendix in the *CodeBridge* manual.

3. The name specified in the CALL statement must be complete enough to search for and locate the program.

A called subprogram is loaded and is in its initial state in the following instances: the first time it is called in the run unit; the first time it is called after execution of a CANCEL statement identifying the program that directly or indirectly contains the subprogram; every time the subprogram is called if it possesses the initial attribute; and the first time the subprogram is called after the execution of a CALL statement identifying a program that possesses the initial attribute and that directly or indirectly contains the subprogram.

In all other entries into the called subprogram, the state of that program is unchanged from its state when last exited.

Called RM/COBOL subprograms remain in memory until implicitly or explicitly canceled. Under UNIX, since the subprogram is linked with the runtime system, memory is not recovered. A called subprogram is implicitly canceled in only two cases. A called subprogram with the initial attribute (that is, one with the INITIAL clause specified in the PROGRAM-ID paragraph) is implicitly canceled whenever it executes an EXIT PROGRAM statement, and is therefore in its initial state every time it is called. All programs associated with a run unit are implicitly canceled when the run unit terminates. In all other cases, an explicit CANCEL statement identifying the program is required in order to cancel it.

Subprogram Loading

When a CALL statement is executed, the program name (the value of *identifier-1* or *literal-1* as defined in the discussion of the CALL statement in Chapter 1, *Language Structure*, of the *RM/COBOL Language Reference Manual*) determines the subprogram to which control is transferred. This is done in the following order:

1. **If the program name matches the value of *program-name* or *literal* as specified in the PROGRAM-ID paragraph** of a program directly contained in the calling program or of a program possessing the common attribute that is directly contained in a program that directly or indirectly contains the calling program, control is transferred to that program.

2. **If a program has been loaded and not canceled**, and is called again by the same program name, control is transferred to that program.

3. **If the program name matches the value of *program-name* or *literal*** (see the *RM/COBOL Language Reference Manual*) **as specified in the PROGRAM-ID paragraph of a program in an RM/COBOL program library**, the program is loaded and control transferred to it. Remember, at the point of loading, the program is in its initial state. In the same manner, if the program name matches a called name literal in a non-COBOL subprogram library (see Appendix D in this user's guide or the "Alternate Method of Preparing Non-COBOL Subprograms Under Windows" appendix in the *CodeBridge* manual), control transfers to the subprogram associated with the called name literal.

   Libraries—both RM/COBOL and non-COBOL—are searched in the order specified by the L Runtime Command Option (see page 7-6). The first program name matched is the only one considered during program loading. Under UNIX, program names linked in C libraries are searched after all RM/COBOL libraries.

4. **If the program name matches the name of a subprogram in the RM/COBOL subprogram library**, control transfers to that subprogram. See Appendix F, *Subprogram Library*, for a description of the RM/COBOL subprogram library.

5. **If the program name contains no extension**, a default filename extension of first **.cob** and then **.COB** is added to the name before beginning the search for a valid program file. If such a file exists and contains only one object program, the program is loaded and control is transferred to that program, regardless of the name in its PROGRAM-ID paragraph. The default extension can be changed with the EXTENSION-NAMES configuration record (see page 10-19).

6. **Under Windows, if the program name specifies a filename extension .dll**—or if it specifies no filename extension at all—the filename extension **.dll** is used with the filename before starting the search for a valid non-COBOL subprogram file. If such a file exists, it is loaded and control is transferred to that program as described in Appendix B, *Alternate Method of Preparing Non-COBOL Subprograms Under Windows*, of the *CodeBridge* manual.

7. **If the program name does not specify a filename extension**, or if the program name specifies a filename extension other than **.dll** (under Windows), the program name is used to search for a valid RM/COBOL program file. If such a file exists, and contains only one object program, the program is loaded and control is transferred to it, regardless of the name in its PROGRAM-ID paragraph.

8. **If the program name cannot be found,** an exception condition occurs. This condition may be detected by the calling program with the ON EXCEPTION or ON OVERFLOW phrase. If the calling statement does not contain the ON EXCEPTION or ON OVERFLOW phrase, execution ends.

Steps 5 through 7 search the environment for a match with the name used in each step. If an environment variable name matches the name in one of those steps, the value of the environment variable replaces that name in that step for the purpose of locating the file. Steps 5 through 7 also use the RUNPATH directory search sequence as described on either page 2-4 for UNIX or page 3-11 for Windows. RM/COBOL for Windows searches for dynamic link libraries (DLLs) specified without a drive or path specification in the following order:

1. The directory from which the application executable was loaded; for example, the directory containing **runcobol.exe**.

2. The directory from which the COM server DLL was loaded; for example, the directory containing **rmcblrun.dll**.

3. The current working directory.

4. The Windows System directory (or directories on NT); for example, **c:\windows\system**.

5. The Windows directory; for example, **c:\windows**.

6. The directories listed in the PATH environment variable.

7. The directories listed in the RUNPATH environment variable.

The use of contained programs and program libraries eliminates Steps 5 through 7. In the case of RM/COBOL program libraries, the I/O overhead of searching for the program file is minimized.

External Objects

A source program may use the EXTERNAL clause to declare three types of external objects:

1. **Data records**, named by record-names

2. **File connectors**, named by file-names

3. **Indexes**, named by index-names

See the discussion of the EXTERNAL clause in Chapter 4, *Data Division,* of the *RM/COBOL Language Reference Manual* for more details.

During execution of a run unit, the runtime system maintains a list of external objects. The list is established as being empty when the run unit begins. When an object program is loaded, the names of external objects it declares are checked for a match—of both name and type—against the list of external objects. If both name and type match, the declared external objects and existing external objects are considered references to the same object. The declared object is then checked to determine whether it matches the description of the external object. A mismatch in the description terminates execution and displays an error message. If either name or type does not match, the declared external object is allocated and added to the list. If there is not enough memory to load the object, execution ends and an error message appears.

The determination of matching descriptions depends on the type of object file:

1. **Data Records.** The record-name for both objects must be described with the same number of character positions.

2. **File Connectors.** The file-name for both objects must be described as follows:

   - The file organization specified in the ORGANIZATION clause, that is, SEQUENTIAL, RELATIVE, or INDEXED, must be the same.

     – If the organization is sequential, both objects must agree on the presence or absence of LINAGE and PADDING CHARACTER.

     – If the organization is relative, both objects must declare the same external data item as the relative key data item, or must omit specification of a relative key data item.

     – If the organization is indexed, both objects must declare the same number of record keys at the same positions in the record, and must agree on the presence or absence of a COLLATING SEQUENCE clause. Both objects must have the same COLLATING SEQUENCE clause, if the clause is present. In addition, if split keys are present, both objects must have the same split key clauses.

   - The access mode specified in the ACCESS MODE clause must be the same.

   - The presence or absence of the OPTIONAL phrase in the SELECT clause of the file control entry must be the same.

   - The number of input-output areas specified in the RESERVE clause must be the same.

   - The alphabet specified in the CODE-SET clause of the file control entry or the file description entry (RM/COBOL allows the CODE-SET clause in either entry) must be the same.

   - The BLOCK CONTAINS clause in the file description entry must specify the same minimum and maximum values, and must agree on whether these are expressed in CHARACTERS or RECORDS.

   - The RECORD clause in the file description entry must specify the same minimum and maximum record size.

   - The LABEL RECORDS clause in the file description entry must specify the same property of OMITTED or STANDARD.

3. **Indexes.** The index-name for both objects must be associated with the same external data record. Both index-names must be associated with table items that span the same number of character positions.

Note It is recommended that source programs use COPY statements to copy a common definition of an external object in order to avoid mismatched external object descriptions.

Once an external object is added to the runtime-maintained list, it remains in existence until the end of the run unit. Execution of a CANCEL statement identifying a program that describes an external object does not affect the allocation, contents or state of the external object. For external file connectors left in an open mode, the runtime system closes the file when the run unit terminates but not when a program describing the file is canceled.

File Sharing

RM/COBOL supports shared environments[1], which allow files to be shared by two or more users. This includes allowing two or more users to have a file open simultaneously and apply updates to that file. The FORCE-USER-MODE keyword of the RUN-FILES-ATTR configuration record (see page 10-28) can force files not to be shared.

The WITH LOCK phrase may be used on the OPEN statement to restrict the use of a file by other users during the period the file is open. When used on an OPEN I-O, OUTPUT or EXTEND statement, the WITH LOCK phrase prevents other RM/COBOL users from opening the file. When used on an OPEN INPUT statement, the WITH LOCK phrase prevents other RM/COBOL users from opening the file I-O, OUTPUT or EXTEND. When the WITH LOCK phrase is used, file performance is improved by eliminating the overhead of locking records and permitting the buffering of file data in program memory.

Note On UNIX systems in which record locking is implemented through the **fcntl()** system call, the file must be available with read/write access to enforce file locking. If the file is not available with read/write access, the file is opened but file locking is not enforced.

When the WITH LOCK phrase is absent, file access permits sharing by other users. The WITH LOCK phrase is ignored in single-user configurations. Table 8-9 illustrates the sharing permitted between applications in shared environments.

In a shared environment, a sequential file is considered shared if the WITH LOCK phrase is omitted, even for OPEN OUTPUT and OPEN EXTEND. This permits other users to OPEN EXTEND the same file and write records at the end of file.

Note RM/COBOL version 5.3 and later runtime systems do not lock program files that are being executed. Although this characteristic improves performance, under certain circumstances it can allow the compiler to recompile a program that is being executed at the time.

Table 8-9 Sharing Permissions

Desired Open Mode	Current Open Mode					
	Input	Input/ Output	Output	Extend	Input[1]	I-O[1] Output Extend
Input	■	■	■	■	■	▨
Input/ Output	■	■	■	■	▨	▨
Output	▨	▨	▨	▨	▨	▨
Extend	■	■	■	■	▨	▨
Input[1]	■	▨	▨	▨	■	▨
I-O[1] Output Extend	▨	▨	▨	▨	▨	▨

■ *Open granted.*

▨ *Open denied with I/O error 93,02 or 90,05.*

[1] *WITH LOCK.*

File Buffering

Buffering of the data in files can significantly increase the speed of accessing a file by keeping frequently accessed data in memory buffers instead of reading the data from disk every time it is needed. RM/COBOL maintains a pool of memory from which it takes the buffers for all files. When the memory in this pool is exhausted, the memory for buffers which have not been used recently will be taken from the file that had been using them and given to the file that needs them. This accommodates applications that open large numbers of files, but concentrates on only a few files at once.

Sequential and relative files must be opened WITH LOCK in order to make use of more than one buffer from the buffer pool.

The amount of memory in the buffer pool can be controlled by use of the BUFFER-POOL-SIZE keyword on the RUN-FILES-ATTR configuration record (see page 10-26). Increasing the default may improve the performance of the I/O of the application file. Decreasing the default value can increase the amount of program memory available.

The minimum size of the buffer pool must be adequate for the block sizes of the files opened by the application. See the description of the BLOCK CONTAINS clause for indexed files on page 8-53 for more information.

File Types and Structure

There are three types of files supported by RM/COBOL. Each file type and structure is most useful for specific functions. This section describes each of the following file types:

1. Sequential files
2. Relative files
3. Indexed files

Sequential Files

Sequential files are organized such that records are always read or written serially. In other words, during a specific I/O operation, the first record read is always the first record in the file, and the next record written is always written after the last record currently in the file. RM/COBOL has two types of sequential files:

1. **Line Sequential Files.** Line sequential files should contain only ASCII text data. (In other words, they are equivalent to standard source files.) Each logical record within line sequential files is variable in length and ends with a line feed or carriage return/line feed pair.

   If the ASCII control codes, that is, carriage return (CR), line feed (LF), form feed (FF) or SUB, are present in a record, the record cannot be written. When reading a file under UNIX, the LF, CR, FF, LF CR, CR LF, and FF CR sequences terminate a record. Under Windows, the CR LF sequence terminates a record and leading and trailing LF and FF sequences are ignored. SUB terminates the file and tab (HT) causes one or more spaces to be inserted according to the default tab column positions, which are every four columns, starting with column 8 and ending with column 72.

   The device-name in the ASSIGN clause of the file control entry determines the treatment of spaces in a line sequential record. If the device-name is DISC, DISK, or RANDOM, trailing spaces are preserved when a line sequential record is written. The record length returned when the record is read is the length of the record when it was written. If the device-name is CASSETTE, INPUT-OUTPUT, MAGNETIC-TAPE, OUTPUT, PRINT or PRINTER, all trailing spaces are removed when a record is written to the file. If the device-name is CARD-READER, CARD-PUNCH, CASSETTE, INPUT, INPUT-OUTPUT or MAGNETIC-TAPE, records read are padded with spaces to the maximum record length, and the record length returned is always the maximum record length.

   A file that is assigned to either of the device-names PRINT or PRINTER, for which the LINAGE clause is used, or for which the ADVANCING phrase of the WRITE statement is used, is always treated as a line sequential file. In this case, ASCII control codes are allowed.

   Each logical record within line sequential files has a maximum record length of 65280 bytes.

2. **Binary Sequential Files.** Whereas line sequential files contain ASCII text data, binary sequential files may contain any type of data. Binary sequential files may be fixed length or variable length.

   A fixed-length binary sequential file is one for which only one record description exists or all record descriptions describe the same number of characters, and for which no record description contains the OCCURS . . . DEPENDING ON clause, or for which the RECORD clause specifies fixed-length records. Such files may have a maximum record length of 65280 characters. Fixed-length binary sequential files are recorded by RM/COBOL without any additional structure; the byte count implied by the record length provides data transparency.

   A variable-length binary sequential file does not satisfy the record length requirements for fixed length. The data is encapsulated in an eight-byte overhead to provide data transparency. The maximum record size for variable-length binary sequential files is 65280 characters.

   Note The compiler listing allocation map indicates in the "Debug" column whether a file has been described with fixed- or variable-length records. This is described on page 6-24 and illustrated in Figure 6-6.

RECORD Clause (File Description Entry)

The RECORD clause specifies the minimum and maximum lengths of records in a sequential file. The minimum and maximum record lengths are not recorded with the file; however, a READ statement encountering a record whose length is less than the minimum record length receives an error. Also, an OPEN EXTEND for a fixed-length binary sequential file succeeds only if the total file size at the time of the OPEN is a multiple of the maximum record length of the file.

BLOCK CONTAINS Clause (File Description Entry)

In a single-user environment, sequential disk files are physically read and written in fixed length pieces called blocks. In a shared environment, sequential files are read and written in blocks only when the WITH LOCK phrase is specified. When the WITH LOCK phrase is omitted, the records of the file are read or written individually (without blocking) from the operating system.

The size of a block is determined by the BLOCK CONTAINS clause in the RM/COBOL program. A larger block size causes more data to be transferred in a single request, requires more time to effect the data transfer, reduces the total number of disk accesses, and requires more memory from the buffer pool. Blocking in this fashion may increase performance; however, because blocking may defer the physical writing of a block to disk until well after the WRITE statement that first places data in the block,

errors (which can include loss of data) caused by that physical write may not be reported until a subsequent WRITE or CLOSE statement for the file is executed.

The file block size is not considered a fixed attribute of a sequential file; different programs may specify different block sizes for the same file.

The runtime system uses the following algorithm to determine the block size when opening a sequential disk file:

1. If no BLOCK CONTAINS clause is present, the block size is 4096 characters. The default block size may be changed with a RUN-SEQ-FILES configuration record (see page 10-34).

2. If a BLOCK CONTAINS *nnn* CHARACTERS clause is present, the block size is the specified number of characters.

3. If a BLOCK CONTAINS *nnn* RECORDS clause is present, the block size is the specified number of records multiplied by the sum of the maximum record length and the record overhead.

The maximum allowed block size on most systems is 65535 characters.

LINAGE Clause (File Description Entry)

When a file described with the LINAGE clause is opened for output, it is assumed the output device is already positioned to the first line of the first logical page body. This is the operator's responsibility. The program should be written to allow the operator an opportunity to adjust the forms in the printer (or any other output device) as required.

As an alternative, the LINAGE-INITIAL-FORM-POSITION keyword in the PRINT-ATTR configuration record may be set to the value TOP-OF-FORM. In this case, which is particularly useful for page printers, it is assumed that the output device is positioned at the top of the form. When the first record is written to the file, the record will be written after advancing over the top margin on the first logical page. The LINAGE-INITIAL-FORM-POSITION keyword is further described on page 10-21.

The logical pages of a file described with the LINAGE clause are normally written contiguously with no additional spacing provided between pages. The LINAGE-PAGES-PER-PHYSICAL-PAGE keyword in the PRINT-ATTR configuration record may be used to cause physical page breaks, such as form feed characters, to be written to the file. The LINAGE-PAGES-PER-PHYSICAL-PAGE keyword is further described on page 10-22.

RESERVE Clause (File Control Entry)

The RESERVE clause is ignored. Buffer memory is automatically managed based on the amount of activity of a particular file. See "File Buffering" on page 8-40.

CODE-SET Clause (File Control Entry or File Description Entry)

The CODE-SET clause determines the character set used to represent the sequential file. For example, if the CODE-SET is EBCDIC, all records written to the file are translated from ASCII to EBCDIC. The CODE-SET is not considered a fixed attribute of the sequential file. Different programs may specify different character sets for the same file.

REVERSED Phrase (OPEN Statement)

The REVERSED phrase is not supported. If specified, it is ignored.

WITH NO LOCK Phrase (READ Statement)

If a READ statement without the WITH NO LOCK phrase fails because the record is locked, the contents of the record area are undefined and the file position indicator is unchanged. A subsequent READ behaves as if the failing READ statement had never been issued.

A READ statement with the WITH NO LOCK phrase may be used to read a record without regard to the lock status of the record. If an OPEN INPUT statement opened the file, the WITH NO LOCK phrase is assumed on all READ statements on the file.

If the file control entry does not contain a FILE STATUS clause or there is no USE declarative procedure defined for a file, record lock status is not reported to the program. Instead, the runtime system waits for the record to become unlocked. By using the FATAL-RECORD-LOCK-TIMEOUT keyword in the RUN-FILES-ATTR configuration record (see page 10-27), the runtime system can be made to return a fatal error instead of waiting indefinitely. If the record is locked using a different file descriptor in the same run unit, then the runtime system never waits. Instead, to prevent a deadlock situation, it returns an error indicating that the record is locked.

If the file control entry does contain a FILE STATUS clause and there is a USE declarative procedure defined for a file, the record lock status is normally reported to the program immediately by calling the USE procedure. By using the USE-PROCEDURE-RECORD-LOCK-TIMEOUT keyword in the RUN-FILES-ATTR configuration record (see page 10-30), the runtime system can be told how long to wait before calling the USE procedure. If the record is unlocked during this time, the USE procedure is not called.

ADVANCING ZERO LINES Phrase (WRITE Statement)

As explained in the discussion on the WRITE statement in Chapter 6, *Procedure Division Statements*, of the *RM/COBOL Language Reference Manual*, WRITE statements acting on sequential files allow overprinting on a line for systems whose physical devices support this feature. However, some line printers are designed to advance one line after each line is printed. In such a case, the ADVANCING ZERO LINES phrase is treated as an ADVANCING 1 LINE phrase.

ADVANCING *mnemonic-name* Phrase (WRITE Statement)

RM/COBOL allows the WRITE . . . ADVANCING *mnemonic-name* statement when *mnemonic-name* is associated with a channel-name from the SPECIAL-NAMES paragraph. No standard way exists to communicate channel slewing information. Because of this, the runtime system interprets C01 as if page were specified; it interprets any other channel as if 1 LINE were specified.

REEL and UNIT Phrases (CLOSE Statement)

The REEL and UNIT phrases are not supported. If specified, they are ignored.

WITH NO REWIND Phrase (CLOSE Statement)

A print file is released to the operating system at run unit termination or when a CLOSE statement (without the WITH NO REWIND phrase) is issued.

The WITH NO REWIND phrase may be used to prevent the release of a print file to the operating system. This feature may be used to prevent undesirable side effects such as banner pages and form feeds provided by the operating system when the print file is released.

A subsequent OPEN statement (typically, OPEN EXTEND) must be issued before the print file can again be successfully accessed by the program.

A print file is a line sequential file that has any or all of the following RM/COBOL source program features:

1. ASSIGN TO PRINT or ASSIGN TO PRINTER clause in the file control entry for the file.

2. LINAGE clause in the file description entry for the file.

3. ADVANCING phrase in a WRITE statement for the file.

For all other file types, the WITH NO REWIND phrase is ignored.

Device Support

Files that are opened on devices are treated as read-only (INPUT) or write-only (OUTPUT or EXTEND) sequential files. A program may open the same device more than once within the same run unit. Those devices that are opened with the same mode (read-only or write-only) share the same file handle and the same buffer. Those devices that are opened with different modes use different file handles and have different buffers.

At most, two buffers are allocated to each device; one when opened for read-only and one when opened for write-only. These buffers are dedicated to the device and do not come from the buffer pool.

Because of the non-portability of applying locks to devices, locks are never applied to device files. Thus, files opened on devices WITH LOCK do not guarantee exclusive access to the file.

Printer Support

Under UNIX, printer support is provided either through the lp or the lpr spooler. Under Windows, RM/COBOL provides printer support using the Windows printer devices.

Under UNIX, the RM/COBOL runtime system creates a write-only pipe to the print spooler and sends all print records to it. The pipe is closed and the output is allowed to print only when the RM/COBOL program issues a CLOSE statement to the file (except for CLOSE WITH NO REWIND, as explained previously).

Under Windows, when a file is opened with the name PRINTER, the output is sent to the default system printer configured under the Windows operating system. When a file is opened with the name PRINTER*x*, where *x* is a single-digit number, output is sent to the device connected to LPT*x*.

The device is opened for writing only and is closed only when the RM/COBOL program issues a CLOSE statement to the file (except for CLOSE WITH NO REWIND, as explained previously).

The destination for files named PRINTER can be changed by assigning an environment variable PRINTER (see the discussion of file access names that begins either on page 2-5 for UNIX or page 3-13 for Windows), by defining a synonym in the Windows registry (see page 3-29), or by configuring a keyword in the DEFINE-DEVICE record (see page 10-16).

Tape Support

Under UNIX, RM/COBOL provides tape support through direct access to the tape devices. When a file is opened with the name TAPE, the RM/COBOL runtime system opens the tape device and writes or reads to it as directed by the RM/COBOL program. The tape device is closed when the RM/COBOL program issues a close to the file except for CLOSE WITH NO REWIND. Since the operating system does not provide a mechanism to write a tape mark to a tape without closing the device (which may rewind it), the RM/COBOL runtime system only simulates the close as it does for the printer device.

Most systems allow multiple files to be placed on a tape by specifying that the tape is not to be rewound on OPEN and CLOSE. This must be specified at the OPEN of the file by using the correct name for the operation. For example, rtpyy may mean rewind on OPEN and CLOSE while rtpyn may mean rewind on OPEN but not on CLOSE. (Actual names vary between implementations. Consult your system administrator for the actual names.) If it is desired to place multiple files on a single tape, it will be necessary to use DEFINE-DEVICE configuration records to name the different options desired and use the names within the RM/COBOL program appropriately.

All sequential record formats are supported on the tape: line, binary fixed, and binary variable-length records. For transfer of information to other RM/COBOL programs, any method may be used. For transferring information to other programs executing on other equipment, fixed-length binary records are most compatible.

The destination for files named TAPE can be changed either by assigning an environment variable TAPE as explained in the discussion of file access names that begins on page 2-5, or by using a DEFINE-DEVICE configuration record as explained in the discussion that begins on page 10-16.

Named Pipe Support

Under UNIX, named pipes are treated as sequential devices. They are allowed to be opened as INPUT, OUTPUT or EXTEND, but never I-O. Also, as with the other devices, OPEN WITH LOCK does not guarantee exclusive access to the pipe.

Relative Files

Relative files are ordered collections of records, each of which is directly addressable by use of a relative record number; this number is a non-zero integer corresponding to the ordinal position of a record within the file. A record within a relative file acquires its record number when it is written to the file with a WRITE statement.

If the access mode of the file at the time the record is written is sequential, the record number is assigned by the runtime system, and is one greater than the last record number assigned (or 1 if no records have been written to the file). If the access mode is random or dynamic, specify the record number before execution of the WRITE statement. To do this, move (or otherwise assign) the value to the data item declared to be the relative key for the file.

Record numbers do not necessarily correspond to actual records in a file. For instance, a record number may never have been given a corresponding data record, or some numbers may correspond to data records that have been deleted.

Relative files must be assigned to a disk device, since the records can be accessed randomly.

The maximum record length is 65280 bytes. Records can be variable length. No restrictions are placed on the value of individual bytes within the record.

Records in a relative file are written to disk in a fixed-length area four bytes longer than the length of the longest record declared for the file. Estimate the total disk space requirement by multiplying the maximum record length plus four by the anticipated number of records.

RECORD Clause (File Description Entry)

The RECORD clause specifies the minimum and maximum record lengths of records in a relative file. The maximum record length is a fixed attribute of the file, and is validated against the file size during an OPEN statement.

The minimum record length is not recorded with the file; however, a READ statement encountering a record whose length is less than the minimum record length will receive an error. A REWRITE statement may change the record length of a record in a relative file.

BLOCK CONTAINS Clause (File Description Entry)

In a single-user environment, relative files are physically read and written in fixed-length pieces called blocks. In a shared environment, relative files are read and written in blocks only when the WITH LOCK phrase is specified. When the WITH LOCK phrase is omitted, the records of the file are read or written individually (without blocking) from the operating system.

The size of a block is determined by the BLOCK CONTAINS clause in the RM/COBOL program. A larger block size causes more data to be transferred in a single request, requires more time to effect the data transfer and requires more memory from the

buffer pool. A smaller block size allows more blocks in memory for a fixed amount of memory. Blocking may increase performance; however, because blocking may defer the physical writing of a block to disk until well after the WRITE statement that first places data in the block, errors (including loss of data) caused by that physical write may not be reported until a subsequent statement for the file is executed.

The file block size is not considered a fixed attribute of a relative file. Different programs may specify different block sizes for the same file.

The runtime system uses the following algorithm to determine the block size when opening a relative file:

1. If no BLOCK CONTAINS clause is present, the block size is typically 4096 characters if the file is opened for DYNAMIC or SEQUENTIAL access. The default block size may be changed with a RUN-REL-FILES configuration record (see page 10-34).

2. If a BLOCK CONTAINS *nnn* CHARACTERS clause is present, the block size is the specified number of characters.

3. If a BLOCK CONTAINS *nnn* RECORDS clause is present, the block size is the specified number of records multiplied by the sum of the maximum record size, plus four. The maximum allowed block size on most systems is 65489 characters.

RESERVE Clause (File Control Entry)

The RESERVE clause is ignored. Allocating buffer memory is automatically managed based on the amount of activity of a particular file. See “File Buffering” on page 8-40.

CODE-SET Clause (File Control Entry or File Description Entry)

The CODE-SET clause determines the character set used to represent the relative file on disk. For example, if the CODE-SET is EBCDIC, all records written to the file will be translated from ASCII to EBCDIC. The CODE-SET is not considered a fixed attribute of the relative file. Different programs may specify different character sets for the same file.

WITH NO LOCK Phrase (READ Statement)

A READ statement with the NEXT phrase and without the WITH NO LOCK phrase that fails because the record to which the file position indicator points is locked, does not modify the file position indicator and the contents of the record area are undefined. The record is not read and the program should not depend on the contents of the record area being unchanged. A subsequent READ statement behaves as if the failing READ statement had never been issued.

A READ statement with the WITH NO LOCK phrase may be used to read a record without regard to the lock status of the record. If an OPEN INPUT statement opened the file, the WITH NO LOCK phrase is assumed on all READ statements on the file.

If the file control entry does not contain a FILE STATUS clause or there is no USE declarative procedure defined for a file, record lock status is not reported to the program. Instead, the runtime system waits for the record to become unlocked. By using the FATAL-RECORD-LOCK-TIMEOUT keyword in the RUN-FILES-ATTR configuration record (see page 10-27), the runtime system can be made to return a fatal error instead of waiting indefinitely. If the record is locked using a different file descriptor in the same run unit, then the runtime system never waits. Instead, to prevent a deadlock situation, it returns an error indicating that the record is locked.

If the file control entry does contain a FILE STATUS clause and there is a USE declarative procedure defined for a file, the record lock status is normally reported to the program immediately by calling the USE procedure. By using the USE-PROCEDURE-RECORD-LOCK-TIMEOUT keyword in the RUN-FILES-ATTR configuration record (see page 10-30), the runtime system can be told how long to wait before calling the USE procedure. If the record is unlocked during this time, the USE procedure is not called.

Indexed Files

Indexed organization files contain data and one or more indexes or keys. These indexes are used to locate data in the file by identifying the key value and the location in the file of the corresponding record.

Every record in an indexed file contains a prime record key and may contain a number of alternate record keys.

Data Compression

Each record of the file may be represented in a compressed or uncompressed data format. Data record compression replaces multiple occurrences of space, zero and null or repeated characters with a single compression character. Uncompressed data records contain the data written by the program, with no compression characters. Data record compression almost always improves the performance of indexed files by reducing the file size and allowing more information to be read in a single physical transfer. When an indexed file is created by the runtime system, data record compression is enabled. This default may be changed as described on page 10-31. Whether data record compression is enabled for a particular file may be established with the Define Indexed File utility (**rmdefinx**), described in the discussion that begins on page G-19.

RM/COBOL indexed files allow index keys to be compressed or uncompressed. Key compression replaces the leading characters of a key that equal the preceding key, and

any trailing space characters of a key, with compression characters. This usually reduces the amount of disk space occupied by a file, especially a file in which many keys contain trailing spaces (such as names and addresses). When an indexed file is created by the runtime system, key compression is enabled. This default may be changed as described on page 10-32. Whether key compression is enabled for a particular file may be established with the **rmdefinx**.

Data Recoverability

RM/COBOL provides a choice of data recovery strategies for indexed files. A data recovery strategy is a tradeoff between deferring the writing of data to disk in order to improve the performance of file modification operations, and forcing the writing of data to disk in order to guarantee that the data is available for recovery if there is a system failure. The data recovery strategy for a particular indexed file is determined when the file is first opened OUTPUT or when the file is predefined. The file may be predefined using the Define Indexed File utility (**rmdefinx**) described on page G-19. If the file is not predefined, the default recovery strategy is used by the runtime system. This default strategy may be configured as described in the discussion of the RUN-INDEX-FILES configuration record beginning on page 10-31. Unlike other attributes associated with an indexed file, the recovery strategy for a file may be changed, thus allowing optimal performance when a file is being built and switching to a higher level of data integrity when a file is updated. Use the Define Indexed File utility (**rmdefinx**) to change the recovery strategy for a file.

The following four options are available to provide the various levels of data recovery strategy:

1. **Force File Closed (FORCE-CLOSED keyword).** The indexed file header contains a count of the number of concurrent run units that have the file open for modification. If the system fails while this count is non-zero, the file index structure must be rebuilt using the Indexed File Recovery utility (**recover1**). (See the discussion of the "Indexed File Recovery Utility (**recover1**)" that begins on page G-23.) Selecting this option causes the runtime system to increment this count before each DELETE, REWRITE or WRITE operation and decrement the count at the end of each operation. Otherwise, the count will be incremented when the OPEN statement is executed and decremented when the CLOSE statement is executed.

   Selecting this option causes two additional disk transfers for each modify operation, but gives a high probability that a file rebuild will not be required if a system failure occurs.

   Selecting this option causes the runtime system to act as if the following three options are also set.

2. **Force Disk (FORCE-DISK keyword).** Your operating system maintains a system disk buffer pool in its memory. Issuing an operating system write request, as described below in the Force Data option, causes data to be written from the buffer maintained by the runtime system to a buffer in this disk buffer pool. The data is not necessarily written to the disk at that time. Thus, the selected data recovery strategy may be defeated.

   Selecting this option causes the runtime system to attempt to force the operating system to actually write its buffer to disk.

3. **Force Data (FORCE-DATA keyword).** Selecting this option causes the runtime system to issue a write request to the operating system when a block containing a data record is modified. Otherwise, such blocks remain in the block buffer pool maintained by the runtime system for the file, and the write request to the operating system is not made until the buffer containing the block is needed for a different block.

   This option is available only when a file is in single-user mode, that is, when the runtime system is in single-user mode or the file is opened WITH LOCK. This option is always selected for files in a shared environment.

4. **Force Index (FORCE-INDEX keyword).** Selecting this option causes the runtime system to issue a write request to the operating system when a block containing index information is modified. Otherwise, such requests are issued only as buffer availability in the block buffer pool maintained by the runtime system dictates. This option is always selected for files in a shared environment.

RECORD Clause (File Description Entry)

The RECORD clause specifies the minimum and maximum length of records in an indexed file. These record lengths are considered fixed attributes of the file. Any program using an indexed file must specify the minimum and maximum length specified in the program that created the file.

The following algorithm computes the maximum disk space required to represent a record:

1. Assume the record representation disk space is the maximum record size of the file.

2. If data record compression is enabled, increase the record representation space by the ceiling of the maximum record size divided by 127.

3. Increase the record representation space by four times the number of alternate keys that allow duplicates.

4. Add four to the record representation disk space.

RM/COBOL indexed files are restricted both in the maximum record size declared in the program and in the maximum disk space required to represent a record. The maximum record size allowed an indexed file is 65280. The maximum disk space required to represent a record must not exceed 65527. The disk space limitation is the more restrictive, especially when data record compression is enabled.

BLOCK CONTAINS Clause (File Description Entry)

RM/COBOL indexed files are physically read and written in fixed-length pieces called blocks. The size of a block is determined by the BLOCK CONTAINS clause in the RM/COBOL program, or with the Define Indexed File utility (**rmdefinx**) (see page G-19). A larger block size transfers more data in a single request, requires more time to effect the data transfer, and requires more memory from the buffer pool. A smaller block size allows more blocks in memory for a fixed amount of memory, but requires more time to randomly access a record by increasing the depth of each index.

The file block size is considered a fixed attribute of the file. The BLOCK CONTAINS clause in a program that uses a file must be identical to the BLOCK CONTAINS clause in the program that created the file.

To access a block of an indexed file, the runtime system must use a piece of the buffer pool memory that is at least as large as the file block size. The indexed file algorithms require that a minimum of three pieces of buffer pool memory be available. If the file block size exceeds 32768, the buffer pool must be at least as large as the sum of 131072 and the block size. If the file block size exceeds 16384, the buffer pool must be at least as large as the sum of 65536 and the block size.

The algorithm used to determine the block size of an indexed file is outlined in the following paragraphs. The algorithm distinguishes specified block size from actual block size. Specified block size is defined by the BLOCK CONTAINS clause, and may be a function of the maximum disk space required to represent a record, defined previously in the RECORD clause description. Actual block size is defined as a function of the specified block size. When the term block size is used by itself elsewhere in this document in reference to an indexed file, it means the computed actual block size.

1. If no BLOCK CONTAINS clause is present, and the file already exists, the current block size is used as the block size.

2. If no BLOCK CONTAINS clause is present, and the file does not already exist, assume the block size is 512. This default may be changed with a RUN-INDEX-FILES configuration record (see page 10-31).

3. If a BLOCK CONTAINS *nnn* CHARACTERS clause is present, the specified block size is the number of characters.

4. If a BLOCK CONTAINS *nnn* RECORDS clause is present, the specified block size is eight characters more than the specified number of records multiplied by the maximum disk space required to represent a record, as described above.
5. The actual block size chosen is the lowest multiple of the specified block size that meets the following criteria:
    a. The actual block size must be at least 256.
    b. The actual block size must be at least 292 if an enumerated CODE-SET or COLLATING SEQUENCE is specified.
    c. The actual block size must be sufficient to contain three index keys. This is approximately the longest key length times 3 plus 46.
    d. The actual block size must be sufficient to contain one data record. This minimum is eight characters more than the maximum disk space required to represent a single record, as described above. If the record described in the FD will not fit in the block size determined by the preceding rules, then the block size is rounded up to the next multiple of the default block size.
6. If the computed actual block size does not meet all the following restrictions, the indexed file description is invalid and the file cannot be opened:
    a. The actual block size must not exceed 65489.
    b. If key entries are compressed, the actual block size must not exceed 65499 less four times the length of the longest key. If no alternate record key allows duplicates, the limit is 65515 less four times the length of the longest key.
    c. If key entries are uncompressed, the actual block size must not exceed 65526, less the length of the longest key. If no alternate record key allows duplicates, the limit is 65530, less the length of the longest key.

RESERVE Clause (File Control Entry)

The RESERVE clause is ignored. Buffer memory is automatically managed based on the amount of activity of a particular file. See “File Buffering” on page 8-40.

CODE-SET Clause (File Control Entry or File Description Entry)

The CODE-SET clause determines the character set used to represent the indexed file on disk. For example, if the CODE-SET is EBCDIC, all records written to the file will be translated from ASCII to EBCDIC. The CODE-SET specified when an indexed file is created is a permanent attribute of the file, and will be used whenever the file is accessed by a program not specifying a CODE-SET. However, a program may specify a different

CODE-SET than that used to create the file, and that code set will be used for the duration of the program.

COLLATING SEQUENCE Clause (File Control Entry)

The COLLATING SEQUENCE clause allows a program to determine the collating function used when comparing keys in an indexed file (for example, whether uppercase and lowercase letters are to be treated identically). The collating function specified when an indexed file was created is a fixed attribute of the file. If a program opening an indexed file specifies a COLLATING SEQUENCE clause, the specified collating function must be identical to that specified when the file was created.

WITH NO LOCK Phrase (READ Statement)

A READ statement with the NEXT phrase and without the WITH NO LOCK phrase that fails because the record is locked does not modify the file position indicator and the contents of the record area are undefined. The record is not read and the program should not depend on the contents of the record area being unchanged. A subsequent READ statement will behave as if the failing READ statement had never been issued.

A READ statement with the WITH NO LOCK phrase may be used to read a record without regard to the lock status of the record. If an OPEN INPUT statement opened the file, the WITH NO LOCK phrase is assumed on all READ statements on the file.

If the file control entry does not contain a FILE STATUS clause or there is no USE declarative procedure defined for a file, record lock status is not reported to the program. Instead, the runtime system waits for the record to become unlocked. By using the FATAL-RECORD-LOCK-TIMEOUT keyword in the RUN-FILES-ATTR configuration record (see page 10-27), the runtime system can be made to return a fatal error instead of waiting indefinitely. If the record is locked using a different file descriptor in the same run unit, then the runtime system never waits. Instead, to prevent a deadlock situation, it returns an error indicating that the record is locked.

If the file control entry does contain a FILE STATUS clause and there is a USE declarative procedure defined for a file, the record lock status is normally reported to the program immediately by calling the USE procedure. By using the USE-PROCEDURE-RECORD-LOCK-TIMEOUT keyword in the RUN-FILES-ATTR configuration record (see page 10-30), the runtime system can be told how long to wait before calling the USE procedure. If the record is unlocked during this time, the USE procedure is not called.

File Allocation

As an indexed file grows in size, the runtime system allocates additional blocks to the file. The number of blocks allocated is determined by the allocation increment. The default allocation increment is eight blocks; a different allocation increment may be set with the Define Indexed File utility (**rmdefinx**). A larger allocation increment may improve performance when writing records to the file, by reducing the number of operating system allocation requests. A smaller allocation increment may yield less wasted space.

Unused blocks in an indexed file are kept on the empty block list. The format of this list is determined by the file version number. Beginning with file version number 2, a new list format and algorithm are used to maintain the empty block list in order to increase performance when adding records to the file. This new algorithm keeps track of the first unused empty block in the file, which is followed only by other unused empty blocks, and avoids reading those blocks from the disk when they are used. New files are created with a version number of 2, although this default can be changed with the DEFAULT-FILE-VERSION-NUMBER configuration keyword (see page 10-31). The version number can also be changed on existing files or set when creating new files with the Define Indexed File utility, **rmdefinx** (see page G-19).

When a file version number is set to 2, the minimum write version number of the file is also set to 2 in order to prevent previous versions of RM/COBOL from attempting to modify the empty block list. The minimum read version number of the file is not changed. Files with a version number of 2 can be read but not modified by versions of RM/COBOL prior to version 6. If an OPEN OUTPUT is performed on a file with version number of 2 by a runtime system prior to version 6, the file version number and minimum write version number will be reset to 0, and the previous style of the empty block list will be used.

File Size Estimation

Use the following formulas to set upper and lower bounds on the number of characters that are required. Of course, with record data compression and key compression, the actual disk space required for records and keys varies greatly with the contents of the records.

In these formulas, “ceiling” means rounding up and “floor” means rounding down.

For example:

```
7.145
```

has a ceiling of 8 and a floor of 7.

```
Variables -  A     =  allocation increments in blocks
             B     =  block size in bytes
             Kn    =  length of nth key in bytes
             MaxL  =  maximum record size
```

```
                MinL  =  minimum record size
                N     =  number of keys
                Nd    =  number of keys that allow duplicates
                R     =  number of records

Subtotals -     H     =  1
                H     =  H + 2  if code-set is enumerated
                H     =  H + 1  if collating sequence is enumerated

                         If N > floor ((B - 256)÷36) then
                H     =  H+ceiling((N-((B-256)÷36))÷((B-6)÷36))

                         If records are compressed:
              MaxD    =  ceiling(R÷(floor((B-8)÷(MaxL+4+
                         (4*Nd)+ceiling(MaxL÷127)))))
              MinD    =  ceiling(R÷(floor((B-8)÷(ceiling
                         (MinL÷65)+4+(4*Nd)))))

                         If records are uncompressed:
              MaxD    =  ceiling(R÷(floor((B-8)÷
                         (MaxL+4+(4*Nd)))))
              MinD    =  ceiling(R÷(floor((B-8)÷
                         MinL+4+(4*Nd)))))

                         For each key n, 0 through N-1:
                TOn   =  4
                TOn   =  TOn+4 if key n allows duplicates


                         If key compression is enabled:
              TOn     =  TOn+2
              MaxTEn  =  floor((B-10)÷TOn)
              MinTEn  =  floor((B-10)÷(2*(TOn+Kn)))
              MaxLEn  =  floor((B-10)÷(TOn+1))
              MinLEn  =  floor((B-10)÷(2*(TOn+Kn+1)))

                         If key compression is not enabled:
              MaxTEn  =  floor((B-10)÷(TOn+Kn))
              MinTEn  =  ceiling(MaxTEn÷2)
              MaxLEn  =  floor((B-10)÷(TOn+Kn+1))
              MinLEn  =  ceiling(MaxLEn÷2)

                         For each key n:
              MaxLBn  =  ceiling(R÷MinLEn)
              MinLBn  =  ceiling(R÷MaxLEn)
              MaxTHn  =  ceiling(Log10(MaxLBn)÷Log10(MinTEn))
              MinTHn  =  ceiling(Log10(MinLBn)÷Log10(MaxTEn))
              MaxWn   =  ceiling(MaxLBn÷(MinTEn**(MaxTHn-1)))
              MinWn   =  floor(MinLBn÷(MaxTEn**(MinTHn-1)))
              MaxTBn  =  1+MaxWn*(((MinTEn**
                         (MaxTHn-1))-1)÷(MinTEn-1))
              MinTBn  =  1+MinWn*((MaxTEn**
                         (MinTHn-1))-1)÷(MaxTEn-1)

Totals -      MaxFB   =  H+MaxD+Sum(MaxLBn+MaxTBn)
              MinFB   =  H+MinD+Sum(MinLBn+MinTBn)
              MaxSize   =  (A*ceiling(MaxFB÷A))*B
              MinSize   =  (A*ceiling(MinFB÷A))*B
```

For example, suppose a single key indexed file of 2000 records is written. Every record is 100 bytes long. The prime record key is 15 bytes. Assume a default block size of 512 bytes, allocation increment of 8 blocks, the default compression state, and that key compression and record compression are enabled. No code-set or collating sequence is specified.

```
Variables -  A     =  8
             B     =  512
             K0    =  15
             MaxL  =  100
             MinL  =  100
             N     =  1
             Nd    =  0
             R     =  2000

Subtotals -  H     =  1
          MaxD     =  ceiling(2000÷(floor((512-8)÷(100+
                       4+(4*0)+ceiling(100÷127)))))
                   =  500

             MinD  =  ceiling(2000÷(floor((512-8)÷
                       (ceiling(100÷65)+4+4(4*0)))))
                   =  24
                TO0  =  4
                TO0  =  4+2
                   =  6
        MaxTE0     =  floor((512-10)÷6)
                   =  83
        MinTE0     =  floor((512-10)÷(2*(6+15)))
                   =  11

        MaxLE0     =  floor((512-10)÷(6+1))
                   =  71
        MinLE0     =  floor((512-10)÷(2*(6+15+1)))
                   =  11

        MaxLB0     =  ceiling(2000÷11)
                   =  182
        MinLB0     =  ceiling(2000÷71)
                   =  29

        MaxTH0     =  ceiling(Log10(182)÷Log10(11))
                   =  3
        MinTH0     =  ceiling(Log10(29)÷Log10(83))
                   =  1

         MaxW0      =  ceiling(182÷(11**(3-1)))
                    =  2
         MinW0      =  floor(29÷(83**(1-1)))
                    =  29

         MaxTB0     =  1+2*(((11**
                       (3-1))-1)÷(11-1))
                    =  25
         MinTB0     =  1+29*((83**
                       (1-1))-1)÷(83-1)
                    =  1
```

```
Totals  -  MaxFB    1+500+(182+25)
           =  708
           MinFB    =  1+24+(29+1)
           =  55
           MaxSize  =  (8*ceiling(708÷8))*512
           =  364544
           MinSize  =  (8*ceiling(55÷8))*512
           =  28672
```

This file will require between 28672 and 364544 bytes, depending on the contents of the records and the order in which the records are written. Since, in most cases, the key and data compression will save much less than all the bytes in the keys and records, the actual file size will probably be nearer to the maximum size than to the minimum size.

Temporary Files

The sort-merge facility of RM/COBOL makes use of temporary files for its intermediate sort files. These files are given unique names and are placed in the current directory and the current disk drive.

The choice of the directory in which to place the temporary files under Windows may be changed by use of the environment variables TMP or TEMP. If both variables are set, the value of TMP is used. Assign the environment variable a value before executing the RM/COBOL program. Under Windows, a synonym may be set in the registry database. Under UNIX, the TMPDIR environment variable is used.

Indexed File Performance

RM/COBOL indexed files contain data records and indexes to these data records. The index structure is based on B+ trees, described by D. E. Knuth and others. The index for each record key is maintained as a separate tree in the file. Each tree consists of nodes that contain key values and pointers to records or to other nodes. If an index node can contain N keys and pointers, a file of N or fewer records can be indexed by a single node. A file containing N*N records may be indexed by two levels of nodes, a root node of N entries pointing to N leaf nodes, each leaf node containing N entries pointing to records. Each random access to an indexed file requires that the entire index tree be traversed from the root node through any intermediate nodes to the leaf node and finally to the desired data record. Write operations to a file require adding the data record to the file, adding each key of the record to the appropriate index tree, possibly creating new leaf and intermediate nodes, or even creating a new root node and increasing the height of the index tree.

Since modifications to an indexed file require updating the index tree for each key added, changed, or deleted, one way to improve performance is to reduce the number of record keys. An application may use an index key to rapidly find a particular record. Some applications use record keys simply to sort records for report generation. If a record key is used only to access records in a particular order when generating a report, consider removing that record key and sorting the records with the SORT verb when the report is generated. Not only will this reduce the number of disk operations by using the more efficient sort algorithm, but it will also perform the operations only when the report is requested. When an index key is used to select a subset of the file's records for a report, the same selection can be performed with a SORT INPUT PROCEDURE.

The index tree manipulation algorithms are designed to keep each index node at least half full of entries. When records are written in ascending order by key, the algorithms can completely fill each index node with entries, reducing both the tree height and the size of the file. This improves performance by reducing both the number of disk operations and the required arm movement for the operations performed. If a file is infrequently modified, it should be built in ascending order by the key most frequently used to access the records.

In-Memory Buffering

Disk operations can be reduced by keeping file fragments in memory as long as possible. Subsequent accesses to the same information use the copy in memory instead of rereading the information from disk. This technique of in-memory buffering of data is the single most effective method of improving performance.

RM/COBOL files offer two levels of in-memory buffering of data: buffering by the operating system and buffering by the runtime system. A combination of the two seems to yield the best performance. Both UNIX and Windows provide buffering automatically. Additional memory may be dedicated to the buffering of disk data by further increasing the number of operating system buffers, or by increasing the size of the memory pool that the runtime system uses for disk buffers. The size of the memory pool may be increased through use of the BUFFER-POOL-SIZE keyword on the RUN-FILES-ATTR configuration record (see page 10-26).

Runtime system disk buffers, like the operating system buffers, are shared among all files opened by an application. Runtime system buffering is especially useful in a network environment. When a file is shared over a network, the operating system is unable to perform any buffering. Every WRITE operation must be sent to the remote machine and every READ operation must receive the data from the remote machine. With runtime system buffering of index files, at the beginning of each operation the runtime system determines which buffers still contain valid data and which contain data that may have been modified by an application on another machine. This significantly reduces the

number of remote READ operations required (although all modified data must still be written to the remote machine).

Providing sufficient space in the buffer memory pool can supply the runtime system with enough buffers to work efficiently.

The optimal number of buffers for a particular file depends on the operations being performed and the height of each index tree. The height of the index trees for a particular indexed file may be obtained with the Map Indexed File utility (**rmmapinx**), described on page G-14. If a file is being read randomly by only a single key, the minimal number of buffers that will improve performance is the height of the particular key's index tree, plus one. Fewer buffers than this number require that all index nodes be read for each operation. Increasing the number of buffers above this minimum increases the probability that needed nodes already will be in memory. WRITE operations require that every key be updated. It is desirable that the number of buffers available be greater than the sum of the heights of all trees. Short of this number, buffers equal to the height of the tallest tree plus one should be available. Again, increasing the number of buffers above the minimum increases the probability that required nodes will already be in memory.

Once the desired number of buffers is known, the amount of space to allocate in the buffer pool can be computed by using the following calculations:

N	=	Desired Number of Buffers		
BSz	=	Size of Buffer[1]		
NBSeg	=	Number of Buffers per Segment	=	INT(65496/BSz)
NSeg	=	Number of Segments	=	INT(N/NBSeg)
PSz	=	Pool Size = NSeg*65496 + (N – NSeg*NBSeg)*BSz		

If more than one file is expected to be active at the same time, the computed Pool Size (PSz) for the files usually can be added together, especially if the files have the same buffer size. (In fact, if the files have the same buffer size, it is best to add the number of desired buffers together and make the calculation using that number.) However, if the files have different buffer sizes and the difference between the buffer size and the block size of the file having the larger buffer size is greater than the buffer size of another active file, the amount of space required will be less than the sum of the separate buffer pool size calculations for the two files. (Recall that the buffer size is computed from the block size rounded to the next power of two. Not all that space, however, is in use by the buffer; only the block size rounded up to the next multiple of 512. The remainder is available for use by other buffers.)

[1] The size of the buffer (Bsz) is computed by rounding the block size up to the next power of two. If this is less than 512, use 512 instead.

Altering the Size of Indexed File Blocks

RM/COBOL indexed files are accessed in fixed size fragments called blocks. The size of these blocks is determined by the application with the BLOCK CONTAINS clause. The default block size is the smallest multiple of the disk sector size sufficient to contain one record or an index node. In general, this default block size is also the optimal choice. Although larger block sizes allow more entries in an index node and thus reduce the height of the index trees, this reduction in height is usually not sufficient to compensate for the reduced number of buffers available. Doubling a file's block size usually reduces the height of the trees by much less than a factor of 2. This means that if the memory available for buffers is just sufficient to contain the height of the tree at the smaller block size, it will no longer be sufficient at the larger block size. If there is insufficient memory even with a block size of only one sector for the desired minimal number of buffers discussed above (for example, the sum of the heights of the index trees when write operations are performed), a larger block size may improve performance. If the application does choose a block size greater than the default, this block size should still be a multiple of the disk sector size; otherwise, whenever a block is written, the operating system must read a sector of the disk, modify the block data in the sector, and rewrite the sector to disk.

Controlling the Length of Record Keys

The length of record keys affects indexed file performance by affecting the height of the index trees. Each index node consists of as many pairs of keys and pointers as fit in a block. A longer key means fewer entries, and increases the number of disk operations. Key length is especially significant if uncompressed keys are requested. When key compression is enabled for a file, leading characters in an entry that duplicate the preceding entry and trailing space characters are removed. This reduces the node entry to its significant characters, reducing an entry whose key is equal to its preceding entry to only 10 bytes.

Whether a key allows or prohibits duplicates affects performance primarily as it affects the tree height. Node entries that allow duplicates are four bytes longer than node entries that prohibit duplicates. If the key length were very short, the height of the index tree may increase. Each key that allows duplicates also increases the length of the data record representation by four bytes. This is usually insignificant, but it may increase the size of the file and degrade performance if the records are very short or if a large number of keys allow duplicates. Of course, any file with a large number of keys may be expected to have poorer performance than a file with a relatively small number of keys. If there are fewer buffers available than the sum of the heights of the index trees, keys that prohibit

duplicates degrade performance more than keys that allow duplicates. When a write request is made, every key that prohibits duplicates must be checked to see if the record to be written will create an illegal duplicate key value. When insufficient disk buffers are available, this will cause some additional disk operations.

Record length affects indexed file performance by placing a lower limit on the block size, perhaps forcing the block size to be larger than one sector, increasing the transfer time and reducing the number of buffers that will fit in available memory. Large record lengths also affect indexed file performance by increasing the disk space required by the file. RM/COBOL indexed files support variable-length records, using only sufficient disk space to contain the actual record data. Converting fixed-length records to variable-length records, however, is not necessary to improve performance. With data record compression enabled, fixed-length records with trailing space filled fields are almost as small as variable-length records. Of course, larger data records require more disk space. This can reduce the effectiveness of the disk buffers by reducing the percentage of the file that can be kept in memory and thus the probability that a desired file block will already be in memory.

Correct Data Recovery Strategy

RM/COBOL indexed files support several optional data recovery strategies that determine when and how much data should be written to the operating system or disk when the application executes a file modification statement. Enabling a data recovery strategy that does not defer I/O operations degrades performance. This is especially true if index tree modifications are written in addition to data record modifications, since a single record operation may cause many index modifications. Of course, the user might consider disabling a data recovery strategy to be a performance problem if the machine is turned off without exiting the application and hours of data entry are lost.

Using Key and Data Compression

RM/COBOL indexed files support key compression, in which leading characters of an index node entry key that match the preceding entry and trailing space characters are removed from the entry. This is usually a performance benefit, by increasing the number of entries in an index node, decreasing the height of the tree, decreasing the size of the file, and decreasing the number of disk operations. An exception occurs when sufficient buffers can be reserved to contain all or almost all of a file's index trees. This will make the file operations compute bound instead of disk bound. Changing the file to have uncompressed keys may improve performance. Typically, this occurs when running small benchmark programs with all of the memory reserved for disk buffers. Key compression may also degrade performance when numeric keys are used or when the key length is only 1 or 2, by unnecessarily adding two compression overhead characters to keys which, in fact, compress by fewer than three characters.

RM/COBOL indexed files support data record compression, in which repeated characters in a data record are replaced by a single compression character. Since the compression algorithm operates on all repeated characters, not just repeated zeros and spaces, this compression almost always results in less disk space for each data record, less disk space for the entire file, less arm movement when reading the file, and fewer disk operations to access the file. It may not be beneficial on very short data records, and data records that are artificially forced to be incompressible. It also yields anomalous results when a file is initially created with records that are almost all spaces, and these records are then rewritten with the actual data.

Using RM/COBOL Facilities

The WITH LOCK phrase on the OPEN statement may be used to improve the performance of exclusively accessed files in a network environment. When files are shared, at the beginning of each operation the runtime system must lock the file, read the header of the file to determine which buffers no longer contain valid data, and lock the record being modified. The file, and sometimes the record, are unlocked at the end of the operation. If a file should be opened by only one user at a time, then opening the file WITH LOCK avoids the locking and validation overhead on each operation. With a sufficient number of buffers, this can make the difference between four network transactions and zero network transactions to perform an operation.

Some applications may be written to delete and write a record when the record contents are changed, instead of using a REWRITE statement. A REWRITE statement always yields better performance than the DELETE and WRITE statements. This is because there is always at least one key whose value has not been changed, the prime record key. The index trees for unchanged keys need not be updated and, except for the prime record key, need not even be accessed.

File Version Level 2

Indexed files with a version level of 2 have a modified structure that can improve performance when adding records to the file. This feature is most noticeable when the file has been opened WITH LOCK. Files with a version level of 2 can be read but not modified by versions of RM/COBOL prior to version 6. Although by default, files are created with a version level of 2, this can be changed by using the DEFAULT-FILE-VERSION-NUMBER keyword of the RUN-INDEX-FILES configuration record. For more information, see page 10-31.

To change the version level of an existing file, use the Define Indexed File utility (**rmdefinx**). If the version level is changed to or from level 0, the Indexed File Recovery utility (**recover1**) must be run on the file. (See Appendix G, *Utilities*, for more information.)

File Version Level 3

Indexed files with a version level of 3 can grow to a larger size than those with a version level of 0 or 2. When creating a file with a version level of 3, the LARGE-FILE-LOCK-LIMIT keyword of the RUN-FILES-ATTR configuration record is used to determine the largest address that can be locked in the file. This value is also stored in the file header, allowing different files to have different lock limit values. Files with a version level of 3 cannot be read or written by prior versions of RM/COBOL. See Chapter 10, *Configuration*, for more information on the LARGE-FILE-LOCK-LIMIT keyword, or for information on how to change the default indexed file version number to 3 using the DEFAULT-FILE-VERSION-NUMBER keyword of the RUN-INDEX-FILES configuration record.

To change the version level of an existing file, or to change the lock limit stored in the header, use the Define Indexed File utility (**rmdefinx**). If the version level is changed to or from level 0, the Indexed File Recovery utility (**recover1**) must be run on the file. (See Appendix G, *Utilities*, for more information.)

Message Control System (MCS)

RM/COBOL does not provide runtime support for the Communications Module of ANSI COBOL 1985, which requires the presence of a highly application-specific Message Control System (MCS). This MCS is required for correct operation of the Communications Module statements: ACCEPT MESSAGE COUNT, DISABLE, ENABLE, PURGE, RECEIVE, and SEND. However, RM/COBOL provides an open MCS interface with which application designers can design and include their own MCS.

Note An MCS interface is not provided by the runtime system in the Windows environment.

Dummy Module osmcs.c

The runtime system provides a dummy module **osmcs.c**, which is replaced by the application designer's own MCS module with the two entry points OSMCSINITIALIZE and OSMCS implementing the desired message control system. A new runtime system executable file must be linked. (See Appendix D, *Customizing RM/COBOL for UNIX*, for more information on preparing C subprograms.)

Initializing the MCS

The routine OSMCSINITIALIZE is called at runtime initialization to initialize the MCS interface. If the interface is present and initialization completes properly, OSMCSINITIALIZE should return TRUE (non-zero). Otherwise, it should return FALSE (zero).

RM/COBOL Statements and the MCS

The MCS is required for correct operation of the following RM/COBOL statements:

- ACCEPT MESSAGE COUNT
- DISABLE
- ENABLE
- PURGE
- RECEIVE
- SEND

The MCS uses two data structures to communicate with the COBOL program. The first structure is the McsPointerArea, described below. The second structure is the communications descriptor map (CCD), which is described in the following section and illustrated in Figure 8-1 on page 8-68.

The McsPointerArea is described with the following C data structure:

```
typedef struct McsPtrAreaStruct
{
          char *CcdAreaAddress;
          char *CdRecordAddress;
          char *MessageAreaAddress;
          char *McsPointer[10];
}
```

This data structure is defined in C and contains only pointers (addresses). The size of the structure (in bytes) depends on the size of pointers for a given system. The structure is aligned so that pointers may be referenced directly. The CcdAreaAddress contains the address of the CCD.

The CdRecordAddress contains a pointer to the record area implicitly associated with the CD.

The MessageAreaAddress contains a pointer to the message area for a SEND or RECEIVE operation, or the key (password) value for an ENABLE or DISABLE operation.

The array of ten McsPointers is reserved for use by the MCS function.

The MCS functions are defined:

```
OSMCSINITIALIZE()
```

and

```
OSMCS (McsFunction, McsPtrArea)
long McsFunction;
char *McsPtrArea;
```

The valid McsFunction codes are as follows:

```
1  ACCEPT MESSAGE COUNT
2  DISABLE
3  ENABLE
4  RECEIVE
5  SEND
6  PURGE
```

The parameter McsPtrArea contains a pointer to the C data structure described previously.

Upon exit, the MCS must return a completion code as defined in Table 8-10.

Table 8-10 MCS Completion Codes

Code	Description
0	Function processed. No error.
1	RECEIVE . . . NO DATA processed. No data.
2–1499	Error. Terminate run unit with MCS error. The displayed error code will be the value plus 350.

The MCS is notified when a program containing one or more CCDs is terminated due to the execution of a CANCEL statement or to run unit termination. In this case, upon entry to the MCS, McsFunction will be 7 and McsArea will point to a CCD. The MCS must then determine the action to be taken for the CCD solely from the CD Type (byte offset 2) field and the area reserved for the MCS. The MCS will be called once for each communications description defined in the program being terminated.

The MCS is explicitly notified of run unit termination after all CCDs have been terminated. When this happens, upon entry to the MCS, McsFunction will be 8.

No error codes are anticipated or processed when the MCS is called with McsFunction 7 or 8.

RM/COBOL Communications Descriptor (CCD)

The RM/COBOL communications descriptor (CCD) contains values derived from the CD description in the Data Division as well as from the Procedure Division statement that caused the request. Figure 8-1 illustrates a map of the CCD.

Figure 8-1 Communications Descriptor Map (CCD)

BYTE OFFSET	
0 1	Reserved - do not modify
2	CD Type
3	Options
4	Destination Table Occurrences
5	
6 . . . 11	Reserved - do not modify
12 . . . 19	Reserved for use by MCS
20 21	Message Area Length
22	Reserved - do not modify
23	Message Indicator
24	Advancing Flags
25	Reserved - do not modify
26 27	Advancing Count
28 . . . 79	Reserved for use by MCS

CD Type has:

Bit 0 (0x01) is set if CD . . .FOR INPUT.

Bit 1 (0x02) is set if CD . . .FOR OUTPUT.

Both bits are set if CD . . .FOR I-O.

Options has:

Bit 0 (0x01) is set if RECEIVE . . .MESSAGE.

Bit 1 (0x02) is set if RECEIVE . . .SEGMENT.

Bit 2 (0x04) is set if RECEIVE . . .NO DATA.

Bit 3 (0x08) is set if ENABLE INPUT TERMINAL or DISABLE INPUT TERMINAL.

Destination Table Occurrences contains the value specified in the DESTINATION TABLE OCCURS clause, most-significant-byte first. Zero indicates that there is no DESTINATION TABLE OCCURS clause.

Message Area Length contains the length, as a short integer of the message area for a SEND or RECEIVE operation, and of the key (password) for an ENABLE or DISABLE operation. Zero indicates no message area (no FROM phrase in a SEND statement), or no key value (no KEY phrase in a DISABLE or ENABLE statement).

Message Indicator contains the binary value of the message indicator specified by the WITH phrase of the SEND statement. 0=no indicator, 1=ESI, 2=EMI and 3=EGI. The value is incremented by 16 if the REPLACING LINE phrase was specified in the SEND statement.

Advancing Flags contains information about the ADVANCING phrase of the SEND statement. Bit 7 (0x80) is set if the BEFORE phrase was specified, and is cleared if the AFTER phrase was specified. Bit 6 (0x40) is set if *mnemonic-name* was specified. Bits 0-3 (0x0F) contain the channel number associated with *mnemonic-name* in this case. If bit 6 is clear, bit 3 (0x08) is set to indicate the page phrase was specified, or bit 0 (0x01) is set to indicate the LINE(S) phrase was specified.

Advancing Count contains the binary values stored as a short integer of the literal or identifier specified in the LINE(S) clause of the ADVANCING phrase of the SEND statement.

The remaining area is set to zero by the RM/COBOL compiler, and may be used by the MCS, as required.

Chapter 9: Debugging

RM/COBOL provides an interactive debugging facility, the RM/COBOL Interactive Debugger (called Debug). This chapter details the concepts, structure, and use of Debug.

This chapter describes the following aspects of Debug:

- Invoking a program for Debug
- General Debug concepts
- Debug references
- Screen positions
- Data address development
- Regaining control
- Debug command prompt
- Debug error messages
- Debug commands

Invoking a Program for Debug

In order to execute programs for debugging, enter the D Option in the RM/COBOL Runtime Command (see page 7-3). Any compiled RM/COBOL program is ready to be run under control of Debug. In general, no special Compile Command options or compilation steps are required. However, if data references are to be specified in the **D** (Display), **M** (Modify), **T** (Trap), and **U** (Untrap) Commands, you need to enter either the A or Y Compile Command Option (you may need to enter both). See pages **6-9** and 6-13, respectively, for details on these options.

Any program within the run unit that was compiled with the Q Compile Command Option will not contain any debugging information and will, therefore, appear “invisible” to the Interactive Debugger.

Table 9-1 summarizes the RM/COBOL Debug commands.

Table 9-1 Debug Command Summary

Command	Function
Address Stop (A)	Sets a breakpoint and resumes program execution (see page 9-20).
Breakpoint (B)	Sets a breakpoint or displays all active breakpoints (see page 9-21).
Clear (C)	Clears breakpoints (see page 9-22).
Display (D)	Displays the value of a specified data item (see page 9-23).
End (E)	Ends debugging and resumes standard program execution (see page 9-27).
Line (L)	Specifies the line on which Debug displays will appear (see page 9-28).
Modify (M)	Modifies the value of a specified data item (see page 9-28).
Quit (Q)	Terminates program execution and returns control to the operating system (see page 9-33).
Resume (R)	Resumes program execution at a specified location (see page 9-34).
Step (S)	Executes the program to the start of the next statement, paragraph or section, or trace execution (see page 9-35).
Trap (T)	Sets a data trap or displays all active data traps (see page 9-36).
Untrap (U)	Clears data traps (see page 9-40).

General Debug Concepts

This section highlights some general concepts about Debug.

Statements

Debug considers section names, paragraph names and procedural statements to be statements for the purpose of setting breakpoints, stepping, execution counts or program area references (see page 9-5). Procedural statements are those RM/COBOL statements that begin with a Procedure Division verb (for example, IF, ADD, MOVE, READ, PERFORM, GO, STOP, and so forth).

Breakpoints

Breakpoints can be set for any statement. When the RM/COBOL runtime system encounters a breakpoint, it stops before it executes the statement at which the breakpoint is set. At this point, using the appropriate Debug commands, you can examine and modify the value of data within the program. Note that line numbers are used to indicate breakpoints. Breakpoints may be set for lines that have no statement (such as comment lines), but this does not cause a stop in response to the breakpoint. Any number of breakpoints can be set.

Traps

Traps are used to compare the current value of a data item to its last known value, to see if a change has occurred. Whereas breakpoints stop program execution before the statement at which the breakpoint was set, traps wait until the statement has completed, then compare for a change in value. If such a change occurs, program execution is suspended and the current value of the data item appears. Any number of traps can be set.

Stepping

When you step through the program, you direct that execution halt before the next statement, paragraph, or section is executed.

Execution Counts

You can specify the number of times a breakpoint is to be ignored before Debug halts the program. For example, if you set a breakpoint at line 100 and specify an execution count of 15, upon resumption of execution the statement at line 100 will be executed 14 times. When the statement is encountered the 15th time, Debug will halt the program before executing that statement. If the statement is not executed the specified number of times before execution ends, execution will not stop in response to the breakpoint.

The maximum value for an execution count is 65535.

Line and Intraline Numbers

References to statements are made by a line number, optionally modified by an intraline value. For example:

```
150  MOVE A TO B, MOVE B TO C, MOVE C TO D1
```

There are three procedural statements here: the first—MOVE A TO B—is referenced only by the line number 150. The second statement in the line—MOVE B TO C—is

referenced by the line number and the intraline number (or offset): in this case, 150 + 1. And the third statement—MOVE C TO D—is referenced by the line number and its intraline number: 150 + 2.

Debug Values

All numeric values used by Debug (for instance, to specify an address) are entered and displayed as decimal numbers (see the section "Data Address Development" that begins on page 9-6 for more information).

Data Types

Certain Debug commands allow (and in some cases require) you to enter a value for *type*. *type* indicates the type of data item. This makes Debug aware of the internal representation of the data item specified. The value of *type* is generally the value shown for the data item in the Debug column of the allocation map. However, other values may be specified for *type* if you want the data item decoded according to a different representation.

The allowed values for *type* are listed in Table 9-2.

Table 9-2 Valid Data Types

Data Type	Meaning	Data Type	Meaning
ABS	Alphabetic	NLC	Numeric display signed (leading combined
ABSE	Alphabetic edited	NLS	Numeric display signed (leading separate)
ANS	Alphanumeric	NPP	Packed unsigned
ANSE	Alphanumeric edited	NPS	Packed signed
GRP	Group	NPU	Numeric unsigned
HEX	Hexadecimal	NSE	Numeric edited
IXN	Index-name	NSU	Numeric display unsigned
NBS	Binary signed	NTC	Numeric display signed (trailing combined)
NBU	Binary unsigned or index data item	NTS	Numeric display signed (trailing separate)
NCS	Numeric unpacked signed	PTR	Pointer
NCU	Numeric unpacked unsigned		

Debug References

There are a number of ways to refer to specific lines of code or to specific data items within an RM/COBOL program.

Program Area References

You can refer to statements by the line number as it exists in your source program, by an intraline number if more than one statement is on a source line, and by a program name as it appears in the PROGRAM-ID paragraph in the Identification Division.

Data Item References

A data item can be referred to by its address and size, plus the specific occurrence (subscript) information if defined within an OCCURS clause, plus the argument number if defined within the Linkage Section or the external number if defined with the external attribute. A data item may be referred to by its symbolic name if the symbol table is included in the object program (see the discussion of the Y Compile Command Option that begins on page 6-13).

Screen Positions

You can request that Debug screen displays appear on a particular line. This feature is useful when you are debugging interactive programs (those that accept and display information on the screen) because it minimizes the risk of overwriting a program display with Debug commands or messages. For instance, if your screen display uses lines 10 through 25, you can direct that Debug commands and messages appear on line 6.

Data Address Development

Several Debug commands require you to specify particular data items, or specific occurrences of specific data items. Debug provides three ways for you to enter this information:

1. Identifier format
2. Address-size format
3. Alias format

All three methods can be used during a single Debug session if the conditions required for their use are satisfied. Only one method can be used for an individual Debug command.

Identifier Format

The identifier format is similar to the source format for identifier specification. This method requires that you specify (or configure) the Y Compile Command Option (see page 6-13), which outputs the symbol table to the object file for use by Debug. If the symbol table is absent from the object file, this format cannot be used.

The syntax is as follows:

```
name-1  [ { IN | OF } name-2 ] …  [ script ]  [ refmod ]
              [ ,  { type | { * | & } [ type ] } ]  [ # alias ]
```

name-1 is a name declared as a constant-name, data-name, or index-name in the Data Division of the current program or a constant-name, data-name, or index-name with the global attribute in a program that contains the current program. *name-2* is a qualifier for *name-1*. References to alphabet-names, cd-names, class-names, condition-names, file-names, mnemonic-names, paragraph-names, program-names, screen-names, section-names and symbolic-characters are not allowed, except that a file-name or cd-name may appear as the final qualifier of a data-name. The sequence of names must form a valid qualified reference to a data item, according to the rules for source program data references. A constant-name may only be specified in the **D** (Display) Command.

script is required if the data item referenced by *name-1* is a table element. If it is not, do not specify *script*. The format for *script* is as follows:



integer-n is a sequence of one or more decimal digits. Parentheses are required. Either commas or spaces can separate the integers. The number of integers must match the number of OCCURS clauses in the hierarchy of data description entries for the data item referenced by *name-1*. The value of *integer-n* is interpreted as an occurrence number in the same way as a literal subscript in the source program.

refmod selects a subfield of the data item in the same manner as a reference-modification in the source program. It has this format:



offset is a string of decimal digits whose value ranges from 1 to the length of the data item referenced by *name-1*. The parentheses and the colon following *offset* are required.

length is a string of decimal digits whose value ranges from 1 to the remaining length of the data item referenced by *name-1*, after *offset* has been applied. Failure to specify *length* requests the maximum length from *offset* to the end of the data item referenced by *name-1*.

type specifies the type of data item referenced. If this parameter is omitted, *type* defaults to the type of the named data item except when a type modifier is specified. (See the list of valid data types in Table 9-2.) The type value **IXN** may only be used with index-names and, when the named data item is an index-name, the only permissible type value is **IXN**. The type value **PTR** may only be used with pointer data items and, when the named data item is a pointer data item, the only permissible type value is **PTR**, except when a type modifier is specified. The type modifiers ***** and **&** have the following effect:

- The ***** type modifier indicates an indirect reference, that is, a reference to the data item referenced by a pointer data item value. The data item specified in the command must be a pointer data item (data type **PTR**). In this case, *type*, if specified, indicates the type of the data item referenced by the pointer data item value. If *type* is not specified, the default is hexadecimal. If *refmod* is not specified, the command refers to the entire effective memory area specified by

the pointer data item value. The effective memory area specified by a pointer data item value begins with the effective address (*pointer.address + pointer.offset*) and ends just before the effective limit address (*pointer.address + pointer.length*). If *refmod* is specified for an indirect reference, *refmod* is applied to the indirect reference rather than the pointer data item itself. Thus, *refmod* may be used to specify an offset and length (subfield) within the current effective memory area of an indirect reference.

- The **&** type modifier indicates that the address of the data item specified is the data item referenced by the command. In this case, the type of the operand will always be a pointer and, if *type* is specified, *type* must be **PTR**. The **D** (Display) Command may use the **&** type modifier for any data item type except index-names (data type **IXN**). The **&** type modifier may not be used with a constant-name since a constant-name does not name a data item. The **&** type modifier may be used in the **M** (Modify), **T** (Trap), and **U** (Untrap) Commands only if the referenced data item is a based linkage record because, otherwise, the address is not modifiable.

alias is a name you enter to serve as another name for the data operand specification that precedes it. If present, *alias* must follow a pound sign (**#**). The characters that follow the **#** must form a valid COBOL word. Only the first three characters of this word are significant. Once specified, *alias* can be used in later Debug commands that use the alias format. (See the discussion of this format that begins on page 9-11.) The three-character alias must be unique. If you assign the same alias to a different data operand, it will no longer refer to the earlier operand. When a command defines an alias and specifies the ***** (indirect through pointer) type modifier, the indirection is resolved at the time the alias is defined. In this case, the alias continues to refer to the data item that that the pointer data item referenced when the alias was defined even if the pointer data item value has subsequently been changed. When a command defines an alias and specifies the **&** (address of data item) type modifier, the address of the data item is resolved each time the alias is specified using an alias format command.

Address-Size Format

This method requires that you specify the A Compile Command Option (see page 6-9) to produce an allocation map in the listing file. This map provides the information that must be entered in a Debug command employing this method.

The syntax is as follows:

```
[ base : ]  address  [ + occur-size * occur-num ] ...  ,  size ,
                [ type ]  [ # alias ]
```

base specifies the base item for formal arguments, based linkage items, and external items as follows:

- For a USING formal argument, *base* is specified as **U** *arg-num*, where *arg-num* specifies the ordinal position of the argument in the USING list of the Procedure Division header provided in the allocation map of the program listing.
- For a GIVING formal argument, *base* is specified as **G**, as shown in the allocation map of the program listing.
- For a based linkage item, *base* is specified as **B** *item-num*, where *item-num* specifies the compiler assigned based linkage item number provided in the allocation map of the program listing.
- For an external item, base is specified as **X** *ext-num*, where *ext-num* specifies the compiler assigned external number provided in the allocation map of the program listing.

Note A Linkage Section data item, which is neither a formal argument item nor a based linkage item, is shown as "Not addressable:" in the allocation map of the program listing. Since such items have not been used in the source program, the compiler does not allocate a base pointer item for them and the Interactive Debugger cannot access them.

address specifies the decimal data address of the data item to be displayed, modified or monitored. The value is obtained from the data allocation map in the compiler listing.

occur-size specifies the size of data items that contain OCCURS clauses in their definitions. If *occur-size* is present, the plus sign (+)must appear as well. When a referenced data item contains an OCCURS clause in its definition, *occur-size* is equal to the value of *size* (defined in this section).

occur-num is the occurrence number for data items with OCCURS clauses in their definitions.

size specifies the size of the data item to be displayed, modified or monitored. (For **IXN** items, *size* specifies the span of the data item indexed by the index-name.)

type specifies the data type of the data item to be displayed, as it appears in the Debug column of the data allocation map. (The allocation map is described on page 6-22; complete details on the types of data allowed with RM/COBOL are found in Chapter 4, *Data Division*, of the *RM/COBOL Language Reference Manual*; and a list of the data types appears in Table 9-2 on page 9-4.) If this parameter is omitted, *type* defaults to hexadecimal. The type modifiers ***** (indirect through pointer) and **&** (address of data item) may not be specified in the address-size format.

alias is the name you assign to the data item referenced by the preceding entry. See the full description of the alias format on page 9-11.

Note that the term:

```
+occur-size*occur-num
```

selects specific occurrences of data items in tables.

Look at the program listing and associated data allocation map in Figure 9-1. Then look at Figure 9-2, which shows a developed reference to GRP-2(3).

The effect of this reference is the creation of a developed data address of 946, which appears as the address on the first line of the data display. Subsequent references to GRP-2(3) may appear as 946, 471 instead of 4 + 471*3, 471.

Note This developed data address is not the algebraic equivalent of the formula 4 + 471*3. It is the algebraic equivalent of 4 + (471*(3-1)) = 4 + (471*2) = 946.

Figure 9-1 Data Allocation Map

```
    8
    9  DATA DIVISION.
   10  WORKING-STORAGE SECTION.
0  11  01  GRP-1.                                                    0
   13      02  GRP-2                        OCCURS 20.
   14          03  FILLER                   PIC X(6).
0  15          03  GRP-3                    OCCURS 15.              0
   16              04  FILLER               PIC X(5).
   17              04  THE-ITEM             PIC 9V9 OCCURS 12.
   18              04  FILLER               PIC X(2).

0  Working-Storage Section for program ALLOCMAP                      0

   Address  Size      Debug Order  Type              Name
0      4    9420      GRP     0    Group             GRP-1           0
       4     471      GRP     1    Group              GRP-2
      10      31      GRP     2    Group               GRP-3
      15       2      NSU     3    Numeric unsigned     THE-ITEM
```

Figure 9-2 Developed Data Address



Alias Format

The alias format allows you to reference a data item or index that had been assigned an alternate name. Once assigned, the alias applies to that data item until you use it to name another data item or you end the Debug session.

The general format for referring to an item with an alias is as follows:

```
# alias
```

is required.

alias must be a valid COBOL word, only the first three characters of which are used. The alias must be previously defined in an identifier or address-size format specification.

Regaining Control

Debug regains control under the following conditions:

- Breakpoint
- Runtime system error
- Step through a statement, paragraph or section
- Execution of a STOP RUN statement
- Trap

Debug Command Prompt

The Debug command prompt first appears at the lower-left corner (line 25) of the screen. It looks like this:

```
condition line [ + intraline ] name   C?_
```

condition is the name of a condition that has stopped program execution. It may be one or more of the following:

- **BP**, which indicates a breakpoint is present.
- **DT**, which indicates a data trap has occurred.
- **ER**, which indicates a runtime system error has occurred.
- **SR**, which indicates the program has executed a STOP RUN statement.
- **ST**, which indicates program stepping is active.

line is the line on which the next statement to be executed begins. The string "Line?" appears if the line number is not known.

intraline indicates the next statement to be executed when line contains more than one statement.

name is the name of the currently executing program.

C?_ is the prompt and cursor.

Any Debug command may be entered when the prompt appears on the screen. If the last Debug command was an **S** (Step) Command, you can repeat it by pressing Enter in response to the prompt.

Debug Error Messages

This section lists and defines the error messages that may be generated during debugging.

Command Error

Indicates that you entered an invalid command character, or a command with inconsistent or invalid parameter values. The Debug command prompt appears again.

This message appears if any errors occur in scanning a reference in address-size format. Further, this message appears after any of the following specific errors are diagnosed.

Address too big

Indicates that the address value specified for a data item in a Debug address-size format is not correct.

This means that the end of the data item, calculated by summing the address of the data item, including any subscript calculations, and the length of the data item less one, exceeds the size of the region containing the data item. If the item resides in the program, the end of the data item must not exceed the sum of the lengths of the File Section and the Working-Storage Section. If the item is a Linkage Section item that is, or is subordinate to, a formal argument, the end of the data item must not exceed the length of the corresponding actual argument item. If the item is a Linkage Section item that is, or is subordinate to, a based linkage item, the end of the data item must not exceed the length of the area of memory addressed by the pointer value used to set the base address of the based linkage item. If the item is external, the end of the data item must not exceed the length of the highest level containing external item.

Colon (:) expected

Indicates that the colon is misplaced or omitted in the reference modification specified with a data item address in a Debug identifier format.

A reference modification specification consists of a left parenthesis, a non-zero integer starting position, a colon, optionally a non-zero integer length, and a right parenthesis. This message appears if the left parenthesis is not followed by a colon, there is no right parenthesis, or the colon follows the right parenthesis. The reference modification specification follows a subscript specification, if present.

Dword alignment

Indicates that the address specified for an index-name (Debug type **IXN**) is not a multiple of four.

Extraneous characters

Indicates that the command entered to Debug contains characters that are not expected past the data item specification or modification value.

The **D** (Display) and **T** Trap Commands accept an alias identifier of a data item or a data item specification with an optional alias definition. The **M** (Modify) Command accepts the same parameters as a **D** (Display) Command followed by a modification value. The **U** (Untrap) Command accepts the data item specification or alias identifier of a data item with which a trap is currently associated. No additional characters are accepted.

Identifier expected

Indicates that the first character of what should be an identifier is not alphabetic, numeric, or hyphen.

An identifier is expected at the start of a Debug reference in an identifier format, following **IN** or **OF** in identifier format, and following the pound sign (**#**), which identifies an alias.

Identifier not a data item

Indicates that the symbolic identifier specified is a user-defined word in the COBOL source, but is not a data item.

The Debug commands, D (Display), M (Modify), and T (Trap), allow access to program data items. The state of user-defined words, such as condition-names or switch-names, which are not data items, cannot be examined. Examine the source or the allocation map to determine the data item that contains the field to be accessed.

This error message also occurs if a symbolic identifier specifies a Linkage Section data item that is neither a formal argument (USING or GIVING) nor a based linkage item. Since such items have not been used in the source program, the compiler does not allocate a base pointer item for them and the Interactive Debugger cannot access them.

Identifier refers to constant

Indicates that in a command other than the **D** (Display) Command, the symbolic identifier specified refers to a constant-name or is the constant address (**&** type modifier specified) for a data item that is not a based linkage data item. Constant-names and constant addresses may not be specified in the **M** (Modify), **T** (Trap), or **U** (Untrap) Commands.

IN or OF expected

Indicates that the symbolic identifier in a Debug identifier format specification of a data item is followed by something other than a qualification specification.

If a symbolic name is not followed by the special characters left parenthesis, comma, or pound sign, it must be followed by **IN** or **OF** and the symbolic name of a higher level data item.

Incorrect number of subscripts

Indicates that too few subscripts are provided with a data item in a Debug identifier format.

Index Error

Indicates that you requested the display of an index-name (Debug type **IXN**) and Debug discovered an inconsistency in the internal representation of the index-name.

This message generally indicates that the address or size value of the index-name was entered incorrectly.

Index-name inconsistency

Indicates that the symbolic identifier conflicts with the type value specified in the command. One of the following conflicts has occurred:

- The symbolic identifier refers to an index-name, but a type value other than **IXN** was specified. Index-names may not use a type value other than **IXN**.
- The symbolic identifier does not refer to an index-name, but the type value **IXN** was specified. Only index-names may be specified with the type value **IXN**.
- The symbolic identifier refers to an index-name and a *refmod* field was specified. Reference modification of an index-name is not allowed.
- The type modifier **&** (address of data item) was specified with a symbolic identifier that refers to an index-name (data type **IXN**). The type modifier **&** may not be specified for an index-name.

Left parenthesis expected

Indicates that the data item in a Debug identifier format refers to a table element and no subscript identifying a particular element is entered.

Length too big

Indicates that the sum of the starting position value and the length, specified in the reference modification of a data item in a Debug identifier format, exceeds the declared length of the data item.

A reference modification specification consists of a left parenthesis, a non-zero integer starting position, a colon, optionally a non-zero integer length, and a right parenthesis. The ending position, that is, the sum of the starting position minus 1 and the length, must not exceed the length of the symbolic data item. If the symbolic data item is a variable-length group, the ending position must not exceed the maximum length of the group.

Name undefined

Indicates that a symbolic identifier entered in a Debug identifier format specification of a data item does not exist in the COBOL program.

The name appears undefined when debugging a contained program if the name is defined in a containing program but is not described with the GLOBAL attribute. When debugging a containing program, names in contained programs appear undefined. This message also appears if a name provided as a qualifier is not defined anywhere in the separately compiled program.

No such based linkage item

Indicates that you specified a based linkage item number for a data item in the Debug address-size format incorrectly. This means that the integer between the letter **B** and the following colon does not correspond to a based linkage item.

No such external

Indicates that you specified an external number for a data item in the Debug address-size format incorrectly. This means that the integer between the letter **X** and the following colon does not correspond to an external group item.

No such parameter

Indicates that a USING argument value for a data item in the Debug address-size format is specified incorrectly.

This means that the integer between the letter **U** and the following colon does not correspond to a Linkage Section data item included in the USING list of the Procedure Division or that the calling program did not pass a value in the corresponding position of its CALL statement.

Non-zero integer expected

Indicates that a subscript, reference modification starting position, or reference modification length in a Debug identifier format specification of a data item is zero or is not numeric.

Not enough free memory to continue

Indicates that Debug cannot allocate memory.

Debug allocates memory to remember names associated with an alias and to contain the symbol table of the current program.

Offset too big

Indicates that the starting position value entered in a reference modification, specified with a data item address in a Debug identifier format, exceeds the declared length of the data item.

Pointer inconsistency

Indicates that the symbolic identifier conflicts with the type value specified in the command. One of the following conflicts has occurred:

- The symbolic identifier refers to a pointer data item, but a type value other than **PTR** was specified without a type modifier. Pointer data items may not use a type value other than **PTR**.
- The symbolic identifier does not refer to a pointer data item, but the type value **PTR** was specified. Only pointer data items may be specified with the type value **PTR**.
- The symbolic identifier refers to a pointer data item without the type modifier ***** (indirect through pointer) and a *refmod* field was specified. Reference modification of a pointer data item is not allowed.
- The type modifier ***** (indirect through pointer) was specified with a symbolic identifier that is not a pointer data item. The type modifier ***** may only be used with pointer data items.
- The type modifier **&** (address of data item) was specified with a type value other than **PTR**. The type modifier **&** always results in a pointer value and thus cannot specify a type value other than **PTR**.
- The type modifier **&** (address of data item) was specified with a symbolic identifier that refers to a constant-name. The type modifier **&** may not be specified with a constant-name.
- For the **M** (Modify) Command, the = value modifier was followed by a symbolic identifier that does not refer to a pointer data item or reference modification was specified for the pointer.

Pointer memory access violation

Indicates that the ***** (indirect through pointer) type modifier was specified with a pointer data item that has a null value or a value that points to memory that cannot be read by the program. For the **M** (Modify) Command, this may mean that the program cannot write to the memory area referenced by the pointer value.

Program not compiled with Y option

Indicates that a data item is entered in a Debug identifier format to a **D** (Display), **M** (Modify), or **T** (Trap) Command, but no symbol table is available.

Qualifier undefined

Indicates that an alias identifier is undefined or that the symbolic qualifier provided after an **IN** or **OF** in a Debug item address in an identifier format is not a higher level data item of the preceding identifier.

Check the qualification specification with the program source or the allocation map of the compilation listing.

Qualification ambiguous

Indicates that the symbolic qualifiers provided after an **IN** or **OF** in a Debug item address in an identifier format do not uniquely identify a data item.

Qualification allows unique specification of data items with the same name. The qualification identifiers must be the names of lower numbered group items or the name of the COBOL filename if the data item is in the File Section. Check the qualification specification with the program source or the allocation map of the compilation listing. Reenter the command with additional qualification items to uniquely identify the desired data item.

Right parenthesis expected

Indicates that a subscript or reference modification field, specified with a data item address in a Debug identifier format, is missing its closing right parenthesis or that too many subscripts are provided.

Subscript value too big

Indicates that a subscript exceeds 65535 or that the offset corresponding to the specified subscripts exceeds 2^{32}.

A (Address Stop) Command

Use the **A** Command to set a breakpoint and to resume program execution from the current location. When the specified breakpoint is reached and Debug regains control, the breakpoint is cleared and has no further effect.

The syntax for the **A** Command is as follows:

```
A  [ line [ + intraline ]  [ ,  [ prog-name ]  [ ,  [ count ] ] ] ]
```

line indicates the line number containing the statement at which the breakpoint is to be set. *line* always refers to the first statement of the line. If this parameter is omitted, no breakpoint is set before execution is resumed.

intraline refers to a specific statement within the program line. For example, 1 indicates the first intraline statement (or the second actual statement), 2 indicates the second intraline statement, and so forth. If this parameter is omitted, the first statement on the line is assumed.

prog-name provides for explicit program qualification during debugging. The value of *prog-name* must be a program name from the PROGRAM-ID paragraph of the Identification Division. If this parameter is omitted, it is assumed the reference is to the currently executing program. If this parameter is omitted and *count* is specified, there must be two commas before *count*.

count is an execution count. Debug allows the statement to execute a number of times equal to *count* minus one, then honors and clears the breakpoint immediately before the next execution (which now equals *count*) of the statement. Debug then regains control. The maximum value for *count* is 65535. If this parameter is omitted, *count* defaults to 1.

When you use the **A** Command, keep in mind that the specified breakpoint remains in effect until it is honored. In other words, if execution halts and Debug regains control at a statement other than that specified in the **A** Command, the breakpoint set by the **A** Command remains in effect. It can be cleared by the **C** Command and displayed by the **B** Command.

B (Breakpoint) Command

Use the **B** Command to display all currently set breakpoints or to set breakpoints at specific procedural statements. Note that—unlike the **A** Command—a breakpoint set by this command is not cleared once the conditions have been satisfied. To clear breakpoints set with a **B** Command, you must enter a **C** Command.

The command syntax is nearly identical to that used with the **A** Command:

```
B  [ line [ + intraline ]  [ ,  [ prog-name ]  [ ,  [ count ] ] ] ]
```

line indicates the line number containing the statement at which the breakpoint is to be set. *line* always refers to the first statement of the line. If this parameter is omitted, no breakpoint is set. Instead, all currently set breakpoints are displayed.

intraline refers to a specific statement within the program line. For example, 1 indicates the first intraline statement (or the second actual statement), 2 indicates the second intraline statement, and so forth. If this parameter is omitted, the first statement on the line is assumed.

prog-name provides for explicit program qualification during debugging. The value of *prog-name* must be a program name from the PROGRAM-ID paragraph of the Identification Division. If this parameter is omitted, it is assumed the reference is to the currently executing program. If this parameter is omitted and *count* is specified, there must be two commas before *count*.

count is an execution count. Debug allows the statement to execute a number of times equal to *count* minus one, then honors and clears the breakpoint immediately before the next execution (which now equals *count*) of the statement. Debug then regains control. The maximum value for *count* is 65535. If this parameter is omitted, *count* defaults to 1. Because the **B** Command does not clear breakpoints after responding to them (as does the **A** Command), it remains in effect for all subsequent occurrences.

For example, entering:

```
B 150+2, PAY-TAX, 5
```

sets a breakpoint at the third statement (second intraline statement) at line 150 in the program PAY-TAX. When execution resumes, the breakpoint is ignored four times and honored the fifth time. Program control then returns to Debug.

The format of the breakpoint display (when *line* is omitted) is as follows for each active breakpoint:

```
line [ + intraline ] prog-name count
```

A count of zero is equivalent to a count of one.

C (Clear) Command

Use the **C** Command to clear any breakpoints that have been set with the **A** or **B** Commands.

The syntax for the **C** Command is as follows:

```
C [ line [ + intraline ] [ , [ prog-name ] ] ]
```

line is the line number containing the statement at which the breakpoint to be cleared is set. If no line number is specified, all currently active breakpoints are removed.

intraline refers to a specific statement within the program line. For example, 1 indicates the first intraline statement (or the second actual statement), 2 indicates the second intraline statement, and so forth. If this parameter is omitted, the first statement on the line is assumed.

prog-name provides for explicit program qualification during debugging. The value of *prog-name* must be a program name from the PROGRAM-ID paragraph of the Identification Division. If this parameter is omitted, it is assumed the reference is to the currently executing program. If a line is specified on which no breakpoint exists, the command is in error.

For example, entering:

```
C 100+2
```

clears the breakpoint set at the second intraline statement of line 100 in the currently executing program.

D (Display) Command

Use the **D** Command to display on the screen the value of a specified data item.

Identifier Format

The syntax for the **D** Command with the identifier format (see the discussion of this format that begins on page 9-6) is as follows:

```
D  name-1  [ { IN | OF }  name-2 ] …  [ script ]  [ refmod ]
             [ ,  { type | { * | & } [ type ] } ]  [ # alias ]
```

name-1 is a name declared as a constant-name, data-name, or index-name for the literal value, data item, or index to be displayed. *name-2* is a qualifier for *name-1*. Qualification is required if the name is not unique. The named data item or index must be described in the Data Division of the current program or be described with the GLOBAL attribute in a program that contains the current program.

script specifies subscripting and is required if the data item referenced by *name-1* is a table element. (See page 9-7 for a complete description.) If the data item is not a table element, do not specify *script*. The format for *script* is as follows:

```
( integer-1 [ [ , ] integer-2 ] … )
```

refmod specifies a subfield of the data item. (See page 9-7 for a complete description.) It has this format:

```
( offset : [ length ] )
```

type specifies the data type to be used for displaying the named data item or index. If this parameter is omitted, *type* defaults to the type of the item specified except when a type modifier is specified. The type value **IXN** may only be used with index-names and, when the named data item is an index-name, the only permissible type value is **IXN**. The type value **PTR** may only be used with pointer data items and, when the named data item is a pointer data item, the only permissible type value is **PTR**,

except when a type modifier is specified. The type modifiers ***** and **&** have the following effect:

- The ***** type modifier indicates that the data item to be displayed is the data item determined by an indirect reference, that is, a reference to the data item referenced by a pointer data item value. The data item specified in the command must be a pointer data item (data type **PTR**). In this case, *type*, if specified, indicates the type of the item referenced by the pointer data item value. If *type* is not specified, the default is hexadecimal. If *refmod* is not specified for an indirect reference, the entire effective memory area specified by the pointer data item value is displayed. The effective memory area specified by a pointer data item value begins with the effective address (*pointer.address + pointer.offset*) and ends just before the effective limit address (*pointer.address + pointer.length*). If *refmod* is specified for an indirect reference, *refmod* is applied to the indirect reference rather than the pointer data item itself. Thus, *refmod* may be used to display a subfield within the current effective memory area of an indirect reference.

- The **&** type modifier indicates that the address of the data item specified is to be displayed as a pointer value (data type **PTR**). Since the result type will always be a pointer, if *type* is specified, *type* must be **PTR**. The **&** type modifier may be used with a data item of any data type except an index-name (data type **IXN**). The **&** type modifier may not be used with a constant-name since a constant-name does not name a data item. The address of the data item will be displayed as three sets of sixteen hexadecimal digits; the first set is the base address, the second set is the offset (SET pointer UP/DOWN), and the third set is the length of the memory area covered by the pointer.

alias is a name you enter to serve as another name for the data operand specification that precedes it. (See page 9-11 for a complete description.) If present, *alias* must follow a pound sign (#). The characters that follow the # must form a valid COBOL word. Only the first three characters of this word are significant. When a command defines an alias and specifies the ***** (indirect through pointer) type modifier, the indirection is resolved at the time the alias is defined. In this case, the alias continues to refer to the data item that the pointer data item referenced when the alias was defined even if the pointer data item value has subsequently been changed. When a command defines an alias and specifies the **&** (address of data item) type modifier, the address of the data item is resolved each time the alias is specified using an alias format command.

For example, entering:

```
D MONTH-NAME(11)(1:3)
```

directs Debug to display the first three bytes of the 11th element in the table MONTH-NAME. Debug then displays the following:

```
140 ANS NOV
```

This shows the data address of 140, the type of data as alphanumeric, and the value as NOV.

Address-Size Format

The syntax for the **D** Command with the address-size format (see the discussion of this format that begins on page 9-9) is as follows:



base specifies the base item for formal arguments, based linkage items, and external items as follows:

- For a USING formal argument, *base* is specified as **U** *arg-num*, where *arg-num* specifies the ordinal position of the argument in the USING list of the Procedure Division header provided in the allocation map of the program listing.
- For a GIVING formal argument, *base* is specified as **G**, as shown in the allocation map of the program listing.
- For a based linkage item, *base* is specified as **B** *item-num*, where *item-num* specifies the compiler assigned based linkage item number provided in the allocation map of the program listing.
- For an external item, base is specified as **X** *ext-num*, where *ext-num* specifies the compiler assigned external number provided in the allocation map of the program listing.

Note A Linkage Section data item, which is neither a formal argument item nor a based linkage item, is shown as "Not addressable:" in the allocation map of the program listing. Since such items have not been used in the source program, the compiler does not allocate a base pointer item for them and the Interactive Debugger cannot access them.

address specifies the address of the data item to be displayed. This is based on the value obtained from the data allocation map. (See page 9-9 for more information on addresses used with Debug.)

occur-size specifies the size of data items that contain OCCURS clauses in their definitions.

occur-num specifies the occurrence number for data items that contain OCCURS clauses in their definitions.

size specifies the size of the data item to be displayed. If type is **IXN**, this is the value that appears in the Span column of the data allocation map.

type specifies the data type of the data item to be displayed. If this parameter is omitted, *type* defaults to hexadecimal. The type modifiers ***** (indirect through pointer) and **&** (address of data item) may not be specified in the address-size format.

alias must form a valid COBOL word, only the first three characters of which are valid. (See page 9-11 for a complete description.) Once specified, the alias can be used to refer to the operand to which it is assigned.

The specified data item appears in the following format:



address is the developed data address.

type is the type of data item to be displayed.

value is the value of the data in the format specified by type in the **D** Command.

For example, entering:

```
D 13 + 2*7,2,NSU
```

directs Debug to display the data item located at decimal data address 25.

Debug then displays:

```
25 NSU 15
```

This shows that at the developed data address of (decimal) 25 is a value of 15, of type numeric string unsigned.

If the **L** Command (described on page 9-28) is used to specify a line number of the monitor, the display appears one line at a time, at the line specified in the **L** Command. If the display does not fit on one line, press the Enter key to see the next line. To return to the Debug command prompt after the last line of data appears, press Enter.

If the **L** Command was not used, the display begins at the next line and scrolls when the bottom of the screen is reached.

Alias Format

The syntax for the **D** Command with the alias format for specifying a data item or index reference is as follows:



is required.

alias must form a valid COBOL word, only the first three characters of which are valid. (See page 9-11 for a complete description.) The alias must have been previously defined in an identifier or address-size format specification.

E (End) Command

Use the **E** Command to leave Debug. The currently executing program runs until completion.

The syntax of the **E** Command is as follows:



L (Line Display) Command

Use the **L** Command to specify a line on the monitor screen at which command input echoes and Debug responses are to be displayed.

The syntax of the **L** Command is as follows:

```
L  [ line-display ]
```

line-display designates a line number on the monitor and may be in the range 0 through the number of lines on the screen.

This command is useful when you are debugging programs that have a variety of interactive ACCEPT and DISPLAY statements. By selecting a specific line for Debug displays, you can reduce or avoid conflicts between lines produced by Debug and lines produced by the program.

If *line-display* is omitted from the command, or *line-display* equals 0, the screen resumes its standard mode of operation (scrolling).

M (Modify) Command

Use the **M** Command to change the value of a specified data item.

Identifier Format

The syntax for the **M** Command with the identifier format (see the discussion of this format that begins on page 9-6) is as follows:

```
M  name-1  [ { IN | OF }  name-2 ] …  [ script ]  [ refmod ]
             [ ,  { type | { * | & } [ type ] } ]  [ # alias ] , value
```

name-1 is a name declared as a data-name or index-name for the data item or index to be modified. *name-2* is a qualifier for *name-1*. Qualification is required if the name is not unique. The named data item or index must be described in the Data Division of the current program or be described with the GLOBAL attribute in a program that contains the current program.

script specifies subscripting and is required if the data item referenced by *name-1* is a table element. (See page 9-7 for a complete description.) If the data item is not a table element, do not specify *script.* The format for *script* is as follows:



refmod specifies a subfield of the data item. (See page 9-7 for a complete description.) It has this format:



type specifies the data type of the item to be modified. If this parameter is omitted, *type* defaults to the type of the item specified except when a type modifier is specified. The type value **IXN** may only be used with index-names and, when the named data item is an index-name, the only permissible type value is **IXN**. The type value **PTR** may only be used with pointer data items and, when the named data item is a pointer data item, the only permissible type value is **PTR**, except when a type modifier is specified. The type modifiers ***** and **&** have the following effect:

- The ***** type modifier indicates that the data item to modify is determined by an indirect reference, that is, a reference to the data item referenced by a pointer data item value. The data item specified in the command must be a pointer data item (data type **PTR**). In this case, *type,* if specified, indicates the type of the data item referenced by the pointer data item value. If *type* is not specified, the default is hexadecimal. If *refmod* is not specified for an indirect reference, the entire effective memory area specified by the pointer data item value is modified. The effective memory area specified by a pointer data item value begins with the effective address (*pointer.address* + *pointer.offset*) and ends just before the effective limit address (*pointer.address* + *pointer.length*). If *refmod* is specified for an indirect reference, *refmod* is applied to the indirect reference rather than the pointer data item itself. Thus, *refmod* may be used to modify a subfield within the current effective memory area of an indirect reference.

- The **&** type modifier indicates that the address of the data item specified is to be modified. The data item referenced in the command must be a based linkage record because, otherwise, the address is not modifiable. The data item referenced in the command may be any data type except an index-name (data type **IXN**). When the **&** type modifier is used, the *value* must be a pointer value and, if *type* is specified, *type* must be **PTR**.

alias is a name you enter to serve as another name for the data operand specification that precedes it. (See page 9-11 for a complete description.) If present, *alias* must follow a pound sign (#). The characters that follow the # must form a valid COBOL word. Only the first three characters of this word are significant. When a command defines an alias and specifies the ***** (indirect through pointer) type modifier, the indirection is resolved at the time the alias is defined. In this case, the alias continues to refer to the data item that the pointer data item referenced when the alias was defined even if the pointer data item value has subsequently been changed. When a command defines an alias and specifies the **&** (address of data item) type modifier, the address of the data item is resolved each time the alias is specified using an alias format command.

value specifies the new value for the data item or index. The format for specifying the value is described by *type* in the following section, "Address-Size Format."

For example, entering:

```
M MONTH-NAME(12), DECEMBER
```

directs Debug to modify the 12th element of the table MONTH-NAME to have the value of DECEMBER.

Address-Size Format

The syntax for the **M** Command with the address-size format (see the discussion of this format that begins on page 9-9) is as follows:

```
M  [ base : ]  address  [ + occur-size * occur-num ] …  ,  size ,
                  [ type ]  [ # alias ] ,  value
```

base specifies the base item for formal arguments, based linkage items, and external items as follows:

- For a USING formal argument, *base* is specified as **U** *arg-num*, where *arg-num* specifies the ordinal position of the argument in the USING list of the Procedure Division header provided in the allocation map of the program listing.
- For a GIVING formal argument, *base* is specified as **G**, as shown in the allocation map of the program listing.
- For a based linkage item, *base* is specified as **B** *item-num*, where *item-num* specifies the compiler assigned based linkage item number provided in the allocation map of the program listing.

- For an external item, base is specified as **X** *ext-num*, where *ext-num* specifies the compiler assigned external number provided in the allocation map of the program listing.

Note A Linkage Section data item, which is neither a formal argument item nor a based linkage item, is shown as "Not addressable:" in the allocation map of the program listing. Since such items have not been used in the source program, the compiler does not allocate a base pointer item for them and the Interactive Debugger cannot access them.

address specifies the address of the data item to be modified. This is based on the value obtained from the data allocation map. (See page 9-9 for more information on addresses used with Debug.)

occur-size specifies the size of data items that contain OCCURS clauses in their definitions.

occur-num specifies the occurrence number for data items that contain OCCURS clauses in their definitions.

size specifies the size of the data item to be modified. If type is **IXN**, this is the value that appears in the Span column of the data allocation map.

type specifies the type of data item referenced. If this parameter is omitted, *type* defaults to hexadecimal. The type modifiers ***** (indirect through pointer) and **&** (address of data item) may not be specified in the address-size format.

alias is a name you enter to serve as another name for the data operand specification that precedes it. (See page 9-11 for a complete description.) If present, *alias* must follow a pound sign (**#**). The characters that follow the **#** must form a valid COBOL word. Only the first three characters of this word are significant.

value is the value of the data in the format specified by type in the **M** Command line.

If *type* is **HEX**—or omitted in the address-size format—*value* is entered as a string of hexadecimal digits. This hex value is stored in the specified data item and is left justified with zero fill or truncation on the right. The hexadecimal value must contain an even number of digits.

If *type* is one of the nonnumeric types **ANS**, **ANSE**, **ABS**, **ABSE**, **GRP** or **NSE**, *value* is stored in the specified data item and is left justified with blank fill or truncation on the right. Note that no editing is performed during this operation.

If *type* is one of the numeric types **NBS**, **NBU**, **NCS**, **NCU**, **NLC**, **NLS**, **NPP**, **NPS**, **NPU**, **NSU**, **NTC** or **NTS**, *value* is converted to a signed integer according to the rules for a MOVE from a numeric edited sending item to a numeric destination item (see the

"MOVE Statement" section in Chapter 6, *Procedure Division Statements*, of the *RM/COBOL Language Reference Manual* for more information).

If *type* is **IXN**, *value* is converted to a signed integer occurrence number. This number is then converted to the internal index-name representation based on the value of *size*.

If *type* is **PTR**, *value* must be a pointer value. The pointer value 0 is equivalent to NULL (NULLS). For pointer values other than 0, a pointer value is forty-eight hex digits, where the first sixteen digits specify the base address, the middle sixteen digits specify the offset from the base address, and the last sixteen digits specify the length of the memory area. Embedded spaces are allowed and ignored. Leading zeroes must be specified. If the program was compiled with the Y Compile Command Option, then a pointer *value* may also be specified with either of the value modifiers **=** or **=&** as follows:

```
{ = | =& } name-3  [ { IN | OF } name-4 ] …  [ script ]  [ refmod ]
```

If the **=** value modifier is specified (without the **&**), *name-3* must refer to a pointer data item and *refmod* is not allowed. The current value of the referenced pointer data item is used for *value*. This is equivalent to the COBOL statement:

```
SET name-1 [OF name-2] …  TO name-3 [OF name-4] …
```

If the **=&** value modifier is specified, *value* is composed from the address of the data item named by *name-3*, an offset of zero, and the length of the data item named by *name-3*. This is equivalent to the COBOL statement:

```
SET name-1 [OF name-2] …  TO
          ADDRESS OF name-3 [OF name-4] …
```

Note The Interactive Debugger attempts to validate a pointer *value* when specified, but the validation results may not be conclusive. It is the user's responsibility to take care when modifying pointer data items or based linkage base addresses to ensure correctness. One easy method of correctly modifying a pointer value is to display the desired pointer value using the **D** Command and then using copy/paste to paste the value into the *value* field of an **M** Command. Another method is to use one of the **=** or **=&** value modifiers described above.

In all other cases, the resulting integer is stored in the data item as if the item had no assumed decimal point. If conversion results in a noninteger, an error message appears and the specified data item remains unaltered.

For example, entering:

```
M 13+2*7,2,NSU,0
```

directs Debug to modify the data item located at decimal data address 25. The **NSU** data item will have a new value of 0.

Alias Format

The syntax for the **M** Command with the alias format for specifying a data item or index reference is as follows:



is required.

alias must form a valid COBOL word, only the first three characters of which are valid. (See page 9-11 for a complete description.) The alias must have been previously defined in an identifier or address-size format reference to the desired item (for example, in a **D** (Display) Command).

value specifies the new value for the data item or index. The format for specifying the value is described by *type* in the preceding section, "Address-Size Format."

Q (Quit) Command

Use the **Q** Command to stop program execution. This command terminates the program as if a STOP RUN statement were executed.

The syntax of the **Q** Command is as follows:



When the **Q** Command is executed, open files are closed and control returns to the operating system.

R (Resume) Command

Use the **R** Command to specify that program execution resume at the current location, or at another location specified in the command.

The syntax of the **R** Command is as follows:

statement-address specifies the specific program address for the sentence at which execution is to resume. If *statement-address* is not specified, execution resumes at the current location. *statement-address* appears in the Debug column at the left of the program listing, and should be entered as printed. *statement-address* is not a line number.

An error condition or stop run condition (that is, the command prompt contains ER or SR) forces the **R** Command to disallow *statement-address*. The **R** Command may be used in its simple form (that is, without an accompanying *statement-address*) to allow Debug to trace back through the program units of a run unit, but the run unit may not be restarted when an error or stop run condition occurs.

Note The **R** Command used with a *statement-address* resets the program counter. If an improper *statement-address* is specified, Debug displays an error. The program counter remains invalid until another **R** Command with a valid *statement-address* is used. An **R** Command with no *statement-address* at this time causes Debug to display an error.

S (Step) Command

Use the **S** Command to specify that program execution occur one step at a time. With Debug, you can step through a statement, a paragraph, or an entire section.

The syntax of the **S** Command is as follows:

```
S  [ P | S ]  [ count ]
```

P specifies that paragraphs are to be stepped through.

S specifies that sections are to be stepped through. If neither P nor S is present, statements are stepped through.

count specifies the number of statements, paragraphs or sections that are to be executed before execution suspends. The maximum value for *count* is 65535. A value of zero is treated as 1. The default is 1.

Specifying *count* greater than 1 causes Debug to trace the statements, paragraphs or sections executed while in stepping mode. The format of the trace message is as follows:

```
TR line [+intraline] name
```

line is the line number on which the statement begins.

intraline is the specific statement within a line.

name is the name of the program as it appears in the PROGRAM-ID paragraph of the Identification Division.

For example, entering:

```
SS 10
```

directs Debug to execute 9 sections, produce 9 trace messages, and then halt before executing the 10th.

T (Trap) Command

Use the **T** Command to monitor the value of a specified data item, and to suspend execution whenever a change in that value occurs. The **T** Command can also be used to display all currently set traps. If you enter only the command keyword **T**, all currently active data traps appear.

A data trap set with the **T** Command can be removed with the **U** (Untrap) Command. A data trap set on a Linkage Section data item is removed automatically when the program exits. A data trap set on a File Section, Working-Storage Section or Screen Section data item is removed automatically when the separately compiled program is canceled. A data trap set on an external data item will continue until the run unit ends.

Identifier Format

The syntax for the **T** Command with the identifier format (see the discussion of this format that begins on page 9-6) is as follows:

```
T  name-1  [ { IN | OF }  name-2 ] …  [ script ]  [ refmod ]
             [ ,  { type | { * | & } [ type ] } ]  [ # alias ]
```

name-1 is a name declared as a data-name or index-name for the data item or index to be monitored. *name-2* is a qualifier for *name-1*. Qualification is required if the name is not unique. The named data item or index must be described in the Data Division of the current program or be described with the GLOBAL attribute in a program that contains the current program.

script specifies subscripting and is required if the data item referenced by *name* is a table element. (See page 9-7 for a complete description.) If it is not a table element, do not specify *script.* The format for *script* is as follows:

```
( integer-1 [ [ , ] integer-2 ] … )
```

refmod specifies a subfield of the data item. (See page 9-7 for a complete description.) It has this format:

```
( offset : [ length ] )
```

type specifies the data type to be used in displaying the monitored data item or index when a change in value occurs. If this parameter is omitted, *type* defaults to the type of the item specified except when a type modifier is specified. The type value **IXN** may only be used with index-names and, when the named data item is an index-name, the only permissible type value is **IXN**. The type value **PTR** may only be used with pointer data items and, when the named data item is a pointer data item, the only permissible type value is **PTR**, except when a type modifier is specified. The type modifiers ***** and **&** have the following effect:

- The ***** type modifier indicates that the data item to start monitoring is determined by an indirect reference, that is, a reference to the data item referenced by a pointer data item value. The data item specified in the command must be a pointer data item (data type **PTR**). In this case, *type*, if specified, indicates the type of the item referenced by the pointer data item value. If *type* is not specified, the default is hexadecimal. If *refmod* is not specified for an indirect reference, the entire effective memory area specified by the pointer data item value is monitored. The effective memory area specified by a pointer data item value begins with the effective address (*pointer.address* + *pointer.offset*) and ends just before the effective limit address (*pointer.address* + *pointer.length*). If *refmod* is specified for an indirect reference, *refmod* is applied to the indirect reference rather than the pointer data item itself. Thus, *refmod* may be used to monitor a subfield within the current effective memory area of an indirect reference. The indirect reference is resolved at the time the trap is set with the **T** (Trap) Command and subsequent changes to the pointer data item used to set the trap do not change the data item that is being monitored by the trap. To monitor changes in the pointer data item itself, do not use the ***** type modifier.

- The **&** type modifier indicates that the base address of the data item specified is to be monitored. The data item referenced in the command must be a based linkage record because, otherwise, the address is not modifiable. The data item referenced in the command may be any data type except an index-name (data type **IXN**). When the **&** type modifier is used, the value to be monitored is a pointer value and, if *type* is specified, *type* must be **PTR**. A trap set on a based linkage data item, without the **&** type modifier, is resolved at the time the trap is set and subsequent changes to the base address of the based linkage item do not change the data item that is being monitored. To monitor changes in the base address of a based linkage item, use the **&** type modifier with the based linkage record data-name.

alias is a name you enter to serve as another name for the data operand specification that precedes it. (See page 9-11 for a complete description.) If present, *alias* must follow a pound sign (#). The characters that follow the # must form a valid COBOL word. Only the first three characters of this word are significant. When a command defines an alias and specifies the ***** (indirect through pointer) type modifier, the

indirection is resolved at the time the alias is defined. In this case, the alias continues to refer to the data item that the pointer data item referenced when the alias was defined even if the pointer data item value has subsequently been changed. When a command defines an alias and specifies the **&** (address of data item) type modifier, the address of the data item is resolved each time the alias is specified using an alias format command.

For example, entering:

```
T MONTH-NAME(12)
```

directs Debug to suspend execution whenever the value of the 12th element in the table MONTH-NAME changes.

Address-Size Format

The syntax for the **T** Command with the address-size format (see the discussion of this format that begins on page 9-9) is as follows:

```
T  [ base : ]  address  [ + occur-size * occur-num ] …  ,  size ,
                       [ type ]  [ # alias ]
```

base specifies the base item for formal arguments, based linkage items, and external items as follows:

- For a USING formal argument, *base* is specified as **U** *arg-num*, where *arg-num* specifies the ordinal position of the argument in the USING list of the Procedure Division header provided in the allocation map of the program listing.
- For a GIVING formal argument, *base* is specified as **G**, as shown in the allocation map of the program listing.
- For a based linkage item, *base* is specified as **B** *item-num*, where *item-num* specifies the compiler assigned based linkage item number provided in the allocation map of the program listing.
- For an external item, base is specified as **X** *ext-num*, where *ext-num* specifies the compiler assigned external number provided in the allocation map of the program listing.

Note A Linkage Section data item, which is neither a formal argument item nor a based linkage item, is shown as "Not addressable:" in the allocation map of the program listing. Since such items have not been used in the source program, the

compiler does not allocate a base pointer item for them and the Interactive Debugger cannot access them.

address specifies the address of the data item to be monitored. This is based on the value obtained from the data allocation map. (See page 9-9 for more information on addresses used with Debug.)

occur-size specifies the size of data items that contain OCCURS clauses in their definitions.

occur-num specifies the occurrence number for data items that contain OCCURS clauses in their definitions.

size specifies the size of the data item to be monitored.

type specifies the type of data item referenced. If this parameter is omitted, *type* defaults to hexadecimal. The type modifiers ***** (indirect through pointer) and **&** (address of data item) may not be specified in the address-size format.

alias is a name you enter to serve as another name for the data operand specification that precedes it. (See page 9-11 for a complete description.) If present, *alias* must follow a pound sign (**#**). The characters that follow the **#** must form a valid COBOL word. Only the first three characters of this word are significant.

Before RM/COBOL executes a statement, it examines the contents of the specified data item with the value the data item had at the point program execution last resumed. If a change has not occurred, execution proceeds to the next statement. If a change has occurred, execution is suspended and the contents of the data item appear according to the rules set down in the discussion of the **D** Command that begins on page 9-23. The trap is updated, and remains in effect until a **U** Command is executed.

Alias Format

The syntax for the **T** Command with the alias format for specifying a data item or index reference is as follows:



is required.

alias must form a valid COBOL word, only the first three characters of which are valid. (See page 9-11 for a complete description.) The alias must have been previously defined in an identifier or address-size format reference to the desired item (for example, in a **D** (Display) Command).

U (Untrap) Command

Use the **U** Command to clear a single active data trap, or all currently active data traps.

Identifier Format

The syntax for the **U** Command with the identifier format (see the discussion of this format that begins on page 9-6) is as follows:

```
U  name-1  [ { IN | OF }  name-2 ] …  [ script ]  [ refmod ]
              [ ,  { type | { * | & } [ type ] } ]
```

name-1 is a name declared as a data-name or index-name for the data item or index whose data trap is to be removed. *name-2* is a qualifier for *name-1*. Qualification is required if the name is not unique. The named data item or index must be described in the Data Division of the current program or be described with the global attribute in a program that contains the current program.

script specifies subscripting and is required if the data item referenced by name is a table element. (See page 9-7 for a complete description.) If it is not a table element, do not specify *script*. The format for *script* is as follows:

```
( integer-1 [ [ , ] integer-2 ] … )
```

refmod specifies a subfield of the data item. (See page 9-7 for a complete description.) It has this format:

```
( offset : [ length ] )
```

type specifies the data type of the monitored data item that is to be removed from the monitored item list. If this parameter is omitted, *type* defaults to the type of the item specified except when a type modifier is specified. The type value **IXN** may only be used with index-names and, when the named data item is an index-name, the only permissible type value is **IXN**. The type value **PTR** may only be used with pointer data items and, when the named data item is a pointer data item, the only permissible type value is **PTR**, except when a type modifier is specified. The type modifiers ***** and **&** have the following effect:

- The ***** type modifier indicates that the data item to discontinue monitoring is determined by an indirect reference, that is, a reference to the data item referenced by a pointer data item value. The data item specified in the command must be a pointer data item (data type **PTR**). In this case, *type*, if specified, indicates the type of the item referenced by the pointer data item value. If *type* is not specified, the default is hexadecimal. If *refmod* is not specified for an indirect reference, the entire effective memory area specified by the pointer data item value is the data reference to discontinue monitoring. The effective memory area specified by a pointer data item value begins with the effective address (*pointer*.*address* + *pointer*.*offset*) and ends just before the effective limit address (*pointer*.*address* + *pointer*.*length*). If *refmod* is specified for an indirect reference, *refmod* is applied to the indirect reference rather than the pointer data item itself. Thus, *refmod* may be used to discontinue monitoring a subfield within the current effective memory area of an indirect reference.

- The **&** type modifier indicates that the data item to discontinue monitoring is the address of the data item specified. The data item referenced in the command must be a based linkage record because, otherwise, the address is not modifiable. The data item referenced in the command may be any data type except an index-name (data type **IXN**). When the **&** type modifier is used, the monitored item is a pointer data item and, if *type* is specified, *type* must be **PTR**.

For example, entering:

```
U MONTH-NAME(12)
```

clears the trap on the 12th element in the table MONTH-NAME.

Address-Size Format

The syntax for the **U** Command with the address-size format (see the discussion of this format that begins on page 9-9) is as follows:

```
U  [ [ base : ] address [ + occur-size * occur-num ] …  ]
```

base specifies the base item for formal arguments, based linkage items, and external items as follows:

- For a USING formal argument, *base* is specified as **U** *arg-num*, where *arg-num* specifies the ordinal position of the argument in the USING list of the Procedure Division header provided in the allocation map of the program listing.
- For a GIVING formal argument, *base* is specified as **G**, as shown in the allocation map of the program listing.
- For a based linkage item, *base* is specified as **B** *item-num*, where *item-num* specifies the compiler assigned based linkage item number provided in the allocation map of the program listing.
- For an external item, base is specified as **X** *ext-num*, where *ext-num* specifies the compiler assigned external number provided in the allocation map of the program listing.

Note A Linkage Section data item, which is neither a formal argument item nor a based linkage item, is shown as "Not addressable:" in the allocation map of the program listing. Since such items have not been used in the source program, the compiler does not allocate a base pointer item for them and the Interactive Debugger cannot access them.

address specifies the address of the data item for which a trap is active. This is based on the value obtained from the data allocation map. (See page 9-9 for more information on addresses used with Debug.) If *address* is not specified, all currently active data traps are cleared.

occur-size specifies the size of data items that contain OCCURS clauses in their definitions.

occur-num specifies the occurrence number for data items that contain OCCURS clauses in their definitions.

If you enter only **U**, all currently activated traps are cleared.

For example:

```
U 13+2*7
```

clears the trap on the data item located at decimal data address 25.

If a specific data trap does not exist, the command is in error.

Alias Format

The syntax for the **U** Command with the alias format for specifying a data item or index reference is as follows:



is required.

alias must form a valid COBOL word, only the first three characters of which are used. (See page 9-11 for a complete description.) The *alias* must have been previously defined in an identifier or address-size format reference to the desired item (for example, in the **T** (Trap) Command which set the trap).

Chapter 10: Configuration

Configuration determines such actions as screen displays, indexed file characteristics, default operational modes, the method by which the terminal is to be accessed, and general terminal characteristics.

Configuration is altered by writing a specific set of configuration directives into a configuration record. The complete set of configuration records is then written to a configuration file.

This chapter details the configuration file structure, configuration error format, configuration record types, and terminal configuration record types.

Configuration File Structure

Configuration directives are contained in the configuration file. The configuration file is a line sequential file, and it can be created with any convenient text editor. The configuration file can then be specified in the Compile Command (using the G and H Options, as described on page 6-6) or in the Runtime Command (using the C and X Options, as described on page 7-3).

Configuration records can appear in any order within the configuration file, except where noted otherwise. The first field in each record identifies the type of record or value being defined. The format of the remainder of the record depends on the type of record. Except for specific character sequences, keywords and parameters in the records are case insensitive; uppercase and lowercase letters are equivalent.

The records are free field; that is, individual fields need not start in any predetermined column. The general syntax is as follows:

```
record-name  keyword=value[,value]
```

record-name is the name of one of the configuration records detailed in this chapter.

keyword is the name of the keyword specification being described. It must be followed by an equal sign. Optional spaces following the equal sign are allowed.

value, depending on the keyword, may be either a string or a number. Value strings that contain a space, equal sign, or comma must be quoted with either the double

quote (") or single quote (') character, and must use the same beginning and ending quote character. Quoted strings that contain the quote character must use a pair of consecutive quote characters to represent one quote character. For some keywords, the value may be either a single character-string or a number. In such cases, if the single character-string is a digit (0–9), it must be quoted or it will be considered to be a number. In all other cases, strings may be specified without quotes. Value strings are limited to a maximum of 80 characters. Value numbers may be specified in decimal notation as a string of decimal digits (0–9) or in hexadecimal notation as string of hexadecimal digits (0–9, A–F) with a leading 0x or trailing h.

Configuration records may vary in length. Configuration records may be continued beyond one record by placing an ampersand (&) character in column 1 of the second and subsequent records. The ampersands are logically replaced with spaces and the records are logically concatenated, ignoring trailing spaces. The maximum total length of a configuration record, including all continued records, is 510 characters.

Comments may be included in the configuration file. Comment text begins with a slash and an asterisk (/*) in columns 1 and 2. Lines that have /* in columns 1 and 2, as well as blank lines, are ignored in their entirety.

Built-In and Attached Configuration Files

The UNIX version of RM/COBOL allows a configuration file to be linked in to the runtime system and compiler system. The source module, **oscnfg.c**, contains a section that can be modified to reflect configuration records that will be linked in to the runtime system and compiler when the runtime and compiler are relinked. Simply take the desired configuration records and using any editor, add quotation marks (") at the beginning and end of each record, add a comma (,) at the end of each record, and then insert the lines into the **oscnfg.c** source file. Then relink the runtime system and compiler by executing the **customiz** script. The **customiz** script is described in Appendix D, *Customizing RM/COBOL for UNIX*.

The Windows version of RM/COBOL allows configuration files to be physically attached to **rmcobol.exe**, **runcobol.exe**, and **recover1.exe** using the Attach Configuration utility (**rmattach.exe)**. When attached, a configuration file will be processed prior to any configuration file specified with a command line option. For more information on this utility, see page G-39.

Configuration Errors

If your configuration file contains errors, you will see a message similar to one of the following:

```
Configuration error code at record number in configuration file.

Configuration error code in configuration file.
```

code is the error number listed for configuration records, described in Appendix A, *Runtime Messages*, starting on page A-37.

number is the logical record in the configuration file where the error occurred. When using *number* to determine which record is in error, count lines combined with their continuation lines as one record, and do not count comment lines or blank lines.

If the message is of the first format shown, the text of the configuration record in error will follow the message.

The actual error message formats are described in Chapter 6, *Compiling*, for the compiler and in Appendix A, *Runtime Messages*, for the runtime system and Indexed File Recovery utility.

Configuration Records

Table 10-1 lists and describes the types of configuration records. Configuration options that are not used by the compiler, the runtime system, or the Indexed File Recovery utility (**recover1**) are ignored. Therefore, the same configuration file may be used to configure the compiler, the runtime system, and the Indexed File Recovery program, if appropriate.

Note Configuration is never necessary unless you want to change default option settings.

Table 10-1 Types of Configuration Records

Record Type	Description	Compiler	Runtime System	Recover1
COMPILER-OPTIONS	Allows default compiler options to be changed (see page 10-6).	✓		
DEFINE-DEVICE	Associates the file access name with a physical filename of a device or process (see page 10-16).	✓	✓	
EXTENSION-NAMES	Defines the character-strings to be used for filename extensions (see page 10-19).	✓	✓	
EXTERNAL-ACCESS-METHOD	Describes the access to external file access methods, such as Btrieve, RM/plusDB, and RM/InfoExpress, from the RM/COBOL file management system (see page 10-20).	✓	✓	
PRINT-ATTR	Describes printer characteristics (see page 10-20).	✓	✓	
RUN-ATTR	Describes general runtime characteristics (see page 10-23).		✓	
RUN-FILES-ATTR	Describes the characteristics common to all file organizations (see page 10-26).	✓	✓	✓

[1] *Terminal configuration records are never necessary because terminal independence is provided by terminfo and termcap. Terminal configuration is still provided, however, to allow extensions to the basic capabilities provided by terminfo and termcap in a manner that will not conflict with other applications on your system.*

✓ *Indicates that the configuration record is used.*

Table 10-1 Types of Configuration Records *(Cont.)*

Record Type	Description	Compiler	Runtime System	Recover1
RUN-INDEX-FILES	Describes indexed file characteristics (see page 10-31).		✓	
RUN-OPTION	Describes default runtime option values (see page 10-33).		✓	
RUN-REL-FILES	Describes relative file characteristics (see page 10-34).	✓	✓	
RUN-SEQ-FILES	Describes sequential file characteristics (see page 10-34).	✓	✓	✓
RUN-SORT	Describes SORT-MERGE characteristics (see page 10-36).		✓	
TERM-ATTR[1]	Describes terminal characteristics (see page 10-36).		✓	✓
TERM-INPUT[1]	Defines incoming character sequences (see page 10-41).		✓	✓
TERM-INTERFACE[1]	Specifies the format for the other terminal configuration records, as well as the interface to be used for screen I/O (see page 10-49).		✓	✓
TERM-UNIT[1] (UNIX Only)	Associates the unit number of ACCEPT and DISPLAY statements with the actual device on the system (see page 10-49).		✓	

COMPILER-OPTIONS Record

The COMPILER-OPTIONS record identifier is followed by one or more keywords. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value. The COMPILER-OPTIONS record allows options to be configured (see the discussion of Compile Command options that begins on page 6-5). Configured options can be overridden by options entered in the Compile Command line.

Certain options require that another option be present before the compiler can proceed. For example, it is not valid to specify a cross reference if the program listing is not being generated. Other options may conflict with each other. For instance, the option to treat COMPUTATIONAL operands as binary is not valid if the program is being compiled in RM/COBOL (74) version 2.*n*-compatible mode. These conditions are not checked when the configuration file is processed. Rather, they are deferred until the command line options have also been processed.

COMPILER-OPTIONS are processed in the order they appear in the configuration file. New options are simply added to old options. If a LISTING-PATHNAME or OBJECT-PATHNAME occurs more than once, the last occurrence of each is used. The possible keywords for the COMPILER-OPTIONS record are as follows:

1. **ACCEPT-SUPPRESS-CONVERSION.** This keyword suppresses automatic input conversion for Format 1 and 3 ACCEPT statements with numeric operands. If the value is set to YES, conversion is suppressed. If the value is set to NO, conversion is performed. The default value is NO.

   This keyword corresponds to the compiler M Option. (see page 6-11).

2. **BINARY-ALLOCATION.** This keyword allows configuration of the allocation sizes allowed for a binary numeric data item. The value may be specified in any of the following ways:

   BINARY-ALLOCATION=RM specifies the traditional RM/COBOL allocation scheme of two, four, eight, or sixteen bytes. This is the default configuration.

   BINARY-ALLOCATION=RM1 specifies that one- and two-digit binary data items will be allocated as a single byte. For three to thirty digits, traditional RM/COBOL allocation of two, four, eight, or sixteen bytes will be used.

   BINARY-ALLOCATION=MF-RM specifies that the minimum number of bytes will be allocated for binary numeric data items consistent with the PICTURE character-string. This is the traditional Micro Focus COBOL binary allocation when the IBMCOMP directive is not specified, but modified to use the minimum number of bytes needed for digit counts of nineteen through thirty. The number of bytes allocated is described in Table 10-2.

Table 10-2 MF-RM Binary Allocation

Digits in PICTURE character-string		Bytes of memory allocated
Signed: S9(*n*)	**Unsigned: 9(*n*)**	
1-2	1-2	1
3-4	3-4	2
5-6	5-7	3
7-9	8-9	4
10-11	10-12	5
12-14	13-14	6
15-16	15-16	7
17-18	17-19	8
19-21	20-21	9
22-23	22-24	10
24-26	25-26	11
27-28	27-28	12
29-30	29-30	13

BINARY-ALLOCATION=CUSTOM=*integer-list* specifies a user-selected custom binary allocation configuration, where *integer-list* is a comma-separated list of integers. Each integer in *integer-list* is 1 through 16 and specifies an allowed allocation size in bytes. Allocation sizes not listed in *integer-list* will not be used. For a custom configuration, the compiler will allocate the minimum number of bytes allowed by the custom configuration that supports the number of digits described in the PICTURE character-string for a numeric binary data item. See Table 10-2 for the minimum number of bytes necessary for a given number of digits.

The RM, RM1, and MF-RM values for the BINARY-ALLOCATION keyword have the following relationships to the CUSTOM=*integer-list* value:

- BINARY-ALLOCATION=RM is equivalent to BINARY-ALLOCATION=CUSTOM=2,4,8,16 when BINARY-ALLOCATION-SIGNED=YES. When BINARY-ALLOCATION-SIGNED=NO (the default), the only difference is that 19-digit unsigned binary is allocated with 16 bytes of storage for RM mode and 8 bytes of storage for the CUSTOM mode.

- BINARY-ALLOCATION=RM1 is equivalent to BINARY-ALLOCATION=CUSTOM=1,2,4,8,16 when BINARY-ALLOCATION-SIGNED=YES. When BINARY-ALLOCATION-SIGNED=NO (the default),

the only difference is that 19-digit unsigned binary is allocated with 16 bytes of storage for RM mode and 8 bytes of storage for the CUSTOM mode.

- BINARY-ALLOCATION=MF-RM is equivalent to BINARY-ALLOCATION=CUSTOM=1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16. Note, however, that since 30 digits only require 13 bytes of storage for signed or unsigned binary, no item will be allocated with 14, 15, or 16 bytes of storage.

Some examples of custom binary allocation are:

- If BINARY-ALLOCATION=CUSTOM=16, all binary items will be 16-bytes long.
- If BINARY-ALLOCATION=CUSTOM=1,4,16, then all one-digit and two-digit binary items will be 1-byte long, any binary items greater than two digits and less than ten digits will be 4-bytes long, and all remaining binary items will be 16-bytes long.

Use of the BINARY-ALLOCATION configuration keyword will affect:

- File record structures that include binary data items.
- REDEFINES validity when the subject or object define binary data items.
- Any LINAGE-COUNTER special-registers.
- CALL statement arguments that are binary or are groups that contain binary data items. This includes CALL statement arguments for the supplied subprogram library, for example, arguments for C$CARG and C$SCRD.
- Pop-up windows, because the Pop-Up Window Control Block is a group that contains binary data items that must be allocated a specific number of bytes.

Thus, this configuration capability should be used with care. The binary allocation override language feature of RM/COBOL (see the USAGE clause in the data description entry) is more appropriate in situations where the programmer wants to control the allocated sizes of certain binary data items on a case by case basis. The binary allocation configuration capability is intended mostly for easing conversion to RM/COBOL from other COBOL dialects that use a different allocation scheme. When this configuration keyword is used, it must be used consistently throughout a programming project, and, in some cases, the binary allocation override language feature may need to be used to resolve conflicts (for example, when defining argument data items for the Liant supplied subprogram library).

3. **BINARY-ALLOCATION-SIGNED**. This keyword causes unsigned binary data items to be allocated as if they were signed, so that signed and unsigned data items with the same number of digits will be allocated the same number of bytes of storage. If the value is set to YES, unsigned binary data items are allocated the same number of bytes of storage as if they were signed; only the allocation is affected, the data item is not treated as signed for any other purpose. If the value is set to NO, unsigned items are allocated the minimum number of bytes necessary to support the unsigned precision specified by the PICTURE character-string, which for several cases is one less byte of storage than for the corresponding signed precision. The default value is NO.

4. **COBOL-74.** This keyword allows programs created for ANSI COBOL 1974 to be compiled. If the value is set to YES, ANSI COBOL 1974 semantics and I-O status values are assumed. If the value is set to NO, ANSI COBOL 1985 semantics and I-O status values are assumed. The default value is NO.

   This keyword corresponds to the compiler 7 Option (see page 6-14).

5. **COMPUTATIONAL-AS-BINARY.** This keyword, when the value is set to YES, causes the compiler to treat data items described in the source program as usage COMP or COMPUTATIONAL as if they had been described as usage BINARY. If you set the value of this keyword to NO—and do not set a value for the COMPUTATIONAL-TYPE keyword—usage COMP and COMPUTATIONAL retain their usual format (see pages C-18 and C-21 for illustrations). The default value is NO.

   Note Setting COMPUTATIONAL-AS-BINARY=YES creates compatibility between COMP data items and IBM OS/VS COMP data items. This can improve computational speed at runtime and reduce the amount of storage occupied by a COMP data item.

   When the value is set to YES, this keyword corresponds to the compiler U=B Option (see page 6-7).

   COMPUTATIONAL-AS-BINARY is an obsolete configuration capability retained for compatibility with existing configuration files. COMPUTATIONAL-AS-BINARY=YES is equivalent to COMPUTATIONAL-TYPE=BINARY.

   COMPUTATIONAL-TYPE and COMPUTATIONAL-AS-BINARY should not be specified together in the same configuration.

6. **COMPUTATIONAL-TYPE.** This keyword determines the data format used for data items described as COMPUTATIONAL or COMP in their data description entry.

   The COMPUTATIONAL-TYPE keyword may be assigned one of the following values: BINARY, DISPLAY, or PACKED-DECIMAL. If the value is set to BINARY, the format is the same as if BINARY had been specified in the USAGE clause in the data description entry. If the value is set to DISPLAY, the format is the same as if DISPLAY had been specified in the USAGE clause in the data description entry. If the value is set to PACKED-DECIMAL, the format is the same as if PACKED-DECIMAL had been specified in the USAGE clause in the data description entry. If the value is set to UNPACKED-DECIMAL, the format is the default unpacked decimal format for COMPUTATIONAL data items (see pages C-11 and C-13 for illustrations). The default data format for COMPUTATIONAL or COMP data items is UNPACKED-DECIMAL.

   Setting COMPUTATIONAL-TYPE=BINARY corresponds to the compiler U=B Option. Setting COMPUTATIONAL-TYPE=DISPLAY corresponds to the compiler U=D Option. Setting COMPUTATIONAL-TYPE=PACKED-DECIMAL corresponds to the compiler U=P Option. See page 6-7.

   COMPUTATIONAL-TYPE and COMPUTATIONAL-AS-BINARY should not be specified together in the same configuration.

7. **COMPUTATIONAL-VERSION.** This keyword modifies the data format of data items described as signed COMPUTATIONAL (COMP) and signed COMPUTATIONAL-3 (COMP-3) in their data description entry. This configuration option affects the value used for positive sign representation.

   The COMPUTATIONAL-VERSION keyword may be assigned one of the following values: RMCOBOL85, RMCOBOL2 or RMCOS. The RMCOBOL85 value represents the default positive sign convention for RM/COBOL compilers and causes UNPACKED data items to use the hexadecimal value 0C to indicate positive values, and PACKED-DECIMAL data items to use the hexadecimal value C to indicate positive values. The RMCOBOL2 value selects the positive sign convention for previous RM/COBOL (74) version 2 compilers and causes UNPACKED data items to use the hexadecimal value 0B to indicate positive values, and PACKED-DECIMAL data items to use the hexadecimal value F to indicate positive values. The RMCOS value selects the positive sign convention for the RM/COBOL-74 compiler for the RM/COS operating system and causes UNPACKED data items to use the hexadecimal value 0B to indicate positive values, and PACKED-DECIMAL data items to use the hexadecimal value B to indicate positive values.

The RMCOBOL2 and RMCOS options allow applications to access files containing COMPUTATIONAL and COMPUTATIONAL-3 data items that use previous sign representations. This keyword has no corresponding Compile Command line option. The default value is RMCOBOL85.

Note 1 The COMPUTATIONAL-VERSION keyword may be used in conjunction with the COMPUTATIONAL-TYPE keyword or the compiler U Option (see page 6-7). For example, by setting COMPUTATIONAL-TYPE=PACKED-DECIMAL (or the compiler U=P Option in the Compile Command) and COMPUTATIONAL-VERSION=RMCOBOL2, COMPUTATIONAL data items will be PACKED-DECIMAL with the RM/COBOL (74) version 2 sign representation.

Note 2 When using the COMPUTATIONAL-VERSION keyword, you cannot specify an object version level less than 7.

8. **DEBUG.** This keyword determines whether source programs are to be compiled as if the WITH DEBUGGING MODE clause appeared in each program. If the value is set to YES, the debugging mode is selected. If the value is set to NO, debugging mode is not selected. The default value is NO.

   This keyword corresponds to the compiler D Option (see page 6-15).

9. **DEBUG-TABLE-OUTPUT.** This keyword, when the value is set to YES, causes the compiler to include both the symbol table and the debug line table in the object program. Furthermore, when the value is set to ALL, the actual text of compiler-generated lines that do not appear in source or copy files is also included in the object file and is available during debugging.

   When the debug line table is included in the object program, CodeWatch can display the program's source at execution time. Setting YES is sufficient for most purposes. If ALL is set, the displayed source has the appearance of a printed listing. Note that this may lead to large object program files. (After debugging is complete, this information may be removed by the STRIP option in the Combine Program utility (**rmpgmcom**), as described in Appendix G, *Utilities*.)

   When the value of this keyword is set to NO, the line table is not included in the object file. The default value is NO.

   Setting DEBUG-TABLE-OUTPUT=YES corresponds to the compiler Y=2 Option. Setting DEBUG-TABLE-OUTPUT=ALL corresponds to the compiler Y=3 Option. (See page 6-13 for a description of these options.) Both options imply SYMBOL-TABLE-OUTPUT=YES (see page 10-16)**.**

10. **DERESERVE.** This keyword directs the compiler to remove words (and their associated language features) from the reserved words list. The value of the DERESERVE keyword is a comma-separated list of those words to be removed from the reserved words list. All words specified must be found in the compiler reserved words list. By default, no words are removed from the reserved words list.

    This keyword has no corresponding Compile Command line option.

11. **FLAGGING.** This keyword flags specified elements of the COBOL language in the listing file. Multiple values are separated by commas. One or more of the following values may be included in any order:

COM1	INTERMEDIATE
COM2	OBSOLETE
EXTENSION	SEG1
HIGH	SEG2

    COM1 flags COM1 and COM2 elements of the language.

    COM2 flags COM2 elements of the language.

    EXTENSION flags RM/COBOL extensions to ANSI COBOL 1985.

    HIGH flags HIGH elements of the language.

    INTERMEDIATE flags HIGH and INTERMEDIATE elements of the language.

    OBSOLETE flags obsolete elements of the language.

    SEG1 flags SEG1 and SEG2 elements of the language.

    SEG2 flags SEG2 elements of the language.

    By default, none of the occurrences of the preceding items is flagged. This keyword corresponds to the compiler F Option (see page 6-15).

12. **LISTING-ATTRIBUTES.** This keyword determines which information is to be included in the program listing, and where the program listing will be directed. One or more of the following values may be included, in any order (multiple values must be separated by commas):

ALLOCATION-MAP	NO-TERMINAL-DISPLAY
CROSS-REFERENCE	PRINT-LISTING
ERROR-ONLY-LIST	SUPPRESS-COPY-FILES
LISTING-FILE	TERMINAL-LISTING

    ALLOCATION-MAP generates an allocation map. When set to this value, the LISTING-ATTRIBUTES keyword corresponds to the compiler A Option (see page 6-9). By default, the allocation map is not generated.

CROSS-REFERENCE generates a cross reference map. When set to this value, the LISTING-ATTRIBUTES keyword corresponds to the compiler X Option (see page 6-11). By default, the cross reference listing is not generated.

ERROR-ONLY-LIST includes only erroneous source lines in the listing file. When set to this value, the LISTING-ATTRIBUTES keyword corresponds to the compiler E Option (see page 6-9). By default, the source program component of the listing is not suppressed.

LISTING-FILE writes a copy of the listing file to disk. When set to this value, the LISTING-ATTRIBUTES keyword corresponds to the compiler L Option (see page 6-9). By default, a copy of the listing file is not written to disk.

NO-TERMINAL-DISPLAY suppresses the display of informational messages on the screen. When set to this value, the LISTING-ATTRIBUTES keyword corresponds to the compiler K Option (see page 6-7). By default, the informational messages are displayed.

PRINT-LISTING prints a copy of the listing file. When set to this value, the LISTING-ATTRIBUTES keyword corresponds to the compiler P Option (see page 6-10). By default, the listing file is not printed.

SUPPRESS-COPY-FILES directs that text in the copy files not be placed in the listing file. When set to this value, the LISTING-ATTRIBUTES keyword corresponds to the compiler C Option (see page 6-9). By default, copy files are placed into the listing file.

TERMINAL-LISTING displays a copy of the listing file on the screen. When set to this value, the LISTING-ATTRIBUTES keyword corresponds to the compiler T Option (see page 6-11). By default, a copy of the listing is not written to the standard output device.

13. **LISTING-DATE-FORMAT.** This keyword directs the compiler to use a specific format for the compilation date in the header lines on listing pages. The value must be one of the following:

    MMDDYY (for month-of-year, day-of-month, year-of-century)
    DDMMYY (for day-of-month, month-of-year, year-of-century)
    YYMMDD (for year-of-century, month-of-year, day-of-month)
    YYDDD (for year-of-century, Julian day-of-year)
    MMDDYYYY (for month-of-year, day-of-month, year-of-millennium)
    DDMMYYYY (for day-of-month, month-of-year, year-of-millennium)
    YYYYMMDD (for year-of-millennium, month-of-year, day-of-month)
    YYYYDDD (for year-of-millennium, Julian day-of-year)

    The default value is MMDDYYYY.

This keyword has no corresponding Compile Command line option.

Note This keyword affects the date inserted for the DATE-COMPILED paragraph. The same date format used in the listing header is inserted in the DATE-COMPILED paragraph.

14. **LISTING-DATE-SEPARATOR.** This keyword directs the compiler to use a specific separator character for the compilation date in the header lines on listing pages. The value of this keyword must be a single character-string or a number from 0 to 255. The default value is "/" (47 or 0x2f).

    This keyword has no corresponding Compile Command line option.

    Note This keyword affects the date inserted for the DATE-COMPILED paragraph. The same date format used in the listing header is inserted in the DATE-COMPILED paragraph.

15. **LISTING-PATHNAME.** This keyword directs the compiler to write the program listing to the indicated directory. When using this keyword, it is not necessary to set LISTING-ATTRIBUTES=LISTING-FILE.

    This keyword corresponds to the compiler L Option (see page 6-9).

16. **LISTING-TIME-SEPARATOR.** This keyword directs the compiler to use a specific separator character for the compilation time in the header lines on listing pages. The value of this keyword must be a single character-string or a number from 0 to 255. The default value is ":" (58 or 0x3a).

    This keyword has no corresponding Compile Command line option.

17. **OBJECT-PATHNAME.** This keyword directs the compiler to write the object file to the indicated directory.

    This keyword corresponds to the compiler O Option (see page 6-12).

18. **OBJECT-VERSION.** This keyword specifies the highest allowed object version level of code generated by the compiler. The value must be an integer in the range 1 through 8. The default value is the current object version number, 8.

    This keyword corresponds to the compiler Z Option (see page 6-14).

19. **RESEQUENCE-LINE-NUMBERS.** This keyword directs the compiler to generate a sequential line number in the first six columns of source records as they appear on the listing. The source file is not affected.

    If the value is set to YES, this keyword numbers records beginning with 1 for each source or copy input file. The number can be helpful when editing the source file. This line number cannot be used with the RM/COBOL Interactive Debugger.

If the value is set to NO, the compiler will print the source record exactly as read, including any commentary information present in columns 1 through 6.

The default value for this keyword is NO. This keyword corresponds to the compiler R Option (see page 6-10).

20. **RMCOBOL-2.** This keyword allows programs created for the RM/COBOL (74) version 2.*n* compiler to be compiled. If the value is set to YES, RM/COBOL (74) version 2.*n* programs are accepted. If the value is set to NO, they are not. The default value is NO.

    This keyword corresponds to the compiler 2 Option (see page 6-16).

21. **SEPARATE-SIGN.** This keyword determines whether the compiler is to use a separate or a combined sign for a signed numeric data item with DISPLAY specified in the USAGE clause when a SIGN clause is not specified in the data description entry. If the value is set to YES, a separate sign is assumed. If the value is set to NO, a combined sign is assumed. The default value is NO.

    This keyword corresponds to the compiler S Option (see page 6-7).

22. **SEQUENTIAL-FILE-TYPE.** This keyword determines the organization of sequential files not explicitly defined as binary sequential or line sequential in their SELECT entries.

    The SEQUENTIAL-FILE-TYPE keyword may be assigned one the following values: LINE or BINARY. If the value is set to LINE, all files not defined as binary sequential are line sequential. If the value is set to BINARY, all files not defined as line sequential are binary sequential. If this keyword is not configured and no selection is made at compile time, the decision on whether the file is BINARY or LINE is deferred to program execution. The choice is then controlled by the configured DEFAULT-TYPE (see page 10-35).

    Setting SEQUENTIAL-FILE-TYPE=BINARY corresponds to the compiler B Option (see page 6-8). Setting SEQUENTIAL-FILE-TYPE=LINE corresponds to the compiler V Option (see page 6-8).

23. **SUPPRESS-NUMERIC-OPTIMIZATION.** The optimized code that the compiler normally generates for numeric operations assumes that all nonbinary numeric data items contain only standard digits and signs as described in Appendix C, *Internal Data Formats*. Setting the value of the SUPPRESS-NUMERIC-OPTIMIZATION keyword to a value of YES directs the compiler to generate unoptimized code for all nonbinary numeric operations. The unoptimized code is more likely to interpret correctly a nonbinary numeric field that contains nonstandard digits and signs. In particular, it will treat space characters and binary zero characters as if they were display zeros, and it will accept a wider range of representations of a positive sign.

The unoptimized code takes longer to execute than the optimized code. The difference will be noticeable in programs that have a very high density of numeric operations. When the value of the SUPPRESS-NUMERIC-OPTIMIZATION keyword is set to NO, the compiler generates the normal, optimized code for numeric operations.

The default value for this keyword is NO. This keyword has no corresponding Compile Command line option.

24. **SYMBOL-TABLE-OUTPUT.** This keyword, when its value is set to YES, causes the compiler to include the symbol table in the object program. (Note that this information may be removed by the STRIP option in the Combine Program utility (**rmpgmcom**), as described in Appendix G, *Utilities*.) When the symbol table is included in the object program, source program data-names and index-names may be used in Debug commands at execution time (see Chapter 9, *Debugging*).

    When the value of this keyword is set to NO, the symbol table is not included in the object program. The default value is NO.

    Selecting SYMBOL-TABLE-OUTPUT=YES corresponds to the compiler Y Option (see page 6-13).

25. **WORKSPACE-SIZE.** This keyword allows the specification of the amount of workspace area that the compiler will allocate for its internal tables. Control of this keyword will allow larger programs to be compiled, or memory to be conserved when compiling small programs on a system with limited memory. This keyword's value is a decimal number that reserves memory in increments of 1024 (1 KB) bytes; for example, a value of 100 would reserve 102400 bytes. The minimum value is 32 and the maximum value is 16384. This keyword may be overridden using the compiler W Option (see page 6-7).

    The default value for this keyword is 1024 kilobytes.

DEFINE-DEVICE Record

The DEFINE-DEVICE record is used to associate a physical device to a value for an RM/COBOL file access name. The keywords DEVICE and PATH must be present. The DEFINE-DEVICE record identifier is followed by one or more keywords. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value. The possible keywords are as follows:

1. **DEVICE.** This keyword specifies the RM/COBOL file access name value that will be associated with the operating system device. If the value of the DEVICE keyword is the same as the value specified as the file access name, the value supplied in the PATH keyword will be used as the actual pathname.

2. **PATH.** This keyword specifies the pathname to be used as the pathname or pipe for the device. This value may be enclosed in quotation marks to allow spaces to be included in a pipe (see the next paragraph). If it necessary to place a quotation mark in the pipe, use a pair of consecutive quotation marks for each quote within the string.

3. **PIPE.** This keyword determines whether the value of the PATH keyword is a process to be spawned. If the value is set to YES, the runtime system will start another program to simulate a device receiving the record by creating a write-only pipe and forking a child shell process using the value of the PATH keyword as the shell's command. Thus, the value of the PATH keyword specifies the program to start. If you use quotation marks to enclose the command, any shell command may be given along with any options. If the value is set to NO, the runtime system will use the PATH value as the actual pathname. The default value is NO.

   Note The PIPE keyword is supported only under UNIX.

4. **RAW.** This keyword determines whether the Windows printer described by the value of the PATH keyword is opened in RAW mode. If the value is set to YES, the runtime system will open the printer in RAW mode. This allows certain Windows NT networked printers to respond to embedded escape sequences. See "P$SetRawMode" subprogram in Appendix E, *Windows Printing*, for a more complete description of RAW mode. Most P$ subprograms are not available if RAW mode is used. If the value is set to NO, the runtime system will treat the printer as a normal Windows printer. The default value is NO.

   Note The RAW keyword is supported only under Windows.

5. **ESCAPE-SEQUENCES.** This keyword determines whether the Windows printer described by the value of the PATH keyword allows embedded RM/COBOL-specific escape sequences. See "RM/COBOL-Specific Escape Sequences" in Appendix E for a more complete description. If the value is set to YES, the RM/COBOL runtime system will recognize the sequences. If the value is set to NO, the runtime system will not recognize those escape sequences. The default value is NO.

   Note The ESCAPE-SEQUENCES keyword is supported only under Windows.

The presence of a single DEFINE-DEVICE record overrides the automatic internal configuration for the PRINTER and TAPE support. See the discussions of printer and tape support on pages 8-46 and 8-47, respectively, for more information.

Windows Printers

The DEFINE-DEVICE record is used to associate a Windows printer device with an RM/COBOL file access name. It is not possible to bypass the Windows printer drivers by using the DEFINE-DEVICE record. If the Windows printer driver is used, it is not possible to send raw escape sequences to the printer. When using DEFINE-DEVICE to specify a Windows printer, both the DEVICE and PATH keywords are required.

The PATH keyword specifies the Windows printer device to use. The syntax is as follows:

```
PATH=[ [Device Name] [, [Port] [, [Font Name] [, [Size] ] ] ]
```

Device Name is the name of the printer.

The name "DEFAULT" can be used to indicate that the default Windows printer should be used. If a *Device Name* is specified, the *Port* is ignored.

Port specifies the port to which the printer is attached. *Port* must be defined on the Details tab for a printer shown in the Printers folder or COBOL I/O error 35 will be returned from the OPEN statement.

Font Name specifies the font to use.

Size specifies the size of the font to use. It is specified in points.

Note If neither a *Device Name* nor *Port* is specified, the default printer is used.

Examples of DEFINE-DEVICE records are as follows:

```
DEFINE-DEVICE DEVICE=PRINTER PATH=",LPT1"
```

Note "**LPT1**" can also be specified as "**LPT1:**". The colon is optional.

```
DEFINE-DEVICE DEVICE=FOO PATH="HP LaserJet"
```

For compatibility with Windows, whenever a device name followed by the colon character is encountered in either the DEVICE or PATH keywords, it is treated as if the colon were not present. For example, the following configuration records:

```
DEFINE-DEVICE DEVICE=PRN: PATH=",LPT1"
DEFINE-DEVICE DEVICE=LPT2 PATH=",LPT2:"
```

would be treated as if they were:

```
DEFINE-DEVICE DEVICE=PRN PATH=",LPT1"
DEFINE-DEVICE DEVICE=LPT2 PATH=",LPT2"
```

To perform translation of "PRINTER*x*" names in the same way that the RM/COBOL for DOS runtime system does, the following default synonym table is used.

```
DEVICE=PRINTER   PATH="DEFAULT"
DEVICE=PRINTER?  PATH="DYNAMIC"
DEVICE=PRINTER1  PATH=",LPT1"
DEVICE=PRINTER2  PATH=",LPT2"
DEVICE=PRINTER3  PATH=",LPT3"
DEVICE=PRINTER4  PATH=",LPT4"
DEVICE=PRINTER5  PATH=",LPT5"
DEVICE=PRINTER6  PATH=",LPT6"
DEVICE=PRINTER7  PATH=",LPT7"
DEVICE=PRINTER8  PATH=",LPT8"
DEVICE=PRINTER9  PATH=",LPT9"
```

The "PRINTER?" synonym is provided to allow dynamic assigning of the Windows at printer open time. See page 3-15 for more information on the use of "PRINTER?".

EXTENSION-NAMES Record

The EXTENSION-NAMES record identifier is followed by one or more keywords indicating file usages. Each keyword is allowed to have a value, and is followed by an equal sign (=) and the value. More than one file usage keyword may be listed in one EXTENSION-NAMES record. The extension value must be one to three characters in length. The extension value may be specified as a single period to indicate that no extension is to be used for files of the file usage indicated by the keyword. In all other cases, the characters specified for the extension value must be in the set of characters that are valid for a filename extension under the current operating system.

The file usage keywords are the following:

1. **COPY.** This keyword specifies the extension to be used for files referenced by COPY statements in a COBOL source program. The default extension for copy files is **cbl**.

2. **LISTING.** This keyword specifies the extension to be used for COBOL listing files. The default extension for listing files is **lst**.

3. **OBJECT.** This keyword specifies the extension to be used for COBOL object program files. The default extension for object files is **cob**.

4. **SOURCE.** This keyword specifies the extension to be used for COBOL source program files. The default extension for source files is **cbl**.

EXTERNAL-ACCESS-METHOD Record

The EXTERNAL-ACCESS-METHOD record is used to identify external file access methods that should be applied. It can be repeated more than once to identify multiple access methods and the order in which they are to be accessed. UNIX supports the following external access methods: RMPLUSDB, RMINFOX, and USRMTACC. Windows supports RMBTRV32, RMSPX32, and RMTCP32. (Refer to Chapter 4, *System Considerations for Btrieve,* for more information about RMBTRV32).

The EXTERNAL-ACCESS-METHOD record identifier is followed by one or more keywords. Each keyword is followed by an equal sign (=) and the value to be assigned to that keyword. The possible keywords are as follows:

1. **CREATE-FILES.** This keyword controls whether the external access method will be called to create new files. If the value is set to YES, the external access method will be allowed to create files. If the value is set to NO, and the file does not exist, the external access method will not be called to create it. The default value for this keyword is YES.

2. **NAME.** This keyword is used to identify the name of the external access method. It is required and has no default value. The external access method names currently identified are RMPLUSDB, RMINFOX, and USRMTACC for UNIX, and RMBTRV32, RMSPX32, and RMTCP32 for Windows.

3. **OPTIONS.** This keyword is used to pass options to the external access method interface. The options must be enclosed in quotation marks. The possible values depend on the external access method that is specified in the NAME keyword. If this keyword is not specified, no options will be passed to the external access method interface.

PRINT-ATTR Record

The PRINT-ATTR record is used to describe the characteristics of the printer to which printer files are assigned or on which printer files will eventually be printed. A printer file is a line sequential file that has any or all of the following RM/COBOL source program features:

- ASSIGN TO PRINT or ASSIGN TO PRINTER phrase in the file control entry for the file
- LINAGE phrase in the file description entry for the file
- ADVANCING phrase in a WRITE statement for the file

The compiler listing is a printer file.

The PRINT-ATTR record identifier is followed by one or more keywords. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value. The possible keywords are as follows:

1. **AUTO-LINE-FEED.** This keyword determines whether a line feed is needed after a carriage return to cause a single line advance of the carriage. If the value is set to YES, a single line advance is automatic so no line feed character will be written. If the value is set to NO, a single line advance is not automatic, thus requiring a line feed character. The default value is NO.

2. **COLUMNS.** This keyword determines the number of columns across a line, represented as a decimal number in the range 1 through 65280. All records written to a printer file will be truncated to this value. The default value is not to truncate.

3. **FORM-FEED-AVAILABLE.** This keyword indicates whether the printer supports the form feed character, FF, to slew to the top of a new page. If the value is set to NO, top-of-page will be reached by issuing an appropriate number of line feeds; the LINES keyword should be used to describe the page size. If the value is set to YES, top-of-page will be reached by writing a form feed character. The default value is YES.

   Note This option only determines the method used by the runtime I-O system to position the file to a new physical page. The runtime I-O system would normally print a form feed character to accomplish a physical page break. If the user's printer does not support advancing to the next physical page when a form feed character is printed, the value of this option can be set to NO to tell the runtime I-O system not to use a form feed character for this purpose. Regardless of the setting of this option, files described with the LINAGE clause do not normally use physical page breaks because the LINAGE clause describes logical rather than physical pages. Files described with the LINAGE clause will be affected by this option only if either of the PRINT-ATTR configuration record keywords LINES or LINAGE-PAGES-PER-PHYSICAL-PAGE are set to a nonzero value.

4. **LINAGE-INITIAL-FORM-POSITION.** This keyword determines the assumed initial position of the form in the printer for a file described with the LINAGE clause (see page 8-43). If set to TOP-OF-FORM, the form is assumed to be positioned at the top of the page (that is, on the first line of the top margin). In this case, the runtime writes the first line after advancing over the top margin of the first page so as to reach the first line of the logical page body. The value TOP-OF-FORM would normally be used for page printers that do not use continuous forms. If set to PAGE-BODY-LINE-1, the form is assumed to be positioned at line one of the page body and the runtime ignores the top margin specified for the first logical page. The value PAGE-BODY-LINE-1 would normally be used with line printers that use

continuous forms that have been positioned by the operator to print the first line of the logical page body. The default value is PAGE-BODY-LINE-1.

5. **LINAGE-PAGES-PER-PHYSICAL-PAGE.** This keyword determines whether physical page breaks are generated for files described with the LINAGE clause (see page 8-43). When this keyword is set to the value 0, the set of logical pages is printed contiguously with no additional spacing provided between logical pages, except as explained in the note regarding the PRINT-ATTR configuration keyword LINES. Form feed characters, in particular, are not normally used between pages. When this keyword is set to a value from 1 to 255, the value indicates the number of logical pages that fit on a physical page. Each time that many pages have been printed, a physical page break will be generated. For example, a value of 1 causes a physical page break (see the note below for additional details on physical page breaks) between each logical page. As another example, assuming that there are three logical pages (for example, checks) per physical page, a value of 3 could be used to cause a physical page break between each set of three logical pages. A nonzero value is typically useful for page printers when the logical page, or a set of logical pages, does not fill a physical page. A zero value is typically useful for line printers using continuous forms. The default value is 0.

   Note This option instructs the runtime I-O system to insert a physical page break between certain logical pages. The physical page break is normally a form feed character. However, the PRINT-ATTR configuration record keyword settings FORM-FEED-AVAILABLE=NO and LINES=*n* may be used together in those cases where a form feed character is either not available or not desirable. In this case, a physical page break is accomplished by printing the number of line feed characters necessary to ensure *n* lines per physical page.

6. **LINES.** This keyword determines the number of lines on a page, represented as a decimal number in the range 1 through 65535. Use this keyword when FORM-FEED-AVAILABLE=NO (see the preceding keyword). This keyword may be used with FORM-FEED-AVAILABLE=YES to cause form feed characters to be placed in the file after the specified number of lines have been written. The default value is not to have page size processing.

   This keyword also determines the number of lines on a page of a compilation listing. If not specified, the RM/COBOL compiler assumes 66 lines per page.

   Note This option, when set to a nonzero value, will cause files described with the LINAGE clause to advance to a new physical page whenever that number of lines have been printed. This may result in unintended additional spacing between or within logical pages, depending on the relationship between the value specified for LINES and the size(s) of logical pages. For page printers, setting LINES to the size of the logical page may have the desired effect of ejecting pages from the printer

when a logical page is complete. However, the PRINT-ATTR configuration record keyword LINAGE-PAGES-PER-PHYSICAL-PAGE, which only affects files described with the LINAGE clause, is better suited to this purpose.

7. **TOP-OF-FORM-AT-CLOSE.** This keyword determines whether the printer file is positioned to top-of-form when closed. If the value is set to YES, the printer file will be positioned to top-of-form with form feed or line feed characters. If the value is set to NO, no additional control characters will be written when the printer file is closed. The default value is NO.

8. **WRAP-COLUMN.** This keyword determines the column number after which automatic line wrap-around occurs, represented as a decimal number in the range 1 through 65535. The default value is to assume that the printer does not automatically wrap long lines.

9. **WRAP-MODE.** This keyword specifies whether automatic line wrapping occurs when the WRAP-COLUMN character is written. If the value is set to EXACT, wrapping occurs when the WRAP-COLUMN character is written. If the value is set to NEXT, wrapping occurs when the character following the WRAP-COLUMN character is written.

RUN-ATTR Record

The RUN-ATTR record identifier is followed by one or more keywords. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value. The following descriptions include the default values that are used if the keyword is not modified by a RUN-ATTR record. The possible keywords are as follows:

1. **ACCEPT-FIELD-FROM-SCREEN.** This keyword controls the behavior of ACCEPT statements that do not specify either the PROMPT or the UPDATE phrase. If the value is set to YES, the field is initialized with the current contents of the field on the display. If the value is set to NO, the field is initialized to all blanks. The default value is NO. In either case, the contents of the field as displayed are unchanged.

   Only fields output by the RM/COBOL runtime system can be reliably retrieved. The contents of a field that appeared on the display prior to the invocation of the runtime are considered undefined.

2. **ACCEPT-INTENSITY.** This keyword determines the default intensity level used within ACCEPT statements. If the value is set to HIGH, high intensity is used. If the value is set to LOW, low intensity is used. The default ACCEPT intensity value is HIGH.

3. **ACCEPT-PROMPT-CHAR.** This keyword enables the ACCEPT statements default prompt character to be overridden with the character corresponding to the value of the keyword. Changing the default prompt character does not affect ACCEPT statements that do not use the PROMPT phrase. The value of this keyword must be a single character-string or a number from 0 to 255. The default value is "_" (95 or 0x5F).

4. **BEEP.** This keyword determines whether the runtime system should override the beeps (BEEP) that are coded in ACCEPT and DISPLAY statements. If the value is set to YES, the beeps that are coded in the statements (including the default beeps on ACCEPT statements) cause the terminal to beep. If the value is set to FORCED-ACCEPT, all Format 3 ACCEPT statements cause the terminal to beep; all other ACCEPT and DISPLAY statements behave as if the value were set to YES. If the value is set to NO, the beeps that are coded in the statements are ignored. The default value is YES.

5. **BLINK.** This keyword determines whether the runtime system should override blinking (BLINK) coded in the ACCEPT and DISPLAY statements. If the value is set to YES, blinking is used as directed by the statements. If the value is set to NO, blinking is not used. The default value is YES.

   Note The blinking attribute is not available under Windows.

6. **DISPLAY-INTENSITY.** This keyword determines the default intensity level used within DISPLAY statements. If the value is set to HIGH, high intensity is used. If the value is set to LOW, low intensity is used. The default DISPLAY intensity is HIGH.

7. **EDIT-COMMA.** This keyword enables the comma edit character (thousands separator) to be overridden with the character corresponding to the value of the keyword. This configuration option is not affected by the presence of the DECIMAL-POINT IS COMMA clause in the source program, except for the default value. The value of this keyword must be a single character-string or a number from 0 to 255. The default value is "," (44 or 0x2c), or, if DECIMAL-POINT IS COMMA clause is specified in the source program, the default is "." (46 or 0x2e).

8. **EDIT-CURRENCY-SYMBOL.** This keyword enables the currency symbol edit character (cs) to be overridden with the character corresponding to the value of the keyword. This keyword has effect only when a CURRENCY SIGN IS clause is present in the Configuration Section of the program. This configuration option does not affect the currency sign ($) (see the EDIT-DOLLAR keyword for overriding the currency sign value). The value must be a single character-string or a number from 0 to 255. The default value is "$" (36 or 0x24).

9. **EDIT-DECIMAL.** This keyword enables the decimal point edit character to be overridden with the character corresponding to the value of the keyword. This configuration option is not affected by the presence of the DECIMAL-POINT IS COMMA clause in the source program, except for the default value. The value of this keyword must be a single character-string or a number from 0 to 255. The default value is "." (46 or 0x2e), or, if the DECIMAL-POINT IS COMMA clause is specified in the source program, the default is "," (44 or 0x2c).

10. **EDIT-DOLLAR.** This keyword enables the currency sign ($) to be overridden with the character corresponding to the value of the keyword. This configuration option is not affected by the presence of the CURRENCY SIGN clause in the source program, unless the program specifies CURRENCY SIGN IS "$". In that case, the "$" in that program is the currency symbol and the EDIT-DOLLAR keyword has no effect. (See the EDIT-CURRENCY-SYMBOL keyword for overriding the currency symbol value.) The value must be a single character-string or a number from 0 to 255. The default value is "$" (36 or 0x24).

11. **ERROR-MESSAGE-DESTINATION.** This keyword determines the destination to which the runtime system should direct error messages, Interactive Debugger input and output, STOP literal messages and STOP RUN messages. ACCEPT . . . FROM CONSOLE and DISPLAY . . . UPON CONSOLE are not affected by this keyword. The two possible values are STANDARD-ERROR and STANDARD-INPUT-OUTPUT. If the value is set to STANDARD-ERROR, these messages are directed to the standard error device. If the value is set to STANDARD-INPUT-OUTPUT, these messages are written to standard output and, in the cases of Debug input and STOP *literal* message operator responses, the responses are read from standard input. The value STANDARD-ERROR does not allow redirection of the messages; STANDARD-INPUT-OUTPUT does allow redirection. The default value is STANDARD-ERROR. (See page 2-22 for information on the standard input, output, and error devices.)

12. **REVERSE.** This keyword determines whether the runtime system should override reverse video (REVERSE) coded in the ACCEPT and DISPLAY statements. If the value is set to YES, reverse video is used as directed by the statements. If the value is set to NO, reverse video is not used. The default value is YES.

13. **SCROLL-SCREEN-AT-TERMINATION.** This keyword determines whether the runtime system should scroll the screen by one line before returning to the shell. If the value is set to NO, the screen is not scrolled. If the value is set to YES, the screen is scrolled only if the COBOL program performed any screen I/O, such as ACCEPT or DISPLAY statements. The default value is YES.

14. **TAB.** This keyword controls the default behavior of ACCEPT statements that do not have a TAB phrase. If the value of the keyword is set to YES, ACCEPT statements are executed as if the TAB phrase were present. If value is set to NO, ACCEPT statements are executed as if the NO TAB keyword were present in the CONTROL phrase. The default value is NO.

15. **UNDERLINE.** This keyword determines whether the runtime system should override underlining (UNDERLINE) coded in the Screen Section or the CONTROL phrase of ACCEPT and DISPLAY statements. If the value is set to YES, underlining is used as directed by the statements. If the value is set to NO, underlining is not used. The default value is YES.

For complete descriptions of the ACCEPT and DISPLAY statements, see Chapter 6, *Procedure Division Statements*, of the *RM/COBOL Language Reference Manual*.

RUN-FILES-ATTR Record

The RUN-FILES-ATTR record identifier is followed by one or more keywords. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value. Some of the following keywords are allowed on both the RUN-FILES-ATTR record and on the RUN-INDEX-FILES, RUN-REL-FILES, and RUN-SEQ-FILES records. For these keywords, specifying a value on a RUN-FILES-ATTR record is equivalent to specifying the same value on RUN-INDEX-FILES, RUN-REL-FILES, and RUN-SEQ-FILES records. If a keyword exists on both a RUN-FILES-ATTR and on a RUN-*xxx*-FILES record, then the last one in the configuration file will be used. The possible keywords are as follows:

1. **ALLOW-EXTENDED-CHARS-IN-FILENAMES**. This keyword controls whether extended characters in the range 128 through 255 (0x80 through 0xFF) are allowed in filenames. If this keyword is set to YES, these characters are allowed. If this keyword is set NO, these characters are excluded from filenames. The default value is NO.

   Note This keyword is supported only under Windows.

2. **BLOCK-SIZE.** This keyword determines the default disk block size for all file organizations except program files, represented as a decimal number. It can be overridden by a configuration record for a particular organization. A program can override this with the BLOCK CONTAINS clause in the file description entry. The maximum value is 65489. The minimum value is 256. Under UNIX, the default value is BUFSIZ, taken from the C include file <**stdio.h**>. Under Windows, the default value is the disk sector size. Program files always use 512-byte blocks.

3. **BUFFER-POOL-SIZE.** This keyword determines the amount of memory that should be allocated in the disk buffer pool, represented as a decimal number. The

maximum value is 664838. The minimum value is 1. A value of 1 will cause the minimum disk buffer pool to be allocated. The default value is 20480 for the compiler and 256000 for the runtime system.

4. **DISABLE-COMMIT-FILE.** This keyword can be used to prevent the use of the DOS Commit File function. If the value is set to YES, then the Commit File function will never be used. If the value is set to NO, and the Commit File function is available, then it will be used to flush data to the disk. The default value is NO.

   Note This keyword is supported only under Windows.

5. **ENABLE-OLD-DOS-FILENAME-HANDLING**. This keyword controls whether filenames are processed in the way they were handled in earlier DOS runtimes. If this keyword is set to YES, filenames are converted to uppercase, all spaces are eliminated, and each node name (characters between separators) is truncated to 8.3 format. For example, the filename "c:\long directory.name\long filename.extension" would become "C:\LONGDIRE.NAM\LONGFILE.EXT". If this keyword is set to NO, filenames remain in mixed case, spaces are allowed, and long node names are allowed (that is, no truncation). The default value is NO.

   Note This keyword is supported only under Windows.

6. **EXPANDED-PATH-SEARCH.** This keyword controls when the directory search sequence is used. If a filename is specified with no directory path, the directory search sequence will always be used. If the filename begins with a forward slash (/), a backward slash (\), or a tilde (~), the directory search sequence will not be used. If the filename contains a directory path that does not begin with a slash or tilde, the directory search sequence will be used only if this keyword is set to YES. In this case, the entire name, including the directory path, will be appended to each entry in the directory search sequence. The default value for this keyword is NO.

7. **FATAL-RECORD-LOCK-TIMEOUT.** This keyword affects record locking. For file descriptors whose file control entry has no FILE STATUS clause and file descriptors that have no USE declarative procedure defined, this keyword determines how many seconds to wait when attempting to lock a record that is locked by another run unit before returning a fatal error to the calling program. A value of 0, the default value, indicates an infinite wait. The minimum value is 0, and the maximum value is 65,535 seconds.

   If the record is locked using a different file descriptor in the same run unit, the error will always be returned immediately to prevent a deadlock situation.

8. **FILE-HANDLE-LIMIT.** This keywords determines the number of file handles the RM/COBOL file management system may use. The default value is 255.

   Note This keyword is supported only under Windows.

9. **FILE-LOCK-LIMIT.** This keyword determines the limit for the location to apply locks to a file. This number can vary depending on the system on which the file resides. The lock limit applies to all file organizations. For record and file locks to perform correctly, all run units opening a file must use the same file lock limit. The lock limit also limits the actual amount of data that can be stored in a file. This data limit is dependent on the file organization. Sequential and relative files can store slightly less than half this number. For indexed files, the data size limit varies with the block size: a block size of 1024 will allow eighty percent of this number for data storage; a block size of 4096 will allow over ninety percent. The maximum value is 07FFFFFEh (approximately two gigabytes). The minimum value is 1. The default value is 07FFFFFEh.

   For information on superseding the limit for the location to apply locks to a file that will be accessed as a large file, see the description of the LARGE-FILE-LOCK-LIMIT keyword later in this section.

10. **FILE-PROCESS-COUNT.** This keyword determines the maximum number of run units that can have a file open at the same time. It applies to all file organizations. For record and file locks to perform correctly, all run units opening a file must use the same file process count. The maximum value is 4096. The minimum value is 8. The default value is 1024.

11. **FORCE-USER-MODE.** This keyword determines whether the runtime system should assume a single-user or a shared environment. If the value is set to SINGLE, local files are locked and treated as if they were unshared. If the value is set to MULTI, local files are treated as if they were shared, and locks are applied as specified in OPEN statements. This keyword does not affect remote files. Remote files are always assumed to be in a shared environment. The default value is MULTI.

    Note This keyword is supported only under Windows.

12. **KEEP-FLOPPY-OPEN.** This keyword determines whether the runtime system will open and close program and message files that reside on a floppy drive every time it accesses them. If the value is set to NO, the RM/COBOL file management system closes these files as often as possible in order to prevent floppy corruption problems that can occur when swapping diskettes during a program execution. If the value is set to YES, the RM/COBOL file management system will not attempt to close floppy-based program and message files after every access. The default value is NO.

    Note This keyword is supported only under Windows.

13. **LARGE-FILE-LOCK-LIMIT.** This keyword determines the limit for the location to apply locks to a file that will be accessed as a large file, superseding the limit specified by the FILE-LOCK-LIMIT keyword. For record and file locks to perform correctly, all run units opening a particular file must use the same file lock limit. The lock limit also limits the actual amount of data that can be stored in a file. (See the

description of the FILE-LOCK-LIMIT keyword, described earlier in this section, for details on this relationship.) The value assigned to this keyword is specified in gigabytes (GB). The maximum value is 1048576, which equates to 1 petabyte (2^{50}). The minimum value is 1. The default value is 64.

For an explanation of how to indicate that a relative file or a sequential file will be accessed as a large file, see the description of the USE-LARGE-FILE-LOCK-LIMIT configuration keyword of the RUN-REL-FILES and RUN-SEQ-FILES records on page 10-34. See the description of File Version Level 3 on page 8-65 and the description of the DEFAULT-FILE-VERSION-NUMBER configuration keyword of the RUN-INDEX-FILES record on page 10-31 for information on using the LARGE-FILE-LOCK-LIMIT with indexed files.

14. **RESOLVE-LEADING-NAME.** This keyword controls when the first directory name specified in a file access name is resolved from the environment. The first directory name is defined as a name that is not preceded by a slash character. Under Windows, the slashes that may appear in a volume name are ignored. If the name is not found in the environment, no substitution will occur, and the name will remain as specified (after the possible removal of the leading character). There are several possible values for this keyword, including ALWAYS, NEVER, or one of these seven leading characters: !, @, #, $, %, ^, or &.

    If RESOLVE-LEADING-NAME is set to ALWAYS, and the directory name exists in the environment, the value of the environment variable will replace the name. If RESOLVE-LEADING-NAME is set to one of the seven leading characters, the directory name begins with that character, and the directory name without that character exists in the environment, then the value of that environment variable will replace the name. If the value is set to NEVER, then the leading directory name will never be replaced. The default value for this keyword is NEVER.

    In the special case that the file access name does not contain any directory specifiers, substitution will always be attempted.

    For example, if the environment contains a variable name DIR with the value MYDIR, and does not contain the variable D1, the following substitutions would occur.

Name Specified	**RESOLVE-LEADING-NAME value**		
	ALWAYS	**NEVER**	**@**
DIR/FILE	MYDIR/FILE	DIR/FILE	DIR/FILE
@DIR/FILE	@DIR/FILE	@DIR/FILE	MYDIR/FILE
@D1/FILE	@D1/FILE	@D1/FILE	D1/FILE
DIR	MYDIR	MYDIR	MYDIR
@DIR	@DIR	@DIR	MYDIR

15. **RESOLVE-SUBSEQUENT-NAMES.** This keyword controls when directory names or the filename specified in a file access name are resolved from the environment. It does not apply to the leading name (see RESOLVE-LEADING-NAME keyword, described previously). If the name is not found in the environment, no substitution will occur, and the name will remain as specified (after the possible removal of the leading character). There are several possible values for this keyword, including ALWAYS, NEVER, or one of these seven leading characters: !, @, #, $, %, ^, or &.

    If RESOLVE-SUBSEQUENT-NAMES is set to ALWAYS, and the directory or filename exists in the environment, the value of the environment variable will replace the name. If RESOLVE-SUBSEQUENT-NAMES is set to one of the seven leading characters, the directory or filename begins with that character, and the directory or filename without that character exists in the environment, then the value of that environment variable will replace the name. If the value is set to NEVER, the directory or filename will never be replaced. The default value for this keyword is NEVER.

    For example, if the environment contains a variable name DIR with the value MYDIR, a variable name FILE with the value MYFILE, and does not contain the variable D1, the following substitutions would occur.

Name Specified	**RESOLVE-SUBSEQUENT-NAMES value**		
	ALWAYS	**NEVER**	**@**
DIR/FILE	DIR/MYFILE	DIR/FILE	DIR/FILE
/DIR/@FILE	/MYDIR/@FILE	/DIR/@FILE	/DIR/MYFILE
/@D1/FILE	/@D1/MYFILE	/@D1/FILE	/D1/FILE

16. **USE-PROCEDURE-RECORD-LOCK-TIMEOUT.** This keyword affects record locking. For file descriptors whose file control entry has a FILE STATUS clause and for which a USE declarative procedure is defined, it determines how many seconds to wait when attempting to lock a record that is locked by another run unit before returning an error to the calling program. A value of 0, the default value, indicates that the error should be returned immediately. The minimum value is 0, and the maximum value is 65,535 seconds.

    If the record is locked using a different file descriptor in the same run unit, the error is always returned immediately to prevent a deadlock situation.

RUN-INDEX-FILES Record

The RUN-INDEX-FILES record identifier is followed by one or more keywords. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value. The possible keywords are as follows:

1. **ALLOCATION-INCREMENT.** This keyword determines the allocation increment of indexed files created by the runtime system. The value is the decimal number of blocks to be added to the file. The maximum value is 9999. The minimum value is 1. The default value is 8.

2. **ATOMIC-TRANSFER-SIZE.** This keyword informs the RM/COBOL file management system of the maximum block size that the network software will transmit as a single atomic entity. The maximum value is 65536. The minimum value is 0. The default value is 65536.

   If an indexed file has a block size greater than this value, then the RM/COBOL file management system will not perform certain network optimizations. If this keyword has a value of zero, the optimizations are disabled for all indexed files.

3. **BLOCK-SIZE.** This keyword determines the default sector size, represented as a decimal number. The sector size is used by the runtime system when creating an indexed file to determine the default block size. A program can override this with the BLOCK CONTAINS clause in the file description entry (see the discussion of this clause in Chapter 4, *Data Division*, of the *RM/COBOL Language Reference Manual*). The maximum value is 65489. The minimum value is 256. Under UNIX, the default value is BUFSIZ, taken from the C include file <**stdio.h**>. Under Windows, the default value is the disk sector size.

4. **DATA-COMPRESSION.** This keyword determines whether the indexed files created by the runtime system use data compression. If the value is set to YES, data compression is used. If the value is set to NO, data is stored in uncompressed form. The default value is YES.

5. **DEFAULT-FILE-VERSION-NUMBER.** This keyword determines the default file version number for new files when an OPEN OUTPUT is performed. The version number for existing files or files predefined with the Define Indexed File utility (**rmdefinx**), as described in Appendix G, *Utilities*, will not be changed when an OPEN OUTPUT is performed. Allowable values are 0, 2, and 3. The default value is 2.

6. **FORCE-CLOSED.** This keyword determines whether an indexed file created by the runtime system is marked closed on disk between file modification operations. If the value is set to YES, the file header is marked open at the beginning of a DELETE, REWRITE, or WRITE operation and marked closed at the end of the

operation. This minimizes the risk that a power interruption would necessitate a recovery of the indexed file. If the value is set to NO and the file is opened I-O, OUTPUT, or EXTEND, any power interruption will require a recovery of the indexed file. The default value is NO.

7. **FORCE-DATA.** This keyword determines—for an indexed file created by the runtime system and opened WITH LOCK—whether the runtime system forces data blocks to be given to the operating system when modified. If the value is set to YES, data block write requests are issued to the operating system whenever information is changed. If the value is set to NO, data block write requests are made as dictated by buffer space. The default value is NO.

8. **FORCE-DISK.** This keyword determines—for an indexed file created by the runtime system—whether the runtime system forces disk blocks to be written to disk when modified. If the value is set to YES, blocks written to the operating system are forced to be written to disk as well. If the value is set to NO, blocks written to the operating system remain in the operating system buffer pool. The default value is NO.

9. **FORCE-INDEX.** This keyword determines—for an indexed file created by the runtime system and opened WITH LOCK—whether the runtime system forces index blocks to be given to the operating system when modified. If the value is set to YES, index block write requests are issued to the operating system whenever the index block is changed. If the value is set to NO, index block write requests are made as buffer space dictates. The default value is NO.

10. **KEY-COMPRESSION.** This keyword determines whether the indexed files created by the runtime system use key compression. If the value is set to YES, key compression is used. If the value is set to NO, keys are stored in uncompressed form. The default value is YES.

RUN-OPTION Record

The RUN-OPTION record identifier is followed by one or more keywords. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value. The possible keywords are as follows:

1. **B.** This keyword controls the default ACCEPT and DISPLAY buffer size and is represented as a decimal number. The maximum value is 65280. The minimum value is 1. A default value specified with this keyword may be overridden by the runtime B Option (see page 7-4).

2. **ENABLE-LOGGING.** This keyword controls the generation of various error and information log files. The LOG-PATH keyword (described below) must be included to specify the location of the directory for the log file. By default, no logging is performed. Multiple keyword values are separated by commas. One or more of the following values may be included:

   ALL
   TERMINATION
   PERM-OS-ERRORS

   ENABLE-LOGGING=ALL turns on all logging.

   ENABLE-LOGGING=TERMINATION turns on logging of termination errors, including all traceback information. The log file generated is named RMTERM.LOG. Note that termination logging is available only for Windows. UNIX users should continue to redirect standard error (STDERR).

   ENABLE-LOGGING=PERM-OS-ERROR turns on logging of detailed information about errors encountered by the runtime when making operating system (OS) calls. This is normally turned on only at the request of a Liant support representative. The log file generated is named RMOSERR.LOG.

3. **K.** This keyword controls the suppression of the banner notice and the STOP RUN message. If the value is set to SUPPRESS, the banner notice and STOP RUN message are suppressed. If the value is set to DISPLAY, the suppression of the banner notice and the STOP RUN message is controlled by the runtime K Option (see page 7-3). The default value is DISPLAY.

4. **LOG-PATH.** This keyword specifies the location (directory) where the log file (as specified in the ENABLE-LOGGING keyword above) will be written. The directory must already exist before the runtime is started, and the user must have create and write permission for the directory. The runtime will create the log file, if necessary, and the file will be opened in append mode.

5. **M.** This keyword controls which level of ANSI semantics is used with ACCEPT and DISPLAY statements. If the value is set to 2, ANSI level 2 semantics are used. If the value is set to 1, the level of ANSI semantics is controlled by the runtime M Option (see page 7-4). The default value is 1.

RUN-REL-FILES Record

The RUN-REL-FILES record identifier is followed by one keyword. The keyword is followed by an equal sign (=) and a value. The possible keyword is as follows:

1. **BLOCK-SIZE.** This keyword determines the default block size, represented as a decimal number, for relative files opened WITH LOCK. The maximum value is 65489. The minimum value is 0, which specifies that the default value is no blocking. The presence of a BLOCK CONTAINS phrase in the file description entry of an unshared relative file forces that file to be blocked, even if no blocking is specified by this keyword. The default value is BUFSIZ, taken from the C include file <**stdio.h**>, if the file is opened for RANDOM access. Under UNIX, if the file is opened for DYNAMIC or SEQUENTIAL access, the default value is BUFSIZ, taken from the C include file <**stdio.h**>, or 4096, whichever is larger. Under Windows, the default value is the disk sector size or 4096, whichever is larger.

2. **USE-LARGE-FILE-LOCK-LIMIT.** This keyword determines which value to use for the limit when applying locks to a relative file. If the value of this keyword is set to NO, the value of the FILE-LOCK-LIMIT configuration keyword of the RUN-FILES-ATTR record is used. If the value is set to YES, the value of the LARGE-FILE-LOCK-LIMIT configuration keyword is used. (For a description of these keywords in the RUN-FILES-ATTR record, see page 10-26.) For record and file locks to perform correctly, all run units opening a file must use the same file lock limit. The default value is NO.

RUN-SEQ-FILES Record

The RUN-SEQ-FILES record identifier is followed by one or more keywords. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value. The possible keywords are as follows:

1. **BLOCK-SIZE.** This keyword determines the default block size represented as a decimal number, for sequential disk files opened WITH LOCK. The maximum value is 65489. The minimum value is 0, which specifies that the default value is no blocking. The presence of a BLOCK CONTAINS phrase in the file description entry of an unshared sequential file forces that file to be blocked, even if no blocking is specified by this keyword. Under UNIX, the default value is BUFSIZ, taken from

the C include file <**stdio.h**>, or 4096, whichever is larger. Under Windows, the default value is the disk sector size or 4096, whichever is larger.

2. **DEFAULT-TYPE.** This keyword determines whether unspecified sequential files are line sequential or binary sequential. If the value is set to BINARY, unspecified sequential files are binary sequential. If the value is set to LINE, unspecified sequential files are line sequential. The default value is BINARY.

3. **DEVICE-SLEWING-RESERVE.** This keyword determines the number of character positions to be reserved for form feed and line feed characters. The value for this keyword is a decimal number. The maximum value is 999. The minimum value is 10. The default value is 255.

   This keyword applies to line sequential files written directly to a nontape device. It also applies to line sequential files on disk that are not opened WITH LOCK or are not blocked. The value required for this keyword is generally the maximum value specified by any BEFORE/AFTER ADVANCING phrase in a WRITE statement in the program, plus 2. This value is configurable for performance considerations only, since it enables the record—along with the appropriate number of control characters—to be written in one write request. If the value specified for this keyword is less than the maximum specified by the BEFORE/AFTER ADVANCING phrase, the operation will be performed correctly, but will require more than one write request to complete the operation.

4. **TAB-STOPS.** This keyword determines an ascending sequence of tab stop columns represented as decimal numbers separated by commas. Up to 18 tab stop columns are allowed. TAB-STOPS=0 specifies that no tab stop columns exist. The default TAB-STOPS sequence is 8, 12, 16, 20, 24, 28, 32, 36, 40, 44, 48, 52, 56, 60, 64, 68, 72.

5. **USE-LARGE-FILE-LOCK-LIMIT.** This keyword determines which value to use for the limit when applying locks to a sequential file. If the value of this keyword is set to NO, the value of the FILE-LOCK-LIMIT keyword of the RUN-FILES-ATTR record is used. If the value is set to YES, the value of the LARGE-FILE-LOCK-LIMIT configuration keyword is used. (For a description of these keywords in the RUN-FILES-ATTR record, see page 10-26.) For record and file locks to perform correctly, all run units opening a file must use the same file lock limit. The default value is NO.

RUN-SORT Record

The RUN-SORT record identifier is followed by one or more keywords. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value. The possible keywords are as follows:

1. **INTERMEDIATE-FILES.** This keyword determines the number of intermediate sort files represented as a decimal number. The maximum value is 9. The minimum value is 3. The default value is 5.

2. **MEMORY-SIZE.** This keyword determines the default sort memory size represented as a decimal number. The maximum value is available memory. The minimum value is 0. If unspecified, the default sort memory size is 256000 bytes. The maximum allowed value is 2147483647 bytes. If the MERGE or SORT statements are used in the run unit, sort memory size must be non-zero.

TERM-ATTR Record

The TERM-ATTR record provides information about terminal attributes. The TERM-ATTR record identifier is followed by one or more keywords. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value. The possible keywords are as follows:

1. **BCOLOR.** This keyword indicates the initial background color value to use for ACCEPT and DISPLAY statements. The terminal will be restored to this color when the run unit ends. The default color value is BLACK.

   Note Under Windows, the default background color is determined by the system settings. In particular, the default background color is the default “window background” color.

2. **CHARACTER-TIMEOUT.** This keyword sets the time-out period related to the inter-character timer used by the RM/COBOL runtime system when processing input sequences. The timer is used to determine whether a character is a final character in a sequence. The default wait time before deciding that no more characters are pending is .5 seconds. The inter-character timer may need to be increased on certain systems or in some cases when the user is logged in from a network (rlogin). The value for the CHARACTER-TIMEOUT keyword is specified in tenths of seconds.

   Note 1 This keyword is supported only under UNIX.

   Note 2 The value of the inter-character timer also affects the BEFORE TIME phrase of the ACCEPT statement (see page 8-21).

3. **COLUMNS.** This keyword determines the number of columns the runtime system will display on the terminal screen, represented as a decimal number between 1 and 255. The default value is 80.

   Note This keyword is supported only under Windows.

4. **DATA-CHARACTERS.** This keyword has as its value a comma-separated pair of decimal integers. The first number is the lower bound of characters to be interpreted as text characters. The second number is the upper bound of characters to be interpreted as text characters. On input, characters not in this range and not part of a TERM-INPUT sequence (see page 10-41) are illegal. The default range is 20h to 7Eh.

5. **DBCS-CHARACTERS.** This keyword enables support for double-byte character set (DBCS) characters and specifies the lead-byte character ranges.

   In DBCS, a character is represented by either one or two bytes. Double-byte character set characters have the following components:

   - **Lead byte.** If the value of this byte falls into the lead-byte range, a DBCS character is indicated.
   - **Trail byte.** This byte further refines the selected character. The trail byte can have any value except zero (0), but is typically restricted to a subset of all possible characters.

   Double-byte character set characters occupy two, physically adjacent positions on the screen and are usually displayed as a double-width character.

   Double-byte character set characters, however, are not the same as "wide" characters. In a wide-character set, such as Unicode, all characters are represented by two bytes, which provides up to 65,536 characters. In DBCS, the value of the first byte determines whether the second byte is considered part of the current character.

   Values for this keyword are specified as a pair of numbers separated by a comma. The syntax of this keyword is as follows:

   ```
   TERM-ATTR DBCS-CHARACTERS=n1,n2
   ```

   These numbers specify a range of characters to be considered lead-byte characters. Multiple ranges of characters can be specified by repeating the DBCS-CHARACTERS keyword, but ranges must not overlap. These numbers must also be wholly contained within the DATA-CHARACTERS range which, by default, is 32 through 254.

DBCS-CHARACTERS must be specified after DATA-CHARACTERS if both keywords are specified. Specifying DATA-CHARACTERS causes preceding DBCS-CHARACTERS and TERM-INPUT values to be discarded.

Note This keyword is only supported under UNIX.

Restrictions

The following restrictions apply to double-byte character set characters in RM/COBOL:

- Because a DBCS character cannot be entered in a field where there is only one remaining character position, DBCS characters cannot be any of the following:
  - Entered into one-character ACCEPT fields.
  - Typed into the last position of a field.
  - Inserted into a field where only one position remains available.
  - Typed over single-byte characters in a field where no positions remain available.
- A DBCS character cannot be displayed on a position that would physically or logically separate the trail byte from the lead byte. DBCS characters, therefore, cannot be displayed in the last column of a screen or window. In addition, when a new window is opened, any lead bytes or trail bytes that would be orphaned by the window are blanked and restored when the window is removed.
- If an ACCEPT field spans a window or screen row, RM/COBOL will permit the entry of a DBCS character when the cursor is in the last column of the window or screen. The cursor advances two character positions and the DBCS character is saved but not displayed (two spaces are displayed instead). If characters are inserted or deleted from the field such that the character no longer wraps across rows, it becomes visible. If another DBCS character wraps as a result, it becomes invisible. All entered characters will be returned to the RM/COBOL program when the ACCEPT is terminated.
- Such an invisible character cannot be retrieved with the ACCEPT-FIELD-FROM-SCREEN keyword in the RUN-ATTR record or the C$SCRD subprogram. Instead, spaces are returned.
- DBCS characters must not be used as a character specified either in the PROMPT phrase of an ACCEPT statement or in the GRAPHICS keyword of the CONTROL phrase of an ACCEPT or DISPLAY statement.
- DBCS characters must not be used in filenames or pathnames.

6. **FCOLOR.** This keyword indicates the initial foreground color value to use for ACCEPT and DISPLAY statements. The terminal will be restored to this color when the run unit ends. The default color value is WHITE.

   Note Under Windows, the default foreground color is determined by the system settings. In particular, the default foreground color will be the default "window text" color. The default high-intensity foreground color is determined by the default "selected text" color.

7. **PASS-THRU-ESCAPE.** This keyword allows certain DISPLAY statements to write sequences directly to standard output, bypassing screen optimization and buffering. If used, any DISPLAY statement that begins with one of the specified characters will exhibit the PASS-THRU behavior. No cursor positioning is performed. All attributes specified in the DISPLAY statement are ignored. The characters are represented in ordinal form (for example, the ASCII ESC character is 27) within a comma separated list as both individual values and ranges (for example, 0-31,255). The default is to have no PASS-THRU-ESCAPE characters.

   Note This keyword is supported only under UNIX.

8. **REDRAW-ON-CALL-SYSTEM.** This keyword sets a variable that is checked by the C language subprogram, SYSTEM, before restoring the screen. The values for this keyword are YES and NO. The default value is YES. A value of YES causes the runtime system to redraw the screen in order to maintain screen integrity. An additional argument, (PIC X) to CALL "SYSTEM", gives control of this feature on an individual call basis. See "Restrictions to C (or Assembly) Language Subprograms" and "Debugging C (or Assembly) Language Subprograms" on page D-19, for more information.

   Note This keyword is supported only under UNIX.

9. **ROWS.** This keyword determines the number of rows the runtime system will display on the terminal screen, represented as a decimal number between 1 and 255. The default value is 25.

   Note This keyword is supported only under Windows.

10. **SCREEN-CONTENT-OPTIMIZE.** This keyword determines whether the runtime system optimizes DISPLAY output based on current screen contents. If the value is set to YES, the runtime system avoids displaying an unnecessary character if the screen image already contains that character in the desired location, thereby increasing terminal I/O efficiency. If the value is set to NO, the runtime system forces every character to be written to the screen even if this results in duplicating the existing screen contents. Because turning off screen content optimization clears the

screen image, repainting the screen will result in a blank display. The default value is YES.

Note This keyword is supported only under UNIX.

11. **SUPPRESS-NULLS.** This keyword controls whether the RM/COBOL runtime system sends NULL or LOW-VALUE characters to the screen. Setting the value of this keyword to YES causes NULL characters to be stripped from all displayed fields. The NULL characters will, however, remain in the internal data storage. The default value is NO.

    Note This keyword is supported only under UNIX.

12. **USE-COLOR.** Setting the value of this keyword to YES forces a COBOL program to perform all DISPLAY and ACCEPT statements using either the default color values or the color values specified in a CONTROL phrase. If the termcap or terminfo database contains color support and the set_foreground and set_background strings are present, these strings are used to process the request. Otherwise, the RM/COBOL runtime system will generate the seven-bit SGR (Set Graphics Rendition) sequences assigned by the International Standards Organization for color. These sequences are defined as follows:

	Control Sequence Introducer	Parameter Selection	Terminator
Foreground	ESC [	3 [0-7]	m
Background	ESC [	4 [0-7]	m

The color values associated with the parameter values zero through seven are as follows:

Color	Parameter Second Digit
BLACK	0
RED	1
GREEN	2
YELLOW	3
BLUE	4
MAGENTA	5
CYAN	6
WHITE	7

If the value of the USE-COLOR keyword is set to NO, color sequences will not be used until the first ACCEPT or DISPLAY that requests to use color and only if there is support for color in the termcap or terminfo database. NO is the default value.

If none of the color keywords is specified, color processing will be disabled until a CONTROL phrase is encountered that specifies the use of a valid color. When a CONTROL phrase is encountered, it is honored provided there is color support in the termcap or terminfo database. When the run unit ends, the terminal will be restored to the values specified in the FCOLOR and BCOLOR keywords in the TERM-ATTR configuration record.

Note This keyword is supported only under UNIX.

TERM-INPUT Record

The TERM-INPUT record associates field editing semantics, exception codes, or a single data character with incoming character sequences. See page 8-2 for more information on defining keys under your operating system.

The TERM-INPUT record identifier is followed by one or more optional keywords and finally, by the character sequence specification. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value. The keywords may appear in any order, but must precede the character sequence specification (see pages 10-42 through 10-44). The possible keywords are as follows:

1. **ACTION.** This keyword specifies the field editing action or screen action to be performed. The allowed values (described in detail under "Field Editing Actions" beginning on page 10-45) are as follows:

BACKSPACE	REPAINT-SCREEN
CONTROL-BREAK	RESET-ANSI-INSERTION
DELETE-CHARACTER	RIGHT-ARROW
ERASE-ENTIRE	SCREEN-ESCAPE
ERASE-REMAINDER	SCREEN-HOME
ESCAPE-TO-COMMAND	SCREEN-PREVIOUS-FIELD
ESCAPE-TO-OS	SCREEN-TERMINATE
FIELD-HOME	SET-ANSI-INSERTION
INSERT-CHARACTER	SET-RM-INSERTION
LEFT-ARROW	TOGGLE-ANSI-INSERTION

2. **CODE.** This keyword specifies the numeric exception code value to be returned to the program. The definition of an exception code identifies a key sequence that terminates input. Key sequences without exception codes do not terminate field input unless one of the screen actions is defined for that key sequence (as described in the ACTION keyword).

3. **DATA.** This keyword specifies the data character or character equivalent to be returned to the program when the incoming character sequence is received (see “Character Sequence Specification” on page 10-42). If a DATA keyword is provided, neither the ACTION nor CODE keywords may be specified.

4. **EXCEPTION.** This keyword specifies whether the ON EXCEPTION clause of the ACCEPT statement should be executed (see “Input Sequence Specification” on page 10-44). The EXCEPTION keyword is legal only if the CODE keyword, described above, is also provided. If a value of YES is specified, the ON EXCEPTION clause is executed; if a value of NO is specified, the ON EXCEPTION clause is not executed. The default value is YES. The EXCEPTION keyword is ignored during an ACCEPT *screen-name* statement.

5. **PRECEDENCE.** This keyword assigns a precedence to the TERM-INPUT record. The value specified is a decimal number from 0 to 14, with 0 considered to have the highest precedence. The PRECEDENCE keyword is used only when a terminal generates the same input character sequence for two different keys. The Left Arrow and Backspace keys form a typical example. The PRECEDENCE keyword can specify which interpretation of the input sequence is to be used. The TERM-INPUT record with the highest precedence replaces that with a lower one. If two TERM-INPUT records have the same precedence, a procedure error occurs when the unit is first accessed. The default value is 0.

   Note This keyword is supported only under UNIX.

Character Sequence Specification

Terminal configuration allows the specification of incoming character sequences. The syntax of the sequences is one or more characters or character equivalents, separated by spaces. Any single character delimited by spaces is interpreted as the represented ASCII character. More than one character delimited by spaces is interpreted as a character equivalent. If the characters are digits, they are interpreted as the decimal value of the ASCII code. The recognized character equivalents may be one of those listed in the following tables.

Table 10-3 lists the ASCII equivalents.

Table 10-3 ASCII Equivalents

ASCII Code	Character Equivalent	ASCII Code	Character Equivalent
000	NUL	017	DC1
001	SOH	018	DC2
002	STX	019	DC3
003	ETX	020	DC4
004	EOT	021	NAK
005	ENQ	022	SYN
006	ACK	023	ETB
007	BEL	024	CAN
008	BS	025	EM
009	HT	026	SUB
010	LF	027	ESC
011	VT	028	FS
012	FF	029	GS
013	CR	030	RS
014	SO	031	US
015	SI	032	SP
016	DLE	127	DEL

Additional character equivalents, listed in Table 10-4, have been defined for the character sequence specifications in Windows. If one of these character equivalents, other than WSFT or WCNT, is used to specify an incoming character sequence, the specification should begin with NUL. This is necessary to distinguish between the special Windows character equivalents and normal ASCII characters.

Note Alt-key sequences are not available under RM/COBOL for Windows because the underlying Windows-based environment traps the Alt-key sequences. Alt-key sequences are entered as Ctrl-Shift-key combination sequences. For example, use Ctrl-Shift-I instead of Alt-I.

Table 10-4 Additional Character Equivalents Under RM/COBOL for Windows

Code Name	Description
WSFT	Shift key
WCNT	Control key
WPGU	PgUp key
WPGD	PgDn key
WEND	End key
WHOM	Home key
WLFT	Left Arrow key
WUP	Up Arrow key
WRGT	Right Arrow key
WDWN	Down Arrow key
WPRT	Print key
WINS	Insert key
WDEL	Delete key
WF1 . . . WF16	Function 1 … Function 16

Input Sequence Specification

Incoming character sequences are specified by the corresponding attribute name. For example, assume you have a keyboard with a Next page key (**knp** in the terminfo database, and **kN** in the termcap database) and you want that to cause the ON EXCEPTION branch of your ACCEPT statement to be taken with the decimal value 80 stored in the EXCEPTION variable. This could be described in the following ways:

For terminfo:

```
TERM-INPUT      CODE=80      EXCEPTION=YES knp
```

For termcap:

```
TERM-INPUT      CODE=80      EXCEPTION=YES       kN
```

For Windows:

```
TERM-INPUT      CODE=80      EXCEPTION=YES NUL WPGU
```

Field Editing Actions

RM/COBOL ACCEPT statements define fields on the terminal in which the operator may enter data. Depending on the phrases specified in the ACCEPT statement and the setting of the ACCEPT-FIELD-FROM-SCREEN keyword of the RUN-ATTR configuration record (see page 10-23), the initial contents of the screen field may be empty (all spaces), filled with characters from the screen, filled with prompt characters or filled with the current value of the associated ACCEPT operand. The operator may then modify the displayed contents of the screen field; all positions of that screen field may continue to be modified until a field termination key is entered. This modification of the displayed data is called field editing.

Data entry is processed in either insertion mode or replacement mode. In insertion mode, incoming text characters are inserted at the current cursor position, and following characters are moved to the right in the field. In replacement mode, incoming text characters replace the characters at the current cursor position. The RM/COBOL terminal model defines three types of insertion mode:

1. Single-character insertion mode reverts to replacement mode after one text character is inserted.

2. RM insertion mode reverts to replacement mode when data entry in the field is terminated or when a field editing key is entered.

3. ANSI insertion mode remains active across ACCEPT operations until reset by the operator to RM insertion mode or replacement mode.

The RM/COBOL terminal interface provides the following field editing facilities that may be made available to the operator. These facilities can be specified with the ACTION keyword of the TERM-INPUT configuration record (see page 10-41).

1. **BACKSPACE.** The BACKSPACE value accomplishes a destructive backspace by moving the cursor left one position in the field, deleting the character at that position, moving all following characters left one position, and inserting a prompt character at the right end of the screen field. If entered in the leftmost position of the screen field, the key sequence is treated as a field termination key or as an illegal keystroke depending on whether an exception code has been assigned to the key sequence.

2. **CONTROL-BREAK.** The CONTROL-BREAK value causes the run unit to be terminated immediately, as if a STOP RUN statement were executed.

3. **DELETE-CHARACTER.** The DELETE-CHARACTER value deletes the character at the current cursor position, moves all following characters left one position, and inserts a prompt character at the right end of the screen field.

4. **ERASE-ENTIRE.** The ERASE-ENTIRE value replaces all character positions in the screen field with prompt characters, and moves the cursor to the leftmost position of the field.

5. **ERASE-REMAINDER.** The ERASE-REMAINDER value replaces characters from the current position to the rightmost position of the screen field with prompt characters.

6. **ESCAPE-TO-COMMAND.** The ESCAPE-TO-COMMAND value causes the runtime system to run a user-specified command whenever the configured key is pressed. The screen is cleared and the terminal is returned to a shell state before the shell command is run. After the shell or command terminates, the COBOL screen is restored. The SHELL environment variable determines the shell that is used. If none is set, /bin/sh is used. The RM_ESCAPE_TO_COMMAND environment variable determines the command that is used. If none is set, /bin/sh is used.

   Note This value is supported only under UNIX.

7. **ESCAPE-TO-OS.** The ESCAPE-TO-OS value causes the runtime system to bring up a command shell whenever the configured key is pressed. This allows the user to press a configured key to bring up a shell, execute OS commands, and then return to the COBOL program without having to change the COBOL source code.

   Note This value is supported only under UNIX.

8. **FIELD-HOME.** The FIELD-HOME value moves the cursor to the leftmost position of the screen field.

9. **INSERT-CHARACTER.** The INSERT-CHARACTER value inserts a single space character at the current character position. When entered in replacement mode, this causes the subsequent text character to appear to be inserted.

10. **LEFT-ARROW.** The LEFT-ARROW value moves the cursor left one position in the screen field. If entered in the leftmost position of the screen field, this value is treated as a field termination key or as an illegal keystroke, depending on whether an exception code has been assigned to the key sequence.

11. **REPAINT-SCREEN.** The REPAINT-SCREEN value causes the runtime system to reinitialize the terminal and redraw the screen from an in-memory image. This allows the user to restore a terminal's display after events such as a loss of power to the terminal.

    Note This value is supported only under UNIX.

12. **RESET-ANSI-INSERTION.** The RESET-ANSI-INSERTION value changes the handling of subsequent text characters to replacement mode.

13. **RIGHT-ARROW.** The RIGHT-ARROW value moves the cursor right one position in the screen field. The key sequence is illegal if the character at the current character position is a prompt character. If entered in the rightmost screen field position, the key sequence is treated as a field termination key or as an illegal keystroke, depending on whether an exception code has been assigned to the key sequence.

14. **SCREEN-ESCAPE.** The SCREEN-ESCAPE value terminates an ACCEPT *screen-name* statement. The current field is neither checked for errors nor moved to the intermediate area for screen data items. If the current ACCEPT is not an ACCEPT *screen-name* statement, no action is taken (unless the keyword CODE is defined for the same key sequence).

15. **SCREEN-HOME.** The SCREEN-HOME value moves the cursor to the first input field defined in the Screen Section for the current screen. The current field is checked for errors. No semantic action is taken for ACCEPT *identifier* statements.

16. **SCREEN-PREVIOUS-FIELD.** The SCREEN-PREVIOUS-FIELD value moves the cursor to the beginning of the previous field (as defined in the Screen Section) after the current field is validated. No semantic action is taken for ACCEPT *identifier* statements.

17. **SCREEN-TERMINATE.** The SCREEN-TERMINATE value terminates an ACCEPT *screen-name* statement, but, unlike the SCREEN-ESCAPE value, the current field is validated and moved to the intermediate area. No semantic action is taken for ACCEPT *identifier* statements.

18. **SET-ANSI-INSERTION.** The SET-ANSI-INSERTION value changes the handling of following text characters. Upon entry to the run unit, terminal handling is in replacement mode. The SET-ANSI-INSERTION value causes later incoming text characters to be handled in insertion mode. Insertion mode continues until a TOGGLE-ANSI-INSERTION, RESET-ANSI-INSERTION or SET-RM-INSERTION value is entered.

19. **SET-RM-INSERTION.** The SET-RM-INSERTION value changes the handling of following text characters. Upon entry to the run unit, terminal handling is in replacement mode. The SET-RM-INSERTION value causes later incoming text characters to be handled in insertion mode.

    RM insertion mode is reset when any field editing key sequence is entered or when the field input is terminated.

20. **TOGGLE-ANSI-INSERTION.** The TOGGLE-ANSI-INSERTION value changes the handling of following text characters. If terminal handling is currently in replacement mode, it is changed to ANSI insertion mode. If terminal handling is currently in RM or ANSI insertion mode, it is changed to replacement mode.

If a key sequence assigned to an exception code has also been assigned to any of the field editing facilities (excluding BACKSPACE, LEFT-ARROW, and RIGHT-ARROW), the editing action is performed and field editing will terminate.

We recommend that all terminal configurations include values to generate the RM/COBOL generic exception keys, which are shown in Table 10-5.

Table 10-5 RM/COBOL Generic Exception Keys

Code	Generic Name	Code	Generic Name
13	Enter	18	Function 18
01	Function 1	19	Function 19
02	Function 2	20	Function 20
03	Function 3	40	Command
04	Function 4	41	Attention
05	Function 5	52	Up Arrow
06	Function 6	53	Down Arrow
07	Function 7	54	Home
08	Function 8	55	New Line
09	Function 9	56	Tab Left
10	Function 10	57	Erase Right
11	Function 11	58	Tab Right
12	Function 12	59	Insert Line
13	Function 13	61	Delete Line
14	Function 14	64	Send
15	Function 15	83	Help
16	Function 16	84	Redo
17	Function 17		

TERM-INTERFACE Record

The terminal configuration records have different formats, depending on the type of terminal interface the runtime system uses: termcap, terminfo, or graphical user interface (GUI). The TERM-INTERFACE record describes the format of records in this configuration file. The runtime system will use this information to correctly process the records and to ensure that it is the correct version of the runtime system (termcap, terminfo, or GUI) to be using the information.

The TERM-INTERFACE record must precede all other terminal interface configuration records except TERM-UNIT.

The TERM-INTERFACE record identifier is followed by one keyword that describes the format. The possible keywords are as follows:

1. **GUI.** This value must be specified for use with RM/COBOL for Windows. It indicates that the terminal interface is a graphical user interface (GUI).

2. **TERMCAP.** This keyword specifies that the runtime system is expected to process the termcap database and handle all input and output to the terminal directly. TERM-INPUT configuration records use termcap input sequence.

3. **TERMINFO.** This keyword specifies that the runtime system is expected to use the terminfo database and handle all input and output to the terminal directly. TERM-INPUT configuration records use terminfo input sequence.

4. **WINDOWS.** This value is identical to the value of GUI.

TERM-UNIT Record

The TERM-UNIT record is used to associate RM/COBOL units to stations (devices). The TERM-UNIT record identifier is followed by one or more keywords. If the keyword is allowed to have a value, it is followed by an equal sign (=) and the value.

Note The TERM-UNIT configuration record is supported only under UNIX.

The TERM-UNIT record must contain the PATH keyword if the UNIT keyword does not specify the default unit. The possible keywords are as follows:

1. **BPS.** This keyword specifies the Bits Per Second to which the communication port should be initialized when the unit is first accessed by the RM/COBOL program. The default for this keyword is the value to which the operating system has set the port. The valid values for this keyword are 50, 75, 110, 134.5, 150, 200, 300, 600, 1200, 1800, 2400, 4800, 9600, EXT-A and EXT-B (for external A and external B).

2. **CHARACTER-WIDTH.** This keyword specifies the character size, in bits, to which the communication port should be initialized when the unit is first accessed by the RM/COBOL program. The default for this keyword is the value to which the operating system has set the port. The valid values for this keyword are 5, 6, 7 and 8.

3. **DEFINE-CONTROL-CHARACTERS.** This keyword specifies whether the terminal control characters, Ctrl+A through Ctrl+Z, are to be predefined in the unit's input sequences to terminate input and generate exception codes of 1 through 26. On the termcap and terminfo runtime systems, Ctrl+H, Ctrl+I, Ctrl+J, and Ctrl+M are always predefined to be Backspace, Tab, New Line, and Carriage Return, respectively.

   If the DEFINE-CONTROL-CHARACTERS keyword has the value YES, the characters are defined. If the DEFINE-CONTROL-CHARACTERS keyword has the value NO, they are not defined. The default value for this keyword is YES.

4. **MOVE-ATTR.** This keyword specifies the handling of terminals with positional attributes. On such terminals, attributes are implemented by placing special characters on the terminal screen. These attribute characters take up screen positions and overwrite any data there.

   If the MOVE-ATTR keyword has the value NO, it specifies that the attribute characters are placed at the line and position requested by the RM/COBOL program and the actual start of the field is moved to the right, accordingly.

   If the MOVE-ATTR keyword has the value YES, it specifies that the field should be placed in the line and position requested and the attributes moved to the left. The only time this will not be done is when the termcap capability database indicates that the attributes set by the attribute characters will not cross a line boundary or if the field starts in line 1, position 1 and the database does not indicate that the attribute will wrap from the bottom to the top of the screen.

   The default value for this keyword is NO.

5. **PARITY.** This keyword specifies the parity to which the communication port should be initialized when the unit is first accessed by the RM/COBOL program. The default for this keyword is the value to which the operating system has set the port. The valid values of this keyword are: EVEN, ODD and NONE.

6. **PATH.** This keyword specifies the device pathname that will be used for this unit. This must be a tty port that currently has no other processes attached to it and has read and write privileges for the user who starts the run unit. This is a required field if the unit being described is not the default unit. If the unit being described is the default unit, this keyword must not be present.

7. **STOP-BITS.** This keyword specifies the number of stop bits that the communication port should send following transmitted characters. The default for this keyword is the value to which the operating system has set the port. The valid values of this keyword are 1 and 2.

8. **TYPE.** This keyword specifies the terminal type connected to the port. This is the name that is used when searching the termcap or terminfo database. The default value for this keyword is the value of the TERM environment variable.

9. **UNIT.** This keyword specifies the RM/COBOL unit number being described and is either a decimal number between 0 and 255 or the value DEFAULT-UNIT. If the value is DEFAULT-UNIT, this TERM-UNIT record describes the unit that is used when no UNIT clause appears on the ACCEPT or DISPLAY statement. If it is a number, this TERM-UNIT record describes a particular UNIT number that will be used in an RM/COBOL ACCEPT or DISPLAY statement. The default for this keyword is DEFAULT-UNIT.

Default Configuration Files

The following examples illustrate the default configuration files for terminfo, termcap, and Windows systems.

Termcap Example

The following records define the default configuration as provided by Liant on systems that use termcap.

```
RUN-ATTR accept-intensity=high beep=yes blink=yes
&display-intensity=high reverse=yes
RUN-ATTR error-message-destination=standard-error
RUN-OPTION b=264 k=display m=1
RUN-INDEX-FILES allocation-increment=8
RUN-INDEX-FILES data-compression=yes force-closed=no force-data=no
&force-disk=no
RUN-INDEX-FILES force-index=no key-compression=yes
RUN-SEQ-FILES default-type=binary
RUN-SEQ-FILES device-slewing-reserve=255
RUN-SEQ-FILES tab-stops=8,12,16,20,24,28,32,36,40,44,48,52,
&56,60,64,68,72
RUN-SORT intermediate-files=5 memory-size=16000
TERM-UNIT move-attr=no define-control-characters=yes
TERM-INTERFACE TERMCAP
TERM-INPUT action=left-arrow                    kl
```

```
TERM-INPUT action=right-arrow                    kr
TERM-INPUT action=backspace precedence=1         kb
TERM-INPUT action=set-rm-insertion               kI
TERM-INPUT action=delete-character               kD
TERM-INPUT action=erase-entire                   kC
TERM-INPUT action=screen-terminate code=01       k1
TERM-INPUT action=screen-terminate code=02       k2
TERM-INPUT action=screen-terminate code=03       k3
TERM-INPUT action=screen-terminate code=04       k4
TERM-INPUT action=screen-terminate code=05       k5
TERM-INPUT action=screen-terminate code=06       k6
TERM-INPUT action=screen-terminate code=07       k7
TERM-INPUT action=screen-terminate code=08       k8
TERM-INPUT action=screen-terminate code=09       k9
TERM-INPUT action=screen-terminate code=10       k;
TERM-INPUT code=11                               F1
TERM-INPUT code=12                               F2
TERM-INPUT code=13                               F3
TERM-INPUT code=14                               F4
TERM-INPUT code=15                               F5
TERM-INPUT code=16                               F6
TERM-INPUT code=17                               F7
TERM-INPUT code=18                               F8
TERM-INPUT code=19                               F9
TERM-INPUT code=20                               FA
TERM-INPUT code=21                               FB
TERM-INPUT code=22                               FC
TERM-INPUT code=23                               FD
TERM-INPUT code=24                               FE
TERM-INPUT code=25                               FF
TERM-INPUT code=26                               FG
TERM-INPUT code=27                               FH
TERM-INPUT code=28                               FI
TERM-INPUT code=29                               FJ
TERM-INPUT code=30                               FK
TERM-INPUT code=31                               FL
TERM-INPUT code=32                               FM
TERM-INPUT code=33                               FN
TERM-INPUT code=34                               FO
TERM-INPUT code=35                               FP
TERM-INPUT code=36                               FQ
TERM-INPUT code=37                               FR
TERM-INPUT code=38                               FS
TERM-INPUT code=39                               FT
TERM-INPUT code=40                               FU
TERM-INPUT code=41                               FV
TERM-INPUT code=42                               FW
```

```
TERM-INPUT code=43                                FX
TERM-INPUT code=44                                FY
TERM-INPUT code=45                                FZ
TERM-INPUT code=46                                Fa
TERM-INPUT code=47                                Fb
TERM-INPUT code=48                                Fc
TERM-INPUT code=49                                Fd
TERM-INPUT code=50                                Fe
TERM-INPUT code=51                                Ff
TERM-INPUT code=52                                Fg
TERM-INPUT code=53                                Fh
TERM-INPUT code=54                                Fi
TERM-INPUT code=55                                Fj
TERM-INPUT code=56                                Fk
TERM-INPUT code=57                                Fl
TERM-INPUT code=58                                Fm
TERM-INPUT code=59                                Fn
TERM-INPUT code=60                                Fo
TERM-INPUT code=61                                Fp
TERM-INPUT code=62                                Fq
TERM-INPUT code=63                                Fr
TERM-INPUT code=13 exception=no                   cr
TERM-INPUT code=40                                k0
TERM-INPUT code=41                                K3
TERM-INPUT code=49                                l0
TERM-INPUT action=screen-previous-field code=52 ku
TERM-INPUT code=53                                kd
TERM-INPUT action=screen-home code=54             kh
TERM-INPUT code=55                                nw
TERM-INPUT code=56                                K4
TERM-INPUT action=erase-remainder code=57         kE
TERM-INPUT code=58                                K5
TERM-INPUT code=59                                kA
TERM-INPUT code=61                                kL
TERM-INPUT code=64                                K2
TERM-INPUT code=67                                kP
TERM-INPUT code=68                                kN
TERM-INPUT code=82                                K1
TERM-INPUT code=83 precedence=1                   %1
TERM-INPUT code=84                                %0
PRINT-ATTR auto-line-feed=no
PRINT-ATTR form-feed-available=yes top-of-form-at-close=no
DEFINE-DEVICE device=PRINTER path="lp -s" pipe=yes
DEFINE-DEVICE device=TAPE path=/dev/rtp pipe=no
```

Terminfo Example

The following records define the default configuration as provided by Liant on systems that use terminfo.

```
RUN-ATTR accept-intensity=high beep=yes blink=yes
&display-intensity=high reverse=yes
RUN-ATTR error-message-destination=standard-error
RUN-OPTION b=264 k=display m=1
RUN-INDEX-FILES allocation-increment=8
RUN-INDEX-FILES data-compression=yes force-closed=no force-data=no
&force-disk=no
RUN-INDEX-FILES force-index=no key-compression=yes
RUN-SEQ-FILES default-type=binary
RUN-SEQ-FILES device-slewing-reserve=255
RUN-SEQ-FILES tab-stops=8,12,16,20,24,28,32,36,40,44,48,52,
&56,60,64,68,72
RUN-SORT intermediate-files=5 memory-size=16000
TERM-UNIT move-attr=no define-control-characters=yes
TERM-INTERFACE TERMINFO
TERM-INPUT action=left-arrow                    kcub1
TERM-INPUT action=right-arrow                   kcuf1
TERM-INPUT action=backspace precedence=1        kbs
TERM-INPUT action=set-rm-insertion              kich1
TERM-INPUT action=delete-character              kdch1
TERM-INPUT action=erase-entire                  kclr
TERM-INPUT action=screen-terminate code=01      kf1
TERM-INPUT action=screen-terminate code=02      kf2
TERM-INPUT action=screen-terminate code=03      kf3
TERM-INPUT action=screen-terminate code=04      kf4
TERM-INPUT action=screen-terminate code=05      kf5
TERM-INPUT action=screen-terminate code=06      kf6
TERM-INPUT action=screen-terminate code=07      kf7
TERM-INPUT action=screen-terminate code=08      kf8
TERM-INPUT action=screen-terminate code=09      kf9
TERM-INPUT action=screen-terminate code=10      kf10
TERM-INPUT code=11                              kf11
TERM-INPUT code=12                              kf12
TERM-INPUT code=13                              kf13
TERM-INPUT code=14                              kf14
TERM-INPUT code=15                              kf15
TERM-INPUT code=16                              kf16
TERM-INPUT code=17                              kf17
TERM-INPUT code=18                              kf18
TERM-INPUT code=19                              kf19
TERM-INPUT code=20                              kf20
TERM-INPUT code=21                              kf21
```

```
TERM-INPUT code=22                                kf22
TERM-INPUT code=23                                kf23
TERM-INPUT code=24                                kf24
TERM-INPUT code=25                                kf25
TERM-INPUT code=26                                kf26
TERM-INPUT code=27                                kf27
TERM-INPUT code=28                                kf28
TERM-INPUT code=29                                kf29
TERM-INPUT code=30                                kf30
TERM-INPUT code=31                                kf31
TERM-INPUT code=32                                kf32
TERM-INPUT code=33                                kf33
TERM-INPUT code=34                                kf34
TERM-INPUT code=35                                kf35
TERM-INPUT code=36                                kf36
TERM-INPUT code=37                                kf37
TERM-INPUT code=38                                kf38
TERM-INPUT code=39                                kf39
TERM-INPUT code=40                                kf40
TERM-INPUT code=41                                kf41
TERM-INPUT code=42                                kf42
TERM-INPUT code=43                                kf43
TERM-INPUT code=44                                kf44
TERM-INPUT code=45                                kf45
TERM-INPUT code=46                                kf46
TERM-INPUT code=47                                kf47
TERM-INPUT code=48                                kf48
TERM-INPUT code=49                                kf49
TERM-INPUT code=50                                kf50
TERM-INPUT code=51                                kf51
TERM-INPUT code=52                                kf52
TERM-INPUT code=53                                kf53
TERM-INPUT code=54                                kf54
TERM-INPUT code=55                                kf55
TERM-INPUT code=56                                kf56
TERM-INPUT code=57                                kf57
TERM-INPUT code=58                                kf58
TERM-INPUT code=59                                kf59
TERM-INPUT code=60                                kf60
TERM-INPUT code=61                                kf61
TERM-INPUT code=62                                kf62
TERM-INPUT code=63                                kf63
TERM-INPUT code=13 exception=no                   cr
TERM-INPUT code=40                                kf0
TERM-INPUT code=41                                ka3
TERM-INPUT code=49                                lf0
TERM-INPUT action=screen-previous-field code=52   kcuu1
```

```
TERM-INPUT code=53                                kcud1
TERM-INPUT action=screen-home code=54             khome
TERM-INPUT code=55                                nel
TERM-INPUT code=56                                kc1
TERM-INPUT action=erase-remainder code=57         kel
TERM-INPUT code=58                                kc3
TERM-INPUT code=59                                kil1
TERM-INPUT code=61                                kdl1
TERM-INPUT code=64                                kb2
TERM-INPUT code=67                                kpp
TERM-INPUT code=68                                knp
TERM-INPUT code=82                                ka1
TERM-INPUT code=83 precedence=1                   khlp
TERM-INPUT code=84                                krdo
PRINT-ATTR auto-line-feed=no
PRINT-ATTR form-feed-available=yes top-of-form-at-close=no
DEFINE-DEVICE device=PRINTER path="lp -s" pipe=yes
DEFINE-DEVICE device=TAPE path=/dev/rtp pipe=no
```

Windows Example

The following records define the default configuration provided by Liant for the Windows operating system.

```
RUN-ATTR accept-intensity=high beep=yes blink=yes
&display-intensity=high reverse=yes
RUN-ATTR error-message-destination=standard-error
RUN-OPTION b=264 k=display m=1
RUN-INDEX-FILES allocation-increment=8
RUN-INDEX-FILES data-compression=yes force-closed=no force-data=no
&force-disk=no
RUN-INDEX-FILES force-index=no key-compression=yes
RUN-SEQ-FILES default-type=binary
RUN-SEQ-FILES device-slewing-reserve=255
RUN-SEQ-FILES tab-stops=8,12,16,20,24,28,32,36,40,44,48,52,
&56,60,64,68,72
RUN-SORT intermediate-files=5 memory-size=16000
PRINT-ATTR auto-line-feed=no
PRINT-ATTR form-feed-available=yes top-of-form-at-close=no
TERM-INTERFACE GUI
TERM-ATTR Data-Characters=32,126
TERM-INPUT Code=1                                   SOH
TERM-INPUT Code=2                                   STX
TERM-INPUT Action=Control-Break                     ETX
TERM-INPUT Code=4                                   EOT
TERM-INPUT Code=5                                   ENQ
TERM-INPUT Code=6                                   ACK
TERM-INPUT Code=7                                   BEL
TERM-INPUT Action=Backspace                         BS
TERM-INPUT Code=9                                   HT
TERM-INPUT Code=10                                  LF
TERM-INPUT Code=11                                  VT
TERM-INPUT Code=12                                  FF
TERM-INPUT Code=13 Exception=No                     CR
TERM-INPUT Code=14                                  SO
TERM-INPUT Code=15                                  SI
TERM-INPUT Code=16                                  DLE
TERM-INPUT Code=17                                  DC1
TERM-INPUT Code=18                                  DC2
TERM-INPUT Code=19                                  DC3
TERM-INPUT Code=20                                  DC4
TERM-INPUT Code=21                                  NAK
TERM-INPUT Code=22                                  SYN
TERM-INPUT Code=23                                  ETB
TERM-INPUT Code=24                                  CAN
TERM-INPUT Code=25                                  EM
```

```
TERM-INPUT Code=26                                      SUB
TERM-INPUT Action=Screen-Escape Code=27                 ESC
TERM-INPUT Code=28                                      FS
TERM-INPUT Code=29                                      GS
TERM-INPUT Code=30                                      RS
TERM-INPUT Code=31                                      US
TERM-INPUT Code=27                                      WCNT [
TERM-INPUT Action=Control-Break                         NUL NUL
TERM-INPUT Action=Backspace                             NUL BS
TERM-INPUT Code=58                                      NUL HT
TERM-INPUT Code=56                                      NUL WSFT HT
TERM-INPUT Code=13 Exception=No                         NUL CR
TERM-INPUT Action=Erase-Remainder Code=57               WSFT WCNT E
TERM-INPUT Code=58                                      WSFT WCNT R
TERM-INPUT Code=59                                      WSFT WCNT I
TERM-INPUT Code=49                                      WSFT WCNT P
TERM-INPUT Code=41                                      WSFT WCNT A
TERM-INPUT Code=64                                      WSFT WCNT S
TERM-INPUT Code=61                                      WSFT WCNT D
TERM-INPUT Action=Erase-Remainder Code=13 Exception=No WSFT WCNT K
TERM-INPUT Code=40                                      WSFT WCNT C
TERM-INPUT Code=55                                      WSFT WCNT N
TERM-INPUT Action=Screen-Home Code=54                   NUL WHOM
TERM-INPUT Action=Screen-Previous-Field Code=52         NUL WUP
TERM-INPUT Code=67                                      NUL WPGU
TERM-INPUT Action=Left-Arrow                            NUL WLFT
TERM-INPUT Action=Right-Arrow                           NUL WRGT
TERM-INPUT Code=82                                      NUL WEND
TERM-INPUT Code=53                                      NUL WDWN
TERM-INPUT Code=68                                      NUL WPGD
TERM-INPUT Action=Set-RM-Insertion                      NUL WINS
TERM-INPUT Action=Delete-Character                      NUL WDEL
TERM-INPUT Action=Screen-Terminate Code=1               NUL WF1
TERM-INPUT Action=Screen-Terminate Code=2               NUL WF2
TERM-INPUT Action=Screen-Terminate Code=3               NUL WF3
TERM-INPUT Action=Screen-Terminate Code=4               NUL WF4
TERM-INPUT Action=Screen-Terminate Code=5               NUL WF5
TERM-INPUT Action=Screen-Terminate Code=6               NUL WF6
TERM-INPUT Action=Screen-Terminate Code=7               NUL WF7
TERM-INPUT Action=Screen-Terminate Code=8               NUL WF8
TERM-INPUT Action=Screen-Terminate Code=9               NUL WF9
TERM-INPUT Action=Screen-Terminate Code=10              NUL WF10
TERM-INPUT Code=11                                      NUL WSFT WF1
TERM-INPUT Code=12                                      NUL WSFT WF2
TERM-INPUT Code=13                                      NUL WSFT WF3
TERM-INPUT Code=14                                      NUL WSFT WF4
TERM-INPUT Code=15                                      NUL WSFT WF5
```

```
TERM-INPUT Code=16                    NUL WSFT WF6
TERM-INPUT Code=17                    NUL WSFT WF7
TERM-INPUT Code=18                    NUL WSFT WF8
TERM-INPUT Code=19                    NUL WSFT WF9
TERM-INPUT Code=20                    NUL WSFT WF10
TERM-INPUT Code=21                    NUL WCNT WF1
TERM-INPUT Code=22                    NUL WCNT WF2
TERM-INPUT Code=23                    NUL WCNT WF3
TERM-INPUT Code=24                    NUL WCNT WF4
TERM-INPUT Code=25                    NUL WCNT WF5
TERM-INPUT Code=26                    NUL WCNT WF6
TERM-INPUT Code=27                    NUL WCNT WF7
TERM-INPUT Code=28                    NUL WCNT WF8
TERM-INPUT Code=29                    NUL WCNT WF9
TERM-INPUT Code=30                    NUL WCNT WF10
TERM-INPUT Code=31                    NUL WSFT WCNT WF1
TERM-INPUT Code=32                    NUL WSFT WCNT WF2
TERM-INPUT Code=33                    NUL WSFT WCNT WF3
TERM-INPUT Code=34                    NUL WSFT WCNT WF4
TERM-INPUT Code=35                    NUL WSFT WCNT WF5
TERM-INPUT Code=36                    NUL WSFT WCNT WF6
TERM-INPUT Code=37                    NUL WSFT WCNT WF7
TERM-INPUT Code=38                    NUL WSFT WCNT WF8
TERM-INPUT Code=39                    NUL WSFT WCNT WF9
TERM-INPUT Code=40                    NUL WSFT WCNT WF10
TERM-INPUT Code=65                    NUL WCNT WLFT
TERM-INPUT Code=66                    NUL WCNT WRGT
TERM-INPUT Code=83                    NUL WCNT WEND
TERM-INPUT Code=70                    NUL WCNT WPGD
TERM-INPUT Code=81                    NUL WCNT WHOM
TERM-INPUT Code=71                    WSFT WCNT 49
TERM-INPUT Code=72                    WSFT WCNT 50
TERM-INPUT Code=73                    WSFT WCNT 51
TERM-INPUT Code=74                    WSFT WCNT 52
TERM-INPUT Code=75                    WSFT WCNT 53
TERM-INPUT Code=76                    WSFT WCNT 54
TERM-INPUT Code=77                    WSFT WCNT 55
TERM-INPUT Code=78                    WSFT WCNT 56
TERM-INPUT Code=79                    WSFT WCNT 57
TERM-INPUT Code=80                    WSFT WCNT 48
TERM-INPUT Code=85                    WSFT WCNT -
TERM-INPUT Code=87                    WSFT WCNT =
TERM-INPUT Code=69                    NUL WCNT WPGU
TERM-INPUT Code=11                    NUL WF11
TERM-INPUT Code=12                    NUL WF12
```

Chapter 11: Instrumentation

RM/COBOL provides a method for examining the performance of RM/COBOL programs at the statement level. This facility—called Instrumentation—involves a two-step process. First, program data must be gathered. Instrumentation provides the tools for data gathering. Next, the gathered data must be analyzed in a manner consistent with your specific requirements. The delivered RM/COBOL Instrumentation contains one example of a data analysis program, called **analysis**. This program also can be used as a starting point for creating your own data analysis program.

The data gathered by Instrumentation and reported by **analysis** can be used during program development to optimize program flow, identify bugs caused by run-away loop control, and improve program integrity by pinpointing unexecuted program code.

Invoking Instrumentation

Instrumentation is invoked when you enter the I Runtime Command Option (see page 7-3). If you intend to use **analysis** as well, all programs in the run unit should be compiled with the L Compile Command Option (see page 6-9).

Keep in mind that the runtime system needs additional memory when the I Runtime Command Option is used. Furthermore, each program in the run unit requires additional memory as it is loaded by the Runtime Command or by a CALL statement (see the "CALL Statement" section in Chapter 6, *Procedure Division Statements*, of the *RM/COBOL Language Reference Manual*). The exact amount of required memory depends on the number of lines in the PROCEDURE DIVISION, as described in the next section.

Data Collection

For each program in a run unit, a file is generated that contains the following information:

- PROGRAM-ID value
- Line number of the PROCEDURE DIVISION header
- Total number of source lines in the program
- Total number of statements executed in the program
- Number of times each statement was executed
- Number of times each paragraph and section were executed

This information is gathered in a data structure that could be described by the RM/COBOL record description, shown in Figure 11-1.

Figure 11-1 Sample Data Structures Description

```
01  PROGRAM-IDENTIFICATION.
    02  PROGRAM-ID-VALUE                    PIC X(30).
    02  PROCEDURE-DIVISION-LINE             PIC 9(8) BINARY.
    02  SOURCE-LINE-COUNT                   PIC 9(8) BINARY.
    02  TOTAL-STATEMENTS-EXECUTED           PIC 9(8) BINARY.
    02  TOTAL-STATEMENTS-PITCHED            PIC 9(8) BINARY.
    02                                      PIC X(14).
    02  OCCURS 1 TO 65000
        DEPENDING ON number of procedure lines.
        03  OCCURS 2.
            04  STATEMENT-TYPE              PIC X(1).
                88  NO-STATEMENT-OR-NOT-EXECUTED
                                            VALUE LOW-VALUE.
                88  SECTION-COUNT           VALUE 'X'.
                88  PARAGRAPH-COUNT         VALUE 'P'.
                88  STATEMENT-COUNT         VALUE 'S'.
            04  COUNT-VALUE                 PIC 9(9) BINARY.
```

The size of the required structure may be calculated as follows:

```
n = source-line-count - procedure-division-line + 1
size (in bytes) = 60 + (n * 10)
```

The data structure for a program is allocated when the first statement in that program is executed. The data structure remains allocated even when the associated program is canceled.

As with the RM/COBOL Interactive Debugger, Instrumentation treats section names, paragraph names and procedural statements as statements for the purpose of data gathering. See pages 9-2 and 9-3 for the definitions of statements and line and intraline

numbers. Likewise, programs within the run unit that were compiled with the Q Compile Command Option are invisible to Instrumentation. No information will be gathered nor file created for such programs.

As each statement is executed, Instrumentation adds 1 to the total number of statements executed for that program (TOTAL-STATEMENTS-EXECUTED in the record description above). If the executing statement is the first or second statement on a line, 1 is added to the count of executions (COUNT-VALUE (line, intraline + 1) in the record descriptor above) and the appropriate statement type (STATEMENT-TYPE (line, intraline + 1) in the record descriptor above) is set to true for that statement. If the executing statement is the third or subsequent statement on a line, 1 is added to a count of statements not counted individually (TOTAL-STATEMENTS-PITCHED in the record description above).

When program execution completes—normally or abnormally—each data structure is written to disk. The name of the disk file is constructed from the first eight characters of the PROGRAM-ID value, concatenated to the file extension **.CNT**. If the program name is less than eight characters, the entire name is concatenated to the file extension. For example, for a program named **example**, the data collection file would be named **example.CNT**. If the name of the program was **generates**, the data collection file would be named **generate.CNT**.

The runtime directory search sequence (described on page 2-4 for UNIX and page 3-11 for Windows) is used when writing these files. An existing file within the directories named in the RUNPATH specification will be replaced by a data collection file with the same name. If no file with the same name exists, a new data collection file will be created.

Instrumentation either replaces or creates new data collection files for each invocation of a run unit. Historical information is not maintained from run unit to run unit. This is a function of the **analysis** program, which processes the data collection files after each run unit.

Instrumentation writes messages to the screen as each data collection file is written. The form of the message when no errors occur is the following:

```
name.CNT Opening Writing Closing
```

name is derived from the first eight characters of the PROGRAM-ID, as described above. Should an error occur during the opening, writing or closing of the file, an error message (see Appendix A, *Runtime Messages*) appears after the name of the operation encountering the error. If Opening receives an error, Writing and Closing are not attempted and will not be included in the message.

Data Analysis

As was mentioned at the start of this chapter, a data analysis program—named **analysis**—is provided with RM/COBOL Instrumentation. Use this program as delivered, or modify it to fit your precise requirements. As delivered, **analysis** provides the following:

- Statement count data from the **.CNT** file is added to the statement count data gathered from earlier invocations of Instrumentation. This keeps a total count of the statements executed.
- Statement count data from the total count file is merged with the listing file, creating a new listing file showing execution counts for each statement.
- A summary of execution counts for each paragraph and section is appended to the new listing file.

To use **analysis** as delivered, first compile the program with the RM/COBOL Compile Command:

```
rmcobol analysis A L X
```

This creates a source listing, allocation map, and cross reference on a listing file named **analysis.lst** in the directory containing **analysis.cbl**. An RM/COBOL object file, **analysis.cob**, is also created in that directory. See Chapter 6, *Compiling*, for more information about the compilation options and parameters.

Next, execute the **analysis** program by entering the RM/COBOL Runtime Command:

```
runcobol analysis [ A='path' ]
```

The optional A=‘*path*’ may be used to supply a pathname of the directory where the merged listing files created by **analysis** are to reside. If this parameter is omitted, the RUNPATH specification is used. See Chapter 7, *Running*, for more information about the Runtime Command options and parameters.

The **analysis** program is listing-file driven, that is, the filenames of one or more listing files are supplied by the user. These listing files are then processed by **analysis**, one at a time, as follows:

1. The merged listing file is opened using the same filename as the listing file, with the extension **.HST**.

2. The source listing section is scanned to find the PROGRAM-ID paragraph.

3. The program name found in the PROGRAM-ID paragraph is used to construct the filename of the **.CNT** file.

4. The **.CNT** file is opened.

5. The program name used in the PROGRAM-ID paragraph is used to construct the filename of the total count (**.TOT**) file.

6. The **.TOT** file is opened.

7. The **.TOT** file is updated (or created if it does not exist) by adding the statement counts from the **.CNT** file to the corresponding statement counts in the **.TOT** file.

8. The source listing section is reformatted merging the statement counts from the **.CNT** or **.TOT** file with the source listing.

9. Summary information about the program is written to the merged file.

10. All listing file information between the end of one program and the beginning of another in the file or end of file is copied to the merged file.

11. If another program exists in the listing file, this process is repeated starting at Step 2.

12. If the name of another listing file is supplied by the user, this process is repeated starting at Step 1.

13. **analysis** terminates.

When prompted to supply a listing filename, enter only the filename portion of the name; the **.lst** extension is supplied automatically. To indicate there are no more listing files, press Enter without typing a name. Use redirected input on the Runtime Command to automate the entry of filenames where repeated runs are desired.

Figure 11-2 illustrates an excerpt from a merged listing, as it pertains to **analysis**.

Figure 11-2 Excerpt of a Merged Listing

```
  Count1 Count2  LINE  PG/LN  A..B..2..3..4..5..6..7..ID...8   FPERF
                    1         IDENTIFICATION DIVISION.
0                   2         PROGRAM-ID.                  FPERF.                0
                                      .
                                      .
                                      .
 205                 77         PROCEDURE DIVISION.
0  1                 78         MAIN SECTION.                                     0
                                      .
                                      .
                                      .
0  1                 91         A.                                                0
   1                 92           MOVE ZEROS TO COUNT-ER, ERROR-COUNT.
   1                 93           MOVE SPACE TO PRINT-RECORD.
0  1    1            94           MOVE "PATH" TO PATH. MOVE "A" TO P-R.             0
   1                 95           PERFORM B.
   1                 96           IF COUNT-ER = 1
   1                 97              WRITE PRINT-RECORD FROM PASS-LINE
0                    98             ELSE                                          0
                     99              WRITE PRINT-RECORD FROM FAIL-LINE
                    100                ADD 1 TO ERROR-COUNT.
   1                101           MOVE "B" TO P-R.
                    102
0  8    8           103         B.WRITE PRINT RECORD FROM PASS-LINE.              0
   8                104           ADD 1 TO COUNT-ER.
  Summary Statistics for FPERF
0 The program contains 242 lines, of which 166 are procedure division lines.      0
  The procedure division has 92 lines which had COBOL verbs executed at least
  once, and 26 lines which had procedure-names executed at least once.
  There were 205 verb executions counted, of which 151 were COBOL statements
0 and 54 were procedures.                                                         0
                                      .
                                      .
                                      .
  Count      %     LineParagraph/Section
0    8    14.81    103   B                                                       0
     6    11.11    197   K
                                      .
                                      .
0                                     .                                           0
     1    1.85     200   A
```

Count1, associated with the PROCEDURE DIVISION line, is the total number of statements executed in this program. Count2, associated with the PROCEDURE DIVISION line, is the total number of statements pitched (unattributed) in this program. For all other lines in the Procedure Division, Count1 is the number of times the section, paragraph or statement was executed. Count2 is the number of times the next statement on the line was executed. If there are more than two statements on the line, the execution counts of the remaining statements are not displayed.

If the line was not referenced or executed, Count1 and Count2 will be blank. This indicates that the line did not contain a verb, or that it is code that was never executed.

Some parts of the merged listing file may be suppressed with the S Runtime Command Option. In this case, the Runtime Command would be:

```
runcobol analysis S=xpnuc [ A='path' ]
```

The values of *x*, *p*, *n*, *u* and *c* have the following results:

- *x* = 1 excludes all lines in the original listing file from the merged listing file; *x* = 0 includes these lines. *x* = 0 is the default.
- *p* = 1 excludes the paragraph and section execution counts from the summary information; *p* = 0 includes these counts. *p* = 0 is the default.
- *n* = 1 excludes all lines from the merged listing file that are not contained in the Procedure Division of the source listing portion; *n* = 0 includes such lines. *n*= 0 is the default. *n* has no additional effect if *x* = 1.
- *u* = 1 suppresses the update of the total execution counts derived from the total count file; *u* = 0 allows the update. *u* = 0 is the default.
- *c* = 1 produces the merged listing file from the **.CNT** file. *c* = 0 produces the merged listing file from the **.TOT** file. *c* = 0 is the default. *c* has no effect if *x* = 1.

For example:

```
runcobol analysis S=10101
```

produces a merge listing file with only paragraph and section execution counts and some summary information from the **.CNT** file but updates historical data for all statements.

Appendix A: Runtime Messages

This appendix presents the types of messages generated during program execution, including those generated following normal termination as well as those generated when an error occurs.

Error Message Types

Data Reference, **Procedure**, **Input/Output**, **Sort-Merge**, **Message Control**, **Configuration**, and **Initialization** errors have error numbers along with the error messages (detailed below) to help pinpoint the error being diagnosed.

A **Traceback** message traces back through one or more calling programs when an error occurs within a called subprogram. The traceback traces the path from the statement causing the error through all programs currently active in the run unit.

An **Internal Error** message indicates that an inconsistency not normally caused by a flaw in the source program has been detected. The numbers within the error message are needed by Liant technical support services should an internal error occur.

An **Operator-Requested Termination** error occurs when an operator ends execution by pressing the Ctrl and Break keys (Interrupt key under UNIX).

A **Normal Termination** message appears when program execution terminates successfully.

Error Message Format

The different types of messages use the same general format:

```
COBOL type error code at line number in
        prog-id compiled date time
```

type is one of the following types of messages:

- Data reference
- Procedure
- Input/output
- Internal
- Traceback
- Operator-requested termination
- Sort-merge
- Message control
- Configuration
- Initialization

code is the first two digits of the error numbers listed in this appendix.

number identifies a particular line in the Procedure Division of the source program. It is the line in which the statement being referred to starts, and it can be looked up in the leftmost column (labeled "Line") of the source listing produced by the compiler. If a question mark appears in this position, the following *prog-id* field refers to a machine language subprogram, or indicates that a valid line number has not been established following an Interactive Debug R (Resume) Command (see page 9-34).

If the program has been compiled with the Q Compile Command Option, line numbers are not available. Instead, the statement address, which appears under the "Debug" heading in the listing, will appear. The statement address consists of a segment number and a segment offset and can be distinguished from a line number since the segment offset is always displayed as a six-digit number (with leading zeros, if necessary). The segment number is not displayed if it is zero. If a segment number is present, it precedes the segment offset and the two are separated by a slash (/) character.

Note The statement address in the error message may not match exactly any of the statement addresses in the program listing. If the statement address in the error message does match a statement address in the program listing, the error condition may have been caused by the statement whose address is just prior to the error address.

prog-id identifies the program interrupted in order to produce this message. It has the following format:

program-name (*pathname.ext*)

program-name is taken from the PROGRAM-ID paragraph of the source program.

pathname.ext is the fully qualified pathname of the object library in which the object program resides.

date and *time* are the date and time the program was compiled. They correspond exactly to the date and time printed on the program listing.

Note 1. Traceback and operator-requested termination messages do not include the "error *code*" portion of this message.

2. The format of configuration and initialization errors does not precisely conform to the format shown above. See the discussion of configuration errors that begins on page A-37.

Data Reference Errors

Data reference errors include invalid data types, improper data definitions, improper data values and illegal subscripting.

Number	Description
101	For one of the following reasons, no operand exists corresponding to the referenced Linkage Section item: 1. There are more data items specified in the Procedure Division header than are specified in the USING phrase of the CALL statement in the calling program. 2. The Procedure Division header in the first (or main) program in the run unit specifies more than one data item (see the discussion of the A Runtime Command Option that begins on page 7-5 for more details). This is just a special case of reason 1 since the main program is called with only one argument. 3. The CALL statement in the calling program specified OMITTED for the argument corresponding to the Procedure Division header argument for the Linkage Section data item in the called program. **Note** This error does not occur if the Linkage Section data item is referenced in the ADDRESS OF special register or in an ADDRESS OF phrase in a SET statement. Thus, this error can be prevented by first testing if ADDRESS OF *identifier-1* NOT = NULL before attempting to reference *identifier-1* directly.

Number	Description
102	A reference to a variable length group is illegal because the value in the DEPENDING data item (*data-name-1*) is less than the minimum value (*integer-1*) or greater than the maximum value (*integer-2*) in the OCCURS clause.
103	An identifier or literal referenced in an INSPECT CONVERTING statement is illegal for one of the following reasons: 1. The source translation template (*identifier-6* or *literal-4*) contains multiple occurrences of the same value. 2. The source translation template (*identifier-6* or *literal-4*) does not have the same length as the destination translation template (*identifier-7* or *literal-5*). 3. The destination translation template (*literal-5*) is figurative and its length is not one.
104	A reference to a data item is illegal for one of the following reasons: 1. The computed composite subscript value for a subscripted reference has a value that is negative, zero or exceeds the maximum value for the referenced item. 2. There is a reference to a Linkage Section data item that is a formal argument whose description specifies more characters than are present in the corresponding operand in the USING or GIVING phrases of the CALL statement that called the current called program. 3. There is a reference to a Linkage Section data item in the first (or main) program in the run unit whose description specifies more characters than are supplied by the A Runtime Command Option. 4. There is a reference to a Linkage Section data item that is a based linkage record whose description specifies more characters than are present in the area of memory covered by the pointer value that was used to set the base address of the record. 5. There is a reference to a Linkage Section data item that is a based linkage record and the offset value for the base address has been set outside the area of memory covered by the address and length fields of the base address. That is, a Format 6 SET statement has set the pointer offset value outside the area of memory covered by

Number	Description
104 *(Cont.)*	the pointer data item. In this case, the error occurs not when the Format 6 SET statement is executed, but when the resultant pointer value is used as the base address of a based linkage record.
105	A subscript calculation overflowed or underflowed.
106	An index-name value indicates more than 65535 occurrences.
107	A reference modification is illegal for one of the following reasons: 1. A reference modification offset value is less than or equal to zero, or is greater than the length of the data item being reference modified. 2. A reference modification length value is less than or equal to zero or is greater than the remaining length of the data item being reference modified after application of the offset value.
108	The referenced Linkage Section data item (which is other than one associated with an argument listed in the USING or GIVING phrases of the Procedure Division header), has a null base address because of one of the following reasons: 1. The base address has never been set during this run unit. 2. The base address has been explicitly set to NULL or to a pointer data item with a null value during this run unit. **Note** This error does not occur if the Linkage Section data item is referenced in the ADDRESS OF special register or in an ADDRESS OF phrase in a SET statement. Thus, this error can be prevented by first testing if ADDRESS OF *identifier-1* NOT = NULL before attempting to reference *identifier-1* directly.
110	A reference to a data item is illegal because the base address for the data item has been set to a pointer value, other than NULL, that does not point to memory that the program may access. This error occurs when the based linkage item is referenced after, but not at, the time the bad base address is established in a Format 6 SET statement.

Procedure Errors

Procedure errors include improper program structure or invalid calls.

Number	Description
201	A CANCEL statement has attempted to cancel a program that is still active. That is, a program that has called, directly or indirectly, the program attempting the cancel.
202	The program-name on a CALL statement has a value that is equal to spaces.
203	The program-name on the Runtime Command or CALL statement does not match any of the PROGRAM-ID names in any library but does match a valid RM/COBOL library object filename. The call-by-filename technique is valid only for single-program object files.
204	The program-name on the Runtime Command or CALL statement does not match any of the PROGRAM-ID names in any library and does not match a valid RM/COBOL object filename or non-COBOL executable file. Note that an object program with a higher object version number than that supported by the runtime system is not considered a valid program (see Appendix H, *Object Versions*, for more information). Under UNIX, if the CALL statement specified a subprogram name that does not match any of the names in the subprogram name table, this error occurs. Under Windows, if the CALL statement specified SYSTEM, this error can occur when the external routine SYSTEM was successfully found and loaded, but the command processor required by SYSTEM could not be found. This can occur when the COMSPEC environment variable is not defined or its value contains an invalid drive, path, or filename. This error can also indicate that the length of the parameter passed to SYSTEM exceeds the limits specified in the documentation of SYSTEM on page F-41. Under Windows, if the CALL statement specified a DLL file that does not contain a nonresident ordinal one entry point, this error occurs. If the CALL statement specified the ON EXCEPTION or ON OVERFLOW phrase, this procedure error is suppressed and execution continues with the imperative statement in the ON EXCEPTION or ON OVERFLOW phrase.

Number	Description
205	A CALL statement has attempted to call a program that is still active. An active program is one that has called, directly or indirectly, the program attempting the call in error.
206	The called filename is not a valid RM/COBOL object file. The file may be corrupt or contain information that makes it invalid for this run unit. A corrupt file could be caused by a system failure or abnormal termination of the RM/COBOL compiler. The file also could be invalid for this run unit if the registration information is not correct or if the object was compiled with features that make it incompatible with the calling program (for example, the computational versions may not match).
207	There is not enough memory to load the program from the Runtime Command or the CALL statement, or to build the in-memory library structures indicated in the Runtime Command, or to reserve memory for the ACCEPT and DISPLAY buffers. This may be caused by memory fragmentation resulting from the dynamics of CALL and CANCEL operations and file I/O, or it may mean the requested program is too large for the available memory. More memory can be made available during a SORT statement by using the T Runtime Command Option to reduce the memory requested by sort. Additional memory can be made available by reducing the amount of buffer pool memory through the use of the BUFFER-POOL-SIZE keyword on the RUN-FILES-ATTR configuration record (see page 10-26). See page 6-29 for details on memory size requirements for object programs. Under Windows, if the CALL statement specified SYSTEM, this error can occur when there is insufficient memory to load the command processor required by SYSTEM. If the CALL statement specified the ON EXCEPTION or ON OVERFLOW phrase, this procedure error is suppressed and execution continues with the imperative-statement in the ON EXCEPTION or ON OVERFLOW phrase.
208	The ALTER statement cannot be executed because of an error in the source program. The compilation listing provides the specific reason for the error; for example, an undefined procedure-name, an ambiguous procedure-name reference, an attempt to ALTER a procedure-name that is not alterable, a conflict with segmentation rules, and so forth.

Number	Description
209	The GO TO statement cannot be executed because it does not specify a default procedure-name and it was not altered before attempting execution. The source program may have a compilation error if no ALTER statement specifies the paragraph containing the GO TO statement. However, the source program may compile without error if at least one ALTER statement exists that specifies the paragraph containing the GO TO statement. In the latter case, no such ALTER statement is executed in the logical sequence of statements leading to the execution of the GO TO statement.
210	The GO TO or PERFORM statement cannot be executed because of an error in the source program. The compilation listing provides the specific reason for the error; for example, an undefined procedure-name, an ambiguous procedure-name reference, a conflict with segmentation rules, and so forth.
211	An “E” level compilation error has been encountered.
212	The USE procedure cannot exit because it was invoked by the execution of a SORT or MERGE statement and the sort-merge operation is either no longer active or the exit location has been lost.
213	The RM/COBOL object library file specified in the Runtime Command cannot be found.
214	The RM/COBOL object library file specified in the Runtime Command does not contain a valid object program.
215	A PERFORM statement in an independent segment has performed a section or paragraph in a fixed segment that performed a section or paragraph in a different independent segment.
216	An external item with the same name and type (data record, file connector or index name) as an existing external in the run unit has a different description than the existing external. For an external data record, the length of the record is different. For an index-name, the span of the table item associated with the index name is different, or the index-name is associated with a different external record.

Number	Description
216 *(Cont.)*	For a file connector, any of the file control clauses, file description clauses or record description lengths are different. For a relative organization external file connector, this error is caused if the new external does not reference the same external data item for the relative key as is referenced by the existing external file connector. For additional details on the matching rules required for external objects with the same name described in more than one program of a run unit, see the discussion of the "External Objects" section that begins on page 8-36.
217	An external file connector is invalid since it indicates a SAME AREA or MULTIPLE FILE TAPE association. Typically, the compiler prevents this error from occurring by diagnosing the problem at compile time.
218	There is not enough memory to allocate the data structures necessary to support an external item declared in the program currently being loaded.
219	There is not enough memory to allocate the data structures necessary to support entry into a USE GLOBAL procedure following the occurrence of an I/O error for which the USE GLOBAL procedure is applicable. The program is terminated as if no applicable USE procedure were found.
222	Under Windows, the SYSTEM routine was called but the command processor required by SYSTEM could not be loaded for some unexpected reason, such as, bad environment, access denied, too many open files, or bad format for the command processor. If the command processor could not be found, error 204 would occur instead of this error. If there was insufficient memory, procedure error 207 would occur instead of this error. If the operating system fails to load the command processor for any other reasons, then this error occurs. If the CALL statement specified the ON EXCEPTION or ON OVERFLOW phrase, this procedure error is suppressed and execution continues with the imperative-statement in the ON EXCEPTION or ON OVERFLOW phrase.

Number	Description
223	Under Windows, an error occurred while loading a DLL file. If the DLL file could not be found, error 204 would occur instead of this error. If there was insufficient memory, procedure error 207 would occur instead of this error. If the operating system fails to load the DLL for any other reasons, then this error occurs. This error generally indicates that the DLL was found, but has an invalid format for the operating system being used. Some "system out of memory" conditions may cause an error 223, since Windows returns an ambiguous error status in some low memory situations. If the CALL statement specified the ON EXCEPTION or ON OVERFLOW phrase, this procedure error is suppressed and execution continues with the imperative-statement in the ON EXCEPTION or ON OVERFLOW phrase.
251	Under UNIX, a syntax error was detected while scanning the termcap entry for a terminal type.
252	Under UNIX, the terminal type name specified by the TERM environment variable or by the termcap entry tc cannot be located.
253	Under UNIX, an internal table overflowed while processing a termcap or terminfo entry. The entry is too complex and its size should be reduced.
254	Under UNIX, two termcap or terminfo entries have identical input sequences for this terminal. Use the PRECEDENCE= keyword to indicate that one entry takes precedence over another (see page 10-42).
255	Under UNIX, the terminal described in the termcap or terminfo entry has no cursor positioning sequence, or the rows or columns for the terminal are zero.
256	Under UNIX, the unit number specified in an ACCEPT or DISPLAY statement has not been defined using a TERM-UNIT configuration record.
257	Under UNIX, an attempted dynamic load of a machine language subprogram or library failed because dynamic load is not supported by your operating system.

Number	Description
299	An attempt to use Instrumentation on a run unit failed because a program in the run unit contains more than 65535 source lines or there was insufficient memory to allocate the data collection structure for a program in the run unit. See the "Data Collection" section on page 11-2 for additional information on the memory requirements of Instrumentation.

Input/Output Errors

Input/output errors include all errors that can occur during file access. The format is as follows:

```
COBOL I/O error number on COBOL-filename
          file file-access-name
```

The numerically ordered list presented below shows the values that can appear as *number* in the I/O error messages, and a description of each error. The list is presented in numerical order. The I/O error number has the form:

```
mm, nn
```

mm is a two-digit decimal number indicating the general class of error that occurred. It is also the value stored into the file status data item if such an item has been specified for the associated file. Thus, this value is available to the program.

nn is a two-digit code that provides more specific information on the nature of the error. This value is available to the program only if you call the subprogram C$RERR (described in the discussion that begins on page F-22).

When the I/O error is 30, the I/O error number has the form:

```
30, OS error nnnnn
```

OS is the operating system that generated the error and indicates how the *nnnnn* code should be interpreted.

nnnnn is the operating system error code that was returned when the error occurred. This value is available to the program only if you call the subprogram C$RERR (described in the discussion that begins on page F-22).

The phrase “1985 mode” indicates that the error message description applies only to ANSI COBOL 1985. The phrase “1974 mode” indicates that the error message description applies only to ANSI COBOL 1974. Messages not marked with either phrase indicate that the description applies to both ANSI COBOL 1985 and 1974.

Number	Description
00	The operation was successful.
02	The operation was successful but a duplicate key was detected. For a READ statement, the key value for the current key of reference is equal to the value of that same key in the next logical record within the current key of reference. For a REWRITE or WRITE statement, the record just written created a duplicate key value for at least one alternate record key for which duplicates are allowed.
04, 05	The record read from the file is shorter than the minimum record length. (1985 mode)
04, 06	The record read from the file is longer than the record area. (1985 mode)
05	The operation was successful but the file was not present at the time the statement began. For a DELETE FILE statement, the file was not found. For an OPEN statement, the optional file was not found. If the open mode is I-O or EXTEND, the file has been created. (1985 mode)
07	The operation was successful. If the operation was a CLOSE statement with a NO REWIND, REEL, UNIT or FOR REMOVAL clause, or if the operation was an OPEN statement with the NO REWIND clause, the file is not on a unit or reel medium. (1985 mode)
10	A sequential READ statement was attempted and no next (or previous) logical record exists in the file because the end (or beginning) of file was reached, or a sequential READ statement was attempted for the first time on an optional input file that is not present.
14	A sequential READ statement was attempted for a relative file and the number of significant digits in the relative record number is larger than the size of the relative key data item. (1985 mode)

Number	Description
21	A sequence error exists for a sequentially or dynamically accessed indexed file using duplicate prime keys. For a REWRITE statement, the prime record key was changed by the program between the execution of the preceding READ statement for the file and the execution of the REWRITE statement. Or, for a WRITE statement, the ascending sequence requirements for successive record key values were violated.
22	The new record value attempts to duplicate an indexed file key which prohibits duplicates, or a relative record number that already exists.
23	An attempt was made to randomly access a record that does not exist in the file, or a START or random READ statement was attempted on an optional input file that is not present.
24	There is insufficient disk space for the operation on a relative or indexed file.
24, 01	A sequential WRITE statement was attempted for a relative file and the number of significant digits in the relative record number is larger than the size of the relative key data item, or the relative record number is zero. (1985 mode)
24, 02	There is insufficient room left in the file for the operation. See the description of the FILE-LOCK-LIMIT and FILE-PROCESS-COUNT keywords of the RUN-FILES-ATTR configuration record on page 10-28 for more details. This error may occur when attempting to delete a record from an indexed file if enough free blocks cannot be made available to split an index block. Running the Indexed File Recovery utility **(recover1)** on the file could consolidate enough index blocks to allow continued use of the file. This error may occur on UNIX systems if the file's size exceeds the user's ulimit.
24, 03	An attempt was made to add the 4294967296th record to an indexed file. The maximum number or records allowed in an indexed file in 4294967295.

Number	Description
24, 04	An attempt was made to add a record to a shared relative file that is so far beyond the current EOF that the entire intervening region exceeds the maximum size of a file region lock.
30, *OS* error *code*	RM/COBOL returned a permanent error in this 30, *OS* error *code* format. *OS* indicates the operating system that is the source of the error *code*. If *OS* is Btrieve, *code* is defined in Table A-1 on page A-32. If *OS* is UNIX, *code* is defined in the **errno.h** include file. If *OS* is Windows, refer to the file **WINERROR.TXT**, which is distributed with the media. If *OS* is Runtime Library, *code* is defined in Table A-2 on page A-35. If *OS* is File Manager Detected, *code* is defined in Table A-3 on page A-35. If *OS* is any other value, then *code* and its meaning are system-dependent. Please refer to the documentation provided with your operating system for more information. Using the eleven-character data item on the C$RERR subprogram will allow permanent errors to include the *OS* error *code*. For example, 30,06,00058 is Btrieve error 58 (see the "C$RERR" section in Appendix F, *Subprogram Library*). A Procedure Division statement that explicitly or implicitly causes an overlay segment to be loaded may receive this error if the RM/COBOL object file cannot be read when the statement is executed.
30, 25	This permanent error may be returned for Btrieve files. It indicates that an error occurred during the creation of the file. It may also mean that the file was already opened during the creation. If the file did not exist at the time the RM/COBOL-to-Btrieve Adapter program checked for the existence of the file but did exist at the time of the attempt to create it, then the Adapter program will misinterpret the error as an I/O error and return the permanent error code.
30, 58	The Btrieve compression size is too small. Use the appropriate Btrieve Setup utility to increase the size for the Largest Compressed Record Size setting (see the appropriate Btrieve installation and operation manual for more details). The Btrieve MicroKernel Database Engine (MKDE) must be restarted before the increase will take effect.
30, 64	End of file occurred when ACCEPTing from a redirected input file.

Number	Description
30, 97	The Btrieve requester's data message length is too small. Reconfigure the requester and specify a higher value. Be certain also to ensure that the maximum record length (Communication Buffer Size), configured on server-based Btrieve, is at least as large as the requester's value (see the appropriate Btrieve installation and operation manual for more details).
34	There is insufficient disk space for the operation on a sequential file.
34, 02	There is insufficient room left in the file for the operation. See the description of the FILE-LOCK-LIMIT and FILE-PROCESS-COUNT keywords of the RUN-FILES-ATTR configuration record on page 10-28 for more details.
35	The file is not available because the file identified by the resultant file access name could not be found. The pathname or filename may be misspelled or may not be valid for the operating system. Specifying a pathname or filename that is not a valid name or that is longer than allowed also results in this error. The directory search sequence specified by RUNPATH may be incorrect. See the "Locating RM/COBOL Files" sections either on pages 2-3 through 2-7 for UNIX or pages 3-10 through 3-15 for Windows for information on the resultant file access name. (1985 mode)
37, 01	The file must be mass storage. The device-name specified for the file was DISC, DISK or RANDOM, but the resultant file access name identifies a file that does not reside on a disk. (1985 mode)
37, 07	The requested operation conflicts with the permissions allowed to the run unit for the file. This error can occur under any of the following conditions: a DELETE FILE statement failed because the run unit did not have write permission for the directory containing the file; an OPEN statement with the OUTPUT or EXTEND phrase failed because the run unit does not have write permission for the file; an OPEN statement with the INPUT phrase failed because the run unit does not have read permission for the file; or, an OPEN statement with the I-O phrase failed because the run unit does not have read and write permissions for the file. (1985 mode)
38	An OPEN or DELETE FILE operation failed because the filename was previously closed WITH LOCK. (1985 mode)

Number	Description
39, 01	The file organization specified for the filename does not match the actual file organization of the physical file. (1985 mode) This message may not occur if the file is actually a Btrieve file. The Btrieve MicroKernel Database Engine (MKDE) always opens its files with lock, and the OPEN WITH LOCK error condition is encountered by the RM/COBOL file management system, preventing it from determining the organization of the file.
39, 02	The minimum record length specified in the RECORD CONTAINS clause or implied by the record descriptions of the filename does not match the actual minimum record length of the physical file. (1985 mode) For Btrieve files, if the minimum record length of the file is less than four bytes, the file will be implemented using four-byte records. In this situation, the RM/COBOL-to-Btrieve Adapter program cannot detect the initial minimum record length and will fail to diagnose the mismatched minimum record length error condition.
39, 03	The maximum record length specified in the RECORD CONTAINS clause or implied by the record descriptions of the filename does not match the actual maximum record length of the physical file. (1985 mode) This error can occur when reopening a print file closed WITH NO REWIND if the OPEN statement specifies a different record length than was used on the previous OPEN statement. This error does not occur with variable-length record Btrieve files. Btrieve files do not support a mechanism to record this information and, thus, it cannot be verified.
39, 04	The minimum block length specified in the BLOCK CONTAINS clause for the filename does not match the actual minimum block size of the physical file. (1985 mode)
39, 05	The maximum block length specified in the BLOCK CONTAINS clause for the filename does not match the actual maximum block size of the physical file. (1985 mode) This error does not occur with variable-length record Btrieve files. Btrieve files do not support a mechanism to record this information and, thus, it cannot be verified.

Number	Description
39, 06	The record delimiting technique, LINE-SEQUENTIAL or BINARY-SEQUENTIAL, specified for the filename does not match the actual record delimiting technique of the physical file. (1985 mode)
39, 07	The CODE-SET specified for the filename does not match the actual character code of the physical file. (1985 mode)
39, 08	The COLLATING SEQUENCE specified for the indexed file does not match the actual collating sequence of the physical file. (1985 mode)
39, 09	The record type attribute, fixed or variable, specified in the RECORD CONTAINS clause or implied by the record descriptions of the filename does not match the record type attribute of the physical file. (1985 mode)
39, 0A	The character specified in the PADDING CHARACTER clause for the filename does not match the actual padding character of the file on the external medium. (1985 mode)
39, 30 through 39, 3E	The key duplicates allowed flag specified for keys 0 through 14 does not match the corresponding key duplicates allowed flag of the physical file. The prime record key is 0. Alternate record keys are numbered in ascending order of key offset, starting with 1. (1985 mode) For Btrieve files, this error also indicates that in the physical file, a key attribute other than duplicate, modifiable, binary, null, alternate collating sequence, or extended type was specified for the Btrieve key that corresponds with the COBOL key defined for the key offset. (For example, descending, supplemental, and manual key attributes may not be used for RM/COBOL keys.) In addition, the primary key may not have a null attribute. Btrieve allows multiple keys to be defined at the same key offset, but only the first is considered by the RM/COBOL-to-Btrieve Adapter program.

Number	Description
39, 3F	The key duplicates allowed flag specified for an alternate record key 15 through 254 does not match the corresponding key duplicates allowed flag of the physical file. (1985 mode) For Btrieve files, this error also indicates that in the physical file, a key attribute other than duplicate, modifiable, binary, null, alternate collating sequence or extended type was specified for the Btrieve key that corresponds with the COBOL key defined for the key offset. (For example, descending, supplemental and manual key attributes may not be used for RM/COBOL keys.) Btrieve allows multiple keys to be defined at the same key offset, but only the first is considered by the RM/COBOL-to-Btrieve Adapter program.
39, 40 through 39, 4E	The offset from the start of the record area to the start of the key area for keys 0 through 14 does not match the corresponding key offset of the physical file. The prime record key is 0. Alternate record keys are numbered in ascending order of key offset, starting with 1. (1985 mode)
39, 4F	The offset from the start of the record area to the start of the key area for an alternate key 15 through 254 does not match the corresponding key offset of the physical file. (1985 mode)
39, 50 through 39, 5E	The length of the key area for keys 0 through 14 does not match the corresponding key length of the physical file. The prime record key is key 0. Alternate record keys are numbered in ascending order of key offset, starting with 1. (1985 mode) This error also occurs if the number of keys specified does not match the actual number of keys in the physical file. The key number 1 through E, if greater than the number of keys in the file description, indicates that the file contains more keys than the program describes. The key number 1 through E, if less than or equal to the number of keys in the file description, provides a value one greater than the number of keys contained in the file. (1985 mode)

Number	Description
39, 5F	The length of the key area for an alternate key 15 through 254 does not match the corresponding key offset of the physical file. (1985 mode) This error also occurs if the number of keys specified does not match the actual number of keys in the physical file. (1985 mode)
39, 60 through 39, 6E	The number of segments for keys 0 through 14 does not match the corresponding key number of segments of the physical file. The prime record key is 0. Alternate record keys are numbered in ascending order of key offset, starting with 1. (1985 mode)
39, 6F	The number of segments for an alternate key 15 through 254 does not match the corresponding key number of segments of the physical file. (1985 mode)
41, 01	A duplicate open was rejected by a system that does not allow the physical file to be opened twice. (1985 mode)
41, 02	A duplicate open was rejected by a system that does not allow the COBOL filename to be opened twice. (1985 mode)
41, 03	A DELETE FILE was rejected because the file was open. (1985 mode)
42	A CLOSE or UNLOCK operation was attempted on an unopened file. (1985 mode)
43	A DELETE or REWRITE operation was attempted on a file declared to be ACCESS MODE SEQUENTIAL or on an indexed file declared to be ACCESS MODE DYNAMIC that specifies a prime key that allows duplicate values, and the last operation on the file was not a successful READ operation. (1985 mode)
44, 03	The length of the record area specified in the WRITE, REWRITE or RELEASE statement is less than the minimum record length of the file. (1985 mode)
44, 04	The length of the record area specified in the WRITE, REWRITE or RELEASE statement is greater than the maximum record length of the file. (1985 mode)
44, 07	A REWRITE statement attempted to change the length of a record in a sequential organization file. (1985 mode)

Number	Description
46	No file position is currently defined. A sequential READ operation was attempted, but the last READ or START operation was unsuccessful or returned an at end condition. (1985 mode)
46, 02	The position was lost. (1985 mode) For Btrieve files, A READ NEXT operation was attempted and could not be completed because the Btrieve MicroKernel Database Engine (MKDE) position was lost due to the current record (and surrounding records) being deleted by programs at other computers. See the "Current Record Position Limitations" section in Chapter 4, *System Considerations for Btrieve*.
47, 01	The requested operation conflicts with the open mode of the file. A START or READ operation was attempted on a file that is not open in the INPUT or I-O mode. (1985 mode)
47, 02	A READ or START operation was attempted on an unopened file. (1985 mode)
48, 01	The requested operation conflicts with the open mode of the file. This error can occur under the following conditions: a WRITE operation was attempted on a file that is not open in the EXTEND, I-O, or OUTPUT mode; or, a WRITE operation was attempted on a file in the sequential access mode that is open in the I-O mode. (1985 mode)
48, 02	A WRITE operation was attempted on an unopened file. (1985 mode)
49, 01	The requested operation conflicts with the open mode of the file. A DELETE or REWRITE operation was attempted on a file that is not open in the I-O mode. (1985 mode)
49, 02	A DELETE or REWRITE operation was attempted on an unopened file. (1985 mode)
90	An unrecognizable message has been received by the RM/COBOL-to-Btrieve Adapter program from the RM/COBOL file management system. This error also indicates that an invalid request has been made to the RM/COBOL file management system or some other external access method. This may be caused by an internal error or when communicating to an earlier version of RM/InfoExpress.

Number	Description
90, 01	The requested operation conflicts with the open mode of the file. This error can occur under the following conditions: a READ or START operation was attempted on a file that is not open in the INPUT or I-O mode; a WRITE operation was attempted on a file that is not open in the EXTEND, I-O, or OUTPUT mode or a WRITE operation was attempted on a file in the sequential access mode that is open in the I-O mode; or, a DELETE or REWRITE operation was attempted on a file that is not open in the I-O mode. (1974 mode)
90, 02	A DELETE or REWRITE operation was attempted on a file declared to be ACCESS MODE SEQUENTIAL, and the last operation on the file was not a successful READ operation. (1974 mode)
90, 03	The requested operation conflicts with the media type. This error can occur under the following conditions: a READ or OPEN INPUT operation was attempted on a file with a device-name of OUTPUT, PRINT or PRINTER; a WRITE, OPEN OUTPUT or EXTEND operation was attempted on a file with a device-name of CARD-READER or INPUT; or a DELETE, REWRITE, START or OPEN I-O operation was attempted on a file with a device-name other than DISC, DISK or RANDOM.
90, 04	The requested operation conflicts with the defined organization. A DELETE or START operation was attempted on an ORGANIZATION SEQUENTIAL file.
90, 05	A file truncate operation conflicts with other users. An OPEN OUTPUT operation was attempted on a physical file that is currently in an open mode for another file connector of this run unit or a file connector of another run unit that shares the file. On Btrieve files, Error 90, 05 also indicates that an I/O error occurred on the creation of the file. (If the file already existed and the Btrieve MicroKernel Database Engine (MKDE) returned a Create I/O Error, 25, then the RM/COBOL-to-Btrieve Adapter program will misinterpret the error as truncation conflict because the Btrieve MKDE uses this error for both conditions.)

Number	Description
90, 06	The file access name specified in the OPEN statement indicates that the file is accessed through an alternative access method and the alternative access method refused to accept the request by the RM/COBOL file management system to establish a session. This error also indicates that the RM/COBOL file management system refused one of the configuration parameters passed to it. The runtime system validates all the configuration parameters of the RM/COBOL file management system; however, if there is insufficient memory to create a buffer pool of the requested size, this will not be detected until later. Reducing the size of the buffer pool may resolve the problem.
90, 07	The requested operation conflicts with the permissions allowed to the run unit for the file. This error can occur under the following conditions: a DELETE FILE statement failed because the run unit did not have write permission for the directory containing the file; an OPEN statement with the OUTPUT or EXTEND phrase failed because the run unit does not have write permission for the file; or, an OPEN statement with the INPUT or I-O phrase failed because the run unit does not have read permission for the file. (1974 mode) For Btrieve files, this error code may also indicate that a DELETE, WRITE, or REWRITE operation was performed on a file that has been opened for read-only access using an RM/COBOL-to-Btrieve Adapter program mode option of M=R (read-only). See page 4-14 for more information about this option. (1974 and 1985 mode)
90, 08	The requested operation is not supported by the alternative access method. A COBOL I/O statement was attempted to a non-RM/COBOL file and the access method for the file does not support the statement.
91	A CLOSE or UNLOCK operation was attempted on an unopened file. (1974 mode)
91, 02	A READ, START, WRITE, DELETE or REWRITE operation was attempted on an unopened file. (1974 mode)
92, 01	A duplicate open was rejected by a system that does not allow the physical file to be opened twice. (1974 mode)
92, 02	A duplicate open was rejected by a system that does not allow the COBOL filename to be opened twice. (1974 mode)

Number	Description
92, 03	A DELETE FILE was rejected because the file was in an open mode. (1974 mode)
93, 02	An operation was rejected because file lock conflicts with another user. An OPEN WITH LOCK was attempted on a file that is already open, or an OPEN without lock was attempted and the file is already open WITH LOCK. A DELETE FILE was attempted on a file that is currently open. This message may occur in cases with Btrieve files when it would not occur with RM/COBOL indexed files, because the Btrieve MicroKernel Database Engine (MKDE) always opens its files WITH LOCK. See error messages 39, 01 and 94, 01 for more information. For Btrieve files, this error code may also indicate either of the following conditions: • Another computer has a transaction in progress on this file. • Or, an attempt was made to open a file that another computer had opened already with a conflicting RM/COBOL-to-Btrieve Adapter program mode option (see page 4-14 for more information about the mode option). For example, if the first computer opens a file with a value of A (accelerated) for the mode option, then the accelerated mode option must be specified by all other computers that subsequently open the file. Conversely, if the first computer opens a file and does not specify the accelerated mode option, then no other computers that subsequently open the file can specify the accelerated mode option either. These restrictions remain in effect until all computers have closed the file.
93, 03	An OPEN or DELETE FILE operation failed because the filename was previously closed WITH LOCK. (1974 mode)
93, 04	The file could not be opened because another file in the same SAME AREA clause is currently open.
93, 05	The file could not be opened because another file in the same MULTIPLE FILE TAPE clause is already open.
93, 06	The file could not be created because a file with the same name already exists.

Number	Description
93, 07	The file could not be opened because a lock table for the requested open mode was full. See the FILE-PROCESS-COUNT keyword of the RUN-FILES-ATTR configuration record on page 10-28 for more information.
94, 01	The file organization specified for the filename does not match the actual file organization of the physical file. (1974 mode) This message may not occur if the file is actually a Btrieve file. The Btrieve MicroKernel Database Engine always opens its files WITH LOCK, and the OPEN WITH LOCK error condition will be encountered by the RM/COBOL file management system, preventing it from determining the organization of the file.
94, 02	The minimum record length specified in the RECORD CONTAINS clause or implied by the record descriptions of the filename does not match the actual minimum record length of the physical file. (1974 mode) For Btrieve files, if the minimum record length of the file is less than four bytes, the file will be implemented using four-byte records. In this situation, the RM/COBOL-to-Btrieve Adapter program cannot detect the initial minimum record length and will fail to diagnose the mismatched minimum record length error condition.
94, 03	The maximum record length specified in the RECORD CONTAINS clause or implied by the record descriptions of the filename does not match the actual maximum record length of the physical file. (1974 mode) This error can occur when reopening a print file closed WITH NO REWIND if the OPEN statement specifies a different record length than was used on the previous OPEN statement. This error will not occur with variable-length record Btrieve files. Btrieve files do not support a mechanism to record this information and, thus, it cannot be verified.
94, 04	The minimum block length specified in the BLOCK CONTAINS clause for the filename does not match the actual minimum block size of the physical file. (1974 mode)

Number	Description
94, 05	The maximum block length specified in the BLOCK CONTAINS clause for the filename does not match the actual maximum block size of the physical file. (1974 mode) This error will not occur with variable-length record Btrieve files. Btrieve files do not support a mechanism to record this information and, thus, it cannot be verified.
94, 06	The record delimiting technique, LINE-SEQUENTIAL or BINARY-SEQUENTIAL, specified for the filename does not match the actual record delimiting technique of the physical file. (1974 mode)
94, 07	The CODE-SET specified for the filename does not match the actual character code of the physical file. (1974 mode)
94, 08	The COLLATING SEQUENCE specified for the indexed file does not match the actual collating sequence of the physical file. (1974 mode)
94, 09	The record type attribute, fixed or variable, specified in the RECORD CONTAINS clause or implied by the record descriptions of the filename does not match the record type attribute of the physical file. (1974 mode)
94, 20	The file is not available because the file identified by the resultant file access name could not be found. The pathname or filename may be misspelled or may not be valid for the operating system. Specifying a pathname or filename that is not a valid name or that is longer than allowed also results in this error. The directory search sequence specified by RUNPATH may be incorrect. See the "Locating RM/COBOL Files" sections either on pages 2-3 through 2-7 for UNIX or pages 3-10 through 3-15 for Windows for information on the resultant file access name. (1974 mode)
94, 21	The file organization specified is invalid or unsupported, or the requested open operation is illegal on the specified organization.
94, 22	The minimum record length is invalid. The minimum record length specified in the RECORD CONTAINS clause for the filename exceeds the maximum record length.
94, 23	The maximum record length is invalid. The maximum record length specified in the RECORD CONTAINS clause of the filename exceeds 65280, or the indexed records are not compressed and the maximum record length exceeds the block size.

Number	Description
94, 24	The minimum block size is invalid. The minimum block size specified in the BLOCK CONTAINS clause of the filename exceeds the maximum block size.
94, 25	The maximum block size is invalid. The maximum block size specified in the BLOCK CONTAINS clause of the filename is too large. The method of computing the block size and the limitations on the block size for each organization are described on pages 8-41 (sequential files), 8-47 (relative files), and 8-50 (indexed files). For indexed organization files, the computed block size is also a function of the maximum record size. In general, if the BLOCK CONTAINS clause is omitted, the runtime system defaults to the valid block size that is a multiple of the disk sector size. For files with a very large record size, specifying BLOCK CONTAINS 1 RECORDS yields the minimum possible block size.
94, 26	The record delimiter is invalid. A record delimiting technique other than LINE-SEQUENTIAL or BINARY-SEQUENTIAL was specified.
94, 27	The CODE-SET specified is invalid or unsupported.
94, 28	The COLLATING SEQUENCE specified for an indexed file is invalid or unsupported.
94, 29	The record type attribute, fixed or variable, specified for the filename is unsupported.
94, 30 through 94, 3E	The key duplicates allowed flag specified for keys 0 through 14 is invalid (1974 and 1985 modes) or does not match the corresponding key duplicates allowed flag of the physical file (1974 mode). The prime record key is 0. Alternate record keys are numbered in ascending order of key offset, starting with 1. For Btrieve files, this error also indicates a key attribute other than duplicate, modifiable, binary, null, alternate collating sequence, or extended type was specified for the Btrieve key that corresponds with the COBOL key defined for the key offset. (For example, descending, supplemental, and manual key attributes may not be used for RM/COBOL keys.) In addition, the primary key may not have a null attribute. Btrieve allows multiple keys to be defined at the same key offset, but only the first key is considered by the RM/COBOL-to-Btrieve Adapter program.

Number	Description
94, 3F	The key duplicates allowed flag specified for an alternate record key 15 through 254 is invalid (1974 and 1985 modes) or does not match the corresponding key duplicates allowed flag of the physical file. (1974 mode) For Btrieve files, this error also indicates that in the physical file, a key attribute other than duplicate, modifiable, binary, null, alternate collating sequence or extended type was specified for the Btrieve key that corresponds with the COBOL key defined for the key offset. (For example, descending, supplemental and manual key attributes may not be used for RM/COBOL keys.) Btrieve allows multiple keys to be defined at the same key offset, but only the first key is considered by the RM/COBOL-to-Btrieve Adapter program.
94, 40 through 94, 4E	The offset from the start of the record area to the start of the key area for keys 0 through 14 is invalid (1974 and 1985 modes) or does not match the corresponding key offset of the physical file (1974 mode). The prime record key is 0. Alternate record keys are numbered in ascending order of key offset, starting with 1. Error 94, 40 also occurs if more than 254 alternate record keys are specified. For Btrieve files, this error also indicates that the key extends into the variable portion of a Btrieve file record.
94, 4F	The offset from the start of the record area to the start of the key area for an alternate key 15 through 254 is invalid (1974 and 1985 modes) or does not match the corresponding key offset of the physical file. (1974 mode) For Btrieve files, this error also indicates that the key extends into the variable portion of a Btrieve file record.

Number	Description
94, 50 through 94, 5E	The length of the key area for keys 0 through 14 is invalid (1974 and 1985 modes) or does not match the corresponding key length of the physical file (1974 mode). The prime record key is key 0. Alternate record keys are numbered in ascending order of key offset, starting with 1. This error also occurs if the number of specified keys does not match the actual number of keys in the physical file. The key number 1 through E, if greater than the number of keys in the file description, indicates that the file contains more keys than the program describes. The key number 1 through E, if less than or equal to the number of keys in the file description, provides a value one greater than the number of keys contained in the file. (1974 mode) A Btrieve file is allowed to have more keys defined in it than in the COBOL description of the file, but not less.
94, 5F	The length of the key area for an alternate key 15 through 254 is invalid (1974 and 1985 modes) or does not match the corresponding key offset of the physical file. (1974 mode) This error also occurs if the number of keys specified does not match the actual number of keys in the physical file (see error messages 94, 50 through 94, 5E). (1974 mode)
94, 60	There is insufficient memory to open file. The amount of memory required to open a file can be reduced by specifying a smaller maximum block size in the BLOCK CONTAINS clause. Additional memory can be made available by decreasing the amount of buffer pool memory through the use of the BUFFER-POOL-SIZE keyword on the RUN-FILES-ATTR configuration record (see page 10-26).
94, 61	There is insufficient disk space to create a file.
94, 62	The LINAGE parameters are invalid for an OPEN statement. One or more LINAGE parameters are negative or greater than 32767, LINAGE equals zero, FOOTING equals zero, or FOOTING is greater than LINAGE.
94, 63	An OPEN WITH LOCK was attempted on a system that does not support WITH LOCK.
94, 64	The filename specified is invalid. This error can occur if the filename is set to spaces.

Number	Description
94, 65	An OPEN was attempted on the controlling console device.
94, 66	There are no more file handles available. An OPEN was rejected because an operating system limit on the number of files was reached.
94, 67	The file is too large. An attempt was made to open a file that is too large for this system. The file was probably created on another system using the LARGE-FILE-LOCK-LIMIT configuration keyword or is a version 3 indexed file, or an attempt was made to use a LARGE-FILE-LOCK-LIMIT value on a system that does not support files larger than 2 GB. See the description of the LARGE-FILE-LOCK-LIMIT keyword in the RUN-FILES-ATTR record on page 10-28, or the description of File Version Level 3 files on page 8-65 for more information.
94, 68	An attempt was made to open an indexed file that has a future file version number. The indexed file may have been created by a later version of RM/COBOL or the indexed file may be corrupt.
94, 69	The specified large file lock limit is too large for either the operating system on which the runtime is running, or the file system on which the file would reside. For example, Windows 98 does not support a large file lock limit greater than four gigabytes (4 GB).
95, 01	The file must be mass storage. The device-name specified for the file was DISC, DISK or RANDOM, but the resultant file access name identifies a file that does not reside on disk. (1974 mode)
96	No file position is currently defined. A sequential READ operation was attempted, but the last READ or START operation was unsuccessful or returned an at end condition. (1974 mode)
96, 02	The position was lost. (1974 mode) For Btrieve files, A READ NEXT operation was attempted and could not be completed because the Btrieve MicroKernel Database Engine (MKDE) position was lost due to the current record (and surrounding records) being deleted by programs at other computers. See the "Current Record Position Limitations" section in Chapter 4, *System Considerations for Btrieve*.
97, 01	One or more characters in the record are illegal in a line sequential file.
97, 02	One or more characters could not be translated from the native character set to the external code-set.

Number	Description
97, 03	The length of the record area specified in the WRITE, REWRITE or RELEASE statement is less than the minimum record length of the file. (1974 mode)
97, 04	The length of the record area specified in the WRITE, REWRITE or RELEASE statement is greater than the maximum record length of the file. (1974 mode)
97, 05	The record read from the file is shorter than the minimum record length.
97, 06	The record read from the file is longer than the record area.
97, 07	A REWRITE statement attempted to change the length of a record in a sequential organization file. (1974 mode)
97, 08	The LINAGE parameters are invalid for a WRITE statement. One or more LINAGE parameters are negative or greater than 32767, LINAGE equals zero, FOOTING equals zero, or FOOTING is greater than LINAGE.
97, 09	The TO LINE value is outside the page body.
98, 01	The indexed file structure includes a count of the number of times the file is currently open for modification. The count should be zero whenever a file in a single-user environment is opened or a file in a shared environment is opened WITH LOCK. If the count is non-zero when the file is opened WITH LOCK, a 98, 01 error is returned. The conditions that determine whether the runtime system assumes a single-user or shared environment are described in the "File Types and Structure" section (see page 8-40) and in the explanation of the FORCE-USER-MODE keyword of the RUN-FILES-ATTR configuration record (see page 10-28). The count is incremented when a program opens the file I-O, OUTPUT, or EXTEND and decremented when the program closes the file. If the count is non-zero when the file is opened in a single-user environment or opened WITH LOCK in a shared environment, then the system must have terminated without closing the file. This error can also appear when a file with a non-zero count is moved from a shared environment to a single-user environment. The indexed file will be inconsistent if all the modifications to it were not written to disk. Use the Indexed File Recovery utility (**recover1**) to rebuild or recover disk information (see page G-23).

Number	Description
98, 01 *(Cont.)*	You can reduce the likelihood of encountering this error by changing the Indexed File Recovery utility strategy to "Force File Closed" (see page 8-51). This causes the count to be changed around every write operation instead of during open and close. Use the Define Indexed File utility (**rmdefinx**) to change the recovery strategy of an existing indexed file (see page G-19).
98, 02	A fatal error occurred during a DELETE, REWRITE, or WRITE statement when the file was last open. The index structure is inconsistent and must be rebuilt. Use the Indexed File Recovery utility (**recover1)** to rebuild or recover disk information (see page G-23).
98, *nn*	Invalid file structure. The *nn* subcode may be useful in determining which runtime system procedure detected the error. For an indexed organization file, there appears to be an inconsistency in the file structure. If the error occurs when the file is being read, it may be a disk read error which goes away when the operation is retried. If the error occurs during a DELETE, REWRITE, or WRITE statement, a later OPEN statement will probably receive a 98, 02 error. It may be possible to correct the file structure inconsistency by rebuilding the index structure. Use the Indexed File Recovery utility (**recover1**) to rebuild or recover disk information (see page G-23). For a sequential or relative organization file, this error usually indicates the file description does not match the organization of the file, record type, record delimiting technique or record length. It may also indicate that the file data was not written or read correctly.
99	A DELETE, READ, or REWRITE statement failed because the record is locked by another user.

Table A-1 Btrieve Status Codes and Messages[1]

Code	Message	Code	Message
1	Invalid operation	19	Unrecoverable error
2	I/O error	20	Record manager inactive
3	File not open	21	Key buffer too short
4	Key value not found	22	Data buffer length
5	Duplicate key value	23	Position block length
6	Invalid key number	24	Page size error
7	Different key number	25	Create I/O error
8	Invalid positioning	26	Number of keys
9	End-of-file	27	Invalid key position
10	Modifiable key value error	28	Invalid record length
11	Invalid filename	29	Invalid key length
12	File not found	30	Not a Btrieve file
13	Extended file error	31	File already extended
14	Pre-image open error	32	Extend I/O error
15	Pre-image I/O error	34	Invalid extension name
16	Expansion error	35	Directory error
17	Close error	36	Transaction error
18	Disk full	37	Transaction is active

[1] *This list of Btrieve status codes and messages is provided for convenience only, and is not intended to supply complete information. For a full list of codes and messages with descriptions, refer to the* Btrieve for Windows NT/Windows 95 Installation and Operation *manual, the* Btrieve for NetWare Installation and Operation *manual, or the* Btrieve for Windows NT Server Edition Installation and Operation *manual.*

Table A-1 Btrieve Status Codes and Messages[1] *(Cont.)*

Code	Message	Code	Message
38	Transaction control I/O error	64	Filter limit reached
39	End/abort transaction error	65	Incorrect field offset
40	Transaction max files	74	Transaction rolled back
41	Operation not allowed	75	Server routing list too small
42	Incomplete accelerated access	76	File server list too small
43	Invalid record address	77	VAP wait error
44	Null key path	78	Deadlock detected
45	Inconsistent key flags	79	Programming error
46	Access to file denied	80	Conflict
47	Maximum open files	81	Lock error
48	Invalid alternate sequence definition	82	Lost position
49	Key type error	83	Read outside transaction
50	Owner already set	84	Record in use
51	Invalid owner	85	File in use
52	Error writing cache	86	File table full
53	Invalid interface	87	Handle table full
54	Variable page error	88	Incompatible mode error
55	Auto-increment error	90	Redirected device table full
56	Incomplete index	91	Server error
57	Expanded memory error	92	Transaction table full
58	Compression buffer too short (see page A-14 for resolution suggestion)	93	Incompatible lock type
59	File already exists	94	Permission error
60	Reject count reached	95	Session no longer valid
61	Work space too small	96	Communications environment error
62	Incorrect descriptor	97	Data message too small (see page A-15 for resolution suggestion)
63	Invalid extended insert buffer	98	Internal transaction error

Table A-1 Btrieve Status Codes and Messages[1] *(Cont.)*

Code	Message	Code	Message
99	Requester cannot access NetWare Runtime server	1008	Initialization parameter invalid
100	No cache buffers	1009	Transaction filename parameter invalid
101	Insufficient OS memory	1010	Transaction control file error
102	Insufficient stack space	1011	Compression buffer parameter invalid
103	Chunk offset too big	1012	Invalid /n option (pre-v6.0)
104	Unknown locale	1013	Task list full
105	Cannot create VAT file	1014	Stop warning. Files still active
106	Cannot get next chunk	1015	Pointer parameter invalid
107	Chunk operation on pre-v6.0 file	1016	MKDE already initialized
109	Unknown error creating or accessing semaphore	1017	Requester cannot locate wbtrvres.dll
130	MKDE out of system locks	1018	MKDE called from callback
132	File full	1019	Operation canceled by callback
133	More than 5 concurrent engines accessing same file	1020	Requester communications error
1001	Lock parameter is invalid	2001	Memory allocation insufficient
1002	Memory allocation error	2002	Requester option invalid
1003	Invalid memory size parameter	2003	Requester cannot access local file
1004	Page size error	2004	SPX not installed
1005	Preimage drive parameter invalid	2005	Incorrect SPX version
1006	Preimage buffer parameter invalid	2006	No available SPX connection
1007	Files parameter invalid	2007	Pointer parameter invalid

Table A-2 Runtime System Library Error Codes[1]

Code	Message	Code	Message
1	No such file or directory	21	I/O error
2	Arg list too big	22	Is a directory
3	Exec format error	23	Not a directory
4	Bad file number	24	Too many links
5	Not enough memory	25	Block device required
6	Permission denied	26	Not a character device
7	File exists	27	No such device or address
8	Cross-device link	28	Not owner
9	Invalid argument	29	Broken pipe
10	File table overflow	30	Read-only file system
11	Too many open files	31	Illegal seek
12	No space left on device	32	No such process
13	Argument too large	33	Text file busy
14	Result too large	34	Bad address
15	Resource deadlock would occur	35	Name too long
16	Interrupt	36	No such device
17	Child does not exist	37	No locks available in system
18	Resource unavailable, try again	38	Unknown system call
19	Device or resource busy	39	Directory not empty
20	File too large		

[1] *This list of runtime system library error codes and meanings is provided for convenience only, and is not intended to supply complete information.*

Table A-3 File Manager Detected Error Codes

Code	Message
1	Memory management failure
2	Operator requested termination
3	Locks lost

Internal Errors

In general, internal errors are caused when the object file has been corrupted. If the corruption was caused by an undetected data error reading the object file from disk or over a network, the failure should disappear or change when the program is run again. If the object file on disk is corrupted, compiling the program to generate correct object should fix the problem.

Sort-Merge Errors

Sort-merge errors include errors processing a SORT or MERGE statement.

Number	Description
301	There was insufficient memory available to initiate a sort or merge process. The default or specified sort memory size was insufficient to hold ten records of the record length to be sorted, or the specified sort memory size is not available. Use the T Runtime Command Option to increase the memory requested by the SORT statement.
302	Fewer than three intermediate files were available to begin a SORT statement. The sort procedure cannot begin unless it is able to create at least three intermediate files.
303	A record read from a MERGE file or SORT USING file was not long enough to include all the keys.
304	Too many out of sequence records were passed to the sort process. Use the T Runtime Command Option to increase the memory available to sort. Or, divide the records to be sorted into several files, sort the several files, and merge the resulting files.
305	A SORT or MERGE statement was attempted while a sort or merge process was already active.
306	A RELEASE or RETURN statement was attempted and no sort or merge was active.
307	A RELEASE or RETURN statement was attempted for a sort or merge description other than the one currently being sorted or merged.

Number	Description
308	A RELEASE statement was attempted in an OUTPUT PROCEDURE, or a RETURN statement was attempted in an INPUT PROCEDURE.
309	A RETURN statement was attempted in an OUTPUT PROCEDURE after the at end condition was returned on the sort or merge file.
310	An application I/O statement was attempted on a file currently opened as a sort or merge USING or GIVING file.

Message Control Errors

Message control errors include errors that occur when using the Message Control System (MCS).

Number	Description
351	An ENABLE, DISABLE, SEND, RECEIVE or ACCEPT . . . FROM MESSAGE COUNT statement was encountered and no MCS was present.

Configuration Errors

Configuration errors include all errors that occur because of an error in the configuration. The formats are as follows:

```
COBOL configuration error code at record
      number in location.
```

```
COBOL configuration error code.  Error
      processing configuration.
```

code is the error number listed below.

number identifies the logical record in the configuration file (location) at which the error was found. Each logical record is identified with a configuration record type. In other words, when you are using the record number provided in the message to determine the erroneous record, count the lines combined with their corresponding continuation lines as one line, and do not count the comment lines and blank lines.

location identifies the configuration file containing the error. The possible values are as follows:

1. Overriding configuration file
2. Supplemental configuration file

These two locations correspond to the C Runtime Command Option (G Compile Command Option) and the X Runtime Command Option (H Compile Command Option), respectively (described on page 7-3).

The first format is used if an error is detected during the processing of a configuration record. The error message will be followed by a line containing the portion of the record being processed when the error occurred and another line placing a currency symbol underneath the item being processed when the error occurred.

The second format is used if an error is detected after all configuration records have been processed or if an error is detected with which a record is not associated.

Number	Description
401	A character has been defined as a data character in a TERM-ATTR record as well as the beginning character of an input sequence in a TERM-INPUT record.
402	An invalid delimiter was found.
403	The input sequence in the current TERM-INPUT record has been defined in a previous TERM-INPUT record.
404	A keyword has not been provided where expected or the keyword is invalid.
405	The resulting terminal input configuration table (used by the runtime system during ACCEPT statements) is too large or out of memory.
406	An attempt has been made to redefine the terminal interface.
407	Syntax error.
408	An attempt has been made to describe a terminal characteristic and either a terminal interface has not been defined, or the terminal characteristic is not valid with the defined terminal interface.
409	A value has not been provided where expected or the value is invalid.

Number	Description
410	The configuration file requested in the Runtime Command was not found.
411	A logical configuration record exceeds the maximum length.

Runcobol Initialization Messages

During its initialization, the runtime system may issue several messages, some of which are error diagnostics and some of which are informational.

Initialization Errors

If the runtime system receives an error from the operating system during initialization, the following message appears:

```
RM/COBOL: Operating System Initialization Error. OS Error
Code: code
```

code depends on the operating system on which the file resides. See the description of the 30, OS error *code* on page A-14 for more information.

Message File Processing Errors

During initialization, the runtime system locates and reads its message file. If it cannot find its message file or the message file is corrupt, one of the following messages appears:

```
Unable to find the system message file
Unable to format the system message file
Unable to read the system message file
```

The runtime system compares its version number and product code with those in the message file. If they do not match, one or both of the following messages appears:

```
RM/COBOL:  Message file version mismatch, expected 7.0n.nn, found n.nn.nn
RM/COBOL:  Message file product mismatch, expected XX, found YY
```

When any of the above messages appear, the runtime system terminates with the following message:

```
Error invoking mismatched runtime and message file.
```

The runtime system message file may have the wrong name or be in the wrong directory. The runtime system message file must have the name **run.msg** (**RUN.MSG** under UNIX). The runtime system attempts to find the message file in the directory that contains the **runcobol** executable file, the current directory, or through the PATH directory search sequence (see page 2-4 for UNIX or page 3-11 for Windows).

Note On some UNIX environments, it is impossible to determine which directory contains the executable file when that directory is specified on the command line.

When the runtime system detects that the message file version does not match its own version, the following message appears:

```
RM/COBOL: Message file version mismatch.
```

The occurrence of this message does not prevent the runtime system from continuing, but the messages that it generates may be not correct.

Option Processing Errors

If the runtime system detects an unknown option letter, a known option letter in error or an option not terminated with a space or comma, the following message appears:

letter option not valid.

letter is the erroneous option letter.

Further processing is done for libraries (as specified by the L Runtime Command Option) during which control structures are built for use later in the run unit. If errors are encountered during this processing, the following message appears:

COBOL procedure error *code*. Error processing library.

code is the first two digits of the error numbers listed in this appendix.

Main Program Loading Errors

If errors are encountered during the load and initialization of the main program, the following message appears:

COBOL procedure error *code*. Error loading main program.

code is the first two digits of the error numbers listed in this appendix.

Runcobol Banner Message

The banner message appears when you first invoke RM/COBOL. This message may be suppressed with the K Runtime Command Option:

```
RM/COBOL Runtime - Version 7.0n.nn for operating system.
Copyright(c) 1985, 1986-1999 by Liant Software Corp. All rights reserved.
Registration Number:  xx-nnnn-nnnnn-nnnn
```

Runcobol Usage Message

The following message appears in response to entering a Runtime Command without parameters:

```
Usage:   runcobol name [options]
Options: [A=arguments] [B=buffersize] [C=configfile] [D] [I] [K]
         [L=libname] [M] [S=switches] [T=sortsize] [X=configmod]
```

Registration Error Messages

Attempting to execute more runtime systems than are authorized causes the following message to appear:

```
Error invoking unauthorized copy of runtime.
```

Note Registration checking on Novell is sometimes performed using server facilities and will be enforced until the runtime product terminates, or the server is aware that the client station is no longer connected to the network. If a runtime system is not properly terminated due to the powering off of the client machine or rebooting it, the server will not be aware of the absence of the client until the client starts the network shell again.

COBOL Normal Termination Messages

When the runtime system encounters a STOP RUN statement or a GOBACK statement in the main program of a run unit, the following message appears:

```
COBOL STOP RUN at line number in prog-id
```

This message may be suppressed with the K Runtime Command Option.

When the runtime system encounters a STOP literal or STOP data item statement, the following message appears:

```
"literal or data item" at line number in prog-id
 Continue (Y/N)?
```

If you enter Y or y, execution continues with the next executable statement. If you enter N or n, execution ends as if a STOP RUN statement was encountered.

Appendix B: Limits and Ranges

This appendix describes RM/COBOL limits and ranges.

Note See also Chapter 4, *System Considerations for Btrieve*, for a description of the limitations of the Btrieve MicroKernel Database Engine (MKDE), and the way in which these limitations affect RM/COBOL indexed files. Although these two systems perform the same functions, they do not operate in the same manner.

RM/COBOL Limits and Ranges

No more than 98133 unique user-defined words (alphabet-names, cd-names, class-names, condition-names, data-names, file-names, index-names, key-names, mnemonic-names, paragraph-names, section-names, and symbolic-characters), where each name is 30 characters in length, may be defined in a single source program. When names average less than 30 characters in length, more unique user-defined words are allowed. For example, names averaging 12 characters in length doubles the limit to 196,266 unique user-defined words. The COBOL user-defined word categories level-number, library-name, program-name, segment-number and text-name do not count towards this limit.

No more than 65534 identifiers may be defined in a single source program, including any of its nested source programs. Only 65533 identifiers may be defined in the Data Division (see below for information about compiler generated identifiers that occur in the Procedure Division). Note that the compiler implicitly defines identifier entries, reducing the number that can be explicitly defined, as follows:

- one for each LINAGE-COUNTER associated with any files described with the LINAGE clause;
- one for each variable length record file that has multiple record descriptions and no record description is a group having the maximum record length;
- one for each indexed file with a CODE-SET or COLLATING-SEQUENCE that requires that an external collating sequence be provided, that is, when the specified or implicit code-set for the file requires a mapping other than identity to obtain the specified or implicit collating sequence used for record keys of the file;
- one for each RERUN clause;
- one for a RETURN-CODE special register item if the program contains an explicit reference to RETURN-CODE or contains a STOP RUN identifier/integer statement;

- one for each temporary index needed for any INITIALIZE, INSPECT, MOVE, STRING or UNSTRING statements that reference one or more subscripted data items (the compiler reuses these for each statement, thus defining only the maximum needed for any one such statement); and
- five for control information if one or more simple (COBOL nucleus level 1) INSPECT statements are contained in the source program. The maximum length of an elementary data item is 65280 characters.

The maximum length of an element of a table is 65280 characters (that is, data items subordinate to an OCCURS clause cannot exceed 65280 characters in length).

The maximum number of occurrences of a table element is 65535. That is, in an OCCURS clause, the value of *integer-2* must be less than or equal to 65535.

Data items greater than 65280 characters in length may be referenced in a MOVE statement or the USING phrase of a CALL statement, but may not be referred to in any other context.

Data items greater than 65280 characters in length may not be reference modified.

The maximum guaranteed precision for mathematical calculations is 36 decimal digits. This limit applies to all mathematical operations except exponentiation where the maximum guaranteed precision is 18 decimal digits.

A record key of an indexed file may not exceed 254 characters in length.

A maximum of 255 keys may be declared for an indexed file (one prime key and up to 254 alternate keys).

A record of a file may not exceed 65280 characters in length.

A single paragraph cannot exceed 32512 bytes of generated object code.

The maximum number of USING items in a CALL statement or a Procedure Division header is 255.

The maximum length of literals generated for any one segment type within a program may not exceed 65535 bytes. Segment type refers to fixed permanent, fixed overlayable and independent. Segmentation can greatly increase the number of literals a program may have, since literals are overlaid for each segment.

The maximum number of external items in a single, separately compiled program—including any of its contained programs—is limited to 2046.

Note Refer to Table 6-1 (beginning on page 6-36) for additional compilation limits.

Appendix C: Internal Data Formats

This appendix describes and illustrates the internal representations of the data types.

Internal Data Formats

The particular format in which the RM/COBOL compiler stores data is determined by the specification of any of the following clauses in the data description entry for the data item:

1. **PICTURE clause.** This clause classifies a data item as signed or unsigned numeric or as nonnumeric.
2. **USAGE clause.** This clause modifies the format of a numeric data item. All nonnumeric data items are always considered to be DISPLAY usage.
3. **SIGN clause.** This clause determines the format and the position (separate leading, combined leading, separate trailing or combined trailing) of the operational sign for signed numeric DISPLAY data items. The SIGN clause cannot be used for any other type of data item.

The following formats are described:

- Nonnumeric data: Alphanumeric Edited, Alphabetic Edited, Alphabetic, and Numeric Edited
- Numeric data:
  - Unsigned numeric DISPLAY (NSU)
  - Signed numeric DISPLAY (TRAILING SEPARATE sign)
  - Signed numeric DISPLAY (LEADING SEPARATE sign)
  - Signed numeric DISPLAY (TRAILING sign)
  - Signed numeric DISPLAY (LEADING sign)
  - Unsigned numeric COMPUTATIONAL
  - Signed numeric COMPUTATIONAL
  - Signed numeric COMPUTATIONAL-1
  - Unsigned numeric COMPUTATIONAL-3 (PACKED-DECIMAL)
  - Signed numeric COMPUTATIONAL-3 (PACKED-DECIMAL)
  - Unsigned numeric COMPUTATIONAL-4 (BINARY)
  - Signed numeric COMPUTATIONAL-4 (BINARY)
  - Unsigned numeric COMPUTATIONAL-6

Illustrations are presented as follows:

```
01 EXAMPLE        PIC S9(3)V9(2)  VALUE +514.72
                  DISPLAY SIGN LEADING SEPARATE.
```



The line of source code shows the RM/COBOL statement itself. The values inside the box show the hexadecimal data values in bytes, as stored in memory. The numbers above the box show the hexadecimal relative byte address.

The ASCII code-set is used to represent all data items whose usage is DISPLAY.

Nonnumeric Data

Nonnumeric data items are formatted one character per byte. The leftmost character starts at the lowest address. Edited nonnumeric data items have an associated editing PICTURE character-string that is used only when the data item is a receiving operand. Nonnumeric data items always have DISPLAY usage.

The SIGN clause does not apply to nonnumeric data items. The BLANK WHEN ZERO clause—when associated with a numeric PICTURE character-string—causes the data item to be treated as numeric edited.

Table C-1 lists the types of nonnumeric data, the compiler designation for each type, and the valid picture symbols for each type.

Table C-1 Nonnumeric Data

Data Type	Compiler Designation	Picture Symbols
Alphanumeric	ANS	A X 9
Alphanumeric Edited	ANSE	A B X 0 9 /
Alphabetic	ABS	A
Alphabetic Edited	ABSE	A B
Numeric Edited	NSE	B P V Z 0 9 / , . $ + – * CR DB

When the CURRENCY SIGN clause is specified in the SPECIAL-NAMES paragraph, the character specified in that clause is also a permissible picture symbol for numeric edited data items.

The full ASCII code-set is stored as follows:

```
01 ANS1          PIC X(95)  VALUE
                              " !""#$%&'()*+,-./0123456789:;<=>?
-                              "@ABCDEFGHIJKLMNOPQRSTUVWXYZ[\]^_
-                              "`abcdefghijklmnopqrstuvwxyz{|}~"
                 DISPLAY.
```

	0	1	2	3	4	5	6	7
00:	20	21	22	23	24	25	26	27
08:	28	29	2A	2B	2C	2D	2E	2F
10:	30	31	32	33	34	35	36	37
18:	38	39	3A	3B	3C	3D	3E	3F
20:	40	41	42	43	44	45	46	47
28:	48	49	4A	4B	4C	4D	4E	4F
30:	50	51	52	53	54	55	56	57
38:	58	59	5A	5B	5C	5D	5E	5F
40:	60	61	62	63	64	65	66	67
48:	68	69	6A	6B	6C	6D	6E	6F
50:	70	71	72	73	74	75	76	77
58:	78	79	7A	7B	7C	7D	7E	

Alphanumeric Edited

```
01 ANSE1          PIC XX/9900/AABB  VALUE "**/1200/QR  " DISPLAY.
```

0	1	2	3	4	5	6	7	8	9	a	b
2A	2A	2F	31	32	30	30	2F	51	52	20	20

Alphabetic

```
01 ABS1           PIC A(12)  VALUE "STOCK NUMBER" DISPLAY.
```

0	1	2	3	4	5	6	7	8	9	a	b
53	54	4F	43	4B	20	4E	55	4D	42	45	52

Alphabetic Edited

```
01 ABSE1          PIC AABAABAA  VALUE "XX YY ZZ" DISPLAY.
```

0	1	2	3	4	5	6	7
58	58	20	59	59	20	5A	5A

Numeric Edited

```
01 NSE1           PIC $*(5).**CR  VALUE "$***24.13  " DISPLAY.
```

0	1	2	3	4	5	6	7	8	9	a
24	2A	2A	2A	32	34	2E	31	33	20	20

```
01 NSE2           PIC $(6).99+  VALUE 4913.78 DISPLAY.
```

0	1	2	3	4	5	6	7	8	9
20	24	34	39	31	33	2E	37	38	2B

Numeric Data

Any numeric data item, regardless of usage, must contain at least one digit position and may contain as many as thirty digit positions.

A numeric data item may vary in size from 1 to 31 bytes. Storage requirements for a numeric item depend on the usage, the number of digits, and the presence of an operational sign.

Numeric DISPLAY data items are formatted one digit character per byte. The number is formatted as an integer aligned with the most significant digit at the lowest address and the least significant digit at the highest address. The position of the implied decimal point is maintained in a separate data descriptor. The format descriptions of the numeric DISPLAY data items begin on page C-6.

Numeric computational data items are formatted in a variety of ways depending on the specific USAGE applied to the data item and whether the data item is unsigned or signed. The various numeric computational data item formats are described beginning on page C-11

Unsigned Numeric DISPLAY (NSU)

No storage is allocated for an operational sign.

Valid picture symbols are 9, V and P. Usage is always DISPLAY.

Format Illustrations

```
01 NSU1          PIC 9(3)V9(2)  VALUE 731.24  DISPLAY.
```

0	1	2	3	4
37	33	31	32	34

```
01 NSU2          PIC 9(6)V9(6)  VALUE 3456.7  DISPLAY.
```

0	1	2	3	4	5	6	7	8	9	a	b
30	30	33	34	35	36	37	30	30	30	30	30

```
01 NSU3          PIC 9(5)PP  VALUE 5712300 DISPLAY.
```

0	1	2	3	4
35	37	31	32	33

```
01 NSU4          PIC P9(7)  VALUE 0.09431726 DISPLAY.
```

0	1	2	3	4	5	6
39	34	33	31	37	32	36

Signed Numeric DISPLAY (TRAILING SEPARATE)

Signed numeric DISPLAY data items described with the SIGN IS TRAILING SEPARATE clause are formatted with an additional byte for the operational sign. This sign occupies a separate byte following the least significant digit byte. A positive sign is represented by a value of 2Bh. A negative sign is represented by a value of 2Dh.

If the S (separate sign) Compile Command Option is specified, the compiler assumes the presence of the SIGN IS TRAILING SEPARATE clause for all signed numeric DISPLAY data items for which the SIGN clause is not explicitly stated.

Signed numeric DISPLAY data (TRAILING SEPARATE) is designated as NTS. The valid picture symbols are S, 9, V and P. Usage is always DISPLAY. The sign is always TRAILING SEPARATE.

Format Illustrations

```
01 NTS1          PIC S9(3)V9(2)  VALUE -731.24
                 SIGN TRAILING SEPARATE DISPLAY.
```




```
01 NTS2          PIC S9(4)V9(7)  VALUE -34.567
                 SIGN TRAILING SEPARATE DISPLAY.
```




```
01 NTS3          PIC S9(5)PP  VALUE +5712300
                 SIGN TRAILING SEPARATE DISPLAY.
```




```
01 NTS4          PIC SP9(7)  VALUE -.09431726
                 SIGN TRAILING SEPARATE DISPLAY.
```



Signed Numeric DISPLAY (LEADING SEPARATE)

Signed numeric DISPLAY data items described with the SIGN IS LEADING SEPARATE clause are formatted with an additional byte for the operational sign. The operational sign occupies a separate byte preceding the most significant digit byte. A positive sign is represented by a value of 2Bh. A negative sign is represented by a value of 2Dh.

Signed numeric DISPLAY data (LEADING SEPARATE) is designated as NLS. The valid picture symbols are S, 9, V and P. Usage is always DISPLAY. The sign is always LEADING SEPARATE.

Format Illustrations

```
01 NLS1          PIC S9(3)V9(2)  VALUE +731.24
                 SIGN LEADING SEPARATE DISPLAY.
```

0	1	2	3	4	5
2B	37	33	31	32	34

```
01 NLS2          PIC S9(2)V9(7)  VALUE -7.6543
                 SIGN LEADING SEPARATE DISPLAY.
```

0	1	2	3	4	5	6	7	8	9
2D	30	37	36	35	34	33	30	30	30

```
01 NLS3          PIC S9(5)PP  VALUE +5712300
                 SIGN LEADING SEPARATE DISPLAY.
```

0	1	2	3	4	5
2B	35	37	31	32	33

```
01 NLS4          PIC SP9(7)  VALUE +.09431726
                 SIGN LEADING SEPARATE DISPLAY.
```

0	1	2	3	4	5	6	7
2B	39	34	33	31	37	32	36

Signed Numeric DISPLAY (TRAILING)

Signed numeric DISPLAY data items described with the SIGN IS TRAILING clause are formatted with the highest addressed byte containing the operational sign combined with the low-order digit.

Because of the combined digit and sign, this format is sometimes called trailing combined sign. It is also sometimes called trailing zoned sign because the sign is represented in a manner consistent with a sign zone punch and digit punch on Hollerith punch cards.

The hexadecimal values that result from this combination are shown in Table C-2.

Table C-2 Combined Digit and Sign

Digit	Positive	Negative
0	7B	7D
1	41	4A
2	42	4B
3	43	4C
4	44	4D
5	45	4E
6	46	4F
7	47	50
8	48	51
9	49	52

This format is the default for all signed numeric DISPLAY data items when the SIGN clause is not specified, unless the S (separate sign) Compile Command Option is specified.

Signed numeric DISPLAY data (TRAILING) is designated as NTC. The valid picture symbols are S, 9, V and P. Usage is always DISPLAY. The sign is always TRAILING.

Note that if an NTC data item is sent directly to a printer or display device, the position that contains the combined sign and digit appears as a special character or letter. A positive zero value appears as {. A negative zero value appears as }. Positive 1 through 9 values appear as A through I. Negative 1 through 9 values appear as J through R.

Format Illustrations

```
01 NTC1          PIC S9(3)V9(2)  VALUE -731.24
                 SIGN TRAILING DISPLAY.
```

0	1	2	3	4
37	33	31	32	4D

```
01 NTC2          PIC S9(2)V9(7)  VALUE -3.14159
                 SIGN TRAILING DISPLAY.
```

0	1	2	3	4	5	6	7	8
30	33	31	34	31	35	39	30	7D

```
01 NTC3          PIC S9(5)PP  VALUE +5712300
                 SIGN TRAILING DISPLAY.
```

0	1	2	3	4
35	37	31	32	43

```
01 NTC4          PIC SP9(7)  VALUE -.09431726
                 SIGN TRAILING DISPLAY.
```

0	1	2	3	4	5	6
39	34	33	31	37	32	4F

Signed Numeric DISPLAY (LEADING)

Signed numeric DISPLAY data items described with the SIGN IS LEADING clause are formatted with the lowest addressed byte containing the operational sign combined with the high-order digit. The hexadecimal values that result from this combination are listed in Table C-2 on page C-9.

Because of the combined digit and sign, this format is sometimes called leading combined sign. It is also sometimes called leading zoned sign because the sign is represented in a manner consistent with a sign zone punch and digit punch on Hollerith punch cards.

Signed numeric DISPLAY data (LEADING) is designated as NLC. The valid picture symbols are S, 9, V and P. Usage is always DISPLAY. The sign is always LEADING.

Note that if an NLC data item is sent directly to a printer or display device, the position that contains the combined sign and digit appears as a special character or letter. A positive zero value appears as {. A negative zero value appears as }. Positive 1 through 9 values appear as A through I. Negative 1 through 9 values appear as J through R.

Format Illustrations

```
01 NLC1          PIC S9(3)V9(2)  VALUE -731.24
                 SIGN LEADING DISPLAY.
```

0	1	2	3	4
50	33	31	32	34

```
01 NLC2          PIC S9V9(7)  VALUE -2.9876
                 SIGN LEADING DISPLAY.
```

0	1	2	3	4	5	6	7
4B	39	38	37	36	30	30	30

```
01 NLC3          PIC S9(5)PP  VALUE +5712300
                 SIGN LEADING DISPLAY.
```

0	1	2	3	4
45	37	31	32	33

```
01 NLC4          PIC SP9(7)  VALUE +.09431726
                 SIGN LEADING DISPLAY.
```

0	1	2	3	4	5	6
49	34	33	31	37	32	36

Unsigned Numeric COMPUTATIONAL

For the default configuration, COMPUTATIONAL (or COMP) data items are formatted as one binary coded decimal digit per byte.

Note The compiler can be configured to treat data items described as COMPUTATIONAL (or COMP) as having been described as BINARY,

PACKED-DECIMAL, or DISPLAY using the COMPUTATIONAL-TYPE keyword of the COMPILER-OPTIONS configuration record. In those cases, the default format for COMPUTATIONAL data items described here does not apply; please refer to the corresponding section of this appendix if you have configured one of the other formats for COMPUTATIONAL data.

The number is formatted as an integer aligned with the most significant digit at the lowest address and the least significant digit at the highest address. The position of the implied decimal point is maintained in a separate data descriptor.

No storage is allocated for an operational sign.

Unsigned numeric COMPUTATIONAL data is designated as NCU. The valid picture symbols are 9, V and P. Usage is always COMPUTATIONAL or COMP.

Format Illustrations

```
01 NCU1          PIC 9(3)V9(2)  VALUE 731.24
                 COMPUTATIONAL.
```

0	1	2	3	4
07	03	01	02	04

```
01 NCU2          PIC 9(3)V9(4)  VALUE 23.45
                 COMPUTATIONAL.
```

0	1	2	3	4	5	6
00	02	03	04	05	00	00

```
01 NCU3          PIC 9(5)PP  VALUE 5712300
                 COMPUTATIONAL.
```

0	1	2	3	4
05	07	01	02	03

```
01 NCU4          PIC P9(7)  VALUE .09431726
                 COMPUTATIONAL.
```

0	1	2	3	4	5	6
09	04	03	01	07	02	06

Signed Numeric COMPUTATIONAL

For the default configuration, signed numeric COMPUTATIONAL (or COMP) data items are formatted as one binary coded decimal digit per byte.

Note The compiler can be configured to treat data items described as COMPUTATIONAL (or COMP) as having been described as BINARY, PACKED-DECIMAL, or DISPLAY using the COMPUTATIONAL-TYPE keyword of the COMPILER-OPTIONS configuration record. In those cases, the default format for signed numeric COMPUTATIONAL data items described here does not apply; please refer to the corresponding section of this appendix if you have configured one of the other formats for COMPUTATIONAL data.

The number is formatted as an integer aligned with the most significant digit at the lowest address and the least significant digit at the highest address. The position of the implied decimal point is maintained in a separate data descriptor.

The operational sign occupies a separate byte following the least significant digit. A negative sign is represented by the value 0Dh. A positive sign is normally represented by a value of 0Ch. The COMPUTATIONAL-VERSION keyword of the COMPILER-OPTIONS configuration record may alter the positive sign representation. Selecting a value of RMCOBOL2 or RMCOS for COMPUTATIONAL-VERSION will cause the positive sign to be represented by a value of 0Bh.

Signed COMPUTATIONAL data is designated as NCS, unpacked signed. The valid picture symbols are S, 9, V and P. Usage is always COMPUTATIONAL or COMP.

Format Illustrations

```
01 NCS1          PIC S9(3)V9(2)  VALUE -731.24
                 COMPUTATIONAL.
```




```
01 NCS2          PIC S9(3)V9(4)  VALUE 123.4567
                 COMPUTATIONAL.
```



```
01 NCS3          PIC S9(5)PP  VALUE +5712300
                 COMPUTATIONAL.
```




```
01 NCS4          PIC SP9(7)  VALUE -.09431726
                 COMPUTATIONAL.
```



Signed Numeric COMPUTATIONAL-1 Data

Signed numeric COMPUTATIONAL-1 (or COMP-1) data items are formatted as 2's complement binary words. The number of 9's in the PICTURE character-string does not affect the allocation size for COMPUTATIONAL-1 data items. Such data items are always considered signed without regard to the presence or absence of an S in the associated PICTURE character-string. COMP-1 usage is restricted to integer data items without "P" scaling.

The number is formatted as a 2's complement binary word with the most significant byte at the lowest address and the least significant byte at the highest address.

The operational sign is indicated by the 2's complement format. If the most significant bit is zero, the number is positive. If this bit is one, the number is negative.

Signed numeric COMPUTATIONAL-1 data is designated as NBS, Binary Signed. The valid picture symbols are S, 9 and V. Usage is always COMPUTATIONAL-1 or COMP-1.

Format Illustrations

```
01 NBS1-COMP-1   PIC S9(4)  VALUE +1000
                 COMPUTATIONAL-1.
```



```
01 NBS2-COMP-1   PIC S9(4)  VALUE -1000
                 COMPUTATIONAL-1.
```




```
01 NBS3-COMP-1   PIC S9(5)  VALUE -32768
                 COMPUTATIONAL-1.
```




```
01 NBS4-COMP-1   PIC S9(5)  VALUE +32767
                 COMPUTATIONAL-1.
```



Unsigned Numeric COMPUTATIONAL-3 Data

Unsigned numeric COMPUTATIONAL-3 (or COMP-3) and PACKED DECIMAL data items are formatted as two binary coded decimal digits per byte, except for the highest addressed byte which contains one digit followed by an operational sign. If the associated PICTURE character-string contains an even number of 9's, an additional high-order digit is included in the storage allocated for the data item so as to complete an integral number of bytes.

The number is formatted as an integer aligned with the most significant digit at the lowest address and the least significant digit at the highest address. The position of the implied decimal point is maintained in a separate data descriptor.

The operational sign is concatenated with the least significant digit in the highest addressed byte. The high-order four bits of the byte is the least significant digit and the low-order four bits of the byte is the operational sign. The sign is always Fh, denoting a positive value.

Unsigned numeric COMPUTATIONAL-3 data is designated as NPP, packed unsigned. The valid picture symbols are 9, V and P. Usage is COMPUTATIONAL-3, COMP-3 or PACKED-DECIMAL.

Format Illustrations

```
01 NPP1          PIC 9(3)V9(3)  VALUE 731.246
                 PACKED-DECIMAL.
```




```
01 NPP2          PIC 9(8)V9(7)  VALUE 123456.789
                 PACKED-DECIMAL.
```




```
01 NPP3          PIC 9(5)PP  VALUE 5712300
                 PACKED-DECIMAL.
```




```
01 NPP4          PIC P9(7)  VALUE .09431726
                 PACKED-DECIMAL.
```



Signed Numeric COMPUTATIONAL-3 Data

Signed numeric COMPUTATIONAL-3 (or COMP-3) and PACKED DECIMAL data items are formatted as two binary coded decimal digits per byte, except for the highest addressed byte, which contains one digit followed by an operational sign. If the associated PICTURE character-string contains an even number of 9's, an additional high-order digit is included in the storage allocated for the data item so as to complete an integral number of bytes.

The number is formatted as an integer aligned with the most significant digit at the lowest address and the least significant digit at the highest address. The position of the implied decimal point is maintained in a separate data descriptor.

The operational sign is concatenated with the least significant digit in the highest addressed byte. The high-order four bits of the byte is the least significant digit and the low-order four bits of the byte is the operational sign. A negative sign is represented by the value Dh. A positive sign is normally represented by a value of Ch. The COMPUTATIONAL-VERSION keyword of the COMPILER-OPTIONS configuration record may alter the positive sign representation. Selecting a value of RMCOBOL2 for COMPUTATIONAL-VERSION causes the positive sign to be represented by a value of Fh. Selecting a value of RMCOS for COMPUTATIONAL-VERSION causes the positive sign to be represented by a value of Bh.

Signed numeric COMPUTATIONAL-3 data is designated as NPS, packed signed. The valid picture symbols are S, 9, V and P. Usage is COMPUTATIONAL-3, COMP-3 or PACKED-DECIMAL.

Format Illustrations

```
01 NPS1          PIC S9(3)V9(3)  VALUE -731.246
                 PACKED-DECIMAL.
```




```
01 NPS2          PIC S9(8)V9(7)  VALUE 123456.789
                 PACKED-DECIMAL.
```




```
01 NPS3          PIC S9(5)PP  VALUE -5712300
                 PACKED-DECIMAL.
```




```
01 NPS4          PIC SP9(7)  VALUE -.09431726
                 PACKED-DECIMAL.
```



Unsigned Numeric COMPUTATIONAL-4 Data

Unsigned numeric COMPUTATIONAL-4 (or COMP-4) and BINARY data items are formatted as binary bytes. If the USAGE clause specified a binary allocation override, the number of bytes allocated is the number specified in the binary allocation override. Otherwise, the number of bytes depends on the number of 9's in the associated PICTURE character-string and the setting of the BINARY-ALLOCATION and BINARY-ALLOCATION-SIGNED keywords of the COMPILER-OPTIONS configuration record according to Table C-3.

Note When BINARY-ALLOCATION=CUSTOM=*integer-list* is configured for the compiler, then the compiler allocates the smallest number of bytes that support the decimal precision indicated by the PICTURE character-string and that is an allowed size in *integer-list*. See Table C-3 under BINARY-ALLOCATION=MF-RM for the smallest number of bytes needed for an unsigned binary numeric data item of a given decimal precision. However, if BINARY-ALLOCATION-SIGNED=YES is also configured for the compiler, the number of byes allocated will be according to Table C-4 (on page C-22) instead of Table C-3. If *integer-list* does not include a size large enough to support the decimal precision, the compiler produces a warning and uses the default allocation sizes shown for BINARY-ALLOCATION=RM.

The number is formatted as a binary integer with the most significant byte at the lowest address and the least significant byte at the highest address. The position of the decimal point is maintained in a separate data descriptor.

For unsigned binary items there is no operational sign. In particular, the most significant bit is not indicative of the sign. The value is always interpreted as a positive number.

Unsigned numeric COMPUTATIONAL-4 data is designated as NBU, binary unsigned. The valid picture symbols are 9, V and P. Usage is COMPUTATIONAL-4, COMP-4 or BINARY.

Table C-3 Bytes Allocated for an Unsigned Binary Numeric Data Item

BINARY-ALLOCATION=RM (Default)	
Number of 9's in PICTURE character-string	**Bytes Allocated**
1-4	2
5-9	4
10-18	8
19-30	16
BINARY-ALLOCATION=RM1	
Number of 9's in PICTURE character-string	**Bytes Allocated**
1-2	1
3-4	2
5-9	4
10-18	8
19-30	16
BINARY-ALLOCATION=MF-RM	
Number of 9's in PICTURE character-string	**Bytes Allocated**
1-2	1
3-4	2
5-7	3
8-9	4
10-12	5
13-14	6
15-16	7
17-19	8
20-21	9
22-24	10
25-26	11
27-28	12
29-30	13

Format Illustrations

```
01 NBU1          PIC 9(3)V9  VALUE 123.4
                 BINARY.
```




```
01 NBU2          PIC 9(5)PP  VALUE 5712300
                 BINARY.
```




```
01 NBU3          PIC 9(18)  VALUE 141824562226
                 BINARY.
```




```
01 NBU4          PIC P9(7)  VALUE .09431726
                 BINARY.
```




```
01 NBU5          PIC 9(5)  VALUE 42034
                 BINARY(2).
```



Signed Numeric COMPUTATIONAL-4 Data

Signed numeric COMPUTATIONAL-4 (or COMP-4) and BINARY data items are formatted as 2's complement binary bytes. If the USAGE clause specified a binary allocation override, the number of bytes allocated is the number specified in the binary allocation override. Otherwise, the number of bytes depends on the number of 9's in the associated PICTURE character-string and the setting of the BINARY-ALLOCATION keyword of the COMPILER-OPTIONS configuration record according to Table C-4.

Note When BINARY-ALLOCATION=CUSTOM=*integer-list* is configured for the compiler, then the compiler allocates the smallest number of bytes that support the decimal precision indicated by the PICTURE character-string and that is an allowed size in *integer-list*. See Table C-4 under BINARY-ALLOCATION=MF-RM for the smallest number of bytes needed for a signed binary numeric data item of a given decimal precision. If *integer-list* does not include a size large enough to support the decimal precision, the compiler produces a warning and uses the default allocation sizes shown for BINARY-ALLOCATION=RM.

The number is formatted as a binary integer with the most significant byte at the lowest address and the least significant byte at the highest address. The position of the decimal point is maintained in a separate data descriptor.

The operational sign is indicated by the 2's complement format. If the most significant bit is zero, the number is positive. If this bit is one, the number is negative.

Signed numeric COMPUTATIONAL-4 data is designated as NBS, binary signed. The valid picture symbols are S, 9, V and P. Usage is COMPUTATIONAL-4, COMP-4 or BINARY.

Table C-4 Bytes Allocated for a Signed Binary Numeric Data Item

BINARY-ALLOCATION=RM (Default)	
Number of 9's in PICTURE character-string	**Bytes Allocated**
1-4	2
5-9	4
10-18	8
19-30	16
BINARY-ALLOCATION=RM1	
Number of 9's in PICTURE character-string	**Bytes Allocated**
1-2	1
3-4	2
5-9	4
10-18	8
19-30	16
BINARY-ALLOCATION=MF-RM	
Number of 9's in PICTURE character-string	**Bytes Allocated**
1-2	1
3-4	2
5-6	3
7-9	4
10-11	5
12-14	6
15-16	7
17-18	8
19-21	9
22-23	10
24-26	11
27-28	12
29-30	13

Format Illustrations

```
01 NBS1          PIC S9(3)V9  VALUE -123.4
                 BINARY.
```




```
01 NBS2          PIC S9(5)PP  VALUE -5712300
                 BINARY.
```




```
01 NBS3          PIC S9(18)  VALUE -141824562226
                 BINARY.
```




```
01 NBS4          PIC SP9(7)  VALUE -.09431726
                 BINARY.
```




```
01 NBS5          PIC S9(3)  VALUE 95
                 BINARY(1).
```

Unsigned Numeric COMPUTATIONAL-6 Data

Unsigned numeric COMPUTATIONAL-6 (COMP-6) data items are formatted as two binary coded decimal digits per byte. If the picture contains an odd number of 9's, an additional high-order digit is included in the storage allocated for the item.

The number is formatted as an integer aligned with the most significant digit at the lowest address and the least significant digit at the highest address. The position of the implied decimal point is maintained in a separate data descriptor.

No storage is allocated for an operational sign.

Unsigned numeric COMPUTATIONAL-6 data is designated as NPU, packed unsigned. The valid picture symbols are 9, V and P. Usage is COMPUTATIONAL-6 or COMP-6.

Format Illustrations

```
01 NPU1          PIC 9(3)V9(2)  VALUE 731.24
                 COMPUTATIONAL-6.
```




```
01 NPU2          PIC 9(8)V9(8)  VALUE 123456.789
                 COMPUTATIONAL-6.
```




```
01 NPU3          PIC 9(5)PP  VALUE 5712300
                 COMPUTATIONAL-6.
```




```
01 NPU4          PIC P9(6)  VALUE .0943172
                 COMPUTATIONAL-6.
```



Appendix D: Customizing RM/COBOL for UNIX

This appendix provides information required to customize the runtime system portion of RM/COBOL for UNIX and to relink other portions of the product. It also contains information on adding C or assembly language subprograms to the runtime system. Examples are provided.

Using the customiz Shell Script to Customize RM/COBOL

This version of RM/COBOL includes a UNIX Bourne Shell script, **customiz**, that can be used to generate a **Makefile** to customize various RM/COBOL products. The RM/COBOL products that can be customized in this manner include the following:

- RM/COBOL runtime system
- RM/COBOL development system (compiler)
- RM/COBOL Indexed File Recovery utility program
- RM/COBOL Open File Manager
- RM/InfoExpress server

For some of these products, different variations can be built by including one or more of the following software components:

- Termcap or terminfo terminal interfaces
- RM/InfoExpress client
- RM/plusDB
- Pop-Up Window Manager
- MCBA C language routines
- Flexgen C language routines

- Enterprise CodeBench
- VanGui Interface Builder

The RM/COBOL runtime system also can be customized by adding C (or assembly) language subprograms, a Message Control System (MCS), or a built-in configuration file (see "Other Runtime Customizations" on page D-5).

Terminfo or Termcap Terminal Interfaces

The RM/COBOL runtime system is shipped with a default terminal interface driver (normally terminfo) for your platform. If you want to change your configuration, you can rebuild your runtime system either with the terminfo or with the termcap terminal interface. To use the termcap terminal interface, invoke **customiz**, choose option 1 (runcobol), and type "2" at the following prompt:

```
Would you like Terminfo or Termcap terminal interface(1/2)?
```

Type "1" to use the terminfo terminal interface.

RM/InfoExpress Client

The RM/InfoExpress add-on product for RM/COBOL is designed to optimize RM/COBOL data file access on various local area networks (LANs) and wide area networks (WANs). It allows RM/COBOL programs to realize significant speed improvements for sequential, relative, and indexed files over conventional network access methods. To add the RM/InfoExpress client to your runtime system, invoke **customiz**, choose option 1 (runcobol), and type "y" at the following prompt:

```
Would you like to build the RM/InfoExpress client (y/n)?
```

Type "n" not to include RM/InfoExpress.

When you answer "y" to the preceding prompt, the **customiz** program will ask for the directory where the RM/InfoExpress server software is installed. See the *RM/InfoExpress User's Guide* for more information on installing RM/InfoExpress.

RM/InfoExpress also can be included with the RM/COBOL Open File Manager and the RM/COBOL compiler in the same way. An RM/COBOL Open File Manager that is linked with the RM/InfoExpress client can be used to access remote RM/COBOL data files using the RM/InfoExpress server. Similarly, an RM/COBOL compiler that is linked with the RM/InfoExpress client (running under UNIX or Windows) can be used to compile a source program or access a library that is present on a machine running RM/InfoExpress server software.

RM/plusDB

RM/plusDB is an add-on product for RM/COBOL that enables an application to access database systems such as Informix or Oracle with COBOL I/O statements. To add RM/plusDB to your runtime system, invoke **customiz**, choose option 1 (runcobol), and type "y" at the following prompt:

```
Would you like to build RM/plusDB (y/n)?
```

Type "n" not to include RM/plusDB.

When you answer "y" to the preceding prompt, the **customiz** program will prompt you for the directory where the RM/plusDB software is installed. See the *RM/plusDB User's Guide* for more information about installing RM/plusDB.

RM/plusDB also can be included with the RM/InfoExpress server product by invoking **customiz**, choosing option 5 (rmserver), and typing "y" at the prompt. (See Example 2 on page D-9.) RM/plusDB enables the remote RM/InfoExpress client applications (running on UNIX and Windows machines) to access transparently the associated database on a UNIX machine over the network.

Pop-Up Window Manager

The RM/COBOL runtime system is shipped with the Pop-Up Window Manager activated. When the Pop-Up Window Manager is removed, it becomes unavailable to all applications using the runtime system. This action may be desirable in some situations in order to reduce the amount of memory used by the runtime system. If your application does not use pop-up windows, screen I/O will be slightly faster with the Pop-Up Window Manager removed.

To build a runtime system with the Pop-Up Window Manager removed, invoke **customiz** (see Example 1 on page D-6), choose option 1 (runcobol), and type "n" at the following prompt:

```
Would you like the Pop-Up Window Manager (y/n)?
```

Type "y" to include the Pop-Up Window Manager.

MCBA C Language Routines

C language subprograms can be acquired from MCBA, Inc. as an add-on product for RM/COBOL. To add the MCBA C language subprograms to your runtime system, invoke **customiz**, choose option 1 (runcobol), and type "y" at the following prompt:

```
Would you like the MCBA subroutines (y/n)?
```

Type "n" not to exclude the subprograms.

Flexgen C Language Routines

Easirun, USA, Inc.'s Flexgen C language subprograms can be requested from Liant as an add-on product for RM/COBOL. To add the Flexgen C language subprograms to your runtime system, invoke **customiz**, choose option 1 (runcobol), and type "y" at the following prompt:

```
Would you like the Flexgen subroutines (y/n)?
```

Type "n" not to exclude the subprograms.

Enterprise CodeBench

Enterprise CodeBench is an add-on product for RM/COBOL that allows you to create, edit, compile, debug, and run RM/COBOL applications on UNIX within the Windows environment.

To add Enterprise CodeBench to your runtime system, invoke **customiz**, choose option 1 (runcobol), and type "y" at the following prompt:

```
Would you like Enterprise CodeBench (y/n)?
```

Type "n" to exclude Enterprise CodeBench.

VanGui Interface Builder

The add-on product, VanGui Interface Builder (referred to as VanGui), is designed to allow you to use your choice of industry-standard GUI tools, such as Delphi or Visual Basic, to update the client user interface of both Windows- and UNIX-based RM/COBOL applications.

To add VanGui Interface Builder to your runtime system, invoke **customiz**, choose option 1 (runcobol), and type "y" at the following prompt:

```
Would you like VanGui Interface Builder (y/n)?
```

Type "n" to exclude VanGui.

Other Runtime Customizations

Three other customizations can be performed on the RM/COBOL runtime system:

1. Adding C (or assembly) language subprograms. The procedures for adding C (or assembly) language subprograms begin on page D-12.

2. Adding a Message Control System (MCS). The Message Control System (MCS) is discussed on page 8-65. To link your MCS with the runtime system, use the **customiz** utility to generate a **Makefile** to build the runtime with the same configuration as that of your current runtime system.

   Use the following command:

   ```
   make <product-name> MCS=mymcs.o
   ```

   mymcs.o is the file containing the code for your MCS. The MCS parameter to the **make** command can also be used with other runtime systems you build.

3. Adding a built-in configuration file. See Chapter 10, *Configuration*, for more information.

Relinking the Same Product

Relinking the RM/COBOL product with the same configuration as originally delivered is normally not performed. However, this can be achieved by using the **customiz** utility to generate a **Makefile** to build the runtime with the same configuration as that of your current runtime system. The only time that it should be necessary to relink RM/COBOL is when the C library (**libc.a**) has been updated.

customiz Utility Examples

The following two examples demonstrate how to use the **customiz** utility to build different products.

Example 1

This first example describes how to generate a **Makefile** to build a runtime system with the termcap terminal interface, an RM/InfoExpress client, RM/plusDB, Enterprise CodeBench, VanGui Interface Builder, and the Pop-Up Window Manager. It does not include MCBA or Flexgen C language routines.

Note This example assumes that RM/InfoExpress, RM/plusDB, MCBA and Flexgen C language routines, Enterprise CodeBench, and VanGui Interface Builder are supported on your UNIX system. If that is not the case, the system prompts associated with these products are not displayed.

1. To execute the **customiz** shell script, you must be in the directory where RM/COBOL is installed. To invoke the shell script, type the following command:

   ```
   customiz
   ```

   If **Makefile** is present in the current directory, the following prompt is displayed:

   ```
   Do you want to write over the existing Makefile (y/n)?
   ```

2. Type “n” to cause the program to exit without affecting the current status. Type “y” to cause the program to erase the **Makefile**. Pressing the Interrupt key at any point causes the program to remove the incomplete **Makefile** before exiting to the system. The program displays the following screen:

   ```
              RM/COBOL Customization
         (Press   system   cancel   to   abort)

   1.  runcobol  - RM/COBOL Runtime System
   2.  rmcobol   - RM/COBOL Compiler
   3.  recover1  - RM/COBOL Indexed File Recovery Utility
   4.  ofm       - RM/COBOL Open File Manager
   5.  rmserver  - RM/InfoExpress Server

   Enter product number:
   ```

   Note Option 5 (rmserver) will not be displayed if RM/InfoExpress is not supported on your UNIX system.

3. Choose option 1 (for runcobol) and press Enter.

   The program responds with the following prompt, which will repeat until an appropriate response is entered:

   ```
   Building runcobol
   -----------------
   Would you like the Terminfo or Termcap terminal interface (1/2)?
   ```

4. Type “2” and press Enter to choose the termcap terminal interface.

   The program responds with the following prompt:

   ```
   Would you like to build the RM/InfoExpress client (y/n)?
   ```

5. Type “y” and press Enter.

   The program displays the following prompt:

   ```
   Enter the directory where RM/InfoExpress is installed
   (Default is /usr/rminfox):
   ```

6. Type the complete pathname for the directory where RM/InfoExpress is installed.

   customiz checks the system for the presence of the specified directory. If no directory name is entered, the program uses **/usr/rminfox** as the default value.

   The program responds with the following prompt:

   ```
   Would you like to build RM/plusDB (y/n)?
   ```

7. Type “y” and press Enter.

   The program displays the following prompt:

   ```
   Enter the directory where RM/plusDB is installed
   (Default is /usr/rmdb):
   ```

   customiz checks the system for the presence of the specified directory. If no directory name is entered, the program uses **/usr/rmdb** as the default value.

   The program responds with the following prompt:

   ```
   Would you like the Pop-Up Window Manager (y/n)?
   ```

8. Type “y” and press Enter. (The Pop-Up Window Manager is required for Enterprise CodeBench, which is described in Step 10.)

The program then responds with the following prompt:

```
Would you like the MCBA C subroutines (y/n)?
```

9. Type “n” and press Enter.

   The program responds with the following prompt:

   ```
   Would you like the Flexgen C subroutines (y/n)?
   ```

10. Type “n” and press Enter.

    The program responds with the following prompt:

    ```
    Would you like the Enterprise CodeBench feature (y/n)?
    ```

11. Type “y” and press Enter.

    The program responds with the following prompt:

    ```
    Would you like the VanGui Interface Builder feature (y/n)?
    ```

12. Type “y” and press Enter.

    customiz allows you to specify the executable filename of the linked product using the following prompt:

    ```
    Enter the product name (Default is <default name>):
    ```

13. Press Enter to use the default name or type the name of the final linked product.

    The program builds the **Makefile** and displays the following prompt:

    ```
    Makefile generation successful.
    Would you like to build the product (y/n)?
    ```

    a. If you want the program to build the product, type “y” and press Enter. The program builds the product using the system **make** utility and the newly generated make script specified in **Makefile**.

    b. You may choose to run the make script yourself if you need to change the values of the macros defined in the make script specified in **Makefile**. If you type “n”, the program displays the following information and then exits:

       ```
       Type ‘make’ to build the <product_name> product
       ```

    Note If you look at the generated **Makefile** using any text editor, you will find comments at the beginning about the configuration of the product built.

Example 2

The following example describes how to generate a **Makefile** to build an RM/InfoExpress server with RM/plusDB.

Note This example assumes that RM/InfoExpress and RM/plusDB are supported on your UNIX system.

1. Change to the directory where RM/COBOL is installed and type:

   ```
   customiz
   ```

   If **Makefile** is present in the current directory, the following prompt is displayed:

   ```
   Do you want to write over existing Makefile (y/n)?
   ```

2. Type "n" to cause the program to exit without affecting the current status. Type "y" to cause the program to erase the **Makefile**. Pressing the Interrupt key at any point causes the program to remove the incomplete **Makefile** before exiting to the system.

   The program displays the following screen:

   ```
            RM/COBOL Customization
         (Press   system   cancel   to   abort)

   1.  runcobol  - RM/COBOL Runtime System
   2.  rmcobol   - RM/COBOL Compiler
   3.  recover1  - RM/COBOL Indexed File Recovery Utility
   4.  ofm       - RM/COBOL Open File Manager
   5.  rmserver  - RM/InfoExpress Server

   Enter product number:
   ```

3. Type "5" (for rmserver) and press Enter.

4. The program responds with the following prompt:

   ```
   Building rmserver
   -----------------
   Would you like to build RM/plusDB (y/n)?
   ```

5. Type "y" and press Enter.

   The program displays the following prompt:

   ```
   Enter the directory where RM/plusDB is installed
   (Default is /usr/rmdb):
   ```

6. Type the complete pathname for the directory where RM/plusDB is installed.

   customiz checks the system for the presence of the specified directory. If no directory name is entered, the program uses **/usr/rmdb** as the default value and displays the following prompt:

   ```
   Enter the directory where RM/InfoExpress is installed
   (Default is /usr/rminfox):
   ```

7. Type the complete pathname for the directory where RM/InfoExpress is installed.

   customiz checks the system for the presence of the specified directory. If no directory name is entered, the program uses **/usr/rminfox** as the default value.

   The program responds with the following prompt, which allows you to specify the name of the linked product:

   ```
   Enter the product name (Default is <default name>):
   ```

8. Press Enter to use the default name or type the name of the final linked product.

   customiz builds the **Makefile** and issues the following prompt:

   ```
   Makefile generation successful.
   Would you like to build the product (y/n)?
   ```

   a. If you want the program to build the product, type "y" and press Enter. The program builds the product using the system **make** utility and the newly generated make script specified in **Makefile**.

   b. You may choose to run the make script yourself if you need to change the values of the macros defined in the make script specified in **Makefile**. If you type "n", the program displays the following information and then exits:

      ```
      Type 'make' to build the <product_name> product
      ```

   Note If you look at the generated **Makefile** using any text editor, you will find comments at the beginning about the configuration of the product built.

Installing Your Customized Product

When you have finished customizing RM/COBOL, you need to install the product again.

1. Log in as root.
2. Change your working directory to the directory in which you initially installed RM/COBOL.

   For example:

   ```
   cd rmc85_dir
   ```

3. Enter the following command:

   ```
   ./rminstall
   ```

During the execution of this command, messages appear periodically indicating the status of the installation.

C (or Assembly) Language Subprograms

If you want to use C (or assembly) language subprograms, they must be linked into the runtime system before you can call them. You must supply a table of routine names and entry points to the runtime system during the linkage. The procedure for doing this is set forth in the discussion of C subprogram preparation that begins on page D-19.

C Calling Sequence

The syntax (Format 2) for the CALL statement in the RM/COBOL program is as follows:



[ON EXCEPTION *imperative-statement-1*]

[NOT ON EXCEPTION *imperative-statement-2*]

[END-CALL]

The value of the contents of the data item specified by *identifier-1* or the value of *literal-1* is the program name of the subprogram to be called.

identifier-2 or *literal-2* are one or more actual arguments to be passed to the called program. If the BY CONTENT phrase applies to an argument, a temporary copy of the item is passed, thus preventing the subprogram from modifying the original item.

identifier-3 is an actual argument to be passed to the called program for the purposes of returning a result to the calling program.

The runtime system locates the subprogram with the program name specified by *literal-1* or *identifier-1*. See the discussion of "Subprogram Loading" on page 8-34 for additional information on locating subprograms.

The runtime system can locate the C subprograms only if their names appear in the subprogram name table. The subprogram name table is an array of structures linked into the runtime system. The name of this table must be LIBTABLE, and must be of the following format:

```
struct PROCTABLE {
    char *subname; /* name of subroutine as in call */
    int (*ent_pnt)(); /* pointer to subroutine function */
};
        /* define library header */

struct PROCTABLE  LIBTABLE [] = {
                  {"SYSTEM", subsys },
                  {"RENAME", subren },
                  {"DELETE", subdel },
                  {(char *) 0, 0 }
};
```

Here, "SYSTEM", "RENAME", and "DELETE" are the program names. subsys, subren, and subdel are the entry points into the routines. The last two entries in the table must be zeroes.

Upon entry to the subprogram, all registers are volatile. The top of the stack contains the following information:

```
long containing the return address
long containing a pointer to null terminated
      string containing the subprogram name
integer containing the number of arguments (n)
long containing a pointer to argument entry table
integer containing the initial entry flag
```

The return address is used during the execution of the C return (*x*) statement, or during the execution of the corresponding assembly instruction.

The remaining values on the stack are accessible as function parameters, as described below. A sample C subprogram function declaration is as follows:

```
int subsys(name, arg_count, arg_vector, initial)
char *name;
int arg_count;
struct ARGUMENT_ENTRY arg_vector[];
int initial;
```

The pointer to the subprogram name (name) is used by the run unit to identify the requested subprogram. This is a null-terminated ASCII string.

The number of the arguments (arg_count) describes the number of USING argument entries in the actual argument entry table (arg_vector) pointed to by the next argument.

The initial entry flag (initial) contains zero to indicate that the subprogram is in its "initial state," which is the state a subprogram is in the first time it is called in the run unit, and a non-zero value to indicate that it should be in its "last used state."

In the initial state, all external and static automatic variables are initialized by the system to the appropriate values. In the last used state, external and static variables are left in the last state they were used. In either state, all automatic variables are reallocated on the stack. It is your responsibility to initialize them to the desired values.

Once memory used by a subprogram has been linked into the runtime system, it cannot be released.

Use of the CANCEL statement to cancel a routine linked with the runtime system sets the initial flag to zero on the next entry into the subprogram. The CANCEL statement has no effect on the values of the external and static variables used in the program.

The argument entry table (arg_vector) contains descriptions of the actual arguments specified in the CALL statement. The arg_vector[0] entry describes the first actual argument in the USING phrase of the CALL statement. The arg_vector[arg_count - 1] entry describes the last actual argument in the USING phrase of the CALL statement. The arg_vector[-1] entry describes the argument specified in the GIVING phrase of the CALL statement. If the GIVING phrase is omitted from the CALL statement, or for any actual argument specified as OMITTED in the USING phrase of the CALL statement, the corresponding arg_vector entry contains a type value 32 (OMITTED, as shown in table D-1) and the remaining fields are zero. C or assembly language subprograms that access the GIVING argument in arg_vector[-1] will function correctly only for RM/COBOL 7.0 and later release runtimes because prior runtimes did not make a GIVING argument entry available in arg_vector[-1].

An argument entry to a subprogram written in assembly language has the following structure:

```
A_ADDRESS:         .long    | Address of argument
A_LENGTH:          .long    | Length of argument
A_TYPE:            .word    | Type of argument
A_DIGIT_COUNT:     .byte    | Number of digits in argument
A_SCALE:           .byte    | Position of implied/actual decimal point
A_PICTURE_ADDRESS: .long    | Address of encoded picture
```

An argument entry on an Intel-based system has the following structure:

```
ARGUMENT_ENTRY     STRUC
A_ADDRESS          DD  ?         ; linear address of argument
A_LENGTH           DW  2 DUP (?) ; length of argument
A_TYPE             DB  ?         ; type of argument
                   DB  ?         ; reserved, set to zero
A_DIGIT_COUNT      DB  ?         ; number of digits in argument
A_SCALE            DB  ?         ; position of implied/actual decimal point
A_PICTURE_ADDRESS  DD  ?         ; linear address of encoded picture
ARGUMENT_ENTRY     ENDS
```

To a subprogram written in C, an argument entry can be defined with the following structure:

```
struct ARGUMENT_ENTRY {
        char *a_address;        /* pointer to start of arg */
        unsigned long a_length; /* length of argument */
        short a_type;           /* arg type see table below */
        char a_digits;          /* digit count 0x1-0x1E */
        signed char a_scale;    /* implied decimal location */
        char *a_picture;        /* pointer to edit DOPE */
}
          ;
```

a_address specifies the lowest address byte of the argument.

a_length specifies the number of bytes allocated to the argument.

a_type specifies the RM/COBOL data type as a number from Table D-1.

Note See also Table 9-2 on page 9-4 for an explanation of the data type abbreviations in the following table and Appendix C, *Internal Data Formats*, for a description of RM/COBOL data types.

Table D-1 Data Types as Numbers

Type Number	RM/COBOL Data Type	Type Number	RM/COBOL Data Type
0	NSE	12	NBU
1	NSU	16	ANS
2	NTS	17	ANS (justified right)
3	NTC	18	ABS
4	NLS	19	ABS (justified right)
5	NLC	20	ANSE
6	NCS	21	ABSE
7	NCU	22	GRP (fixed length)
8	NPP	23	GRPV (variable length)
9	NPS	25	PTR
10	NPU	32	OMITTED
11	NBS		

Note The data type GRPV (23) occurs only when C$CARG is called with the formal argument in the main program. In all other cases, RM/COBOL passes variable length group actual arguments as if they were a fixed length group of the maximum length.

a_digits specifies the actual number of digits in a numeric data item (where the type of argument is in the range 0 through 30). It is set to zero for nonnumeric data items.

a_scale specifies the power of 10 by which the digits in a numeric data item (where the type of argument is in the range 1 through 12) must be multiplied to obtain the numeric value of the data item. The power of 10 is represented as a signed, 2's complement number. It is set to zero for nonnumeric data items.

a_picture specifies the lowest addressed byte of the encoded picture for edited items (type of argument equals 0, 20 or 21). It is set to zero for all other types.

For example, for a Motorola 68000-based computer, a CALL statement specifies one argument in its USING list, a three-byte numeric unsigned (NSU) data item whose picture is 99V9 located at address 0x12850. The argument entry will contain:



For Intel-based computers, the memory organization is different, so the values for the fields are different but the organization of the structure is the same. Using the same example as above except that the argument address is 0xdf:0x2850, the argument entry will contain:



The preceding examples apply to subprograms written in assembly language. However, subprograms written in C are more portable because C masks the distinctions between the microprocessors. The following is a diagram of the structure in C.



Upon exit from a C subprogram, the exit code must be returned using the return(*x*) statement. The exit code may be set to zero to request a normal return to the calling RM/COBOL program, or to non-zero to request an immediate STOP RUN with the program exit code (see page 7-8) equal to the contents of *x*.

Assembly language subprograms are entered using the same methods as C programs. Therefore, assembly language subprograms should return using the same conventions as C. Precautions should be taken to leave the stack in the state it was in before the call.

C subprograms should return explicitly using the return(*x*) statement; otherwise, the C subprogram will have an unknown value as the return code, which may be interpreted as a STOP RUN request.

C subprograms should not exit with an exit( ) statement, as this will result in a premature termination of the run unit.

Accessing C Subprograms

Two methods are available to access a C (or assembly) language subprogram that has been linked to the runtime system: either each subprogram can be given a unique name and entry point or each subprogram can be given a unique name and share the same entry point. In the second case, it is necessary to determine which subprogram has been called. Here is an example:

```
struct PROCTABLE LIBTABLE [] =  {
       {"SUBA",  library },
       {"SUBB",  library },
       {(char *) 0, 0 }
   };
int library(name, arg_count, arg_vector, initial)
char *name;
int arg_count;
struct ARGUMENT_ENTRY arg_vector[];
int initial;
{
   if  (!strcmp  (  "SUBA", name)) {
      return( suba( arg_count, arg_vector, initial));
   }
   else
   {
      if (!strcmp ( "SUBB", name)) {
      return( subb( arg_count, arg_vector, initial));
      }
      else
      {
      return( 1);/* error stop run */
      }
   }
}
```

Preparing C (or Assembly) Subprograms

C (or assembly) subprograms are compiled (or assembled) as if they were to be linked with similar programs. Assembly language source files are assumed to be those with an extension of **.s**; C source files are assumed to have an extension of **.c** and all object files are assumed to have an extension of **.o**.

If a single source module is to be linked into the runtime system, ensure that LIBTABLE is present (as described previously). The following commands automatically generate the subprogram object file and link it with the runtime system:

```
make runcobol CLIBRARY=mysub.o
```

mysub.c is your C subprogram source file that will be automatically compiled to produce ***mysub.o***.

mysub.o is the C subprogram object file you want to link.

If you want to modify the routine (called **sub.c**) that is delivered with your system, you would edit **sub.c**, making changes as appropriate, and then enter:

```
make runcobol
```

The **make** utility automatically compiles and links the default subprogram module **sub.c**.

You can link multiple subprograms into the runtime system. Only one LIBTABLE can be declared, holding all the subprogram names and entry points. For example, if you want to link three subprograms, you would enter these commands (assuming that one of the C routines contains LIBTABLE):

```
make runcobol CLIBRARY="mysub1.o mysub2.o mysub3.o..."
```

mysubn.c is the name of the files that contain your C programs. These files will be automatically compiled to produce ***mysubn.o***.

Restrictions to C (or Assembly) Language Subprograms

The runtime system changes terminal characteristics before passing control to a C (or assembly) language subprogram. If any processing requiring terminal I/O is done (including operating system commands that use the terminal), you must reset the terminal to its original state by making a call to the routine resetunit(). If resetunit() was called, a call to setunit() must be made before control is returned to the run unit. Both functions are part of the runtime system.

Debugging C (or Assembly) Language Subprograms

It is recommended that subprograms initially be tested using a C main program that sets up the RM/COBOL argument entries and calls the subprogram. It is possible, however, to use the **adb** or **sdb** utility. Using these commands on a newly created run unit allows you to place a breakpoint at your function, and then run the program. The utility regains control as soon as the run unit passes control to the subprogram.

C Subprogram Examples

The programs that have been provided with your distribution media as examples include **sub.c**, **subtest.cbl**, **subtype.c**, and **typetest.cbl**.

Example 1

sub.c is the default subprogram library that is distributed and already linked into the runtime system. This routine includes the following subprograms:

SYSTEM — Submits operating system commands as if they were typed at a keyboard. SYSTEM is called with one to three arguments. The first argument must be the command to execute. The runtime system automatically calls resetunit() before executing the command to place the terminal in a "normal state" (the state before the runtime system was executed). Following the execution of the command, the runtime system automatically calls setunit() to return the terminal to the state that it requires for terminal I/O, and also causes the terminal screen to be redrawn. However, redrawing the screen may not always be desirable. For example, the command executed might not change the screen. If all of the calls to SYSTEM in a COBOL program do not change the screen, the REDRAW-ON-CALL-SYSTEM keyword (see page 10-39) of the TERM-ATTR configuration record may be set to NO and the runtime system will not redraw the screen after every call to SYSTEM.

If some of the calls to SYSTEM in a COBOL program change the screen contents, the redrawing of the screen can be controlled through the use of the optional second argument to CALL "SYSTEM". This argument may have the value "Y" or "y" to redraw the screen, or "N" or "n" not to redraw the screen. A blank or any other value defaults to the TERM-ATTR configuration record REDRAW-ON-CALL-SYSTEM value.

Note If the second argument is "N", or the REDRAW-ON-CALL-SYSTEM configuration keyword value is NO, and the called program changes the screen contents, unpredictable results occur on the next DISPLAY

statement because of the changed cursor position. CALL “SYSTEM” output is not stored in the runtime system’s in-memory screen image.

The third parameter must be defined as PIC S9(4) BINARY and contains the return code from the command when control is returned to the COBOL program.

Note The OSSYSTEM function call in the subsys subroutine is implemented as:

```
"return (wexitstatus(system(command))"
```

and returns the same value as returned by the call to SYSTEM.

DELETE — Deletes a file. DELETE is called with one argument, which is the full or relative pathname of the file to be deleted.

RENAME — Renames a file. RENAME is called with one or two arguments. If one argument is passed to the routine, the routine handles the request in the same fashion as the RENAME subprogram in RM/COBOL (74) 2.*n*. That is, the one argument contains both the source filename and the target filename. If the subprogram is invoked this way, the argument must be NULL terminated (that is, the last character must be COBOL LOW-VALUES). If the subprogram is invoked with two arguments, it uses the first argument as the source filename and the second as the target filename. In this case, the names do not have to be NULL terminated.

In all cases, except using RENAME in the RM/COBOL (74) 2.*n* fashion, the use of literals in the CALL statement is supported. In the case of the RM/COBOL (74) 2.*n* RENAME subprogram, it is not possible to have LOW-VALUES as part of a literal. Use a Working-Storage Section variable. See **subtest.cbl** for examples of all calling sequences.

subtest.cbl is an interactive program to call the subprograms in **sub.c**. To run Example 1, enter the following commands:

```
rmcobol subtest
runcobol subtest
```

Example 2

subtype.c is a subprogram that returns the type of the first argument in the second argument. The second argument must be declared as COMP-1.

typetest.cbl is an RM/COBOL program that calls **subtype** with many different types of arguments, and tests that the proper value is returned. In order to run this test, you must link this routine into the runtime system. To run Example 2, enter the following commands:

```
cc -c subtype.c
make runcobol CLIBRARY=subtype.o
rmcobol typetest
runcobol typetest
```

Remember, by doing this you have replaced the default subprogram library, **sub.o**, with this test subprogram. It is recommended that after you run this test, you relink the default subprogram library into the runtime system, as described previously in this appendix.

C Entry Points For COBOL Functions

RM/COBOL provides user-supplied C subprograms with entry points to some COBOL functions. The following routines use the standard C calling and parameter passing conventions:

- **RmForget (int y1, int x1, int y2, int x2).** This function marks the indicated area of screen memory as unknown. By doing so, the next COBOL display to that area will not be optimized based on the screen contents. This allows COBOL output to be correctly displayed over linked C subprogram output, which is not stored in the in-memory screen image.

  This routine requires four int parameters (two line and position pairs), which specify the upper-left (y1,x1) and lower-right (y2,x2) coordinates of the area of the screen to be marked as unknown. Valid values range from 0 to the line or position limit of the screen. Passing zero values mark the entire screen as being unknown. See the "C$Forget" section in Appendix F, *Subprogram Library*, for more information.

- **RmRepaintScreen().** This function causes the COBOL runtime system to redraw the entire current screen from an in-memory image. C routine output is erased. This function requires no parameters. See the REPAINT-SCREEN keyword of the CONTROL phrase on page 8-18 for more information.

- **RmRefreshCwd().** This function causes the COBOL runtime system to refresh its internal copy of the current working directory. This internal copy is used to construct complete file names from any filename that is not fully qualified. This function should be called before returning to the COBOL program if a non-COBOL subprogram changes the current working directory with the chdir() C library routine. The RmRefreshCwd() routine has no parameters and does not return a value.

Appendix E: Windows Printing

The RM/COBOL for Windows runtime system supplies a P$ subprogram library that allows access to Windows printing features. This appendix describes the required RM/COBOL calling sequence and the USING list parameters for each P$ subprogram. Note that failure to comply with the USING list requirements will halt the run unit with a STOP RUN indication at the line containing the incorrect CALL statement.

The COBOL copy files that are supplied with an RM/COBOL development system to facilitate Windows printing program development are described starting on page E-44. Examples illustrating some common uses for the P$ subprograms begin on page E-71.

In addition to the Windows printing subprogram library, this appendix also describes an alternative means of printing under Windows using a set of RM/COBOL-specific escape sequences (see page E-85).

P$ Subprogram Library

Note P$ subprogram names are case-insensitive. For readability, mixed case is used in this document except in calling sequences and code fragments, where uppercase letters are used.

The P$ subprograms can be logically grouped into the following categories that control:

- The standard Windows Print dialog box
- Drawing activities
- Text manipulation
- Activities common to both drawing and text manipulation
- Printer control activities

Table E-1 lists the subprograms alphabetically within each of these categories.

Table E-1 RM/COBOL Windows Printing Subprogram Library

Windows Print Dialog Box Subprograms	Function
P$ClearDialog	Clears the standard Windows Print dialog box values back to their default (unset) state. See page E-15.
P$DisplayDialog	Invokes the standard Windows Print dialog box. See page E-16.
P$EnableDialog	Causes the standard Windows Print dialog box to display automatically the next time the predefined printer device, "PRINTER?", is opened. See page E-16.
P$GetDialog	Retrieves values from the standard Windows Print dialog box. See page E-17.
P$SetDialog	Sets values for the standard Windows Print dialog box. See page E-18.
Drawing Subprograms	**Function**
P$DrawBitmap	Prints a bitmap file (.BMP). See page E-19.
P$DrawBox	Draws a box. See page E-20.
P$DrawLine	Draws a line. See page E-20.
P$GetPosition	Retrieves the ending position of the last print operation. See page E-20.
P$LineTo	Draws a line starting at the current position. See page E-21.
P$MoveTo	Repositions the line-draw pen without drawing a line. See page E-22.
P$SetBoxShade	Sets shading color and percentage for a box. See page E-22.
P$SetPen	Sets the style, width, and color of the pen tool for a box or a line. See page E-23.
P$SetPosition	Sets a new position for the next print operation. See page E-23.

Table E-1 RM/COBOL Windows Printing Subprogram Library (*Cont.)*

Text Manipulation Subprograms	Function
P$ClearFont	Clears font description values back to their default (unset) state. See page E-24.
P$GetTextExtent	Retrieves the bounding rectangle size for the text passed to the function, calculated using the current font size. The returned values can be used to draw boxes around text. See page E-25.
P$GetTextMetrics	Retrieves the characteristics of the current font. See page E-25.
P$GetTextPosition	Retrieves the ending position of the last print operation adjusted to the top or bottom of the current font. See page E-28.
P$SetDefaultAlignment	Sets default alignment used in text positioning. See page E-28.
P$SetFont	Changes fonts for subsequent text print operations. See page E-29.
P$SetLineExtendMode	Concatenates output from two COBOL WRITE statements on the same line. See page E-31.
P$SetPitch	Sets normal, compressed, or expanded font pitch. See page E-31.
P$SetTabStops	Sets the tab stop increment. See page E-32.
P$SetTextColor	Sets the color for text output. See page E-32.
P$SetTextPosition	Sets a new position for the next print operation adjusted from the top or bottom of the current font. See page E-33.
P$TextOut	Allows the program to control the position of the text. This provides an alternative to using the COBOL WRITE to print text. See page E-34.
Common Drawing and Text Manipulation Subprograms	**Function**
P$SetDefaultMode	Sets default mode used in positioning and sizing parameters. See page E-35.
P$SetDefaultUnits	Sets default unit of measurement in positioning and sizing parameters. See page E-36.
P$SetLeftMargin	Sets left margin for subsequent printer output. See page E-36.
P$SetTopMargin	Sets the top margin for subsequent printer output. See page E-37.

Table E-1 RM/COBOL Windows Printing Subprogram Library (*Cont.)*

Printer Control Subprograms	Function
P$ChangeDeviceModes	Changes device mode (DEVMODE) values for the standard Windows Print dialog box. Values take effect beginning with the next page. See page E-37.
P$EnableEscapeSequences	Enables RM/COBOL-specific escape sequences. See page E-38.
P$GetDeviceCapabilities	Retrieves the device capabilities of a P$ printer. See page E-39.
P$GetHandle	Retrieves the handle of the current P$ printer. See page E-41.
P$GetPrinterInfo	Retrieves detailed information about a P$ printer. See page E-41.
P$SetHandle	Changes the current P$ printer. See page E-43.
P$SetRawMode	Bypasses Windows printer drivers, enabling printing with escape sequences to a remote Windows NT printer. See page E-43.

Overview

Prior to version 7 of RM/COBOL for Windows, a COBOL Windows application had limited control of printing, as printer and font selection could only be specified using a configuration record. The RM/COBOL 7 for Windows runtime provides enhanced capabilities and flexibility when printing under Windows.

A new predefined printer device, “PRINTER?”, has been added to the RM/COBOL runtime (see page 10-19). When this device is opened, a standard Windows Print dialog box, as shown in Figure E-1, is presented to the user to allow dynamic selection of the Windows printer.

Figure E-1 Standard Windows Print Dialog Box



A broad range of COBOL callable subprograms (P$) has been added to the runtime to allow printer control, font control, drawing of bitmaps, lines, and boxes, color control, positioning of printed objects, and other print-related functions.

These new functions can be applied to a single printer or, if the application uses multiple printers, a printer "handle" is available to allow selection of an open printer on which subsequent P$ subprograms will operate. The printer handle can be ignored by the application if it opens only one printer at a time.

The C$SetDevelopmentMode subprogram may be used to enable expanded error information reporting (known as "development mode") for the P$ subprograms. This may be useful during program development. Development mode may also be used to bracket particular P$ calls by using both C$SetDevelopmentMode and C$ClearDevelopmentMode. These programs are described in Appendix F, *Subprogram Library*.

Note Some of the more advanced printer functions require knowledge of Windows printing structures. Only limited documentation is given here because it is assumed that the developer who requires advanced functions has access to the appropriate Windows documentation.

WARNING Due to differences among printers and printer drivers, output produced using P$ subprograms can vary from printer to printer. To avoid surprises after application deployment, test your application on printers that you plan to support.

Using Windows Printing Functions

The basic steps for using the Windows printing functions are as follows:

1. Open a printer that selects the “PRINTER?” device using the standard COBOL OPEN statement.

   This allows the end-user to choose the desired P$ printer.

2. Optionally retrieve the printer handle by calling P$GetHandle (see page E-41).

   Disregard this step if the application does not open more than one printer at a time.

3. Call various P$ subprograms to control the font, orientation, color, position, and so on, of printed text or drawing objects.

   If more than one printer is opened at one time, call the P$SetHandle subprogram (see page E-43) to switch between them.

4. Intermix P$ subprogram calls with standard COBOL WRITE statements to the printer to produce the desired output.

5. Close the COBOL printer file.

Returning to a "Normal" Font

In order to implement the concept of returning to a “normal” font (after using the RM/COBOL-specific escape sequences, Shift In or Shift Out, to specify expanded or compressed fonts), the RM/COBOL runtime keeps a copy of the normal font for each printer. That normal font is updated whenever the P$SetFont subprogram (see page E-29) or the Print Pitch or Font Height escape sequences (see page E-85) are used.

Common P$ Subprogram Arguments

Many of the P$ subprograms use similar arguments to control positioning, size, color, and other common values. The arguments are described using the following terms: *Position, Size, Point, Amount* and *Increment, Mode, Units, Yes/No,* and *Color*. The descriptions of these types of arguments are given below, but are omitted from the individual subprogram argument descriptions.

- ***Position.*** *XPosition, YPosition, XPoint,* and *YPoint* arguments can be any COBOL numeric data type. The default value for these arguments is the current position. An *XPosition* or *XPoint* argument must have a corresponding *YPosition* or *YPoint* argument, respectively.

  Note 1 For any of the P$Get subprograms receiving a *Position* argument, the format of the receiving field's PICTURE clause varies, depending on the type of *Units* being used. If *Units* is "Device-Units", the format of the PICTURE clause must be PIC S9(10). If *Units* is "Characters", the format of the PICTURE clause must be PIC S9(3). If *Units* is "Inches" or "Metric", the format of the PICTURE clause must be PIC S99v99.

  Note 2 Position 0,0 is the upper-left corner of the printable area of the page.

- ***Alignment.*** *Alignment* arguments can be any alphabetic or alphanumeric COBOL data type. *Alignment* arguments allow the application to specify "Top" alignment or "Bottom" alignment of text positioning. The default mode is "Top" unless changed by the P$SetDefaultAlignment call (see page E-28). Only the first letter of the value is relevant, and it is case-insensitive. Possible values are contained in the WINDEFS.CPY copy file (see page E-69).

- ***Size.*** *Size* arguments can be any COBOL numeric data type. *Size* arguments are used to specify the width (*SizeWidth*) and height (*SizeHeight*) of objects. Except when used with P$DrawBitmap (see page E-19), *Size* arguments have default values of 1 for width and 1 for height.

  Note For any of the P$Get subprograms receiving a *Size* argument, the format of the receiving field's PICTURE clause varies, depending on the type of *Units* being used. If *Units* is "Device-Units", the format of the PICTURE clause must be PIC 9(10). If *Units* is "Characters", the format of the PICTURE clause must be PIC 9(3). If *Units* is "Inches" or "Metric", the format of the PICTURE clause must be PIC 99v99.

- ***Amount and Increment.*** *Amount* and *Increment* arguments can be any COBOL numeric data type. These arguments specify the value of an argument used in subprogram calls.

- ***Mode.*** *Mode* arguments can be any alphabetic or alphanumeric COBOL data type. *Mode* arguments allow the application to specify "Absolute" positioning (with 0,0 being the upper-left corner of the page) or "Relative" positioning (relative to the last printed object or text). The default mode is "Absolute" unless changed by the P$SetDefaultMode call (see page E-35). Only the first letter of the value is relevant, and it is case-insensitive. Possible values are contained in the WINDEFS.CPY copy file (see page E-69).

- ***Units.*** *Units* arguments can be any alphabetic or alphanumeric COBOL data type. *Units* arguments allow the application to select one of four units of measurement: "Inches", "Metric", "Characters", and "Device-Units". "Inches" are expressed in inches with 2.5 meaning 2½ inches and have precision to 1/1000th of an inch. "Metric" is expressed in centimeters and has precision to 1/1000th of a centimeter. "Characters" are expressed in character cell row/column position (computed using the current font). "Device-Units" are expressed in the low-level Windows device unit measurement. The default value for *Units* is "Inches" unless changed by the P$SetDefaultUnits call (see page E-36). Only the first letter of the value is relevant, and it is case-insensitive. Possible values are contained in the WINDEFS.CPY copy file (see page E-69).

- ***Yes/No.*** *Yes/No* arguments can be any alphabetic or alphanumeric COBOL data type. Only the first letter of the value is relevant, and it is case-insensitive. The default value is N (no). For possible values to make the COBOL statement more readable, see the WINDEFS.CPY copy file on page E-69.

- ***Color.*** *Color* arguments may be specified in one of two methods:

  1. Color-name/Percentage method. Any COBOL alphabetic or alphanumeric variable specifying the color-name. For possible values, see Table E-2 and the WINDEFS.CPY copy file on page E-69. A second optional argument indicates the percentage (intensity) to apply to the color value. For example, the following code fragment sets the box shading color to 30 percent red:

     ```
     CALL P$SetBoxShade USING ColorRed 30.
     ```

  2. RGB (Red, Green, Blue) triplet method. These values may be any COBOL numeric data items. Possible values for each data item are 0 through 255. See Table E-2 for a list of default colors to use with RM/COBOL. Note that if you use the RGB triplet method, you must specify a value for all three colors.

Table E-2 Default Colors Used With RM/COBOL

String	78-Level Value	Red, Green, Blue Values
ColorBlack	“Black”	000,000,000
ColorDarkBlue	“Dark Blue”	000,000,127
ColorDarkGreen	“Dark Green”	000,127,000
ColorDarkCyan	“Dark Cyan”	000,127,127
ColorDarkRed	“Dark Red”	127,000,000
ColorDarkMagenta	“Dark Magenta”	127,000,127
ColorBrown	“Brown”	127,127,000
ColorDarkGray	“Dark Gray”	085,085,085
ColorLightGray	“Light Gray”	192,192,192
ColorBlue	“Blue”	000,000,255
ColorGreen	“Green”	000,255,000
ColorCyan	“Cyan”	000,255,255
ColorRed	“Red”	255,000,000
ColorMagenta	“Magenta”	255,000,255
ColorYellow	“Yellow”	255,255,000
ColorWhite	“White” (will not print)	255,255,255

Omitting P$ Subprogram Arguments

The COBOL CALL statement in RM/COBOL now supports the OMITTED keyword to explicitly omit an argument in the USING list. See “CALL Statement” in the *RM/COBOL Language Reference Manual* for more information.

The calling COBOL program may omit arguments by passing fewer arguments than expected or passing the reserved word, OMITTED, for one or more arguments. The following example illustrates how the OMITTED keyword may be used with P$ subprograms.

```
CALL P$SETPOSITION USING 5, 3, OMITTED, "Inches"
```

This example causes the next drawn object to appear at the specified coordinates. The *Mode* argument (see the “Common P$ Subprogram Arguments” topic on page E-7) has been omitted, which causes the RM/COBOL runtime to use the default value for *Mode*.

Windows Print Dialog Box Subprograms

The following subprograms control the configuration of the standard Windows Print dialog box (see page E-5):

- P$ClearDialog
- P$DisplayDialog
- P$EnableDialog
- P$GetDialog
- P$SetDialog

Each subprogram is described in detail in this section beginning on page E-15.

Note 1 P$GetDialog and P$SetDialog use the printer dialog/device mode parameters listed in Table E-3. In this table, the fields listed in the "Parameter Name" column represent the string that must be passed to the P$ subprograms that use the *ParameterName/Value* pairs calling sequence, which allows parameters to be set or changed individually. Possible values are provided in the 78-level entries in the PRINTDLG.CPY copy file, described on page E-51.

The description in the "PICTURE Clause" column indicates whether the field is numeric or alphanumeric and its required number of digits or characters. When setting values using P$SetDialog with the *ParameterName/Value* pairs calling sequence, there is no minimum requirement on the number of digits or characters. When retrieving values using P$GetDialog with the *ParameterName/Value* pairs calling sequence, the PICTURE may specify BINARY and must specify at least the number of digits or characters shown.

Note 2 Some user selections in the Windows Print dialog box must be acted on by the COBOL application, while others will be handled automatically by the device driver. Still other user selections will vary from driver to driver. See "Printing Multiple Copies" on page E-13 and "Printing Partial Reports" on page E-14 for more information.

Table E-3 Printer Dialog/Device Mode Parameters

Parameter Name	PICTURE Clause	Description
Return	PIC X	Standard Windows Print dialog box status: Y = OK N = An error occurred (see Extended Error below).
Extended Error	PIC 9(5)	Extended error code. See PD-ExtendedErrorValue in PRINTDLG.CPY (page E-51) for details.
All Pages Flag	PIC X	"All" radio button is selected.
Selection Flag	PIC X	"Selection" radio button is selected. See "Printing Partial Reports" on page E-14.
Page Numbers Flag	PIC X	"Pages" radio button is selected.
No Selection Flag	PIC X	Disables the "Selection" radio button.
No Page Numbers Flag	PIC X	Disables the "Pages" radio button.
Collate Flag	PIC X	"Collate" check box is checked.
Print Setup Flag	PIC X	Displays the Print Setup dialog box rather than the Print dialog box. The Print dialog box has Print Range and Copies features that are replaced by Paper and Orientation features in the Print Setup dialog box.
Print to File Flag	PIC X	"Print to File" check box is checked.
No Warning Flag	PIC X	Prevents the warning message from being displayed when there is no default printer.
Use Device Mode Copies Flag	PIC X	Indicates whether your application supports multiple copies and collation. See "Printing Multiple Copies" on page E-13.
Disable Print to File Flag	PIC X	Disables the "Print to File" check box.
Hide Print to File Flag	PIC X	Hides the "Print to File" check box.
No Network Button Flag	PIC X	Hides and disables the "Network" button.
From Page	PIC 9(5)	First page to print.
To Page	PIC 9(5)	Last page to print.
Min Page	PIC 9(5)	Minimum value for From Page and To Page. If Min Page equals Max Page, the "Pages" radio button and the starting and ending page edit controls are disabled. See "Printing Partial Reports" on page E-14.

Table E-3 Printer Dialog/Device Mode Parameters *(Cont.)*

Parameter Name	PICTURE Clause	Description
Max Page	PIC 9(5)	Maximum value for From Page and To Page. See “Printing Partial Reports” on page E-14.
Print Dialog Copies	PIC 9(5)	Initial number of copies for the Copies edit control. If a value is specified for Device Name (or any of the parameters following Device Name in this table), the value specified for Device Mode Copies overrides the value specified for Print Dialog Copies. See “Printing Multiple Copies” on page E-13.
Device Name	PIC X(31)	Name of the printer selected by the user.
Fields	Group	**Note** This parameter is not available when using the *ParameterName/Value* pairs calling sequence because the pairs calling sequence automatically sets the appropriate Fields bits when setting Device Mode fields. The Fields parameter is available when using the *PrinterDialogDescription* group data item calling sequence. The developer is responsible for setting the appropriate Fields bits.
Orientation	PIC 9(5)	Portrait versus landscape.
Paper Size	PIC 9(5)	The size of the paper.
Paper Length	PIC 9(5)	Length of the paper (overrides Paper Size).
Paper Width	PIC 9(5)	Width of the paper (overrides Paper Size).
Scale	PIC 9(5)	Scale factor applied while printing, expressed as a percentage. For example, 50 would print text and graphics at 50% of their specified height and width.
Device Mode Copies	PIC 9(5)	The number of copies to print (overrides Print Dialog Copies). See “Printing Multiple Copies” on page E-13.
Default Source	PIC 9(5)	The default paper bin.
Print Quality	PIC S9(5)	High, medium, low, or draft.
Color	PIC 9(5)	Color versus monochrome.
Duplex	PIC 9(5)	One-sided versus two-sided printing.

Table E-3 Printer Dialog/Device Mode Parameters *(Cont.)*

Parameter Name	PICTURE Clause	Description
Y Resolution	PIC 9(5)	Y-resolution of the printer specified in dots-per-inch. If this parameter is set, Print Quality specifies the X-resolution of the printer in dots-per-inch.
True Type Option	PIC 9(5)	TrueType® rendering options.
Collate	PIC X	True or False. See "Printing Multiple Copies" on page E-13.
ICM Method	PIC 9(10)	System-specific. See Microsoft documentation.
ICM Intent	PIC 9(10)	System-specific. See Microsoft documentation.
Media Type	PIC 9(10)	System-specific. See Microsoft documentation.
Dither Type	PIC 9(10)	System-specific. See Microsoft documentation.

Printing Multiple Copies

Creating multiple copies generally requires that the printer driver support printing multiple copies. If the COBOL application is not prepared to generate multiple copies of each page, the PD-UseDevModeCopiesFlag (see the definitions of the PRINTDLG.CPY copy file beginning on page E-51) should be set to TRUE to indicate that the application is depending on the printer driver to print multiple copies.

Not all printers, however, can print multiple copies. If the printer driver does not support printing multiple copies, the "Copies" edit control on the standard Windows Print dialog box (see Figure E-1 on page E-5) will be disabled. Similarly, if the printer driver does not support collation, the "Collate" check box will be disabled. After the printer is opened or the standard Windows Print dialog box is displayed, the application may use P$GetDialog (see page E-17) to retrieve values set by the user in the Windows Print dialog box. The application developer should first check the return information provided by P$DisplayDialog (see page E-16) or by P$GetDialog to determine whether or not the user canceled the Print dialog box. If the application set PD-UseDevModeCopiesFlag to TRUE, P$GetDialog will return PD-Copies with a value of one and PD-CollateFlag set to FALSE.

If the application is prepared to generate multiple copies of each page, the PD-UseDevModeCopiesFlag should be set to FALSE to indicate that the application will handle multiple copies if requested by the user. Similarly, if the PD-UseDevModeCopiesFlag is set to FALSE, the application is responsible for collating multiple copies.

Regardless of how the PD-UseDevModeCopiesFlag is set, an application can determine from PD-Copies and PD-CollateFlag (obtained from P$GetDialog) how many copies to generate and whether to simulate collation by generating the complete report multiple times.

To preset the number of copies in the Windows Print dialog box to a number other than one, the application should set DM-Copies to the desired number and, if not using the *ParameterName/Value* pairs method, set DM-CopiesField to TRUE.

After the printer is opened or the Windows Print dialog box is displayed, the DM-Copies and DM-CollateValue data items (obtained from P$GetDialog) contain the copies and collate information used by the printer driver. If the PD-UseDevModeCopiesFlag is set to FALSE, DM-Copies will contain the number of copies the printer will print, and DM-CollateValue will be zero (FALSE). If the PD-UseDevModeCopiesFlag is set to TRUE and the printer driver supports multiple copies, DM-Copies will contain the number of copies requested by the user and, if the printer driver supports collation, DM-CollateValue will indicate whether the user wants collation.

Remember, fields in the DEVMODE portion of the PRINTDLG.CPY copy file (that is, those fields that begin with the DM- prefix) are meaningful only if the associated item in DM-Fields is set to TRUE. Therefore, it is necessary to set the appropriate item in DM-Fields in addition to setting such values as DM-Copies. Similarly, the application should check the appropriate item in DM-Fields before referencing the associated item after calling P$GetDialog. When using the *ParameterName/Value* pairs method, although it is not necessary to set DM-Fields before using P$SetDialog (see page E-18), it is necessary to check the Validity-Flag when using P$GetDialog.

The example code fragment, “Presetting the Print Dialog Box” on page E-75, illustrates the proper way to set fields before calling P$SetDialog.

Printing Partial Reports

It is possible to print less than a full report, but in order to do this, the application must do all the work. Neither the printer driver nor the RM/COBOL runtime will print partial reports. The COBOL application must generate only the pages selected by the user.

If the application does not support generating partial reports, the PD-NoPageNumbersFlag (see the definitions of the PRINTDLG.CPY copy file beginning

on page E-51) should be set to TRUE to disable the Pages radio button and the associated edit controls on the Windows Print dialog box. Similarly, the PD-NoSelectionFlag may be set to TRUE to disable the Selection radio button.

If the application does support generating partial reports (that is, the PD-NoPageNumbersFlag is set to FALSE), the application should set PD-MinPage and PD-MaxPage to specify the minimum and maximum values, respectively, allowed for the page range specified in the From and To page edit controls. If PD-MinPage and PD-MaxPage have the same value, the Pages radio button and the starting and ending page edit controls are disabled. The application may specify the initial starting and ending pages with PD-FromPage and PD-ToPage. These values must be within the range of PD-MinPage and PD-MaxPage. If the user selects the Pages radio button, then the PD-PageNumberFlag will be set to TRUE when the application calls P$GetDialog to determine what the user selected. Remember to first check the return information provided by P$DisplayDialog (see page E-16) or by P$GetDialog (see page E-17) to determine whether or not the user canceled the Print dialog box. If the user selected a range of pages to print, the range will be returned by P$GetDialog in the PD-FromPage and PD-ToPage fields. It is then the application's responsibility to generate only those pages.

P$ClearDialog

P$ClearDialog is used to clear the standard Windows Print dialog box values back to their default (unset) state.

For an example that includes P$ClearDialog, see "Presetting the Print Dialog Box" on page E-75.

Calling Sequence

```
CALL "P$CLEARDIALOG"
```

P$DisplayDialog

P$DisplayDialog is used to invoke the standard Windows Print dialog box. After choosing a printer with this dialog box, the next open of a "PRINTER?" device will use the selected printer (and no dialog box will appear at that time). See also the discussion of "PRINTER?" on page 10-19.

For an example that includes P$DisplayDialog, see "Checking the Return Code After Displaying the Print Dialog Box" on page E-76.

Calling Sequence

```
CALL "P$DISPLAYDIALOG" GIVING DialogReturn
```

DialogReturn is a COBOL data item that receives the results of the Windows Print dialog box return value. This allows the application to determine whether the dialog was dismissed using the OK or Cancel button, or by an error condition. Possible values are contained in the 78-level entries in the copy file, PRINTDLG.CPY under the heading, "P$DisplayDialog Return Values."

P$EnableDialog

P$EnableDialog is used to control the automatic invoking of the standard Windows Print dialog box when opening a "PRINTER?" device. Normally, the Print dialog box is presented only the first time a dynamic printer is opened. Calling P$EnableDialog causes the Print dialog box to appear the next time a "PRINTER?" device is opened. See also the discussion of "PRINTER?" on page 10-19.

For an example that includes P$EnableDialog, see "Opening and Writing to Separate Printers" on page E-80.

Calling Sequence

```
CALL "P$ENABLEDIALOG"
```

P$GetDialog

P$GetDialog retrieves fields from the standard Windows Print dialog box. The two calling sequences for this subprogram allow parameters to be retrieved either individually or collectively. You can retrieve parameters individually by using *ParameterName/Value/Validity-Flag* triplets. Retrieve parameters collectively using the *PrinterDialogDescription* group data item.

Calling Sequences

```
CALL "P$GETDIALOG" USING PrinterDialogDescription

CALL "P$GETDIALOG" USING ParameterName-1 Value-1
Validity-Flag-1 [ParameterName-n Value-n
Validity-Flag-n...]
```

PrinterDialogDescription is a group data item, as defined in the PRINTDLG.CPY copy file (see page E-51).

ParameterName is an alphanumeric data item that contains the name of the printer dialog or device mode parameter to get (see Table E-3 on page E-11).

Value is a COBOL data item used to get the value of the parameter named by *ParameterName*. Possible values are contained in the 78-level entries in the copy file, PRINTDLG.CPY.

Validity-Flag is a returned numeric data item that indicates the validity of the returned parameter value. A non-zero value indicates a valid parameter.

Note For a more complete discussion of printer dialog and device mode parameters, see the Microsoft Windows documentation for the PRINTDLG and DEVMODE structures. For web site information, see page E-51.

P$SetDialog

P$SetDialog initializes fields for the standard Windows Print dialog box.

The two calling sequences for this subprogram allow parameters to be set either individually or collectively. Setting parameters individually using *ParameterName/Value* pairs allows multiple calls to the subprogram to accumulate values for the standard Windows Print dialog box. Setting parameters collectively using the *PrinterDialogDescription* group data item sets all values, after which the *ParameterName/Value* method can be used to modify values.

For examples that include P$SetDialog, see "Presetting the Print Dialog Box" on page E-75 and "Checking the Return Code After Displaying the Print Dialog Box" on page E-76.

Calling Sequences

```
CALL "P$SETDIALOG" USING PrinterDialogDescription

CALL "P$SETDIALOG" USING ParameterName-1 Value-1
[ParameterName-n Value-n...]
```

PrinterDialogDescription is a group data item, as defined in the PRINTDLG.CPY copy file (see page E-51).

ParameterName is an alphanumeric data item that contains the name of the printer dialog or device mode parameter to set (see Table E-3 on page E-11).

Value is a COBOL data item used to set the value of the parameter named by *ParameterName.* Possible values are contained in the 78-level entries in the copy file, PRINTDLG.CPY.

Note For a more complete discussion of printer dialog and device mode parameters, see the Microsoft Windows documentation for the PRINTDLG and DEVMODE structures. For web site information, see page E-51.

Drawing Subprograms

The following subprograms control the drawing of objects on a printed page:

- P$DrawBitmap
- P$DrawBox
- P$DrawLine
- P$GetPosition
- P$LineTo
- P$MoveTo
- P$SetBoxShade
- P$SetPen
- P$SetPosition

Each subprogram is described in detail in this section.

P$DrawBitmap

P$DrawBitmap is used to print a bitmap file from an existing Windows bitmap file. For an example that includes this subprogram, see "Printing a Bitmap" on page E-77.

Calling Sequence

```
CALL "P$DRAWBITMAP" USING Filename [XPosition
YPosition] [PositionMode] [PositionUnits]
[SizeWidth SizeHeight] [SizeUnits]
```

Filename can be any alphabetic or alphanumeric COBOL data type. It specifies the pathname of the Windows bitmap file to draw.

XPosition/YPosition. See *Position* in "Common P$ Subprogram Arguments" on page E-7.

PositionMode. See *Mode* in "Common P$ Subprogram Arguments."

PositionUnits/SizeUnits. See *Units* in "Common P$ Subprogram Arguments."

SizeWidth and *SizeHeight* are the values used to determine the size of the bitmap. If you specify a value for *SizeWidth*, you must also specify a value for *SizeHeight*. A value of 0,0 indicates that the new bitmap should be the same size as the original bitmap. A value of 0 in one position but not in the other indicates that the new bitmap should be scaled to match the proportions of the original bitmap. For example, a non-zero *SizeWidth* value specifies the width and requests that *SizeHeight* be determined by the original width/height ratio.

P$DrawBox

P$DrawBox is used to draw a box. For examples that include P$DrawBox, see "Drawing Shaded Boxes with Colors" on page E-73 and "Drawing a Box Around Text" on page E-73.

Calling Sequence

```
CALL "P$DRAWBOX" USING [XPosition YPosition]
[PositionMode] [PositionUnits] [SizeWidth
SizeHeight] [SizeUnits] [ShadeYesNo]
```

XPosition/YPosition. See *Position* in "Common P$ Subprogram Arguments" on page E-7.

PositionMode. See *Mode* in "Common P$ Subprogram Arguments."

PositionUnits/SizeUnits. See *Units* in "Common P$ Subprogram Arguments."

SizeWidth/SizeHeight. See *Size* in "Common P$ Subprogram Arguments."

ShadeYesNo is an alphanumeric data item that specifies a yes/no value (see *Yes/No* in "Common P$ Subprogram Arguments"). It specifies whether or not to shade the interior of the box using the current box shading color (set with P$SetBoxShade, described on page E-22).

P$DrawLine

P$DrawLine is used to draw a line. For an example that includes P$DrawLine, see "Drawing a Ruler" on page E-74.

Calling Sequence

```
CALL "P$DRAWLINE" USING [X1Point Y1Point]
[Point1Mode] [Point1Units] [X2Point Y2Point]
[Point2Mode] [Point2Units]
```

XnPoint/YnPoint. See *Position* in "Common P$ Subprogram Arguments" on page E-7.

PointnMode. See *Mode* in "Common P$ Subprogram Arguments."

PointnUnits. See *Units* in "Common P$ Subprogram Arguments."

P$GetPosition

P$GetPosition is used to retrieve the ending position of the last print operation. For instance, P$GetPosition could be used to return to a previous position after printing a bitmap elsewhere on the page.

For an example that includes P$GetPosition, see “Setting Text Position” on page E-84.

Calling Sequence

```
CALL "P$GETPOSITION" USING XPosition YPosition [Units]
```

XPosition/YPosition. See *Position* in “Common P$ Subprogram Arguments” on page E-7.

Units. See *Units* in “Common P$ Subprogram Arguments.”

P$LineTo

P$LineTo is used to draw a line starting at the current position.

For an example that includes P$LineTo, see “Drawing a Ruler” on page E-74.

Calling Sequence

```
CALL "P$LINETO" USING [XPoint YPoint] [Mode] [Units]
```

XPoint/YPoint. See Position in “Common P$ Subprogram Arguments” on page E-7.

Mode. See *Mode* in “Common P$ Subprogram Arguments.”

Units. See *Units* in “Common P$ Subprogram Arguments.”

P$MoveTo

P$MoveTo is used to reposition the line-draw pen without drawing a line.

For an example that includes P$MoveTo, see “Drawing a Ruler” on page E-74.

Calling Sequence

```
CALL "P$MOVETO" USING [XPoint YPoint] [Mode] [Units]
```

XPoint/YPoint. See *Position* in “Common P$ Subprogram Arguments” on page E-7.

Mode. See *Mode* in “Common P$ Subprogram Arguments.”

Units. See *Units* in “Common P$ Subprogram Arguments.”

P$SetBoxShade

P$SetBoxShade is used to set color and density of the color used in P$DrawBox (see page E-20) calls.

For an example that includes P$SetBoxShade, see “Drawing Shaded Boxes with Colors” on page E-73.

Calling Sequence

```
CALL "P$SETBOXSHADE" USING [Color]
```

Color. See *Color* in “Common P$ Subprogram Arguments” on page E-7.

P$SetPen

P$SetPen is used to set the style, width, and color of the pen used in P$DrawBox (see page E-20), P$DrawLine (see page E-20), and P$LineTo (see page E-21) calls.

For an example that includes P$SetPen, see "Drawing Shaded Boxes with Colors" on page E-73.

Calling Sequence

```
CALL "P$SETPEN" USING Style [Width] [Color]
```

Style can be any COBOL numeric data type. It specifies the style of the pen. Possible values are contained in the WINDEFS.CPY copy file (see page E-69).

Width can be any COBOL numeric data type. It specifies the pen width in logical units. If *Width* is zero, the pen is a single pixel wide. The default value is 1.

Note If you specify a *Width* value greater than 1 for the pen styles, Dash, Dot, DashDot, or DashDotDot, Windows will force *Style* to a value of Solid.

Color. See *Color* in "Common P$ Subprogram Arguments" on page E-7.

P$SetPosition

P$SetPosition is used to set a position for the next print operation.

For examples that include P$SetPosition, see "Drawing a Box Around Text" on page E-73 and "Setting Text Position" on page E-84.

Calling Sequence

```
CALL "P$SETPOSITION" USING [XPosition YPosition]
[Mode] [Units]
```

XPosition/YPosition. See *Position* in "Common P$ Subprogram Arguments" on page E-7.

Mode. See *Mode* in "Common P$ Subprogram Arguments."

Units. See *Units* in "Common P$ Subprogram Arguments."

Text Manipulation Subprograms

The following subprograms control the manipulation of text on a printed page:

- P$ClearFont
- P$GetTextExtent
- P$GetTextMetrics
- P$GetTextPosition
- P$SetDefaultAlignment
- P$SetFont
- P$SetLineExtendMode
- P$SetPitch
- P$SetTabStops
- P$SetTextColor
- P$SetTextPosition
- P$TextOut

Each subprogram is described in detail in this section.

P$ClearFont

P$ClearFont clears the font description values that were set using the P$SetFont subprogram (see page E-29) and returns them to their default (unset) state. This subprogram can be used to clear previous values before calling P$SetFont using the *ParameterName/Value* method to set information for a new font.

Calling Sequence

```
CALL "P$CLEARFONT"
```

P$GetTextExtent

P$GetTextExtent is used to retrieve the bounding rectangle size for text passed to the subprogram, calculated using the current font size. The returned values can be used to draw boxes around text or determine whether the text will fit within a desired region (such as the current line).

For examples that include P$GetTextExtent, see “Drawing a Box Around Text” on page E-73, “Printing Text at the Top of a Page” on page E-81, and “Printing Text at the Corners of a Page” on page E-82.

Calling Sequence

```
CALL "P$GETTEXTEXTENT" USING Text, SizeWidth,
SizeHeight [Units]
```

Text can be any alphabetic or alphanumeric COBOL data type, where *n* must be at least 1. It specifies the text to use in calculating the bounding rectangle.

SizeWidth/SizeHeight. See *Size* in “Common P$ Subprogram Arguments” on page E-7.

Units. See *Units* in “Common P$ Subprogram Arguments.”

P$GetTextMetrics

P$GetTextMetrics is used to retrieve the characteristics of the current font. Figure E-2 illustrates some of these characteristics.

For examples that include P$GetTextMetrics, see “Drawing a Box Around Text” on page E-73 and “Setting the Point Size for a Font” on page E-83.

Figure E-2 Text Metrics



The two calling sequences for this subprogram allow parameters to be retrieved either individually or collectively. You can retrieve parameters individually by using *ParameterName/Value* pairs. Retrieve parameters collectively using the *TextMetricDescription* group data item.

Note The values retrieved by P$GetTextMetrics are available after opening a P$ printer. All values returned by P$GetTextMetrics are in device units.

Calling Sequences

```
CALL "P$GETTEXTMETRICS" USING TextMetricDescription

CALL "P$GETTEXTMETRICS" USING ParameterName-1 Value-1
[ParameterName-n Value-n ...]
```

TextMetricDescription is a group data item as defined in the TXTMTRIC.CPY copy file (see page E-65).

ParameterName is an alphanumeric data item that contains the name of the font parameter to get (see Table E-4).

Value is a COBOL data item used to receive the value of the parameter named by *ParameterName*. Possible values are contained in the 78-level entries in the copy file, TXTMTRIC.CPY.

Note For a more complete discussion of text metric parameters, see the Microsoft Windows documentation for the TEXTMETRIC structure. For web site information, see page E-65.

Table E-4 Text Metric Parameters

Parameter Name	PICTURE Clause	Description
Height	PIC 9(10)	Ascender line to descender line.
Ascent	PIC 9(10)	Ascender line to baseline.
Descent	PIC 9(10)	Baseline to descender line.
Internal Leading	PIC 9(10)	Point size of a font minus the physical size of the font.
External Leading	PIC 9(10)	Extra space to be added between lines.
Average Character Width	PIC 9(10)	Average character width for a font.
Maximum Character Width	PIC 9(10)	Width of the widest character.
Weight	PIC 9(10)	Font weight.
Overhang	PIC 9(10)	Extra width added to some synthesized fonts.
Digitized Aspect X	PIC 9(10)	Horizontal aspect of the device for which the font was designed.
Digitized Aspect Y	PIC 9(10)	Horizontal aspect of the device for which the font was designed. The ratio of Digitized Aspect X and Digitized Aspect Y is the aspect ratio of the device for which the font was designed.
First Character	PIC X	First character defined in the font.
Last Character	PIC X	Last character defined in the font.
Default Character	PIC X	Character that will be substituted for characters that are not in the font.
Break Character	PIC X	Character that will be used for word breaks in text justification.
Italic	PIC X	‘Y’ if italic font; ‘N’ otherwise.
Underlined	PIC X	‘Y’ if underlined font; ‘N’ otherwise.
Struck Out	PIC X	‘Y’ if “struck-out” font; ‘N’ otherwise.
Pitch	PIC 9(10)	Pitch of the font.
Family	PIC 9(10)	Family of the font.
Character Set	PIC 9(10)	Character set of the font.

P$GetTextPosition

P$GetTextPosition is used to retrieve the ending position the last print operation adjusted to the top or bottom of the current font.

For examples that include P$GetTextPosition, see “Drawing a Box Around Text” on page E-73 and “Setting Text Position” on page E-84.

Calling Sequence

```
CALL "P$GETTEXTPOSITION" USING XPosition YPosition
[Alignment] [Units]
```

XPosition/YPosition. See *Position* in “Common P$ Subprogram Arguments” on page E-7.

Alignment. See *Alignment* in “Common P$ Subprogram Arguments.”

Units. See *Units* in “Common P$ Subprogram Arguments.”

Note The P$GetPosition subprogram (see page E-21) returns the ending “baseline” position. P$GetTextPosition should be used when you need the ascender line (top) or descender line (bottom) position of the current font.

P$SetDefaultAlignment

P$SetDefaultAlignment is used to set default alignment used in text positioning. Possible values are “Top” and “Bottom”. The initial value is “Top”.

Calling Sequence

```
CALL "P$SETDEFAULTALIGNMENT" USING Alignment
```

Alignment. See *Alignment* in “Common P$ Subprogram Arguments” on page E-7.

P$SetFont

P$SetFont is used to change fonts. Selecting a font with this subprogram call causes the next COBOL WRITE or OPEN operation on a P$ printer to use that newly selected font.

The two calling sequences for this subprogram allow parameters to be set either individually or collectively. Setting parameters individually using *ParameterName/Value* pairs allows multiple calls to the subprogram to accumulate values for the desired font. Setting parameters collectively using the *LogicalFontDescription* group data item sets all values, after which the *ParameterName/Value* method can be used to modify values.

For examples that include this subprogram, see "Printing a Watermark" on page E-73, “Changing a Font While Printing” on page E-77, "Using the COBOL WRITE Statement to Print Multiple Text Outputs on the Same Line" on page E-78, “Setting the Point Size for a Font” on page E-83, and “Setting Text Position” on page E-84.

Note The values set by P$SetFont are available to P$GetTextMetrics (see page E-25) after the OPEN for the printer. You can use P$ClearFont (see page E-24) to clear the existing font description before calling P$SetFont using the *ParameterName/Value* method to set information for a new font.

Calling Sequences

```
CALL "P$SETFONT" USING LogicalFontDescription

CALL "P$SETFONT" USING ParameterName-1 Value-1
[ParameterName-n Value-n...]
```

LogicalFontDescription is a group data item as defined in the LOGFONT.CPY copy file (see page E-47).

ParameterName is an alphanumeric data item that contains the name of the font parameter to set (see Table E-5).

Value is the COBOL data item used to set the value of the parameter named by *ParameterName.* Possible values are contained in the 78-level entries in the copy file, LOGFONT.CPY.

Note For a more complete discussion of font attribute parameters, see the Microsoft Windows documentation for the LOGFONT structure. For web site information, see page E-47.

Table E-5 Font Parameters

Parameter Name	COBOL Data Type	Description
Height	Any numeric	Font height in logical units.
Width	Any numeric	Average font width in logical units.
Escapement	Any numeric	Angle, in tenths of degrees, for a string of characters (relative to the X-axis of the device).
Orientation	Any numeric	Angle, in tenths of degrees, for individual characters (relative to the X-axis of the device).
Weight	Any numeric	Font weight in the range 0 through 1000. For example, 400 is normal and 700 is bold. If this value is zero, a default weight is used.
Italic	Any alphabetic or alphanumeric	'Y' if italic font; 'N' otherwise.
Underline	Any alphabetic or alphanumeric	'Y' if underlined font; 'N' otherwise.
Strike Out	Any alphabetic or alphanumeric	'Y' if "struck-out" font; 'N' otherwise.
Char Set	Any numeric	Specifies the character set.
Out Precision	Any numeric	Specifies the output precision for font matching.
Clip Precision	Any numeric	Specifies the clipping precision for font matching.
Quality	Any numeric	Specifies the output quality for font matching.
Pitch	Any numeric	Pitch of the font.
Family	Any numeric	Family of the font.
Face Name	Any alphabetic or alphanumeric	Windows typeface name.

P$SetLineExtendMode

P$SetLineExtendMode is used to concatenate output from two COBOL WRITE statements on the same line. This is useful for mixing fonts or styles. Specifically, by using the COBOL WRITE statement, then calling P$SetLineExtendMode, and using another WRITE statement with the ADVANCING phrase specifying 0 lines, the output from the second WRITE statement will appear on the same line as the output from the first WRITE statement.

For an example that includes P$SetLineExtendMode, see "Using the COBOL WRITE Statement to Print Multiple Text Outputs on the Same Line" on page E-78.

Calling Sequence

```
CALL "P$SETLINEEXTENDMODE" USING SpaceAmount [Units]
```

SpaceAmount can be any COBOL numeric data type. It specifies the amount of space to leave between the two sets of output. The default value is 0.

Units. See *Units* in "Common P$ Subprogram Arguments" on page E-7.

P$SetPitch

P$SetPitch is used to set normal, compressed, or expanded font pitch.

For an example that includes P$SetPitch, see "Changing Orientation and Pitch" on page E-79.

Calling Sequence

```
CALL "P$SETPITCH" USING Type [Factor]
```

Type can be any alphabetic or alphanumeric COBOL data type. It specifies "Normal", "Expanded", or "Compressed" font pitch. Only the first letter of the value is relevant, and it is case-insensitive. Possible values are contained in the 78-level entries in the WINDEFS.CPY copy file (see page E-69).

Factor can be any numeric COBOL data type. It specifies the compression/expansion ratio to apply to the current font pitch. The default values are 1.65 for "Compressed" (1.65 times as many characters per inch) and 0.5 for "Expanded" (half as many characters per inch). A *Type* value of "Normal" does not allow the *Factor* argument, that is, "Normal" is the current font's normal pitch.

P$SetTabStops

P$SetTabStops sets the increment used for computing the next tab stop location. Tabs are sent using the Horizontal Tab escape sequence (see Table E-9 on page E-85).

Calling Sequence

```
CALL "P$SETTABSTOPS" USING Increment [Units]
```

Increment. See *Increment* in "Common P$ Subprogram Arguments" on page E-7.

Units. See *Units* in "Common P$ Subprogram Arguments."

P$SetTextColor

P$SetTextColor is used to set the color of text for subsequent P$TextOut (see page E-34) and COBOL WRITE statements.

For an example that includes P$SetTextColor, see "Printing a Watermark" on page E-73.

Calling Sequence

```
CALL "P$SETTEXTCOLOR" USING Color
```

Color. See *Color* in "Common P$ Subprogram Arguments" on page E-7.

P$SetTextPosition

P$SetTextPosition is used to set a new position for the next print operation adjusted from the top or bottom of the current font.

For examples that include P$SetTextPosition, see “Printing Text at the Top of a Page” on page E-81, “Printing Text at the Corners of a Page” on page E-82, and “Setting Text Position” on page E-84.

Calling Sequence

```
CALL "P$SETTEXTPOSITION" USING XPosition YPosition
[Alignment] [Mode] [Units]
```

XPosition/YPosition. See *Position* in “Common P$ Subprogram Arguments” on page E-7.

Alignment. See *Alignment* in “Common P$ Subprogram Arguments.”

Mode. See *Mode* in “Common P$ Subprogram Arguments.”

Units. See *Units* in “Common P$ Subprogram Arguments.”

Note 1 The P$SetPosition subprogram (see page E-23) should be used to set the “baseline” for the next text print operation.

Note 2 To print a line of text in the top left corner of a page, without cutting off the top of the characters, call P$SetTextPosition specifying a value of “Top” for *Alignment*. To print a line of text in the bottom left corner of a page without cutting off the bottom of the characters, call P$SetTextPosition specifying a value of “Bottom” for *Alignment*.

P$TextOut

P$TextOut is an alternative to using the COBOL WRITE statement to print text. It allows the program to control the position of the text. The COBOL WRITE statement has no positioning capabilities.

For examples that include P$TextOut, see “Drawing a Box Around Text” on page E-73, “Changing a Font While Printing” on page E-77, “Changing Orientation and Pitch” on page E-79, “Opening and Writing to Separate Printers” on page E-80, “Printing Text at the Top of a Page” on page E-81, “Printing Text at the Corners of a Page” on page E-82, and “Setting Text Position” on page E-84.

Calling Sequence

```
CALL "P$TEXTOUT" USING Text [XPosition YPosition]
[Mode] [Units] [BoxYesNo] [ShadeYesNo]
```

Text can be any COBOL alphanumeric data item. It specifies the text to be printed.

XPosition/YPosition. See *Position* in “Common P$ Subprogram Arguments” on page E-7.

Mode. See *Mode* in “Common P$ Subprogram Arguments.”

Units. See *Units* in “Common P$ Subprogram Arguments.”

BoxYesNo can be any COBOL alphanumeric data item that specifies a yes/no value (see *Yes/No* in “Common P$ Subprogram Arguments”). It specifies whether or not to draw a box around the text.

ShadeYesNo can be any COBOL alphanumeric data item that specifies a yes/no value (see *Yes/No* in “Common P$ Subprogram Arguments”). It specifies whether or not to shade the interior of the box using the current box shading color (set with P$SetBoxShade, described on page E-22).

Common Drawing and Text Manipulation Subprograms

The following subprograms are common to both drawing and text manipulation activities:

- P$SetDefaultMode
- P$SetDefaultUnits
- P$SetLeftMargin
- P$SetTopMargin

Each subprogram is described in detail in this section.

P$SetDefaultMode

P$SetDefaultMode is used to control the default mode used in positioning and sizing parameters. Possible values are “Relative” and “Absolute”. The initial value is “Absolute”.

Calling Sequence

```
CALL "P$SETDEFAULTMODE" USING Mode
```

Mode. See *Mode* in “Common P$ Subprogram Arguments” on page E-7.

P$SetDefaultUnits

P$SetDefaultUnits is used to control the default unit of measurement in position and sizing parameters. Possible values are “Inches”, “Metric”, “Characters”, and “Device-Units”. The initial value is “Inches”.

For an example that includes P$SetDefaultUnits, see “Drawing a Ruler” on page E-74.

Calling Sequence

```
CALL "P$SETDEFAULTUNITS" USING Units
```

Units. See *Units* in “Common P$ Subprogram Arguments” on page E-7.

P$SetLeftMargin

P$SetLeftMargin is used to set a left margin (offset from left side of paper) for subsequent COBOL WRITE statements. This margin will be cleared to zero at the next page boundary. This subprogram is useful for generating columns of text.

Calling Sequence

```
CALL "P$SETLEFTMARGIN" USING SizeWidth [Units]
```

SizeWidth. See *Size* in “Common P$ Subprogram Arguments” on page E-7.

Units. See *Units* in “Common P$ Subprogram Arguments.”

P$SetTopMargin

P$SetTopMargin is used to set a top margin (offset from top edge of paper) for subsequent pages.

Calling Sequence

```
CALL "P$SETTOPMARGIN" USING SizeHeight [Units]
```

SizeHeight. See *Size* in "Common P$ Subprogram Arguments" on page E-7.

Units. See *Units* in "Common P$ Subprogram Arguments."

Printer Control Subprograms

The following subprograms are used to control various properties of a P$ printer:

- P$ChangeDeviceModes
- P$EnableEscapeSequences
- P$GetDeviceCapabilities
- P$GetHandle
- P$GetPrinterInfo
- P$SetHandle
- P$SetRawMode

Each subprogram is described in detail in this section.

P$ChangeDeviceModes

P$ChangeDeviceModes changes the device mode (DEVMODE) values for the standard Windows Print dialog box. The new values take effect beginning with the next page. This subprogram is used for such tasks as changing the paper source or the orientation of paper.

The two calling sequences for this subprogram allow parameters to be set either individually or collectively. Setting parameters individually using *ParameterName/Value* pairs allows multiple calls to the subprogram to accumulate values for the standard Windows Print dialog box (see page E-5). Setting parameters collectively using the *PrinterDialogDescription* group data item sets all values, after which the *ParameterName/Value* method can be used to modify values.

Note Only DEVMODE fields of the *PrinterDialogDescription* can be changed by this subprogram. These fields are defined in the PRINTDLG.CPY copy file and have a DM- prefix.

For an example that includes P$ChangeDeviceModes, see "Changing Orientation and Pitch" on page E-79.

Calling Sequences

```
CALL "P$CHANGEDEVICEMODES" USING PrinterDialogDescription

CALL "P$CHANGEDEVICEMODES" USING ParameterName-1 Value-1
[ParameterName-n Value-n...]
```

PrinterDialogDescription is a group data item, as defined in the PRINTDLG.CPY copy file (see page E-51).

ParameterName is an alphanumeric data item that contains the name of the printer dialog/device mode parameter to set (see Table E-3 on page E-11).

Value is the COBOL data item used to set the value of the parameter named by *ParameterName.* Possible values are contained in the 78-level entries in the copy file, PRINTDLG.CPY.

Note For a more complete discussion of device mode parameters, see the Microsoft Windows documentation for the DEVMODE structure. For web site information, see page E-51.

P$EnableEscapeSequences

P$EnableEscapeSequences is used to enable RM/COBOL-specific escape sequences, as described on page E-85. (This subprogram is used in conjunction with the ESCAPE-SEQUENCES keyword of the DEFINE-DEVICE configuration record. See page 10-17 for more information.)

Calling Sequence

```
CALL "P$EnableEscapeSequences"
```

P$GetDeviceCapabilities

P$GetDeviceCapabilities is used to retrieve the device capabilities of a P$ printer. This subprogram can be used to compute the printable area of the page to be printed.

The two calling sequences for this subprogram allow parameters to be retrieved either individually or collectively. You can retrieve parameters individually using *ParameterName/Value* pairs. Retrieve parameters collectively using the *DeviceCapabilitesDescription* group data item.

Note The values retrieved by P$GetDeviceCapabilities are available after opening a P$ printer**.**

For examples that include P$GetDeviceCapabilities, see “Setting the Point Size for a Font” on page E-83, “Printing Text at the Top of a Page” on page E-81, and “Printing Text at the Corners of a Page” on page E-82.

Calling Sequences

```
CALL "P$GETDEVICECAPABILITIES" USING TextMetricDescription

CALL "P$GETDEVICECAPABILITIES" USING ParameterName-1
Value-1 [ParameterName-n Value-n...]
```

DeviceCapabilitesDescription is a group data item, as defined in the DEVCAPS.CPY copy file (see page E-45).

ParameterName is an alphanumeric data item that contains the name of the device capability parameter (see Table E-6).

Value is the COBOL data item used to receive the value of the parameter named by *ParameterName.* Possible values are contained in the 78-level entries in the copy file, DEVCAPS.CPY.

Note For a more complete discussion of device capability parameters, see the Microsoft Windows documentation for the GetDeviceCaps function. For web site information, see page E-45.

Table E-6 Device Capability Parameters

Parameter Name	PICTURE Clause	Description
Driver Version	PIC 9(10)	Device driver version.
Technology	PIC 9(10)	Device technology.
Horizontal Size	PIC 9(10)	Width of printable area, in millimeters.
Vertical Size	PIC 9(10)	Height of printable area, in millimeters.
Horizontal Resolution	PIC 9(10)	Width of printable area, in dots.
Vertical Resolution	PIC 9(10)	Height of printable area, in dots.
Logical Pixels X	PIC 9(10)	Horizontal dots-per-inch.
Logical Pixels Y	PIC 9(10)	Vertical dots-per-inch.
Aspect X	PIC 9(10)	Length of horizontal sides of a square.
Aspect Y	PIC 9(10)	Length of vertical sides of the same square.
Aspect XY	PIC 9(10)	Length of diagonal lines connecting opposite vertices of the same square.
Physical Width	PIC 9(10)	Width of the printable area, in device units.
Physical Height	PIC 9(10)	Height of the printable area, in device units.
Physical Offset X	PIC 9(10)	Width of unprintable area (left and right edges) in device units.
Physical Offset Y	PIC 9(10)	Height of unprintable area (top and bottom edges) in device units.
Scaling Factor X	PIC 9(10)	X-axis scale factor.
Scaling Factor Y	PIC 9(10)	Y-axis scale factor.

P$GetHandle

P$GetHandle is used to retrieve the handle of the current P$ printer. This allows the developer to use P$SetHandle (see page E-43) to change the printer for subsequent P$ print operations. These calls are not needed unless multiple "PRINTER?" devices are open at the same time. See also the discussion of "PRINTER?" on page 10-19. For an example that includes P$GetHandle, see "Opening and Writing to Separate Printers" on page E-80.

Calling Sequence

```
CALL "P$GETHANDLE" USING Handle
```

Handle is a PICTURE 9(2) numeric data item. It specifies the variable to receive the handle of the current P$ printer.

P$GetPrinterInfo

P$GetPrinterInfo is used to retrieve detailed information about a P$ printer.

The two calling sequences for this subprogram allow parameters to be retrieved either individually or collectively. You can retrieve parameters individually using *ParameterName/Value* pairs. Retrieve parameters collectively using the *PrinterInfoDescription* group data item.

Calling Sequences

```
CALL "P$GETPRINTERINFO" USING PrinterInfoDescription

CALL "P$GETPRINTERINFO" USING ParameterName-1
Value-1 [ParameterName-n Value-n...]
```

PrinterInfoDescription is a group data item, as defined in the PRINTINF.CPY copy file (see page E-62).

ParameterName is an alphanumeric data item that contains the name of the device capability parameter to get (see Table E-7).

Value is the COBOL data item used to receive the value of the parameter named by *ParameterName.* Possible values are contained in the 78-level entries in the copy file, PRINTINF.CPY.

Note For a more complete discussion of printer information parameters, see the Microsoft Windows documentation for the PRINTER_INFO_2 structure. For web site information, see page E-62.

Table E-7 Printer Information Parameters

Parameter Name	PICTURE Clause	Description
Server Name	PIC X(80)	Name of the server that controls the printer.
Printer Name	PIC X(80)	Name of the printer.
Share Name	PIC X(80)	Shared name of the printer
Port Name	PIC X(80)	Port(s) used to transmit data to the printer.
Driver Name	PIC X(80)	Name of the printer driver.
Comment	PIC X(80)	A brief description of the printer.
Location	PIC X(80)	Physical location of the printer.
Sep File	PIC X(80)	Name of file used to create the separator page.
Print Processor	PIC X(80)	Name of the print processor used by the printer.
Data Type	PIC X(80)	Data type used to record the print job.
Parameters	PIC X(80)	Default print-processor parameters.
Attributes	Group	**Note** This parameter is not available when using the *ParameterName/Value* pairs calling sequence. It is available only when using the *PrinterInfoDescription* group data item calling sequence.
Priority	PIC 9(10)	Print spooler priority.
Default Priority	PIC 9(10)	Default spooler priority.
Start Time	PIC 9(10)	Earliest allowed print time, in minutes, after midnight GMT.
Until Time	PIC 9(10)	Latest allowed print time, in minutes, after midnight GMT.
Status	Group	**Note** This parameter is not available when using the *ParameterName/Value* pairs calling sequence. It is available only when using the *PrinterInfoDescription* group data item calling sequence.
Jobs	PIC 9(10)	Number of jobs in the print queue.
Average PPM	PIC 9(10)	Average print speed in pages-per-minute.

P$SetHandle

P$SetHandle is used to change the current P$ printer. This call is not needed unless multiple "PRINTER?" devices are open at the same time. See also the discussion of "PRINTER?" on page 10-19.

For an example that includes P$SetHandle, see "Opening and Writing to Separate Printers" on page E-80.

Calling Sequence

```
CALL "P$SETHANDLE" USING Handle
```

Handle can be any COBOL numeric data item. It specifies the variable that contains the handle of the printer to use in subsequent P$ calls.

P$SetRawMode

P$SetRawMode is used to set a raw mode output when the next printer is opened. This subprogram allows completely raw byte-stream I/O in applications that require it. It is intended to be used when a user is having problems sending escape sequences to networked printers on a Windows NT server. The RAW keyword of the DEFINE-DEVICE configuration record (see page 10-17) or the Printer Enable Raw Mode property (see page 3-26) may also be used to set raw mode output for a printer.

Only the following P$ subprograms can be used for a raw mode printer:

- P$ClearDialog (see page E-13)
- P$DisplayDialog (see page E-16)
- P$EnableDialog (see page E-16)
- P$GetDialog (see page E-17)
- P$SetDialog (see page E-18)
- P$GetDeviceCapabilities (see page E-39)
- P$GetHandle (see page E-41)
- P$GetPrinterInfo (see page E-41)
- P$SetHandle (see page E-43)

Calling Sequence

```
CALL "P$SETRAWMODE"
```

Copy Files

The RM/COBOL development system supplies COBOL copy files to facilitate Windows printing program development using P$ subprograms.

The following copy files are supplied:

- **DEVCAPS.CPY**, shown on page E-45, is associated with the P$GetDeviceCapabilities subprogram (see page E-39).
- **LOGFONT.CPY**, shown on page E-47, is associated with the P$SetFont subprogram (see page E-29).
- **PRINTDLG.CPY**, shown on page E-51, is associated with the following subprograms:
  - P$ChangeDeviceModes (see page E-37)
  - P$GetDialog (see page E-17)
  - P$SetDialog (see page E-18)
- **PRINTINF.CPY**, shown on page E-62, is associated with the P$GetPrinterInfo subprogram (see page E-41).
- **TXTMTRIC.CPY**, shown on page E-65, is associated with the P$GetTextMetrics subprogram (see page E-25).
- **WINDEFS.CPY**, shown on page E-69, contains miscellaneous items used by several P$ subprograms. This copy file is also used with C$PlaySound subprogram (see Appendix F, *Subprogram Library*).

WARNING We strongly recommend that you do not change these Liant-supplied copy files, as unpredictable results may occur if the copy files are changed incorrectly. If you must alter the files, please be aware that the names of the data items are the only thing that can be changed. Do not alter the pictures, types, sizes, or order of the data items.

DEVCAPS.CPY

Information regarding the Microsoft Windows GetDeviceCaps function can be found on the Internet at http://msdn.microsoft.com/library/. Periodically, Microsoft reorganizes the MSDN information on the web site. Use the search capability to find information on the requested topic.

The following search tree was accurate when this document went to print:

```
Platform SDK
 Graphics and Multimedia Services
  Windows GDI
   Device Contexts
    Device Context Reference
     Device Context Functions
      GetDeviceCaps
```

DEVCAPS.CPY contains the following definitions.

```
*
*   Device Capabilities Definitions
*
 01 DeviceCapabilities.
    02  DC-DriverVersion              Picture 9(10) Binary(4).
    02  DC-TechnologyValue            Picture 9     Binary(4).
        88  DC-TechnologyIsPlotter      Value 0.
        88  DC-TechnologyIsRASDisplay   Value 1.
        88  DC-TechnologyIsRASPrinter   Value 2.
        88  DC-TechnologyIsRASCamera    Value 3.
        88  DC-TechnologyIsCharStream   Value 4.
        88  DC-TechnologyIsRASMetafile  Value 5.
        88  DC-TechnologyIsRASDispfile  Value 6.
    02  DC-HorzSize                   Picture 9(10) Binary(4).
    02  DC-VertSize                   Picture 9(10) Binary(4).
    02  DC-HorzRes                    Picture 9(10) Binary(4).
    02  DC-VertRes                    Picture 9(10) Binary(4).
    02  DC-LogPixelsX                 Picture 9(10) Binary(4).
    02  DC-LogPixelsY                 Picture 9(10) Binary(4).
    02  DC-AspectX                    Picture 9(10) Binary(4).
    02  DC-AspectY                    Picture 9(10) Binary(4).
    02  DC-AspectXY                   Picture 9(10) Binary(4).
    02  DC-PhysicalWidth              Picture 9(10) Binary(4).
    02  DC-PhysicalHeight             Picture 9(10) Binary(4).
```

```
    02  DC-PhysicalOffsetX          Picture 9(10) Binary(4).
    02  DC-PhysicalOffsetY          Picture 9(10) Binary(4).
    02  DC-ScalingFactorX           Picture 9(10) Binary(4).
    02  DC-ScalingFactorY           Picture 9(10) Binary(4).
*
*   Technology Values
*
 78 DC-TechnologyPlotter              Value 0.
 78 DC-TechnologyRASDisplay           Value 1.
 78 DC-TechnologyRASPrinter           Value 2.
 78 DC-TechnologyRASCamera            Value 3.
 78 DC-TechnologyCharStream           Value 4.
 78 DC-TechnologyRASMetafile          Value 5.
 78 DC-TechnologyRASDispfile          Value 6.
*
*   Parameter Name Values
*
 78 DC-DriverVersionParam             Value "Driver Version".
 78 DC-TechnologyParam                Value "Technology".
 78 DC-HorizontalSizeParam            Value "Horizontal Size".
 78 DC-VerticalSizeParam              Value "Vertical Size".
 78 DC-HorizontalResolutionParam      Value "Horizontal Resolution".
 78 DC-VerticalResolutionParam        Value "Vertical Resolution".
 78 DC-LogicalPixelsXParam            Value "Logical Pixels X".
 78 DC-LogicalPixelsYParam            Value "Logical Pixels Y".
 78 DC-AspectXParam                   Value "Aspect X".
 78 DC-AspectYParam                   Value "Aspect Y".
 78 DC-AspectXYParam                  Value "Aspect XY".
 78 DC-PhysicalWidthParam             Value "Physical Width".
 78 DC-PhysicalHeightParam            Value "Physical Height".
 78 DC-PhysicalOffsetXParam           Value "Physical Offset X".
 78 DC-PhysicalOffsetYParam           Value "Physical Offset Y".
 78 DC-ScalingFactorXParam            Value "Scaling Factor X".
 78 DC-ScalingFactorYParam            Value "Scaling Factor Y".
```

LOGFONT.CPY

Information regarding the Microsoft Windows LOGFONT structure can be found on the Internet at http://msdn.microsoft.com/library/. Periodically, Microsoft reorganizes the MSDN information on the web site. Use the search capability to find information on the requested topic.

The following search tree was accurate when this document went to print:

```
Platform SDK
 Graphics and Multimedia Services
  Windows GDI
   Fonts and Text
    Font and Text Reference
     Font and Text Structures
      LOGFONT
```

LOGFONT.CPY contains the following definitions.

```
*
*   Logical Font Definitions
*
 01 LogicalFont.
    02  LF-Height                   Picture 9(5) Binary(2).
    02  LF-Width                    Picture 9(5) Binary(2).
    02  LF-Escapement               Picture 9(5) Binary(2).
    02  LF-Orientation              Picture 9(5) Binary(2).
    02  LF-WeightValue              Picture 9(3) Binary(2).
        88  LF-WeightIsDontCare        Value 0.
        88  LF-WeightIsThin            Value 100.
        88  LF-WeightIsExtraLight      Value 200.
        88  LF-WeightIsUltraLight      Value 200.
        88  LF-WeightIsLight           Value 300.
        88  LF-WeightIsNormal          Value 400.
        88  LF-WeightIsRegular         Value 400.
        88  LF-WeightIsMedium          Value 500.
        88  LF-WeightIsSemiBold        Value 600.
        88  LF-WeightIsDemiBold        Value 600.
        88  LF-WeightIsBold            Value 700.
        88  LF-WeightIsExtraBold       Value 800.
        88  LF-WeightIsUltraBold       Value 800.
        88  LF-WeightIsHeavy           Value 900.
        88  LF-WeightIsBlack           Value 900.
```

```
02  LF-ItalicValue               Picture X.
    88  LF-Italic                 Value 'Y'  When False 'N'.
02  LF-UnderlineValue            Picture X.
    88  LF-Underline              Value 'Y'  When False 'N'.
02  LF-StrikeoutValue            Picture X.
    88  LF-Strikeout              Value 'Y'  When False 'N'.
02  LF-CharSetValue              Picture 9(3) Binary(2).
    88  LF-CharSetIsANSI            Value 0.
    88  LF-CharSetIsDefault         Value 1.
    88  LF-CharSetIsSymbol          Value 2.
    88  LF-CharSetIsMAC             Value 77.
    88  LF-CharSetIsShiftJIS        Value 128.
    88  LF-CharSetIsHangeul         Value 129.
    88  LF-CharSetIsJohab           Value 130.
    88  LF-CharSetIsChineseBig5     Value 136.
    88  LF-CharSetIsGreek           Value 161.
    88  LF-CharSetIsTurkish         Value 162.
    88  LF-CharSetIsHebrew          Value 177.
    88  LF-CharSetIsArabic          Value 178.
    88  LF-CharSetIsBaltic          Value 186.
    88  LF-CharSetIsRussian         Value 204.
    88  LF-CharSetIsThai            Value 222.
    88  LF-CharSetIsEastEurope      Value 238.
    88  LF-CharSetIsOEM             Value 255.
02  LF-OutPrecisValue            Picture 9    Binary(2).
    88  LF-OutPrecisIsDefault       Value 0.
    88  LF-OutPrecisIsString        Value 1.
    88  LF-OutPrecisIsStroke        Value 3.
    88  LF-OutPrecisIsTrueType      Value 4.
    88  LF-OutPrecisIsDevice        Value 5.
    88  LF-OutPrecisIsRaster        Value 6.
    88  LF-OutPrecisIsTruTypeOnly   Value 7.
    88  LF-OutPrecisIsOutline       Value 8.
02  LF-ClipPrecisValue           Picture 9(3) Binary(2).
    88  LF-ClipPrecisIsDefault      Value 0.
    88  LF-ClipPrecisIsStroke       Value 2.
    88  LF-ClipPrecisIsLHAngles     Value 16.
    88  LF-ClipPrecisIsEmbedded     Value 128.
02  LF-QualityValue              Picture 9    Binary(2).
    88  LF-QualityIsDefault         Value 0.
    88  LF-QualityIsDraft           Value 1.
    88  LF-QualityIsProof           Value 2.
02  LF-PitchValue                Picture 9    Binary(2).
```

```
           88  LF-PitchIsDefault           Value 0.
           88  LF-PitchIsFixed             Value 1.
           88  LF-PitchIsVariable          Value 2.
       02  LF-FamilyValue                Picture 9    Binary(2).
           88  LF-FamilyIsDontCare         Value 0.
           88  LF-FamilyIsRoman            Value 1.
           88  LF-FamilyIsSwiss            Value 2.
           88  LF-FamilyIsModern           Value 3.
           88  LF-FamilyIsScript           Value 4.
           88  LF-FamilyIsDecorative       Value 5.
       02  LF-FaceName                   Picture X(31).
*
*   Font Weight Values
*
    78 LF-WeightDontCare                  Value 0.
    78 LF-WeightThin                      Value 100.
    78 LF-WeightExtraLight                Value 200.
    78 LF-WeightUltraLight                Value 200.
    78 LF-WeightLight                     Value 300.
    78 LF-WeightNormal                    Value 400.
    78 LF-WeightRegular                   Value 400.
    78 LF-WeightMedium                    Value 500.
    78 LF-WeightSemiBold                  Value 600.
    78 LF-WeightDemiBold                  Value 600.
    78 LF-WeightBold                      Value 700.
    78 LF-WeightExtraBold                 Value 800.
    78 LF-WeightUltraBold                 Value 800.
    78 LF-WeightHeavy                     Value 900.
    78 LF-WeightBlack                     Value 900.
*
*   Font Character Set Values
*
    78 LF-CharSetANSI                     Value 0.
    78 LF-CharSetDefault                  Value 1.
    78 LF-CharSetSymbol                   Value 2.
    78 LF-CharSetMAC                      Value 77.
    78 LF-CharSetShiftJIS                 Value 128.
    78 LF-CharSetHangeul                  Value 129.
    78 LF-CharSetJohab                    Value 130.
    78 LF-CharSetChineseBig5              Value 136.
    78 LF-CharSetGreek                    Value 161.
    78 LF-CharSetTurkish                  Value 162.
    78 LF-CharSetHebrew                   Value 177.
```

```
           78 LF-CharSetArabic                   Value 178.
           78 LF-CharSetBaltic                   Value 186.
           78 LF-CharSetRussian                  Value 204.
           78 LF-CharSetThai                     Value 222.
           78 LF-CharSetEastEurope               Value 238.
           78 LF-CharSetOEM                      Value 255.
          *
          *   Font Output Precision Values
          *
           78 LF-OutPrecisDefault                Value 0.
           78 LF-OutPrecisString                 Value 1.
           78 LF-OutPrecisStroke                 Value 3.
           78 LF-OutPrecisTrueType               Value 4.
           78 LF-OutPrecisDevice                 Value 5.
           78 LF-OutPrecisRaster                 Value 6.
           78 LF-OutPrecisTruTypeOnly            Value 7.
           78 LF-OutPrecisOutline                Value 8.
          *
          *   Font Clipping Precision Values
          *
           78 LF-ClipPrecisDefault               Value 0.
           78 LF-ClipPrecisStroke                Value 2.
           78 LF-ClipPrecisLHAngles              Value 16.
           78 LF-ClipPrecisEmbedded              Value 128.
          *
          *   Font Quality Values
          *
           78 LF-QualityDefault                  Value 0.
           78 LF-QualityDraft                    Value 1.
           78 LF-QualityProof                    Value 2.
          *
          *   Font Pitch Values
          *
           78 LF-PitchDefault                    Value 0.
           78 LF-PitchFixed                      Value 1.
           78 LF-PitchVariable                   Value 2.
          *
          *   Font Family Values
          *
           78 LF-FamilyDontCare                  Value 0.
           78 LF-FamilyRoman                     Value 1.
           78 LF-FamilySwiss                     Value 2.
           78 LF-FamilyModern                    Value 3.
```

```
 78 LF-FamilyScript                    Value 4.
 78 LF-FamilyDecorative                Value 5.
*
*   Parameter Name Values
*
 78 LF-HeightParam                     Value "Height".
 78 LF-WidthParam                      Value "Width".
 78 LF-EscapementParam                 Value "Escapement".
 78 LF-OrientationParam                Value "Orientation".
 78 LF-WeightParam                     Value "Weight".
 78 LF-ItalicParam                     Value "Italic".
 78 LF-UnderlineParam                  Value "Underline".
 78 LF-StrikeOutParam                  Value "Strike Out".
 78 LF-CharSetParam                    Value "Char Set".
 78 LF-OutPrecisionParam               Value "Out Precision".
 78 LF-ClipPrecisionParam              Value "Clip Precision".
 78 LF-QualityParam                    Value "Quality".
 78 LF-PitchParam                      Value "Pitch".
 78 LF-FamilyParam                     Value "Family".
 78 LF-FaceNameParam                   Value "Face Name".
```

PRINTDLG.CPY

Information regarding the Microsoft Windows PRINTDLG and DEVMODE structures can be found on the Internet at http://msdn.microsoft.com/library/. Periodically, Microsoft reorganizes the MSDN information on the web site. Use the search capability to find information on the requested topic.

The following search trees were accurate when this document went to print:

For PRINTDLG:

```
Platform SDK
 User Interface Services
  Windows User Interface
   User Input
    Common Dialog Box Library
     Common Dialog Box Reference
      Common Dialog Box Structures
       PRINTDLG
```

For DEVMODE:

```
Platform SDK
 Graphics and Multimedia Services
  Windows GDI
   Printing and Print Spooler
    Printing and Print Spooler Reference
     Printing and Print Spooler Structures
      DEVMODE
```

PRINTDLG.CPY contains the following definitions.

```
*
*   Print Dialog Definitions
*
 01 PrintDialog.
    02  PD-ReturnValue                  Picture X.
        88  PD-OKReturn                   Value 'Y' When False 'N'.
    02  PD-ExtendedErrorValue           Picture 9(5) Binary(2).
        88  PD-ExtErrIsCanceled           Value 0.
        88  PD-ExtErrIsStructSize         Value 1.
        88  PD-ExtErrIsInitialization     Value 2.
        88  PD-ExtErrIsNoTemplate         Value 3.
        88  PD-ExtErrIsNoHInstance        Value 4.
        88  PD-ExtErrIsLoadStrFailure     Value 5.
        88  PD-ExtErrIsFindResFailure     Value 6.
        88  PD-ExtErrIsLoadResFailure     Value 7.
        88  PD-ExtErrIsLockResFailure     Value 8.
        88  PD-ExtErrIsMemAllocFailure    Value 9.
        88  PD-ExtErrIsMemLockFailure     Value 10.
        88  PD-ExtErrIsNoHook             Value 11.
        88  PD-ExtErrIsRegisterMsgFail    Value 12.
        88  PD-ExtErrIsSetupFailure       Value 4097.
        88  PD-ExtErrIsParseFailure       Value 4098.
        88  PD-ExtErrIsRetDefFailure      Value 4099.
        88  PD-ExtErrIsLoadDrvFailure     Value 4100.
        88  PD-ExtErrIsGetDevModeFail     Value 4101.
        88  PD-ExtErrIsInitFailure        Value 4102.
        88  PD-ExtErrIsNoDevices          Value 4103.
        88  PD-ExtErrIsNoDefaultPrn       Value 4104.
        88  PD-ExtErrIsDNDMMismatch       Value 4105.
        88  PD-ExtErrIsCreateICFailure    Value 4106.
        88  PD-ExtErrIsPrinterNotFound    Value 4107.
        88  PD-ExtErrIsDefaultDifferent   Value 4108.
```

```
    88  PD-ExtErrIsDialogFailure      Value 65535.
02  PD-Flags.
    03  PD-AllPagesFlagValue         Picture X.
        88  PD-AllPagesFlag            Value 'Y' When False 'N'.
    03  PD-SelectionFlagValue        Picture X.
        88  PD-SelectionFlag           Value 'Y' When False 'N'.
    03  PD-PageNumbersFlagValue      Picture X.
        88  PD-PageNumbersFlag         Value 'Y' When False 'N'.
    03  PD-NoSelectionFlagValue      Picture X.
        88  PD-NoSelectionFlag         Value 'Y' When False 'N'.
    03  PD-NoPageNumbersFlagValue    Picture X.
        88  PD-NoPageNumbersFlag       Value 'Y' When False 'N'.
    03  PD-CollateFlagValue          Picture X.
        88  PD-CollateFlag             Value 'Y' When False 'N'.
    03  PD-PrintSetupFlagValue       Picture X.
        88  PD-PrintSetupFlag          Value 'Y' When False 'N'.
    03  PD-PrintToFileFlagValue      Picture X.
        88  PD-PrintToFileFlag         Value 'Y' When False 'N'.
    03  PD-NoWarningFlagValue        Picture X.
        88  PD-NoWarningFlag           Value 'Y' When False 'N'.
    03  PD-UseDevModeCopiesFlagValue Picture X.
        88  PD-UseDevModeCopiesFlag    Value 'Y' When False 'N'.
    03  PD-DisablePrintToFileFlagValue Picture X.
        88  PD-DisablePrintToFileFlag Value 'Y' When False 'N'.
    03  PD-HidePrintToFileFlagValue Picture X.
        88  PD-HidePrintToFileFlag     Value 'Y' When False 'N'.
    03  PD-NoNetworkButtonFlagValue Picture X.
        88  PD-NoNetworkButtonFlag     Value 'Y' When False 'N'.
02  PD-FromPage                      Picture 9(5) Binary(2).
02  PD-ToPage                        Picture 9(5) Binary(2).
02  PD-MinPage                       Picture 9(5) Binary(2).
02  PD-MaxPage                       Picture 9(5) Binary(2).
02  PD-Copies                        Picture 9(5) Binary(2).
02  DM-DeviceName                    Picture X(31).
02  DM-Fields.
    03  DM-OrientationFieldValue     Picture X.
        88  DM-OrientationField        Value 'Y' When False 'N'.
    03  DM-PaperSizeFieldValue       Picture X.
        88  DM-PaperSizeField          Value 'Y' When False 'N'.
    03  DM-PaperLengthFieldValue     Picture X.
        88  DM-PaperLengthField        Value 'Y' When False 'N'.
    03  DM-PaperWidthFieldValue      Picture X.
        88  DM-PaperWidthField         Value 'Y' When False 'N'.
```

```
           03  DM-ScaleFieldValue          Picture X.
               88  DM-ScaleField             Value 'Y' When False 'N'.
           03  DM-CopiesFieldValue         Picture X.
               88  DM-CopiesField            Value 'Y' When False 'N'.
           03  DM-PaperSourceFieldValue    Picture X.
               88  DM-PaperSourceField       Value 'Y' When False 'N'.
           03  DM-PrintQualityFieldValue   Picture X.
               88  DM-PrintQualityField      Value 'Y' When False 'N'.
           03  DM-ColorFieldValue          Picture X.
               88  DM-ColorField             Value 'Y' When False 'N'.
           03  DM-DuplexFieldValue         Picture X.
               88  DM-DuplexField            Value 'Y' When False 'N'.
           03  DM-YResolutionFieldValue    Picture X.
               88  DM-YResolutionField       Value 'Y' When False 'N'.
           03  DM-TrueTypeOptionFieldValue Picture X.
               88  DM-TrueTypeOptionField    Value 'Y' When False 'N'.
           03  DM-CollateFieldValue        Picture X.
               88  DM-CollateField           Value 'Y' When False 'N'.
           03  DM-ICMMethodFieldValue      Picture X.
               88  DM-ICMMethodField         Value 'Y' When False 'N'.
           03  DM-ICMIntentFieldValue      Picture X.
               88  DM-ICMIntentField         Value 'Y' When False 'N'.
           03  DM-MediaTypeFieldValue      Picture X.
               88  DM-MediaTypeField         Value 'Y' When False 'N'.
           03  DM-DitherTypeFieldValue     Picture X.
               88  DM-DitherTypeField        Value 'Y' When False 'N'.
       02  DM-OrientationValue             Picture 9    Binary(2).
           88  DM-OrientationIsPortrait      Value 1.
           88  DM-OrientationIsLandscape     Value 2.
       02  DM-PaperSizeValue               Picture 9(2) Binary(2).
           88  DM-PaperSizeIsLetter          Value 1.
           88  DM-PaperSizeIsLetterSmall     Value 2.
           88  DM-PaperSizeIsTabloid         Value 3.
           88  DM-PaperSizeIsLedger          Value 4.
           88  DM-PaperSizeIsLegal           Value 5.
           88  DM-PaperSizeIsStatement       Value 6.
           88  DM-PaperSizeIsExecutive       Value 7.
           88  DM-PaperSizeIsA3              Value 8.
           88  DM-PaperSizeIsA4              Value 9.
           88  DM-PaperSizeIsA4Small         Value 10.
           88  DM-PaperSizeIsA5              Value 11.
           88  DM-PaperSizeIsB4              Value 12.
           88  DM-PaperSizeIsB5              Value 13.
```

```
    88  DM-PaperSizeIsFolio           Value 14.
    88  DM-PaperSizeIsQuarto          Value 15.
    88  DM-PaperSizeIs10x14           Value 16.
    88  DM-PaperSizeIs11x17           Value 17.
    88  DM-PaperSizeIsNote            Value 18.
    88  DM-PaperSizeIsEnv9            Value 19.
    88  DM-PaperSizeIsEnv10           Value 20.
    88  DM-PaperSizeIsEnv11           Value 21.
    88  DM-PaperSizeIsEnv12           Value 22.
    88  DM-PaperSizeIsEnv14           Value 23.
    88  DM-PaperSizeIsCSheet          Value 24.
    88  DM-PaperSizeIsDSheet          Value 25.
    88  DM-PaperSizeIsESheet          Value 26.
    88  DM-PaperSizeIsEnvDl           Value 27.
    88  DM-PaperSizeIsEnvC5           Value 28.
    88  DM-PaperSizeIsEnvC3           Value 29.
    88  DM-PaperSizeIsEnvC4           Value 30.
    88  DM-PaperSizeIsEnvC6           Value 31.
    88  DM-PaperSizeIsEnvC65          Value 32.
    88  DM-PaperSizeIsEnvB4           Value 33.
    88  DM-PaperSizeIsEnvB5           Value 34.
    88  DM-PaperSizeIsEnvB6           Value 35.
    88  DM-PaperSizeIsEnvItaly        Value 36.
    88  DM-PaperSizeIsEnvMonarch      Value 37.
    88  DM-PaperSizeIsEnvPersonal     Value 38.
    88  DM-PaperSizeIsFanFoldUS       Value 39.
    88 DM-PaperSizeIsFanFoldStdGerman Value 40.
    88 DM-PaperSizeIsFanFoldLglGerman Value 41.
02  DM-PaperLength                  Picture 9(5) Binary(2).
02  DM-PaperWidth                   Picture 9(5) Binary(2).
02  DM-Scale                        Picture 9(5) Binary(2).
02  DM-Copies                       Picture 9(5) Binary(2).
02  DM-PaperSourceValue             Picture 9(2) Binary(2).
    88  DM-PaperSourceIsUpper         Value 1.
    88  DM-PaperSourceIsOnlyOne       Value 1.
    88  DM-PaperSourceIsLower         Value 2.
    88  DM-PaperSourceIsMiddle        Value 3.
    88  DM-PaperSourceIsManual        Value 4.
    88  DM-PaperSourceIsEnvelope      Value 5.
    88  DM-PaperSourceIsEnvManual     Value 6.
    88  DM-PaperSourceIsAuto          Value 7.
    88  DM-PaperSourceIsTractor       Value 8.
    88  DM-PaperSourceIsSmallFmt      Value 9.
```

```
           88  DM-PaperSourceIsLargeFmt      Value 10.
           88  DM-PaperSourceIsLargeCapacity Value 11.
           88  DM-PaperSourceIsCassette      Value 14.
           88  DM-PaperSourceIsFormSource    Value 15.
       02  DM-ResolutionValue              Picture S9   Binary(2).
           88  DM-ResolutionIsDraft          Value -1.
           88  DM-ResolutionIsLow            Value -2.
           88  DM-ResolutionIsMedium         Value -3.
           88  DM-ResolutionIsHigh           Value -4.
       02  DM-ColorValue                   Picture 9    Binary(2).
           88  DM-ColorIsMonochrome          Value 1.
           88  DM-ColorIsColor               Value 2.
       02  DM-DuplexValue                  Picture 9    Binary(2).
           88  DM-DuplexIsSimplex            Value 1.
           88  DM-DuplexIsVertical           Value 2.
           88  DM-DuplexIsHorizontal         Value 3.
       02  DM-YResolution                  Picture 9(5) Binary(2).
       02  DM-TrueTypeValue                Picture 9    Binary(2).
           88  DM-TrueTypeIsBitmap           Value 1.
           88  DM-TrueTypeIsDownload         Value 2.
           88  DM-TrueTypeIsSubDev           Value 3.
       02  DM-CollateValue                 Picture 9    Binary(2).
           88  DM-CollateIsFalse             Value 0.
           88  DM-CollateIsTrue              Value 1.
       02  DM-ICMMethodValue               Picture 9    Binary(4).
           88  DM-ICMMethodIsNone            Value 1.
           88  DM-ICMMethodIsSystem          Value 2.
           88  DM-ICMMethodIsDriver          Value 3.
           88  DM-ICMMethodIsDevice          Value 4.
       02  DM-ICMIntentValue               Picture 9    Binary(4).
           88  DM-ICMIntentIsSaturate        Value 1.
           88  DM-ICMIntentIsContrast        Value 2.
           88  DM-ICMIntentIsColorMetric     Value 3.
       02  DM-MediaTypeValue               Picture 9    Binary(4).
           88  DM-MediaTypeIsStandard        Value 1.
           88  DM-MediaTypeIsTransparency    Value 2.
           88  DM-MediaTypeIsGlossy          Value 3.
       02  DM-DitherTypeValue              Picture 99   Binary(4).
           88  DM-DitherTypeIsNone           Value 1.
           88  DM-DitherTypeIsCoarse         Value 2.
           88  DM-DitherTypeIsFine           Value 3.
           88  DM-DitherTypeIsLineArt        Value 4.
           88  DM-DitherTypeIsErrorDiffusion Value 5.
```

```
       88  DM-DitherTypeIsGrayScale      Value 10.
*
*   Print Dialog Extended Error Values
*
 78  PD-ExtErrCanceled                   Value 0.
 78  PD-ExtErrStructSize                 Value 1.
 78  PD-ExtErrInitialization             Value 2.
 78  PD-ExtErrNoTemplate                 Value 3.
 78  PD-ExtErrNoHInstance                Value 4.
 78  PD-ExtErrLoadStrFailure             Value 5.
 78  PD-ExtErrFindResFailure             Value 6.
 78  PD-ExtErrLoadResFailure             Value 7.
 78  PD-ExtErrLockResFailure             Value 8.
 78  PD-ExtErrMemAllocFailure            Value 9.
 78  PD-ExtErrMemLockFailure             Value 10.
 78  PD-ExtErrNoHook                     Value 11.
 78  PD-ExtErrRegisterMsgFail            Value 12.
 78  PD-ExtErrSetupFailure               Value 4097.
 78  PD-ExtErrParseFailure               Value 4098.
 78  PD-ExtErrRetDefFailure              Value 4099.
 78  PD-ExtErrLoadDrvFailure             Value 4100.
 78  PD-ExtErrGetDevModeFail             Value 4101.
 78  PD-ExtErrInitFailure                Value 4102.
 78  PD-ExtErrNoDevices                  Value 4103.
 78  PD-ExtErrNoDefaultPrn               Value 4104.
 78  PD-ExtErrDNDMMismatch               Value 4105.
 78  PD-ExtErrCreateICFailure            Value 4106.
 78  PD-ExtErrPrinterNotFound            Value 4107.
 78  PD-ExtErrDefaultDifferent           Value 4108.
 78  PD-ExtErrDialogFailure              Value 65535.
*
*   Device Mode Orientation Values
*
 78  DM-OrientationPortrait              Value 1.
 78  DM-OrientationLandscape             Value 2.
*
*   Device Mode Paper Size Values
*
 78  DM-PaperSizeLetter                  Value 1.
 78  DM-PaperSizeLetterSmall             Value 2.
 78  DM-PaperSizeTabloid                 Value 3.
 78  DM-PaperSizeLedger                  Value 4.
 78  DM-PaperSizeLegal                   Value 5.
```

```
 78  DM-PaperSizeStatement              Value 6.
 78  DM-PaperSizeExecutive              Value 7.
 78  DM-PaperSizeA3                     Value 8.
 78  DM-PaperSizeA4                     Value 9.
 78  DM-PaperSizeA4Small                Value 10.
 78  DM-PaperSizeA5                     Value 11.
 78  DM-PaperSizeB4                     Value 12.
 78  DM-PaperSizeB5                     Value 13.
 78  DM-PaperSizeFolio                  Value 14.
 78  DM-PaperSizeQuarto                 Value 15.
 78  DM-PaperSize10x14                  Value 16.
 78  DM-PaperSize11x17                  Value 17.
 78  DM-PaperSizeNote                   Value 18.
 78  DM-PaperSizeEnv9                   Value 19.
 78  DM-PaperSizeEnv10                  Value 20.
 78  DM-PaperSizeEnv11                  Value 21.
 78  DM-PaperSizeEnv12                  Value 22.
 78  DM-PaperSizeEnv14                  Value 23.
 78  DM-PaperSizeCSheet                 Value 24.
 78  DM-PaperSizeDSheet                 Value 25.
 78  DM-PaperSizeESheet                 Value 26.
 78  DM-PaperSizeEnvDl                  Value 27.
 78  DM-PaperSizeEnvC5                  Value 28.
 78  DM-PaperSizeEnvC3                  Value 29.
 78  DM-PaperSizeEnvC4                  Value 30.
 78  DM-PaperSizeEnvC6                  Value 31.
 78  DM-PaperSizeEnvC65                 Value 32.
 78  DM-PaperSizeEnvB4                  Value 33.
 78  DM-PaperSizeEnvB5                  Value 34.
 78  DM-PaperSizeEnvB6                  Value 35.
 78  DM-PaperSizeEnvItaly               Value 36.
 78  DM-PaperSizeEnvMonarch             Value 37.
 78  DM-PaperSizeEnvPersonal            Value 38.
 78  DM-PaperSizeFanFoldUS              Value 39.
 78  DM-PaperSizeFanFoldStdGerman       Value 40.
 78  DM-PaperSizeFanFoldLglGerman       Value 41.
*
*   Device Mode Paper Source Values
*
 78  DM-PaperSourceUpper                Value 1.
 78  DM-PaperSourceOnlyOne              Value 1.
 78  DM-PaperSourceLower                Value 2.
 78  DM-PaperSourceMiddle               Value 3.
```

```
 78  DM-PaperSourceManual                Value 4.
 78  DM-PaperSourceEnvelope              Value 5.
 78  DM-PaperSourceEnvManual             Value 6.
 78  DM-PaperSourceAuto                  Value 7.
 78  DM-PaperSourceTractor               Value 8.
 78  DM-PaperSourceSmallFmt              Value 9.
 78  DM-PaperSourceLargeFmt              Value 10.
 78  DM-PaperSourceLargeCapacity         Value 11.
 78  DM-PaperSourceCassette              Value 14.
 78  DM-PaperSourceFormSource            Value 15.
*
*   Device Mode Resolution Values
*
 78  DM-ResolutionDraft                  Value -1.
 78  DM-ResolutionLow                    Value -2.
 78  DM-ResolutionMedium                 Value -3.
 78  DM-ResolutionHigh                   Value -4.
*
*   Device Mode Color Values
*
 78  DM-ColorMonochrome                  Value 1.
 78  DM-ColorColor                       Value 2.
*
*   Device Mode Duplex Values
*
 78  DM-DuplexSimplex                    Value 1.
 78  DM-DuplexVertical                   Value 2.
 78  DM-DuplexHorizontal                 Value 3.
*
*   Device Mode True Type Values
*
 78  DM-TrueTypeBitmap                   Value 1.
 78  DM-TrueTypeDownload                 Value 2.
 78  DM-TrueTypeSubDev                   Value 3.
*
*   Device Mode Collate Values
*
 78  DM-CollateFalse                     Value 0.
 78  DM-CollateTrue                      Value 1.
*
*   Device ICM Method Values
*
 78  DM-ICMMethodNone                    Value 1.
```

```
 78  DM-ICMMethodSystem                  Value 2.
 78  DM-ICMMethodDriver                  Value 3.
 78  DM-ICMMethodDevice                  Value 4.
*
*   Device ICM Type Values
*
 78  DM-ICMTypeSaturate                  Value 1.
 78  DM-ICMTypeContrast                  Value 2.
 78  DM-ICMTypeColorMetric               Value 3.
*
*   Device Mode Media Type Values
*
 78  DM-MediaTypeStandard                Value 1.
 78  DM-MediaTypeTransparency            Value 2.
 78  DM-MediaTypeGlossy                  Value 3.
*
*   Device Mode Dither Type Values
*
 78  DM-DitherTypeNone                   Value 1.
 78  DM-DitherTypeCoarse                 Value 2.
 78  DM-DitherTypeFine                   Value 3.
 78  DM-DitherTypeLineArt                Value 4.
 78  DM-DitherTypeErrorDiffusion         Value 5.
 78  DM-DitherTypeGrayScale              Value 10.
*
*   P$DisplayDialog Return Values
*
 78  PD-ReturnParam                      Value 0.
 78  PD-ReturnCancelled                  Value 1.
 78  PD-ReturnError                      Value 2.
*
*   Parameter Name Values
*
 78 PD-ReturnParam                      Value "Return".
 78 PD-ExtendedErrorParam               Value "Extended Error".
 78 PD-AllPagesFlagParam                Value "All Pages Flag".
 78 PD-SelectionFlagParam               Value "Selection Flag".
 78 PD-PageNumbersFlagParam             Value "Page Numbers Flag".
 78 PD-NoSelectionFlagParam             Value "No Selection Flag".
 78 PD-NoPageNumbersFlagParam           Value "No Page Numbers Flag".
 78 PD-CollateFlagParam                 Value "Collate Flag".
 78 PD-PrintSetupFlagParam              Value "Print Setup Flag".
 78 PD-PrintToFileFlagParam             Value "Print To File Flag".
```

```
78 PD-NoWarningFlagParam               Value "No Warning Flag".
78 PD-UseDevModeCopiesFlagParam        Value
                                       "Use Device Mode Copies Flag".
78 PD-DisablePrintToFileFlagParam      Value
                                       "Disable Print To File Flag".
78 PD-HidePrintToFileFlagParam         Value "Hide Print To File Flag".
78 PD-NoNetworkButtonFlagParam         Value "No Network Button Flag".
78 PD-FromPageParam                    Value "From Page".
78 PD-ToPageParam                      Value "To Page".
78 PD-MinPageParam                     Value "Min Page".
78 PD-MaxPageParam                     Value "Max Page".
78 PD-PrintDialogCopiesParam           Value "Print Dialog Copies".
78 DM-DeviceNameParam                  Value "Device Name".
78 DM-OrientationParam                 Value "Orientation".
78 DM-PaperSizeParam                   Value "Paper Size".
78 DM-PaperLengthParam                 Value "Paper Length".
78 DM-PaperWidthParam                  Value "Paper Width".
78 DM-ScaleParam                       Value "Scale".
78 DM-DeviceModeCopiesParam            Value "Device Mode Copies".
78 DM-DefaultSourceParam               Value "Default Source".
78 DM-PrintQualityParam                Value "Print Quality".
78 DM-ColorParam                       Value "Color".
78 DM-DuplexParam                      Value "Duplex".
78 DM-YResolutionParam                 Value "Y Resolution".
78 DM-TrueTypeOptionParam              Value "True Type Option".
78 DM-CollateParam                     Value "Collate".
78 DM-ICMMethodParam                   Value "ICM Method".
78 DM-ICMIntentParam                   Value "ICM Intent".
78 DM-MediaTypeParam                   Value "Media Type".
78 DM-DitherTypeParam                  Value "Dither Type".
```

PRINTINF.CPY

Information regarding the Microsoft Windows PRINTER_INFO_2 structure can be found on the Internet at http://msdn.microsoft.com/library/. Periodically, Microsoft reorganizes the MSDN information on the web site. Use the search capability to find information on the requested topic.

The following search tree was accurate when this document went to print:

```
Platform SDK
 Graphics and Multimedia Services
  Windows GDI
   Printing and Print Spooler
    Printing and Print Spooler Reference
     Printing and Print Spooler Structures
      PRINTER_INFO_2
```

PRINTINF.CPY contains the following definitions.

```
*
*   Printer Information Definitions
*
01 PrinterInformation.
    02  PI-ServerName                  Picture X(80).
    02  PI-PrinterName                 Picture X(80).
    02  PI-ShareName                   Picture X(80).
    02  PI-PortName                    Picture X(80).
    02  PI-DriverName                  Picture X(80).
    02  PI-Comment                     Picture X(80).
    02  PI-Location                    Picture X(80).
    02  PI-SepFile                     Picture X(80).
    02  PI-PrintProcessor              Picture X(80).
    02  PI-DataType                    Picture X(80).
    02  PI-Parameters                  Picture X(80).
    02  PI-Attribute.
        03  PI-QueuedAttributeValue    Picture X.
            88  PI-QueuedAttribute      Value 'Y' When False 'N'.
        03  PI-DirectAttributeValue    Picture X.
            88  PI-DirectAttribute      Value 'Y' When False 'N'.
        03  PI-DefaultAttributeValue   Picture X.
            88  PI-DefaultAttribute     Value 'Y' When False 'N'.
        03  PI-SharedAttributeValue    Picture X.
            88  PI-SharedAttribute      Value 'Y' When False 'N'.
```

```
    03  PI-NetworkAttributeValue    Picture X.
        88  PI-NetworkAttribute      Value 'Y' When False 'N'.
    03  PI-HiddenAttributeValue     Picture X.
        88  PI-HiddenAttribute       Value 'Y' When False 'N'.
    03  PI-LocalAttributeValue      Picture X.
        88  PI-LocalAttribute        Value 'Y' When False 'N'.
    03  PI-EnableDEVQAttributeValue Picture X.
        88  PI-EnableDEVQAttribute   Value 'Y' When False 'N'.
    03  PI-KeepPrintedAttributeValue   Picture X.
        88  PI-KeepPrintedJobsAttribute Value 'Y' When False 'N'.
    03  PI-DoComplete1stAttributeValue Picture X.
        88  PI-DoCompleteFirstAttribute Value 'Y' When False 'N'.
    03  PI-WorkOfflineAttributeValue   Picture X.
        88  PI-WorkOfflineAttribute  Value 'Y' When False 'N'.
    03  PI-EnableBIDIAttributeValue Picture X.
        88  PI-EnableBIDIAttribute   Value 'Y' When False 'N'.
02  PI-Priority                     Picture 9(10) Binary(4).
02  PI-DefaultPriority              Picture 9(10) Binary(4).
02  PI-StartTime                    Picture 9(10) Binary(4).
02  PI-UntilTime                    Picture 9(10) Binary(4).
02  PI-Status.
    03  PI-PausedStatusValue        Picture X.
        88  PI-PausedStatus          Value 'Y' When False 'N'.
    03  PI-ErrorStatusValue         Picture X.
        88  PI-ErrorStatus           Value 'Y' When False 'N'.
    03  PI-PendingDeletionStatusValue  Picture X.
        88  PI-PendingDeletionStatus Value 'Y' When False 'N'.
    03  PI-PaperJamStatusValue      Picture X.
        88  PI-PaperJamStatus        Value 'Y' When False 'N'.
    03  PI-PaperOutStatusValue      Picture X.
        88  PI-PaperOutStatus        Value 'Y' When False 'N'.
    03  PI-ManualFeedStatusValue    Picture X.
    88  PI-ManualFeedStatus          Value 'Y' When False 'N'.
    03  PI-PaperProblemStatusValue  Picture X.
        88  PI-PaperProblemStatus    Value 'Y' When False 'N'.
    03  PI-OfflineStatusValue       Picture X.
        88  PI-OfflineStatus         Value 'Y' When False 'N'.
    03  PI-IOActiveStatusValue      Picture X.
        88  PI-IOActiveStatus        Value 'Y' When False 'N'.
    03  PI-BusyStatusValue          Picture X.
        88  PI-BusyStatus            Value 'Y' When False 'N'.
    03  PI-PrintingStatusValue      Picture X.
        88  PI-PrintingStatus        Value 'Y' When False 'N'.
```

```
           03  PI-OutputBinFullStatusValue Picture X.
               88  PI-OutputBinFullStatus   Value 'Y' When False 'N'.
           03  PI-NotAvailableStatusValue  Picture X.
               88  PI-NotAvailableStatus    Value 'Y' When False 'N'.
           03  PI-WaitingStatusValue       Picture X.
               88  PI-WaitingStatus         Value 'Y' When False 'N'.
           03  PI-ProcessingStatusValue    Picture X.
               88  PI-ProcessingStatus      Value 'Y' When False 'N'.
           03  PI-IntializingStatusValue   Picture X.
               88  PI-InitializingStatus    Value 'Y' When False 'N'.
           03  PI-WarmingUpStatusValue     Picture X.
               88  PI-WarmingUpStatus       Value 'Y' When False 'N'.
           03  PI-ToneLowStatusValue       Picture X.
               88  PI-TonerLowStatus        Value 'Y' When False 'N'.
           03  PI-NoTonerStatusValue       Picture X.
               88  PI-NoTonerStatus         Value 'Y' When False 'N'.
           03  PI-PagePuntStatusValue      Picture X.
               88  PI-PagePuntStatus        Value 'Y' When False 'N'.
           03  PI-UserInterventionStatusValue Picture X.
               88  PI-UserInterventionStatusValue 'Y' When False 'N'.
           03  PI-OutOfMemoryStatusValue   Picture X.
               88  PI-OutOfMemoryStatus     Value 'Y' When False 'N'.
           03  PI-DoorOpenStatusValue      Picture X.
               88  PI-DoorOpenStatus        Value 'Y' When False 'N'.
           03  PI-ServerUnknownStatusValue Picture X.
               88  PI-ServerUnknownStatus   Value 'Y' When False 'N'.
           03  PI-PowerSaveStatusValue     Picture X.
               88  PI-PowerSaveStatus       Value 'Y' When False 'N'.
       02  PI-Jobs                         Picture 9(10) Binary(4).
       02  PI-AveragePPM                   Picture 9(10) Binary(4).
   *
   *   Parameter Name Values
   *
    78  PI-ServerNameParam                  Value "Server Name".
    78  PI-PrinterNameParam                 Value "Printer Name".
    78  PI-ShareNameParam                   Value "Share Name".
    78  PI-PortNameParam                    Value "Port Name".
    78  PI-DriverNameParam                  Value "Driver Name".
    78  PI-CommentParam                     Value "Comment".
    78  PI-LocationParam                    Value "Location".
    78  PI-SepFileParam                     Value "Sep File".
    78  PI-PrintProcessorParam              Value "Print Processor".
    78  PI-DataTypeParam                    Value "Data Type".
```

```
 78  PI-ParametersParam                  Value "Parameters".
 78  PI-PriorityParam                    Value "Priority".
 78  PI-DefaultPriorityParam             Value "Default Priority".
 78  PI-StartTimeParam                   Value "Start Time".
 78  PI-UntilTimeParam                   Value "Until Time".
 78  PI-JobsParam                        Value "Jobs".
 78  PI-AveragePPMParam                  Value "Average PPM".
```

TXTMTRIC.CPY

Information regarding the Microsoft Windows TEXTMETRIC structure can be found on the Internet at http://msdn.microsoft.com/library/. Periodically, Microsoft reorganizes the MSDN information on the web site. Use the search capability to find information on the requested topic.

The following search tree was accurate when this document went to print:

```
Platform SDK
 Graphics and Multimedia Services
  Windows GDI
   Fonts and Text
    Font and Text Reference
     Font and Text Structures
      TEXTMETRIC
```

TXTMTRIC.CPY contains the following definitions.

```
*
*   Text Metric Definitions
*
01 TextMetrics.
    02  TM-Height                    Picture 9(10)  Binary(4).
    02  TM-Ascent                    Picture 9(10)  Binary(4).
    02  TM-Descent                   Picture 9(10)  Binary(4).
    02  TM-InternalLeading           Picture 9(10)  Binary(4).
    02  TM-ExternalLeading           Picture 9(10)  Binary(4).
    02  TM-AveCharWidth              Picture 9(10)  Binary(4).
    02  TM-MaxCharWidth              Picture 9(10)  Binary(4).
    02  TM-WeightValue               Picture 9(3)   Binary(4).
        88  TM-WeightIsDontCare        Value 0.
        88  TM-WeightIsThin            Value 100.
        88  TM-WeightIsExtraLight      Value 200.
        88  TM-WeightIsUltraLight      Value 200.
```

```
           88  TM-WeightIsLight           Value 300.
           88  TM-WeightIsNormal          Value 400.
           88  TM-WeightIsRegular         Value 400.
           88  TM-WeightIsMedium          Value 500.
           88  TM-WeightIsSemiBold        Value 600.
           88  TM-WeightIsDemiBold        Value 600.
           88  TM-WeightIsBold            Value 700.
           88  TM-WeightIsExtraBold       Value 800.
           88  TM-WeightIsUltraBold       Value 800.
           88  TM-WeightIsHeavy           Value 900.
           88  TM-WeightIsBlack           Value 900.
       02  TM-Overhang                   Picture 9(10)  Binary(4).
       02  TM-DigitizedAspectX           Picture 9(10)  Binary(4).
       02  TM-DigitizedAspectY           Picture 9(10)  Binary(4).
       02  TM-ItalicValue                Picture X.
           88  TM-Italic                  Value 'Y' When False 'N'.
       02  TM-UnderlinedValue            Picture X.
           88  TM-Underlined              Value 'Y' When False 'N'.
       02  TM-StruckOutValue             Picture X.
           88  TM-StruckOut               Value 'Y' When False 'N'.
       02  TM-FirstChar                  Picture X.
       02  TM-LastChar                   Picture X.
       02  TM-DefaultChar                Picture X.
       02  TM-BreakChar                  Picture X.
       02  TM-PitchValue                 Picture 9    Binary(2).
           88  TM-PitchIsFixedPitch       Value 1.
           88  TM-PitchIsVector           Value 2.
           88  TM-PitchIsTrueType         Value 4.
           88  TM-PitchIsDevice           Value 8.
       02  TM-FamilyValue                Picture 9    Binary(2).
           88  TM-FamilyIsDontCare        Value 0.
           88  TM-FamilyIsRoman           Value 1.
           88  TM-FamilyIsSwiss           Value 2.
           88  TM-FamilyIsModern          Value 3.
           88  TM-FamilyIsScript          Value 4.
           88  TM-FamilyIsDecorative      Value 5.
       02  TM-CharSetValue               Picture 9(3) Binary(2).
           88  TM-CharSetIsANSI           Value 0.
           88  TM-CharSetIsDefault        Value 1.
           88  TM-CharSetIsSymbol         Value 2.
           88  TM-CharSetIsMAC            Value 77.
           88  TM-CharSetIsShiftJIS       Value 128.
           88  TM-CharSetIsHangeul        Value 129.
```

```
           88  TM-CharSetIsJohab           Value 130.
           88  TM-CharSetIsChineseBig5     Value 136.
           88  TM-CharSetIsGreek           Value 161.
           88  TM-CharSetIsTurkish         Value 162.
           88  TM-CharSetIsHebrew          Value 177.
           88  TM-CharSetIsArabic          Value 178.
           88  TM-CharSetIsBaltic          Value 186.
           88  TM-CharSetIsRussian         Value 204.
           88  TM-CharSetIsThai            Value 222.
           88  TM-CharSetIsEastEurope      Value 238.
           88  TM-CharSetIsOEM             Value 255.
      *
      *   Weight Values
      *
       78 TM-WeightDontCare                 Value 0.
       78 TM-WeightThin                     Value 100.
       78 TM-WeightExtraLight               Value 200.
       78 TM-WeightUltraLight               Value 200.
       78 TM-WeightLight                    Value 300.
       78 TM-WeightNormal                   Value 400.
       78 TM-WeightRegular                  Value 400.
       78 TM-WeightMedium                   Value 500.
       78 TM-WeightSemiBold                 Value 600.
       78 TM-WeightDemiBold                 Value 600.
       78 TM-WeightBold                     Value 700.
       78 TM-WeightExtraBold                Value 800.
       78 TM-WeightUltraBold                Value 800.
       78 TM-WeightHeavy                    Value 900.
       78 TM-WeightBlack                    Value 900.
      *
      *   Pitch Values
      *
       78 TM-PitchFixedPitch                Value 1.
       78 TM-PitchVector                    Value 2.
       78 TM-PitchTrueType                  Value 4.
       78 TM-PitchDevice                    Value 8.
      *
      *   Family Values
      *
       78 TM-FamilyDontCare                 Value 0.
       78 TM-FamilyRoman                    Value 1.
       78 TM-FamilySwiss                    Value 2.
       78 TM-FamilyModern                   Value 3.
```

```
 78 TM-FamilyScript                    Value 4.
 78 TM-FamilyDecorative                Value 5.
*
*   Character Set Values
*
 78 TM-CharSetANSI                     Value 0.
 78 TM-CharSetDefault                  Value 1.
 78 TM-CharSetSymbol                   Value 2.
 78 TM-CharSetMAC                      Value 77.
 78 TM-CharSetShiftJIS                 Value 128.
 78 TM-CharSetHangeul                  Value 129.
 78 TM-CharSetJohab                    Value 130.
 78 TM-CharSetChineseBig5              Value 136.
 78 TM-CharSetGreek                    Value 161.
 78 TM-CharSetTurkish                  Value 162.
 78 TM-CharSetHebrew                   Value 177.
 78 TM-CharSetArabic                   Value 178.
 78 TM-CharSetBaltic                   Value 186.
 78 TM-CharSetRussian                  Value 204.
 78 TM-CharSetThai                     Value 222.
 78 TM-CharSetEastEurope               Value 238.
 78 TM-CharSetOEM                      Value 255.
*
*   Parameter Name Values
*
 78 TM-HeightParam                     Value "Height".
 78 TM-AscentParam                     Value "Ascent".
 78 TM-DescentParam                    Value "Descent".
 78 TM-InternalLeadingParam            Value "Internal Leading".
 78 TM-ExternalLeadingParam            Value "External Leading".
 78 TM-AverageCharacterWidthParam      Value "Average Character Width".
 78 TM-MaximumCharacterWidthParam      Value "Maximum Character Width".
 78 TM-WeightParam                     Value "Weight".
 78 TM-OverhangParam                   Value "Overhang".
 78 TM-DigitizedAspectXParam           Value "Digitized Aspect X".
 78 TM-DigitizedAspectYParam           Value "Digitized Aspect Y".
 78 TM-FirstCharacterParam             Value "First Character".
 78 TM-LastCharacterParam              Value "Last Character".
 78 TM-DefaultCharacterParam           Value "Default Character".
 78 TM-BreakCharacterParam             Value "Break Character".
 78 TM-ItalicParam                     Value "Italic".
 78 TM-UnderlinedParam                 Value "Underlined".
 78 TM-StruckOutParam                  Value "Struck Out".
```

```
 78 TM-PitchParam                       Value "Pitch".
 78 TM-FamilyParam                      Value "Family".
 78 TM-CharacterSetParam                Value "Character Set".
```

WINDEFS.CPY

Information regarding the Microsoft Windows PlaySound function and LOGPEN structure can be found on the Internet at http://msdn.microsoft.com/library/. Periodically, Microsoft reorganizes the MSDN information on the web site. Use the search capability to find information on the requested topic.

The following search trees were accurate when this document went to print:

For PlaySound:

```
Platform SDK
 Graphics and Multimedia Services
  Windows Multimedia
   Multimedia Reference
    Multimedia Functions
     PlaySound
```

For LOGPEN:

```
Platform SDK
 Graphics and Multimedia Services
  Windows GDI
   Pens
    Pen Reference
     Pen Structures
      LOGPEN
```

WINDEFS.CPY contains the following definitions.

```
*
*   Miscellaneous Windows Definitions
*
*
*   C$PlaySound Options
*
 78 SoundSync                           Value 0.
 78 SoundAsync                          Value 2 ** 0.
 78 SoundNoDefault                      Value 2 ** 1.
 78 SoundNoStop                         Value 2 ** 4.
```

```
 78 SoundPurge                          Value 2 ** 6.
 78 SoundApplication                    Value 2 ** 7.
 78 SoundNoWait                         Value 2 ** 13.
 78 SoundAlias                          Value 2 ** 16.
 78 SoundFilename                       Value 2 ** 17.
 78 SoundAliasId                        Value (2 ** 16) + (2 ** 20).
*
*   Pen Style Values
*
 78 PenStyleSolid                       Value 0.
 78 PenStyleDash                        Value 1.
 78 PenStyleDot                         Value 2.
 78 PenStyleDashDot                     Value 3.
 78 PenStyleDashDotDot                  Value 4.
 78 PenStyleNull                        Value 5.
*
*   Position Alignment Argument Values
*
 78 PositionIsTop                       Value "Top".
 78 PositionIsBottom                    Value "Bottom".
*
*   Position Mode Argument Values
*
 78 ModeIsAbsolute                    Value "Absolute".
 78 ModeIsRelative                    Value "Relative".
*
*   Position Unit Argument Values
*
 78 UnitsAreInches                      Value "Inches".
 78 UnitsAreMetric                      Value "Metric".
 78 UnitsAreCharacters                  Value "Characters".
 78 UnitsAreDeviceUnits                 Value "Device Units".
*
*   Yes/No Argument Values
*
 78 DrawBoxWithShading                  Value "Yes".
 78 DrawBoxWithoutShading               Value "No".
 78 DrawBoxNoShading                    Value "No".
 78 TextOutWithBox                      Value "Yes".
 78 TextOutWithoutBox                   Value "No".
 78 TextOutNoBox                        Value "No".
 78 TextOutWithShading                  Value "Yes".
 78 TextOutWithoutShading               Value "No".
```

```
 78 TextOutNoShading                  Value "No".
 78 WithBox                           Value "Yes".
 78 WithoutBox                        Value "No".
 78 NoBox                             Value "No".
 78 WithShading                       Value "Yes".
 78 WithoutShading                    Value "No".
 78 NoShading                         Value "No".
*
*   Color Argument Values
*
 78 ColorBlack                        Value "Black".
 78 ColorDarkBlue                     Value "Dark Blue".
 78 ColorDarkGreen                    Value "Dark Green".
 78 ColorDarkCyan                     Value "Dark Cyan".
 78 ColorDarkRed                      Value "Dark Red".
 78 ColorDarkMagenta                  Value "Dark Magenta".
 78 ColorBrown                        Value "Brown".
 78 ColorDarkGray                     Value "Dark Gray".
 78 ColorLightGray                    Value "Light Gray".
 78 ColorBlue                         Value "Blue".
 78 ColorGreen                        Value "Green".
 78 ColorCyan                         Value "Cyan".
 78 ColorRed                          Value "Red".
 78 ColorMagenta                      Value "Magenta".
 78 ColorYellow                       Value "Yellow".
 78 ColorWhite                        Value "White".
*
*   Pitch Name Values
*
 78 PitchNormal                       Value "Normal".
 78 PitchExpanded                     Value "Expanded".
 78 PitchCompressed                   Value "Compressed".
```

Example Code Fragments

The code fragments in this section illustrate the use of P$ subprograms to facilitate Windows printing program development. Table E-8 provides a quick reference for the tasks performed in the code fragment examples. These code fragments can be found in **pexample.cbl** in the Samples directory.

Note Additional comprehensive examples using P$ subprograms can be found in the Samples directory. These samples may clarify any remaining questions you might have about using the P$ subprogram library.

Table E-8 Task Reference List

To	See Example
Change a font while printing	Changing a Font While Printing (see page E-77)
Change the print orientation	Presetting the Print Dialog Box (see page E-75) and Changing Orientation and Pitch (see page E-79)
Change the pitch of a font	Changing Orientation and Pitch (see page E-79)
Change the print resolution	Presetting the Print Dialog Box (see page E-75)
Check the return code value	Checking the Return Code After Displaying the Print Dialog Box (see page E-76).
Draw a box around text	Drawing a Box Around Text (see page E-73)
Draw a shaded box with colors	Drawing Shaded Boxes with Colors (see page E-73)
Draw a box using “relative” positioning	Drawing Shaded Boxes with Colors (see page E-73)
Draw a ruler	Drawing a Ruler (see page E-74)
Open three separate printers and write to each one	Opening and Writing to Separate Printers (see page E-80
Print text at corners of a page	Printing Text at the Corners of a Page (see page E-82)
Print text at the top of a page	Printing Text at the Top of a Page (see page E-81)
Print a bitmap file	Printing a Bitmap (see page E-77)
Print multiple copies	Presetting the Print Dialog Box (see page E-75)
Print multiple text outputs on the same line	Using the COBOL WRITE Statement to Print Multiple Text Outputs on the Same Line (see page E-78)
Print a word in italics	Using the COBOL WRITE Statement to Print Multiple Text Outputs on the Same Line (see page E-78)
Print a word in boldface type	Using the COBOL WRITE Statement to Print Multiple Text Outputs on the Same Line (see page E-78)
Print a word underlined	Using the COBOL WRITE Statement to Print Multiple Text Outputs on the Same Line (see page E-78)
Print a watermark	Printing a Watermark (see page E-73)
Set the point size for a font	Setting the Point Size for a Font (see page E-83)
Set text position	Setting Text Position (see page E-84)

Printing a Watermark

The following code fragment illustrates printing a watermark diagonally across a page. The font is set to a large point size with a 45-degree angle (Escapement). The color is set to a light gray, and the text is positioned with metric measurements.

```
CALL "P$SETFONT" USING LF-HeightParam 500, LF-EscapementParam, 450.
CALL "P$SETTEXTCOLOR"  USING ColorLightGray.
CALL "P$TEXTOUT"  USING  "Example", 5.08, 17.78, "Absolute", "Metric".
```

Drawing Shaded Boxes with Colors

The following code fragment illustrates drawing two boxes. The first box is drawn with a thick pen, shaded with ten-percent gray, positioned at 2,2 inches on the page, and is one-inch square. The second box is positioned using "relative" positioning so that the lower-right corner of the first box is connected to the upper-left corner of the second box. It is drawn with a thin, dashed red line, no shading, and is 1.5-inches square.

```
CALL "P$SETPEN" USING PenStyleSolid, 5.
CALL "P$SETBOXSHADE" USING ColorBlack, 10.
CALL "P$DRAWBOX" USING 2.00, 2.00, "Absolute", "Inches",
                       1.00, 1.00, "Inches", WithShading.
CALL "P$SETPEN" USING PenStyleDash, 1, ColorRed.
CALL "P$DRAWBOX" USING 0, 0, "Relative", "Inches",
                       1.50, 1.50, "Inches".
```

Drawing a Box Around Text

The following code fragment illustrates drawing a box centered around a line of text. The box allows one-half the average character width of the current font before and after the text. The top of the box is positioned at the top alignment of the current font. The height of the box is the height of the current font plus external leading.

```
CALL "P$GETTEXTMETRICS" Using TextMetrics.
CALL "P$SETPOSITION" USING 0.5, 5.50, "Absolute", "Inches".
CALL "P$GETTEXTPOSITION" USING X-POS, Y-POS, "Top", "Device-Units".
CALL "P$GETTEXTEXTENT" USING "AAaaGGggYYyyTTttH",
                             WIDTH, HEIGHT, "Device-Units".
COMPUTE X-POS  = X-POS - (TM-AveCharWidth / 2).
COMPUTE WIDTH = WIDTH + TM-AveCharWidth.
COMPUTE HEIGHT = TM-ExternalLeading + TM-Height.
CALL "P$DRAWBOX" USING X-POS, Y-POS, "Absolute", "Device-Units",
                       WIDTH, HEIGHT, "Device-Units".
CALL "P$TEXTOUT" USING "AAaaGGggYYyyTTttH",
                       0.5, 5.50, "Absolute", "Inches".
```

The following code fragment performs the same task as the previous part of this example, but allows the runtime to compute the size and position of the box as well as draw the box. For top, bottom, left, and right margins, the box allows one-quarter the average character width of the current font.

```
CALL "P$TEXTOUT" USING "AAaaGGggYYyyTTttH", 0.5, 6.00,
                       "Absolute", "Inches", WithBox.
```

Drawing a Ruler

The following code fragment draws a 5-centimeter ruler.

```
Centimeter-Ruler.
   MOVE 0.0 TO WS-X, WS-Y, WS-Y2.
   MOVE 5.0 TO WS-X2.
   MOVE 0 to WS-CENT-COUNT.
   CALL "P$SETDEFAULTUNITS" USING "Metric".

*Draw a Line 5 Centimeters Long.
   CALL "P$DRAWLINE" USING WS-X, WS-Y, "Absolute", "Metric",
                           WS-X2, WS-Y2.
   PERFORM VARYING WS-X FROM 0 BY 0.1 UNTIL WS-X > 5
      EVALUATE TRUE
        WHEN WS-CENT-COUNT = 5
          MOVE .4 TO WS-Y
        WHEN WS-CENT-COUNT = 10 OR 0
          MOVE .7 TO WS-y
        WHEN OTHER
          MOVE .2 TO WS-Y
      END-EVALUATE
      CALL "P$MOVETO" USING WS-X, WS-Y
      CALL "P$LINETO" USING WS-X, WS-Y2
      IF WS-CENT-COUNT = 10
          MOVE 1 TO WS-CENT-COUNT
      ELSE
          ADD  1 TO WS-CENT-COUNT
      END-IF

   END-PERFORM.
```

Presetting the Print Dialog Box

The following code fragment causes two copies of the output to be printed with high resolution. The orientation of the print will be in landscape mode. When the Windows Print dialog box appears, the All Pages option button will be selected, the Page Numbers option button and associated edit control will be disabled, the Selection button will be disabled, and the Print to File check box will be hidden.

Note The example code fragment shown below sets the collate flag to false, that is, printed pages will not be collated. Some printers do not support printing multiple copies with the pages collated. For more information, see "Printing Multiple Copies" on page E-13.

```
INITIALIZE PrintDialog.
CALL "P$CLEARDIALOG".
SET PD-AllPagesFlag               TO TRUE.       *>Sets All Pages
                                                 *>option on
SET PD-NoPageNumbersFlag          TO TRUE.       *>Disable Pages
                                                 *>option button and
                                                 *>associated edit
                                                 *>controls
SET PD-NoSelectionFlag            TO TRUE.       *>Disables Selection
                                                 *>button
SET PD-CollateFlag                TO FALSE.      *>Don't check Collate
                                                 *>check box
SET PD-HidePrintToFileFlag        TO TRUE.       *>Hides Print To File
                                                 *>checkbox
SET DM-CopiesField                TO TRUE.
MOVE 2                            TO DM-Copies.
SET DM-OrientationField           TO TRUE.
SET DM-OrientationIsLandscape     TO TRUE.
SET DM-PrintQualityField          TO TRUE.
SET DM-ResolutionIsHigh           TO TRUE.
CALL "P$SETDIALOG" USING PrintDialog.
OPEN OUTPUT PFILE.
WRITE FD-RECORD FROM
      "Example 5:  Presetting the Printer Dialog Box Page 1"
       AFTER PAGE.
WRITE FD-RECORD FROM
      "Example 5:  Text After CALLING P$SETDIALOG".
WRITE FD-RECORD FROM
      "Example 5:  This should be printed in landscape mode.".
WRITE FD-RECORD FROM
      "Example 5:  There should be two copies printed.".
CLOSE PFILE.
```

Checking the Return Code After Displaying the Print Dialog Box

The following code fragment will set the printer device, display the Windows Print dialog box, and check the return code value. If the value is zero, the user pressed the OK button. If the value is 1, the user pressed the Cancel button or closed the dialog box. If the value is 2, an error occurred while displaying the dialog box and the error code is checked by making a call to P$GetDialog.

```
        Set PD-NoWarningFlag To True.
        CALL "P$SetDialog" Using DM-DeviceNameParam, DM-DeviceName.
        CALL "P$DisplayDialog" Giving Dialog-Return.

        Evaluate True
               When Dialog-OK                       *> Value zero
                 Display "OK Button Pressed" Line 13 Col 1
                 Perform Open-Printer-Para
               When Dialog-Cancel                   *> Value one
                 Display "Cancel Button Pressed"  Line 13 Col 1
                 Perform Printer-Canceled-Para
               When Dialog-Error                    *> Value two
                 Display "Error in Dialog"  Line 13 Col 1
                 Perform Printer-Error-Para
               When Other                           *> Value other
                 Display "Invalid Value: " Line 13 Col 1 Dialog-Return
                 End-Evaluate.
        STOP RUN.

    Open-Printer-Para.
        Open Output Printer-File.
        Write Fd-Record From
            "Checking the Printer Dialog Box " After Page.
        Close Pfile.

    Printer-Canceled-Para.
        Display "Printer Dialog Canceled" Line 22 Col 3 Reverse Erase Eol.

    Printer-Error-Para.
        CALL "P$GetDialog" Using  PD-ExtendedErrorParam,
                                  PD-ExtendedErrorValue,
                                  Validity-Flag.

        If PD-ExtErrIsPrinterNotFound
               Display "Printer Not Found!" Line 22 Col 3 Reverse
               Erase Eol
        Else
               Display "Printer Dialog Had Error" Line 22 Col 3 Reverse
                                            PD-ExtendedErrorValue Convert
               Erase Eol

        End-If.
```

Printing a Bitmap

The following code fragment prints a bitmap at location 2,2 (inches). The bitmap will be two inches wide, and the height will be scaled to match the original width/height ratio.

```
CALL "P$DRAWBITMAP" USING "rmlogo.bmp", 2, 2, "Absolute",
                          "Inches", 2, 0, "Inches".
```

Changing a Font While Printing

The following code fragment prints the text, "Original FONT" in the current font, then switches to Monotype Corsiva and prints the text, "Monotype Corsiva FONT Italic".

```
CALL "P$TEXTOUT" USING "Original FONT", 0.5, 3.50, "Absolute",
    "Inches".
CALL "P$SETFONT" USING LF-FaceNameParam, "Monotype Corsiva",
    LF-ItalicParam, "Y".
CALL "P$TEXTOUT" USING "Monotype Corsiva FONT Italic", 0.5,
    4.50, "Absolute", "Inches".
```

Using the COBOL WRITE Statement to Print Multiple Text Outputs on the Same Line

The following code fragment causes multiple outputs to appear on a single line. The COBOL WRITE statement is used with the ADVANCING phrase and the P$SetLineExtendMode subprogram to produce the following line of text:

Printing a word in *Italic*, Underline, or **Bold** on the same line is no problem with RM/COBOL.

```
INITIALIZE LogicalFont.
CALL "P$SETFONT" USING    LF-HeightParam    50,
                          LF-WeightParam    10,
                          LF-FaceNameParam  "Arial".
WRITE PRINT-RECORD FROM "Printing a word in".
CALL "P$SETLINEEXTENDMODE" USING 1, "Characters".
CALL "P$SETFONT" USING LF-ItalicParam, "Y".
WRITE PRINT-RECORD FROM "Italic", AFTER ADVANCING ZERO.
CALL "P$SETLINEEXTENDMODE" USING 1, "Characters".
CALL "P$SETFONT" USING LF-ItalicParam, "N", LF-UnderlineParam, "Y".
WRITE FD-RECORD FROM "Underline," AFTER ADVANCING ZERO.
CALL "P$SETLINEEXTENDMODE" USING 1, "Characters".
CALL "P$SETFONT" USING LF-WeightParam, LF-WeightBold,
                       LF-UnderlineParam, "N".
WRITE PRINT-RECORD FROM "or Bold" AFTER ADVANCING ZERO.
CALL "P$SETLINEEXTENDMODE" USING 1, "Characters".
CALL "P$SETFONT" USING LF-WeightParam, LF-WeightNormal.
WRITE PRINT-RECORD FROM
    "on the same line is no problem with RM/COBOL."
    AFTER ADVANCING ZERO.
```

Changing Orientation and Pitch

The following code fragment demonstrates how to change the print orientation from portrait to landscape and how to change the font pitch from normal to compressed.

```
CALL "P$TEXTOUT" USING "This is Orientation Portrait Normal
      Pitch" 0, 1.50, "Absolute", "Inches".
CALL "P$SETPITCH" USING PitchCompressed.
CALL "P$CHANGEDEVICEMODES" USING  DM-OrientationParam,
                                  DM-OrientationLandscape.
WRITE FD-RECORD FROM SPACES AFTER PAGE.
CALL "P$TEXTOUT" USING
                      "This is printed with the Orientation
                      "Landscape with a Compressed Type Size",
                      0, 1.50, "Absolute", "Inches".
CALL "P$SETPITCH" USING PitchNormal.

CALL "P$CHANGEDEVICEMODES" USING  DM-OrientationParam,
                                  DM-OrientationPortrait.
WRITE FD-RECORD FROM SPACES AFTER PAGE.
CALL "P$TEXTOUT" USING
    "This is back to Portrait using the Normal Pitch Size",
    0, 1.50, "Absolute", "Inches".
```

Opening and Writing to Separate Printers

The following code fragment demonstrates how to open three separate printers and write to each one.

```
OPEN OUTPUT PFILE1.
CALL "P$GETHANDLE" USING HANDLE-1.

CALL "P$ENABLEDIALOG".
OPEN OUTPUT PFILE2.
CALL "P$GETHANDLE" USING HANDLE-2.

CALL "P$ENABLEDIALOG".
OPEN OUTPUT PFILE3.
CALL "P$GETHANDLE" USING HANDLE-3.

CALL "P$SETHANDLE" USING HANDLE-3.
CALL "P$TEXTOUT"   USING "Text written to PRINTER 3".

CALL "P$SETHANDLE" USING HANDLE-2.
CALL "P$TEXTOUT"   USING "Text written to PRINTER 2".

CALL "P$SETHANDLE" USING HANDLE-1.
CALL "P$TEXTOUT"   USING "Text written to PRINTER 1".

CLOSE PFILE1, PFILE2, PFILE3.
```

Printing Text at the Top of a Page

The following code fragment demonstrates how to position and print text at the top center of the page.

```
       CALL "P$GetDeviceCapabilities" Using DC-HorizontalSizeParam,
                                            DC-HorzSize.
       CALL "P$GetTextExtent" Using "Top Center",
                                            Ws-Text-Width,
                                            Ws-Text-Height,
                                            UnitsAreMetric.
   * Divide by 10 to convert millimeters to centimeters.
       Compute Ws-X-M = ((DC-HorzSize / 10) / 2) - (Ws-Text-Width / 2).
       Move Zero to Ws-Y-M.
       CALL "P$SetTextPosition" USING Ws-X-M, Ws-Y-M,
                                            PositionIsTop,
                                            ModeIsAbsolute,
                                            UnitsAreMetric.
       CALL "P$TextOut" Using "Top Center".
```

Printing Text at the Corners of a Page

The following code fragment demonstrates how to position and print text at the top left corner and bottom right corner of the page.

```
* Position Text Top Left.
    CALL "P$SetTextPosition" Using 0, 0,
                                   PositionIsTop,
                                   ModeIsAbsolute,
                                   UnitsAreDeviceUnits.

    CALL "P$TextOut" Using "Top Left".

* Position Text Bottom Right.
    CALL "P$GetTextExtent" Using "Bottom Right",
                                   Ws-Text-Width,
                                   Ws-Text-Height,
                                   UnitsAreMetric.

    CALL "P$GetDeviceCapabilities" Using DC-HorizontalSizeParam,
                                   DC-HorzSize,
                                   DC-VerticalSizeParam,
                                   DC-VertSize.

* Divide by 10 to convert millimeters to centimeters.
    Compute Ws-X-M = (DC-HorzSize / 10) - Ws-Text-Width.
    Compute Ws-Y-M = (DC-VertSize / 10).
    CALL "P$SetTextPosition" Using Ws-X-M, Ws-Y-M,
                                   PositionIsBottom,
                                   ModeIsAbsolute,
                                   UnitsAreMetric.

    CALL "P$TextOut" Using "Bottom Right".
```

Setting the Point Size for a Font

The following code fragment demonstrates how to set the point size for a specified font.

```
       Open Output PrintFile.
       CALL "P$GetDeviceCapabilities" Using  DC-LogicalPixelsYParam,
                                             DC-LogPixelsY.

    * Compute Font Height for desired Point-Size.
    * If Point-Size is 72, this produces a 1-inch high font, including
    * Internal Leading.
       Compute LF-Height Rounded = (Point-Size * Dc-LogPixelsY) / 72.

       Move "Times New Roman" To LF-FaceName.
       CALL "P$SetFont" Using LF-FaceNameParam, LF-FaceName,
                              LF-HeightParam, LF-Height.
       CALL "P$GetTextMetrics" Using TextMetrics.

    * Add bias for Internal Leading.
    * If Point-Size is 72, this adjustment produces a 1-inch high font
    * excluding Internal Leading.
       Compute LF-Height = (LF-Height * TM-Height) /
                              (TM-Height - TM-InternalLeading).

    * Set Font with computed LF-Height
       CALL "P$SetFont" Using LF-HeightParam, LF-Height.
       Write Printer-Record from "Greetings" After Advancing 1.
```

Setting Text Position

The following code fragment will print large "Greetings" followed by three smaller "Greetings" positioned by top alignment, base line alignment and bottom alignment.

```
* Print initial Greetings in a Large Font Size.
   CALL "P$SetFont"         Using LF-HeightParam, 330.
   CALL "P$TextOut"         Using "Greetings", 0.25, 2,
                                  ModeIsAbsolute,
                                  UnitsAreInches.
* Get the Top Text Position.
   CALL "P$GetTextPosition" Using Ws-X-D, Ws-Top,
                                  PositionIsTop,
                                  UnitsAreDeviceUnits.
* Get the Bottom Text Position.
   CALL "P$GetTextPosition" Using Ws-XB-D, Ws-Bottom,
                                  PositionIsBottom,
                                  UnitsAreDeviceUnits.
* Get the Base Line Position.
   CALL "P$GetPosition" Using Ws-XP-D, Ws-Base,
                                  UnitsAreDeviceUnits.
   CALL "P$SetFont" Using LF-HeightParam, 50.
* Set the Top Text Position and print, get next X Position.
   CALL "P$SetTextPosition" Using Ws-X-D, Ws-Top,
                                  PositionIsTop,
                                  ModeIsAbsolute,
                                  UnitsAreDeviceUnits.
   CALL "P$TextOut" Using "Greetings".
   CALL "P$GetPosition" Using Ws-X-D, Ws-Dummy,
                                  UnitsAreDeviceUnits.
* Set the Base Line Position and print, get next X Position.
   CALL "P$SetPosition" Using Ws-X-D, Ws-Base,
                                  ModeIsAbsolute,
                                  UnitsAreDeviceUnits.
   CALL "P$TextOut" Using "Greetings".
   CALL "P$GetPosition" Using Ws-X-D, Ws-Dummy,
                                  UnitsAreDeviceUnits.
* Set the Bottom Position and print.
   CALL "P$SetTextPosition" Using Ws-X-D, Ws-Bottom,
                                  PositionIsBottom,
                                  ModeIsAbsolute,
                                  UnitsAreDeviceUnits.
   CALL "P$TextOut"         Using "Greetings".
```

RM/COBOL-Specific Escape Sequences

The typical COBOL application written for Windows makes use of the various Windows printer drivers to control printing functions. Many legacy COBOL programs, however, contain embedded or programmatic escape sequences and thus cannot take advantage of Windows printer drivers. To accommodate these programs, the RM/COBOL runtime has been enhanced to implement a set of RM/COBOL-specific escape sequences to control printing. These escape sequences, which are similar to the Hewlett Packard PCL (Print Command Language) commands, are then mapped by the runtime to the correct printer driver GDI (Graphics Device Interface) calls to accomplish the desired function.

Table E-9 lists the available printing functions and their escape sequences and options. The "Options" column of the table describes the permissible values for certain variables in an escape sequence that are represented by the characters #, ##, or ###. These variables are always binary values, that is, they are not ASCII characters representing the values.

Table E-9 RM/COBOL-Specific Escape Sequences

Function	ASCII	Decimal	Hex	Options (#, ##, or ###)
Reset	<Esc>E	027 069	1B 45	Clears the margins, clears line spacing, clears line extend mode, resets text length, sets page orientation back to portrait, sets paper source back to DMBIN_ONLYONE, and sets the font back to default font.
Left Margin	<Esc>&a#L	027 038 097 ### 076	1B 26 61 ## 4C	Size of left margin, in characters (calculated using current font).
Set Tab Stops	<Esc>&k#H	027 038 107 ### 072	1B 26 6B ## 48	Horizontal increment in characters (calculated using current font).
Line Spacing	<Esc>&l#D	027 038 108 ### 068	1B 26 6C ## 44	Lines per inch.
Top Margin	<Esc>&l#E	027 038 108 ### 069	1B 26 6C ## 45	Size of top margin, in lines (calculated using current font).
Text Length	<Esc>&l#F	027 038 108 ### 070	1B 26 6C ## 46	Length of page, in lines (calculated using current font).

Table E-9 RM/COBOL-Specific Escape Sequences (*Cont.*)

Function	ASCII	Decimal	Hex	Options (#, ### or ##)
Paper Source	<Esc>&l#H	027 038 108 ### 072	1B 26 6C ## 48	1 - DMBIN_ONLYONE 2 - DMBIN_LOWER 3 - DMBIN_MIDDLE 4 - DMBIN_MANUAL 5 - DMBIN_ENVELOPE 6 - DMBIN_ENVMANUAL 7 - DMBIN_AUTO 8 - DMBIN_TRACTOR 9 - DMBIN_SMALLFMT 10 - DMBIN_LARGEFMT 11 - DMBIN_LARGECAPACITY 14 - DMBIN_CASSETTE 15 - DMBIN_FORMSOURCE
Orientation	<Esc>&l#O	027 038 108 ### 079	1B 26 6c ## 4F	0 - Portrait 1 - Landscape
Print Pitch	<Esc>(s#H	027 040 115 ### 072	1B 28 73 ## 48	Characters per horizontal inch.
Style	<Esc>(s#S	027 040 115 ### 083	1B 28 73 ## 53	0 - Normal 1 - Italic 2 - Bold 4 - Underline 8 - Compressed 16 - Expanded
Font Height	<Esc>(s#V	027 040 115 ### 086	1B 28 73 ## 56	Characters per vertical inch.
Clear Margins	<Esc>9	027 057	1B 39	Clear left and top margin.
Null	<NUL>	000	00	See **Note** below.*
Horizontal Tab	<HT>	009	09	Position to next tab stop.
Shift Out	<SO>	014	0E	Shifts normal font to expanded font. Shifts compressed font to normal. Stays in effect until start of new line.
Shift In	<SI>	015	0F	Shifts normal font to compressed font. Shifts expanded font to normal font. Stays in effect until start of new line.

Note RM/COBOL normally changes nulls to spaces before sending them to the printer. This behavior may be changed by setting the property “Printer Enable Null Esc. Seq.” value to Yes.

Appendix F: Subprogram Library

This appendix describes the subprograms that are supplied with the RM/COBOL runtime system. It also describes the required RM/COBOL calling sequence and the USING list parameters. Failure to comply with the USING list requirements will halt the run unit with a STOP RUN indication at the line containing the incorrect CALL statement.

Note Subprogram names are case insensitive. For readability, mixed case is used in this document when subprogram names are lengthy. Uppercase letters are used for short subprogram names, in calling sequences, and in code fragments.

Subprogram Library

Table F-1 lists the subprograms alphabetically and gives a brief description.

Table F-1 RM/COBOL Subprogram Library

Subprogram	Function
C$Bitmap	Sets the name of a bitmap file for a program.
C$BTRV	Calls Btrieve directly from an RM/COBOL program.
C$CARG	Returns information about a passed argument.
C$Century	Facilitates updating RM/COBOL programs to handle the year 2000.
C$ClearDevelopmentMode	Disables expanded error information reporting (known as "development mode") for many of the C$ and P$ subprograms.
C$Delay	Relinquishes the CPU for a specified length of time.
C$Forget	Marks an area of the runtime system's in-memory screen image as unknown.
C$GetEnv	Retrieves environment variables.
C$GetLastFileName	Retrieves the last file used in a COBOL I/O statement.
C$GetLastFileOp	Retrieves information about the last COBOL I/O operation.
C$GetRMInfo	Retrieves RM/COBOL runtime system information.
C$GetSyn	Retrieves the values of RM/COBOL synonyms from the Windows registry file.
C$GetSysInfo	Retrieves operating system information

Table F-1 RM/COBOL Subprogram Library *(Cont.)*

Subprogram	Function
C$GUICFG	Changes the RM/COBOL graphical user interface (GUI) properties.
C$MBar	Sets the menu bar for a program.
C$MemoryAllocate	Allocates dynamic memory.
C$MemoryDeallocate	Deallocates (frees) dynamic memory.
C$NARG	Returns the number of arguments passed to the called subprogram.
C$OSLockInfo	Returns the process ID of the process that performed the last lock operation.
C$PlaySound	Plays Windows predefined sound events or sound files.
C$RBMenu	Sets the pop-up menu for a program that is displayed when the right mouse button is pressed.
C$RERR	Returns expanded completion status for the last I/O operation.
C$SBar	Sets the status bar for a program.
C$SCRD	Allows the contents of the screen to be read into an alphanumeric data item.
C$SCWR	Allows the quick display of a large amount of screen data containing various attributes.
C$SetDevelopmentMode	Enables expanded error information reporting (known as “development mode”) for many of the C$ and P$ subprograms.
C$SetEnv	Sets environment variables.
C$SetSyn	Sets the values of RM/COBOL synonyms in the Windows registry file.
C$Show	Sets the show state of the main RM/COBOL window.
C$ShowArgs	Displays the list of arguments used to call C$ShowArgs.
C$TBar	Sets the toolbar for a program.
C$TBarEn	Enables and disables buttons on the toolbar.
C$TBarSeq	Sets the bitmap sequence of buttons on the toolbar.
C$Title	Sets the title displayed for the RM/COBOL window.
C$WRU	Returns the location from which a subprogram was called.
SYSTEM	Allows an arbitrary operating system command to be executed.

Subprogram Library

C$Bitmap

C$Bitmap is used to display a bitmap file on the RM/COBOL window.

To use this subprogram, the runtime system must be able to locate the **c$bitmap.dll** file. The following example illustrates how to add this DLL to the Runtime Command line with the L Option:

```
runcobol program-name L=C$BITMAP.DLL
```

Other Runtime Command Options can be used (see Chapter 7, *Running*).

Note This subprogram is supported only under Windows.

Calling Sequence

```
CALL "C$BITMAP" USING filename
```

filename is an alphanumeric data item that contains the name of an existing Windows bitmap (**.bmp)** file. The file will be located using the runtime system search path.

C$BTRV

C$BTRV is used to call Btrieve directly from an RM/COBOL program.

To use this subprogram, the runtime system must be able to locate the **c$btrv.dll** file. In addition, Btrieve, available from Pervasive Software, must be installed on the computer.

Note This subprogram is supported only under 32-bit Windows.

Calling Sequence

```
CALL "C$BTRV" USING opcode, status, position-block,
      data-buffer, buffer-length, key-buffer, key-number
```

opcode is any unsigned numeric data item that contains the desired Btrieve operation code value.

status is any signed numeric data item that receives the Btrieve status code result of the operation.

position-block is a 128-byte alphanumeric data item that is used by many of the Btrieve operations and should not be modified by the COBOL program.

data-buffer is an alphanumeric data item that contains the data associated with the Btrieve operation. The contents may be input and/or output depending upon the given Btrieve operation.

buffer-length is any unsigned numeric data item that contains the length of the data in the data buffer. This value may be input and/or output depending upon the given Btrieve operation.

key-buffer is a 256-byte alphanumeric data item that contains the key value associated with the Btrieve operation. The contents may be input and/or output depending upon the given Btrieve operation.

key-number is any signed numeric data item into which the key number or special option value is stored depending upon the given Btrieve operation.

Note This subprogram uses the CodeBridge parameter conversion facility for the four numeric arguments to allow maximum flexibility in their definition. See the CodeBridge documentation for more details.

Examples

The following is a typical DATA DIVISION description of the arguments (the data buffer item can be any size that is appropriate for the operation being performed):

```
01  B-OPCODE            PIC 9(5).
01  B-STATUS            PIC S9(5).
01  B-POSITION-BLOCK    PIC X(128).
01  B-DATA-BUFFER       PIC X(10000).
01  B-BUFFER-LENGTH     PIC 9(5).
01  B-KEY-BUFFER        PIC X(256).
01  B-KEY-NUMBER        PIC S9(3).
```

The following is a typical PROCEDURE DIVISION call of C$BTRV using the arguments described above:

```
CALL "C$BTRV" USING B-OPCODE, B-STATUS, B-POSITION-BLOCK,
                    B-DATA-BUFFER, B-BUFFER-LENGTH,
                    B-KEY-BUFFER, B-KEY-NUMBER.
```

Refer to your *Btrieve Programmer's Manual* for a complete description of the parameters sent from and returned to the application for each Btrieve operation.

The following specific example, using the Btrieve Version (26) operation, also will work:

```
01  B-OP-VERSION        PIC 99 VALUE 26.
01  B-STATUS            PIC S9(5) SIGN LEADING SEPARATE.
01  B-POSITION-BLOCK    PIC X(128).
01  B-VERSION-BUFFER    PIC X(30).
01  B-VER-BUF-LEN       PIC 99 VALUE 30.
01  B-KEY-BUFFER        PIC X(256)
                        VALUE "\\RM1\VOL2\USERS\BTRV.FIL".
01  B-KEY-NUMBER        PIC S9 VALUE 0.

CALL "C$BTRV" USING B-OP-VERSION, B-STATUS, B-POSITION-BLOCK,
                    B-VERSION-BUFFER, B-VER-BUF-LEN,
                    B-KEY-BUFFER, B-KEY-NUMBER.
```

C$CARG

C$CARG returns information about the actual parameter that corresponds to a formal parameter in the USING or GIVING phrases in the Procedure Division header of a subprogram. This information identifies the type and length of the argument and, when the argument is numeric, the number of digits and scale factor for the argument.

Calling Sequence

```
CALL "C$CARG" USING okay, argument-name,
      argument-description
```

okay is a one-character alphanumeric data item into which the ASCII character Y is stored if C$CARG successfully identifies the argument named by *argument-name*; otherwise, the ASCII character N is stored in the data item.

argument-name is the name of a Linkage Section data item named in the Procedure Division header USING list.

argument-description is a ten-character group data item into which the desired information about *argument-name* is stored. A typical description for *argument-description* is as follows:

```
01 ARGUMENT-DESCRIPTION      BINARY(2).
   02 ARGUMENT-TYPE          PIC  9(2).
   02 ARGUMENT-LENGTH        PIC  9(8) BINARY(4).
   02 ARGUMENT-DIGIT-COUNT   PIC  9(2).
   02 ARGUMENT-SCALE         PIC S9(2).
```

Note The *argument-description* group item will only have the correct length if ARGUMENT-TYPE, ARGUMENT-DIGIT-COUNT, and ARGUMENT-SCALE are allocated as two-byte binary and ARGUMENT-LENGTH is allocated as four-byte binary. Use of the BINARY-ALLOCATION compiler configuration keyword (see page 10-6) can change the allocation of binary numeric data items such that this requirement is not met. For example, if BINARY-ALLOCATION=RM1, the default allocation for a data item described with PIC 9(2) is one byte. The example shown specifies a binary allocation override for each binary item to guarantee the right allocation regardless of the configured binary allocation scheme. The binary allocation override is not necessary if BINARY-ALLOCATION=RM. The binary allocation override would also not be necessary for binary allocation schemes RM1 and MF-RM if all three 9(2) entries were changed to 9(3) entries.

A description of the values that may be stored in ARGUMENT-TYPE is found in Table D-1 on page D-16. The number of character positions occupied by ARGUMENT-NAME is stored in ARGUMENT-LENGTH. If ARGUMENT-TYPE indicates that ARGUMENT-NAME is a nonedited numeric data item, the number of digits defined in the picture character-string for the data item is stored in ARGUMENT-DIGIT-COUNT and the power of 10 scale factor (that is, the position of the implied decimal point) is stored in ARGUMENT-SCALE.

Note If a calling program passes a called program two arguments that begin at the same location (either through redefinition, with reference modification, or because one is a group that contains the other), when the called program asks C$CARG for the parameter descriptions, it always receives that of the first actual argument passed.

C$Century

C$Century facilitates updating RM/COBOL programs to handle the year 2000 issue. It retrieves the first two digits of the current year. For example, for the year 1999, it will return 19; for the year 2000, it will return 20.

Note A number of changes have been made to the Format 2 ACCEPT statement related to improving the way dates and times are handled. These changes provide additional ways of writing Y2K-compliant COBOL. New phrases include CENTURY-DATE, CENTURY-DAY, DATE-AND-TIME, and DAY-AND-TIME. See the *RM/COBOL Language Reference Manual* for more information.

Calling Sequence

```
CALL "C$CENTURY" USING value-buffer
```

value-buffer is a data item with a format of either unsigned numeric display (NSU) or alphanumeric display (ANS).

C$ClearDevelopmentMode

C$ClearDevelopmentMode is used to disable expanded error information reporting (known as “development mode”) for many of the C$ and P$ subprograms. (The P$ subprograms are discussed in Appendix E, *Windows Printing*.) When development mode is enabled (see “C$SetDevelopmentMode” on page F-33), more verbose error reporting is performed to assist the COBOL developer in implementing these subprogram calls.

Calling Sequence

```
CALL "C$CLEARDEVELOPMENTMODE"
```

C$Delay

C$Delay is used to relinquish the CPU for a length of time specified in seconds. Calling C$Delay will allow other programs to run while the original program waits. The amount of delay is not exact. It depends upon the particular machine configuration and the load on the machine.

Calling Sequence

```
CALL "C$DELAY" USING seconds
```

seconds is a PICTURE 9(*n*) BINARY, where *n* can be a digit from 1 to 9. It specifies the length of time, in seconds, to delay. Delays longer than one day are not normally meaningful and should not be used.

C$Forget

C$Forget marks an area of the runtime system's in-memory screen image as unknown. The next COBOL output to the unknown area will not be optimized based on the screen contents. This allows COBOL output to be displayed correctly over linked C subprogram output, which is not stored in the in-memory screen image.

Note This subprogram is supported only under UNIX.

Calling Sequence

```
CALL "C$FORGET" [USING upper-left-line, upper-left-position,
     lower-right-line lower-right-position]
```

upper-left-line and *upper-left-position* are optional, three-digit, COMP-4 (BINARY) data items that describe the upper-left corner of the area of the screen to be marked as unknown. Valid values range from 0 to the limit of the screen line or position.

lower-right-line and *lower-right-position* are optional, three-digit, COMP-4 (BINARY) data items that describe the lower-right corner of the area of the screen to be marked as unknown. Valid values range from 0 to the limit of the screen line or position.

If you call C$Forget with no parameters, the entire screen is marked as unknown. The same result can be achieved by passing parameters with a value of 0. When a pop-up window is displayed and then removed over an unknown area, the original screen contents are replaced with spaces, except for the pop-up window borders and titles, which are not stored in the in-memory screen image.

Linked C subprograms also can use C$Forget by calling RmForget() with four int parameters specifying the area to be marked as unknown. (See the section "C Entry Points For COBOL Functions" on page D-23 in Appendix D, *Customizing RM/COBOL for UNIX*.)

C$GetEnv

C$GetEnv is used to retrieve the values of environment variables.

Calling Sequence

```
CALL "C$GETENV" USING name, value[, return]
```

name is an alphanumeric data item that contains the name of the environment variable to retrieve.

value is an alphanumeric data item that contains the value of the environment variable upon return from the call.

return is a PICTURE 9(*n*) BINARY, where *n* can be a digit from 1 to 9. It is set to 0 if the call was successful and non-zero if it failed.

C$GetLastFileName

C$GetLastFileName is used to retrieve the last file-name and pathname used in a COBOL I-O statement (including OPEN and CLOSE).

Calling Sequence

```
CALL "C$GETLASTFILENAME" USING filename [, pathname ]
```

filename is an alphanumeric data item that will contain the COBOL file-name specified in the most recently executed I-O statement. For REWRITE and WRITE statements, the COBOL file-name associated with the specified file record-name is provided. The alphanumeric data item should be 30 characters long. If the COBOL file-name is longer than the length of the data item, it will be truncated on the right.

pathname is an alphanumeric data item that will contain the name of the last used pathname (complete file-name). The value SPACES indicates that no name is available (the last file used in an I/O operation was probably closed or no file has been opened). The alphanumeric data item should be at least 64 characters long. If the complete file access name is longer than the length of the data item, it will be truncated on the right.

C$GetLastFileOp

C$GetLastFileOp is used to retrieve information about the last COBOL I/O operation performed. The function returns the COBOL operation performed, and the line number and the intraline number where the operation was done. The intended use of this library subprogram is within a declarative procedure after an I/O error has occurred.

Calling Sequence

```
CALL "C$GETLASTFILEOP" USING operation
       [, prog-line [, prog-intraline ]]
```

operation is an alphanumeric data item that will contain the name of the last COBOL I/O operation performed (see the list below for possible values). The value SPACES indicates that no operation is available (the file was probably never opened). The

alphanumeric data item should be 20 characters long. If the operation value is longer than the length of the data item, it will be truncated on the right.

- "Close"
- "CloseUnit"
- "Delete"
- "DeleteFile""
- "DeleteRandom"
- "Open"
- "ReadNext"
- "ReadPrevious"
- "ReadRandom"
- "Rewrite"
- "RewriteRandom"
- "Start"
- "Unlock"
- "Write"
- "WriteRandom"

prog-line is a BINARY data item with the picture PIC 9(6), which will contain the line number of the most recent COBOL I/O operation. If the program that contains the I/O operation was compiled with the Q Compile Command Option (see Chapter 6, *Compiling*), the value stored in *prog-line* is the segment offset of the statement. Use the values from the Debug heading of the program listing to locate the statement.

prog-intraline is a BINARY data item with the picture PIC 9(2), which will contain the intraline number of the I/O operation. See page 9-3 for a description of Debug line and intraline numbers. If the program that contains the I/O operation was compiled with the Q Option, the value stored in *prog-intraline* is zero.

Note The PROGRAM-ID special register may be used to obtain the program-name of the COBOL program that performed the COBOL I/O operation. For more information about the PROGRAM-ID special register, see Chapter 1, *Language Structure*, of the *RM/COBOL Language Reference Manual*.

C$GetRMInfo

C$GetRMInfo is used to retrieve information about the RM/COBOL runtime system.

Calling Sequence

```
CALL "C$GETRMINFO" USING RMInfoGroup
```

RMInfoGroup is a group data item as defined in the following copy file, RMINFO.CPY. The RMINFO.CPY copy file is supplied with an RM/COBOL development system.

```
*
*   RM/COBOL Information Definitions
*
01  RMInformation.
    02  RM-BinaryVersionNumber.
        03  RM-MajorVersion           Picture 9(5) Binary(2).
        03  RM-MinorVersion           Picture 9(5) Binary(2).
        03  RM-PointVersion           Picture 9(5) Binary(2).
    02  RM-VersionNumber              Picture X(8).
    02  RM-RegistrationNumber.
        03  RM-ProductCode            Picture XX.
        03  RM-Filler                 Picture X.
        03  RM-ADRNumber              Picture 9(4).
        03  RM-Filler                 Picture X.
        03  RM-SerialNumber           Picture 9(5).
        03  RM-Filler                 Picture X.
        03  RM-UseCount               Picture 9(4).
    02  RM-UseCountLimit              Picture 9(5) Binary(2).
    02  RM-UseCountInUse              Picture 9(5) Binary(2).
    02  RM-MainProgramName            Picture X(30).
    02  RM-ApplRegistrationNumber     Picture X(16).
    02  RM-BuildPlatform              Picture X(80).
    02  RM-InterfaceValue             Picture 9 Binary(2).
        88  RM-InterfaceIsTermcap       Value 1.
        88  RM-InterfaceIsTerminfo      Value 2.
        88  RM-InterfaceIsVMS           Value 3.
        88  RM-InterfaceIsDOS           Value 4.
        88  RM-InterfaceIsBIOS          Value 5.
        88  RM-InterfaceIsRAM           Value 6.
        88  RM-InterfaceIsJBIOS         Value 7.
        88  RM-InterfaceIsJRAM          Value 8.
        88  RM-InterfaceIsGUI           Value 9.
    02  RM-TerminalInterface          Picture X(10).
    02  RM-ConfigurationValue         Picture X.
        88  RM-ConfigurationIsBuiltIn   Value 'Y' When False 'N'.
    02  RM-WindowMangerValue          Picture X.
        88  RM-WindowManagerIsPresent   Value 'Y' When False 'N'.
    02  RM-EnterpriseCodeBnchValue    Picture X.
        88  RM-EnterpriseCodeBnchIsPresent  Value 'Y' When False 'N'.
    02  RM-VGIBValue                  Picture X.
        88  RM-VGIBIsPresent            Value 'Y' When False 'N'.
```

```
02  RM-INFOXValue                Picture X.
    88  RM-INFOXIsPresent          Value 'Y' When False 'N'.
02  RM-plusDBValue               Picture X.
    88  RM-plusDBIsPresent         Value 'Y' When False 'N'.
02  RM-MCBAValue                 Picture X.
    88  RM-MCBAIsPresent           Value 'Y' When False 'N'.
02  RM-FlexGenValue              Picture X.
    88  RM-FlexGenIsPresent        Value 'Y' When False 'N'.
02  RM-RPCValue                  Picture X.
    88  RM-RPCIsPresent            Value 'Y' When False 'N'.
02  RM-CGIXValue                 Picture X.
    88  RM-CGIXIsPresent           Value 'Y' When False 'N'.
02  RM-OFMValue                  Picture X.
    88  RM-OFMIsPresent            Value 'Y' When False 'N'.
02  RM-Reserved                  Picture X(21).
```

C$GetSyn

C$GetSyn is used to retrieve the values of RM/COBOL synonyms from the Windows registry file.

Note This subprogram is supported only under Windows.

Calling Sequence

```
CALL "C$GETSYN" USING name, value, program
```

name is an alphanumeric data item that contains the name of the synonym to retrieve.

value is an alphanumeric data item that contains the value of the synonym upon return from the call.

program is an alphanumeric data item that indicates the name of the program whose synonym properties are being retrieved. A value of SPACES indicates to use the "Defaults" properties.

C$GetSysInfo

C$GetSysInfo is used to retrieve information about the operating system on which the RM/COBOL runtime system is running. Under UNIX, this information is retrieved directly from the operating system. Under DOS and Windows, information that is not available from the operating system is instead retrieved from the environment.

Calling Sequence

```
CALL "C$GETSYSINFO" USING SystemInfoGroup
```

SystemInfoGroup is a group data item as defined in the following copy file, SYSINFO.CPY. The SYSINFO.CPY is supplied with an RM/COBOL development system.

```
*
*   System Information Definitions
*
01  SystemInformation.
    02  Sys-Name                    Picture X(20).
    02  Sys-Version.
        03  Sys-MajorVersion        Picture 9(5) Binary(2).
        03  Sys-MinorVersion        Picture 9(5) Binary(2).
    02  Sys-NodeName                Picture X(20).
    02  Sys-Machine                 Picture X(20).
    02  Sys-UserName                Picture X(20).
    02  Sys-UserID                  Picture 9(10) Binary(4).
    02  Sys-GroupName               Picture X(20).
    02  Sys-GroupID                 Picture 9(10) Binary(4).
    02  Sys-StationName             Picture X(20).
    02  Sys-ProcessID               Picture 9(10) Binary(4).
    02  Sys-IsMultiUserValue        Picture X.
        88  Sys-IsMultiUser            Value 'Y' When False 'N'.
    02  Sys-Reserved                Picture X(23).
```

Value	Meaning
Sys-Name	Contains the name of the operating system. Under Windows, it may be “Windows 95”, “Windows 98”, “Windows NT”, “Windows 2000”, or “Windows Unknown”. Under UNIX, it is the name of the operating system.
Sys-Version	Contains the major and minor version number of the operating system.
Sys-NodeName	Contains the NETBIOS computer name established at system startup.
Sys-Machine	Contains the identity of the processor. It is set to “Intel 386”, “Intel 486”, “Intel Pentium”, “MIPS R4000”, “Alpha 21064”, or “Unknown *nnnnn*”, where *nnnnn* is the raw processor value returned by the operating system.
Sys-UserName	Contains the name of the user. This is obtained by querying the following three sources, in the following order: 1. The name of the currently logged-in user. 2. The NAME environment variable. 3. The USER environment variable. If none of the above are set, the field is set to “USER”.
Sys-UserID	Contains the numeric ID assigned to this user. Under Windows, this item is set to the numeric contents of the USERID environment variable, or 0 if this variable is not set or is non-numeric.
Sys-GroupName	Contains the name of the group to which the user belongs. Under Windows, this item is set to the contents of the GROUP environment variable, or “GROUP” if this variable is not set.
Sys-GroupID	Contains the numeric ID assigned to the group to which this user belongs. Under Windows, this item is set to the numeric contents of the GROUPID environment variable, or 0 if this variable is not set or is non-numeric.
Sys-StationName	Contains the name of the terminal. Under Windows, this item is set to the contents of the STATION environment variable, or “CON” if not set. Under UNIX, this item is set to the name of the current tty.
Sys-ProcessID	Contains the numeric ID of the current process.
Sys-IsMultiUserValue	Indicates if this runtime is running in single or in multiuser mode. This will normally be multiuser mode unless the FORCE-USER-MODE configuration option has been specified.
Sys-Reserved	Reserved for future expansion.

C$GUICFG

C$GUICFG is used to dynamically manipulate certain graphical user interface (GUI) settings. The settings changes are temporary until the next access of the Windows registry file. The registry entries remain unchanged. To use this subprogram, the runtime system must be able to locate the **c$guicfg.dll** file.

Note This subprogram is supported only under Windows.

Calling Sequence

```
CALL "C$GUICFG" USING settingstr [, settingstr
        …  ], exit-code
```

settingstr is an alphanumeric data item that contains the settings modification information. The settings are in the form of *item=value* where *item* is one of the properties listed below. (The descriptions of the items and values are described in the "Setting Miscellaneous Properties" section on page 3-19 in Chapter 3, *Installation and System Considerations for Microsoft Windows*.)

- Auto Paste
- Auto Scale
- Enable Close
- Enable Properties Dialog
- Full OEM To ANSI Conversions
- Icon File
- Mark Alphanumeric
- Paste Termination
- Persistent
- Printer Dialog Always
- Printer Dialog Never
- Remove Trailing Blanks
- Sizing Priority
- Status Bar
- SYSTEM Window Type
- Toolbar
- Update Timeout

exit-code is a PICTURE 9(*n*) BINARY, where *n* can be a digit from 1 to 9.

C$MBar

C$MBar is used to display a menu bar in the RM/COBOL window.

To use this subprogram, the runtime system must be able to locate the **rmbars.dll** file. The following example illustrates how to add this DLL to the Runtime Command line with the L Option:

```
runcobol program-name L=RMBARS.DLL
```

Other Runtime Command Options can be used (see Chapter 7, *Running*).

Note This subprogram is supported only under Windows.

Calling Sequence

```
CALL "C$MBAR" [USING  menustring [, menustring
      …  ], exit-code]
```

menustring is an alphanumeric data item that contains the menu text, as described in the section “Setting Menu Bar Properties” on page 3-34.

exit-code is a PICTURE 9(*n*) BINARY, where *n* can be a digit from 1 to 9.

Note Calling C$MBar with no arguments turns off the menu bar.

C$MemoryAllocate

C$MemoryAllocate is used to allocate dynamic memory.

Calling Sequence

```
CALL "C$MEMORYALLOCATE" USING  memory-pointer,
      memory-size
```

memory-pointer must be a pointer data item (USAGE POINTER) that will contain the address of the allocated memory area upon successful completion of the call. A null pointer value is returned if the call is not successful.

memory-size must be a numeric data item that specifies the size of the area to allocate in bytes. The maximum value for *memory-size* is approximately 2,147,483,611, depending on the size of overhead structures. If the maximum value is exceeded, the allocation request will be unsuccessful and a null pointer will be returned. A null pointer will likely be returned for much smaller values since the operating system will be unable to satisfy the request. If the COBOL data item used to specify *memory-size* supports 10 or more decimal digits, a large value in *memory-size* may be truncated upon conversion internal to C$MemoryAllocate. In this case, an area may be allocated that is smaller than the requested size or the run unit terminated with an error in C$MemoryAllocate.

If the memory allocation is successful, the allocated memory is initialized to spaces.

The allocated memory belongs to the run unit and may be accessed by any program in the run unit that has access to the pointer data item *memory-pointer* or a copy of that pointer data item. Upon termination of the run unit, all dynamically allocated memory will be freed.

The pointer returned by C$MemoryAllocate may be used to set the base address of a based linkage item in a Format 5 SET statement. The memory area may then be accessed by references to the based linkage item or data items subordinate to the based linkage item. References to based linkage items are slower than references to Working-Storage items, so if the program makes frequent references to the based linkage item (for example, in a PERFORM loop), it is a good idea to move the based linkage item to a Working-Storage item.

C$MemoryDeallocate

C$MemoryDeallocate is used to deallocate (free) dynamic memory allocated by a previous call to C$MemoryAllocate.

Calling Sequence

```
CALL "C$MEMORYDEALLOCATE" USING memory-pointer
```

memory-pointer must be a pointer data item (USAGE POINTER) that points to a memory area previously allocated by a call to C$MemoryAllocate. If the pointer does not point to such a memory area, the call does nothing. If the pointer does point to such a memory area and the memory is successfully freed, then the value of *memory-pointer* is set to a null pointer value.

After memory has been deallocated, the program should not make any references to based linkage items whose base address was set to the area of memory that was deallocated until those based linkage items are reassigned to a new valid base address in a Format 5 SET statement. If the program does reference the deallocated memory, an error may occur or undefined data may be accessed, either from the original memory area while it is still on the free memory list or after the memory has been reallocated for a different use. It is the programmer's responsibility to manage pointer data items and the setting of based linkage base addresses to avoid such conditions.

It is not necessary to call C$MemoryDeallocate. The runtime will free any dynamically allocated memory upon termination of the run unit.

C$NARG

C$NARG returns the number of parameters passed in the CALL statement USING list to the subprogram that contains the call to C$NARG. The GIVING argument is not included in the count. Arguments specified explicitly as OMITTED in the USING list of the CALL statement are included in the count. An RM/COBOL subprogram may be called with a variable number of actual parameters if it does not attempt, during its execution, to reference formal parameters for which no actual parameters exist.

Calling Sequence

```
CALL "C$NARG" USING parameter-count
```

parameter-count is a BINARY, COMPUTATIONAL-4 or COMPUTATIONAL-1 data item with the PICTURE 9(3) into which is stored the number of parameters in the USING list on the CALL statement that called the subprogram that called C$NARG.

Note The restriction on a reference to a formal argument for which no corresponding actual argument exists does not apply to a reference in an ADDRESS OF *identifier-1* special register. Thus, the calling program's omission of the GIVING argument or omission of an embedded USING argument (by use of the OMITTED keyword) can be detected by using IF ADDRESS OF *identifier-1* IS EQUAL TO NULL, where *identifier-1* refers to the appropriate formal argument. The restriction also does not apply to Linkage Section 01 or 77 data items specified in the USING or GIVING phrase of a CALL statement.

C$OSLockInfo

C$OSLockInfo returns the process ID of the process that has the record locked when a lock request fails. This subprogram should be called immediately after a lock request has failed.

Note This subprogram is available only under UNIX and only if the system uses the fcntl() system call to perform record locking.

Calling Sequence

```
CALL "C$OSLOCKINFO" USING processid
```

processid is a four-byte, unsigned COMP-4 numeric item.

C$PlaySound

C$PlaySound is used to play Windows predefined sound events or sound files, that is, files with the **.wav** extension.

Calling Sequence

```
CALL "C$PLAYSOUND" USING sound , flags
```

sound is an alphanumeric data item that contains the name of a Windows sound event or **.wav** sound file to play.

flags is a numeric data item that contains flags to use when playing the sound. The possible values are provided below and in the 78-level entries in the WINDEFS.CPY copy file (see page E-69), and may be combined by adding them together.

Value	Meaning
SoundSync	Synchronous playback of a sound event.
SoundAsync	Sound is played asynchronously.
SoundNoDefault	No default sound event is used.
SoundNoStop	The specified sound event will yield to another sound event that is already playing.
SoundPurge	Sounds are to be stopped for the calling task.
SoundApplication	The sound is played using an application-specific association.
SoundNoWait	If the driver is busy, return immediately without playing the sound.
SoundAlias	*sound* is a system-event alias in the Windows registry file or the win.ini file.
SoundFilename	*sound* is a filename.
SoundAliasId	*sound* is a predefined sound identifier.

Example

The following code fragment plays the default Windows 95 **Chimes.wav**:

```
Call "C$PlaySound" Using "Chimes.wav".
```

C$RBMenu

C$RBMenu is used to display a pop-up menu in the RM/COBOL window when the right mouse button is pressed.

To use this subprogram, the runtime system must be able to locate the **rmbars.dll** file. The following example illustrates how to add this DLL to the Runtime Command line with the L Option:

```
runcobol program-name L=RMBARS.DLL
```

Other Runtime Command Options can be used (see Chapter 7, *Running*).

Note This subprogram is supported only under Windows.

Calling Sequence

```
CALL "C$RBMENU" [USING menustring [, menustring
      …  ], exit-code]
```

menustring is an alphanumeric data item that contains the menu text, as described in the "Setting Pop-up Menu Properties" section on page 3-36.

exit-code is a PICTURE 9(*n*) BINARY, where *n* can be a digit from 1 to 9.

Note Calling C$RBMenu with no arguments turns off the pop-up menu.

C$RERR

C$RERR returns the expanded I-O completion status shown beginning on page A-11. It returns either a four-character or an eleven-character extended status code depending upon the length of the data item specified in the USING phrase. This status is for the last attempted I/O operation. When the COBOL I-O status for the last operation is represented differently under ANSI COBOL 1985 and 1974, the value returned conforms to ANSI COBOL 1974 when the calling program is compiled in 1974 mode (that is, when the 7 Compile Command Option is specified, as described in Chapter 6, *Compiling*). The value returned conforms to ANSI COBOL 1985 when the calling program is compiled in 1985 mode.

Calling Sequence

```
CALL "C$RERR" USING extended-status
```

extended-status is either a four-character or an eleven-character alphanumeric data item into which the expanded I/O completion status is stored in ASCII characters.

If *extended-status* is four characters in length, the first two character positions contain the same digits as would the file status data item on completion of the I/O operation. The last two character positions provide additional information about the file status. In cases where Appendix A, *Error Messages*, shows only two digits for a status, the last two character positions will contain ASCII zeroes. Although most statuses contain only the decimal digits 0 through 9, note that the hexadecimal digits A through F are possible in some character positions (for example, 39,3A through 39,3F, as shown on page A-17).

If *extended-status* is eleven characters in length, the first two character positions (positions one and two) contain the same digits as would the file status data item on completion of the I/O operation. In cases where Appendix A shows only two digits for a status, the remaining nine character positions contain ASCII blanks. In cases where Appendix A shows four digits for a status, character position three contains an ASCII comma, character positions four and five contain the last two digits of the status, and the remaining six character positions contain ASCII blanks. For permanent errors (that is, when the first two digits are 30 as shown on pages A-11 and A-14), character position three contains an ASCII comma, character positions four and five contain a two-digit OS code (see Table F-2), character position six contains an ASCII comma, and character positions seven through eleven contain a five-digit, OS-specific error code. Although most statuses contain only the decimal digits 0 through 9, note that the hexadecimal digits A through F are possible in some character positions (for example, 39,3A through 39,3F shown on page A-17).

Table F-2 Two-Digit OS Codes

Code	Description
00	Unknown OS error.
01	File Manager Detected error.
02	MS-DOS error.
03	OS/2 error.
04	UNIX error.
05	RM/COS error.
06	Btrieve error.
07	Informix error.
08	Oracle error.
09	AmigaDos error.
10	Open File Manager error.
11	Runtime Library error.
12	MS-Windows error.
13	NetWare error.
14	VMS error.
15	RM/InfoExpress Server error.
16	RM/InfoExpress Client error.
17	RM/InfoExpress TLI error.
18	RM/InfoExpress TLISYS error.
19	RM/InfoExpress NetBIOS error.
20	RM/InfoExpress SPX error.
21	RM/InfoExpress WinSock error.

Examples

The following examples illustrate the difference between four-character and eleven-character expanded I-O completion status codes.

Four-character	Eleven-character	Meaning
0000	00	Successful.
1000	10	At end.
0405	04,05	Record read shorter than minimum.
395A	39,5A	Key length mismatch (alt. key #10).
3010	30,06,01002	Btrieve error 1002 (memory).
3010	30,21,10054	Windows Sockets error 10054 (reset).

C$SBar

C$SBar is used to display a status bar in the RM/COBOL window.

To use this subprogram, the runtime system must be able to locate the **rmbars.dll** file. The following example illustrates how to add this DLL to the Runtime Command line with the L Option:

```
runcobol program-name L=RMBARS.DLL
```

Other Runtime Command Options can be used (see Chapter 7, *Running*).

Note This subprogram is supported only under Windows.

Calling Sequence

```
CALL "C$SBAR" [USING status-text ]
```

status-text is an alphanumeric data item that contains the text to be displayed on the status line. See “Status Bar Text” property on page 3-27 for more information.

Note Calling C$SBar with no arguments turns off the status bar.

C$SCRD

C$SCRD allows the contents of the screen to be read into an alphanumeric data item.

Calling Sequence

```
CALL "C$SCRD" USING screen-buffer [, buffer-size [,
      screen-line [, screen-position ]]]
```

screen-buffer is an alphanumeric data item that will receive the characters read from the terminal display screen.

buffer-size is an optional COMP-1 data item that specifies the number of characters to be read. If the value is 0 or the parameter is omitted, the actual size of *screen-buffer* is used.

screen-line is a COMP-1 data item that specifies the line where the cursor is to be placed prior to the screen read. If omitted, a value of 1 is used. If a pop-up window is active, *screen-line* is window-relative, not screen-relative.

screen-position is a COMP-1 data item that specifies the position where the cursor is to be placed prior to the screen read. If omitted, a value of 1 is used. If a pop-up window is active, *screen-position* is window-relative, not screen-relative.

Note The three optional arguments, *buffer-size*, *screen-line*, and *screen-position*, may be explicitly omitted by specifying the keyword OMITTED in the corresponding position in the USING list.

The cursor position after the call obeys the rules for the ACCEPT and DISPLAY statements. No errors are returned.

If this function is requested to read characters past the end of the screen or window, as many actual characters as possible are returned. The remainder of the buffer is set to spaces.

It is not possible to retrieve attribute information from the display. Only the actual character values are returned.

If graphic characters have been written to the display using the GRAPHICS keyword of the CONTROL phrase of the ACCEPT and DISPLAY statements, and this call is used to read such characters, the characters returned are the displayed characters, not the values used by the program in the ACCEPT or DISPLAY statement that originally wrote the

characters. For more information, see the description of the GRAPHICS keyword of the CONTROL phrase on page 8-13.

C$SCWR

C$SCWR allows a COBOL program to display quickly a large amount of information containing multiple display attributes.

Calling Sequence

```
CALL "C$SCWR" USING display-description, text-characters
     [, attribute-codes, palette-table ]
```

display-description is a required, 8- to 14-character group data item into which the location and size of the display are stored. The COBOL description is as follows:

```
01 DISPLAY-DESCRIPTION        USAGE BINARY (2).
   02 DISPLAY-VERSION         PIC  9(4) VALUE 0.
   02 DISPLAY-UNIT            PIC  9(4) VALUE 0.
   02 DISPLAY-LINE            PIC  9(4).
   02 DISPLAY-POSITION        PIC  9(4).
   02 DISPLAY-LENGTH          PIC  9(4).
   02 DISPLAY-EXCEPTION-CODE  PIC  9(4).
   02 DISPLAY-EXCEPTION-VALUE PIC  9(4).
```

DISPLAY-VERSION (required, input) is reserved for future use and must be set to a value of 0.

DISPLAY-UNIT (required, input) is the unit number of the terminal to which the display is directed. Under UNIX, specifying a value of 0 causes output to be written to the terminal from which the runtime system was started. Under Windows, this value must be set to 0.

DISPLAY-LINE (required, input) is the one-relative line number in the current window where the text is to be displayed. If set to a value of 0, the display begins on the current line (as described in the "Determining Line and Position" section of the DISPLAY statement in Chapter 6, *Procedure Division Statements*, of the *RM/COBOL Language Reference Manual*).

DISPLAY-POSITION (required, input) is the one-relative column number in the current window where the text is to be displayed. If set to a value of 0, the display begins at the current column (as described in the "Determining Line and

Position" of the DISPLAY statement in Chapter 6, *Procedure Division Statements*, of the *RM/COBOL Language Reference Manual*).

DISPLAY-LENGTH (optional, input) is the number of characters of text to display. If set to a value of 0 or omitted, the actual length of *text-characters* is used (see *text-characters* below).

DISPLAY-EXCEPTION-CODE (optional, output) is set to a value of 0 if this function succeeds. Otherwise, one of the exception codes, described beginning on page F-31, is returned. Notice that some exception codes are merely warnings.

DISPLAY-EXCEPTION-VALUE (optional, output) is set to a value of 0 if this function succeeds. Otherwise, it contains a value that provides more details on the exception that occurred (see page F-31 for more information on the exception codes).

Note *display-description* will only have the correct length if four-digit binary data items are allocated with two bytes of storage. The example shown specifies a binary allocation override to guarantee the right allocation regardless of the configured binary allocation scheme. The binary allocation override is not necessary if BINARY-ALLOCATION=RM, RM1, or MF-RM.

text-characters is a required alphanumeric data item that contains the characters to be displayed. The number of characters to be displayed is controlled by DISPLAY-LENGTH. If DISPLAY-LENGTH is set to a value of 0, all of *text-characters* is displayed. If DISPLAY-LENGTH is less than the length of *text-characters*, the first DISPLAY-LENGTH characters are displayed. Otherwise, *text-characters* is displayed padded with spaces to DISPLAY-LENGTH characters.

attribute-codes is an optional alphanumeric data item that contains the attribute codes used to display *text-characters*. Each attribute code occupies a single character and controls the character at the same relative position in *text-characters*. The value of each attribute code is a one-relative indicator of an entry in *palette-table* (described below). An attribute code of X'00' causes the preceding code in *attribute-codes* to be used again. If there is no preceding code, the colors currently in effect (set by the preceding ACCEPT, DISPLAY, or C$SCWR) are used with all PALETTE-ATTRIBUTE-VALUES set to off.

If *attribute-codes* is omitted, or the length of *attribute-codes* is less than the actual DISPLAY-LENGTH (as described previously), *attribute-codes* is internally padded with X'00'. If *attribute-codes* is longer than the actual DISPLAY-LENGTH, the excess attribute codes are ignored.

If *attribute-codes* is specified, *palette-table* must also be specified.

palette-table is an optional group data item that is used to interpret *attribute-codes*. The table consists of 1 to 255 entries. Each *palette-table* entry describes a combination of colors and attributes.

Here are two possible COBOL descriptions for *palette-table*:

```
01 PALETTE-TABLE-1.
   03 PALETTE-TABLE-ENTRIES.
      05 PALETTE-TABLE-ENTRY-1.
         07 FOREGROUND-COLOR-1   PIC X.
         07 BACKGROUND-COLOR-1   PIC X.
         07 ATTRIBUTE-VALUE-1    PIC 9(4) BINARY(2).
         07 FILL-CHARACTER-1     PIC X.
      05 PALETTE-TABLE-ENTRY-2.
         07 FOREGROUND-COLOR-2   PIC X.
         07 BACKGROUND-COLOR-2   PIC X.
         07 ATTRIBUTE-VALUE-2    PIC 9(4) BINARY(2).
         07 FILL-CHARACTER-2     PIC X.
                    ⋮
      05 PALETTE-TABLE-ENTRY-255.
         07 FOREGROUND-COLOR-255 PIC X.
         07 BACKGROUND-COLOR-255 PIC X.
         07 ATTRIBUTE-VALUE-255  PIC 9(4) BINARY(2).
         07 FILL-CHARACTER-255   PIC X.
01 PALETTE-TABLE-2.
   03 PALETTE-TABLE-ENTRIES.
      05 PALETTE-TABLE-ENTRY         OCCURS 255 TIMES.
         07 FOREGROUND-COLOR-VALUE   PIC X.
         07 BACKGROUND-COLOR-VALUE   PIC X.
         07 ATTRIBUTE-VALUE          PIC 9(4) BINARY(2).
         07 FILL-CHARACTER           PIC X.
```

In the following description of color values, FOREGROUND-COLOR-VALUE contains a value from PALETTE-COLOR-VALUES that indicates the text color; BACKGROUND-COLOR-VALUE contains a value from PALETTE-COLOR-VALUES that indicates the background color. Both FOREGROUND-COLOR-VALUE and BACKGROUND-COLOR-VALUE are ignored with a warning unless a color monitor is being used or the USE-COLOR keyword of the TERM-ATTR configuration record is set to YES (see page 10-40).

The permitted color values are listed below. Using a value not included in this list results in undefined behavior.

```
01 PALETTE-COLOR-VALUES          USAGE DISPLAY.
   03 PALETTE-UNSPECIFIED-1      PIC X VALUE SPACE.
   03 PALETTE-UNSPECIFIED-2      PIC X VALUE X"00".
   03 PALETTE-BLACK              PIC X VALUE "0".
   03 PALETTE-RED                PIC X VALUE "1".
   03 PALETTE-GREEN              PIC X VALUE "2".
   03 PALETTE-YELLOW             PIC X VALUE "3".
   03 PALETTE-BLUE               PIC X VALUE "4".
   03 PALETTE-MAGENTA            PIC X VALUE "5".
   03 PALETTE-CYAN               PIC X VALUE "6".
   03 PALETTE-WHITE              PIC X VALUE "7".
```

PALETTE-UNSPECIFIED-1 or PALETTE-UNSPECIFIED-2 cause the last color output to be used.

ATTRIBUTE-VALUE contains a value that specifies what attributes are to be applied. The value is produced by summing together the desired values from PALETTE-ATTRIBUTE-VALUES, listed below. Values omitted from the following table are reserved and must not be set.

```
01 PALETTE-ATTRIBUTE-VALUES       USAGE BINARY(2).
   03 INTENSITY-HIGH              PIC 9(4) VALUE 1.
   03 BLINK-ON                    PIC 9(4) VALUE 2.
   03 REVERSE-ON                  PIC 9(4) VALUE 4.
   03 UNDERLINE-ON                PIC 9(4) VALUE 8.
   03 GRAPHICS-ON                 PIC 9(4) VALUE 16.
   03 FILL-CHARACTER-ON           PIC 9(4) VALUE 32.
```

With the exception of FILL-CHARACTER-ON, the meaning of each attribute is the same as if the attribute were specified in the CONTROL phrase of a DISPLAY statement. To combine multiple attributes, sum the values together. The FILL-CHARACTER-ON attribute specifies a character to be used instead of the character specified in the *text-characters*.

FILL-CHARACTER contains a character to be displayed if PALETTE-ATTRIBUTE-VALUES indicate FILL-CHARACTER-ON. The FILL-CHARACTER is optional and is needed only when the FILL-CHARACTER-ON attribute has been set.

Because the *palette-table* contains both alphanumeric and numeric fields, use the INITIALIZE statement to remove all colors and attributes from the table. To reset the example palette tables, enter:

```
INITIALIZE PALETTE-TABLE-1, PALETTE-TABLE-2.
```

Usage Notes

If this function is requested to write characters past the end of the screen (or window, if pop-up windows are active), the screen or window is scrolled.

The current line and current position after the call obey the rules for the ACCEPT and DISPLAY statements.

Colors set by this function also affect subsequent ACCEPT and DISPLAY operations if those operations do not specify an FCOLOR or BCOLOR keyword in the CONTROL phrase (see page 8-12).

Fatal Errors

The runtime system terminates if the C$SCWR function is called with any of the following four conditions:

1. C$SCWR is called with other than two or four parameters, or any one of the parameters is a simple numeric parameter.
2. The length of DISPLAY-DESCRIPTION is less than six characters.
3. The length of text-characters is zero.
4. The size of any passed data item exceeds 65535 bytes.

Exception Codes

The following exception codes are stored in the DISPLAY-EXCEPTION-CODE variable. The C$SCWR function reports three types of exception codes: error, warning, and informational. Lower-numbered exception codes are reported before higher-numbered exception codes. These codes and their associated definitions are listed in Table F-3.

Note Error codes take precedence over warning and informational codes. If multiple exceptions occur, the first occurring exception at a given level is returned. If warnings are returned, the display is performed, but the results may not be as expected.

Table F-3 C$SCWR Exception Codes

Code	Type	Description
0		No error detected.
1	Error	An invalid DISPLAY-VERSION was specified. This data item must be set to a value of 0.
2	Error	An I/O error occurred while the write operation was being performed. DISPLAY-EXCEPTION-VALUE contains the RM/COBOL I/O error code.
3	Error	DISPLAY-LINE is greater than the number of lines on the window or screen. The display was not performed. DISPLAY-EXCEPTION-VALUE contains the number of lines on the window or on the screen. An out-of-range line specification is diagnosed before an out-of-range position specification.
4	Error	DISPLAY-POSITION is greater than the number of columns on the screen. The display was not performed. DISPLAY-EXCEPTION-VALUE contains the number of columns on the window or on the screen.
5	Error	The specified palette is invalid. DISPLAY-EXCEPTION-VALUE indicates either (a) the palette table does not contain complete palette entries, or (b) the table contains more than 255 entries.
20	Warning	An out-of-range palette index was specified. DISPLAY-EXCEPTION-VALUE contains the offending palette index. The palette specification is ignored and treated as if unspecified.
21	Warning	The palette contains an invalid foreground color specification. DISPLAY-EXCEPTION-VALUE contains the offending palette index. The color is ignored and treated as if unspecified.
22	Warning	The palette contains an invalid background color specification. DISPLAY-EXCEPTION-VALUE contains the offending palette index. The color is ignored and treated as if unspecified.
23	Warning	The palette contains an invalid foreground and background color specification. DISPLAY-EXCEPTION-VALUE contains the offending palette index. The color is ignored and treated as if unspecified.

Table F-3 C$SCWR Exception Codes *(Cont.)*

Code	Type	Description
24	Warning	The palette contains an invalid attribute value. DISPLAY-EXCEPTION-VALUE contains the offending palette index. The entire attribute code is ignored and treated as if unspecified.
40	Informational	A monochrome display is in use, or USE-COLOR=N was configured. The specified foreground and background colors are not validated and are ignored. This condition cannot be detected under all circumstances. However, in all cases, DISPLAY-EXCEPTION-VALUE contains the palette index of the offending attribute.

C$SetDevelopmentMode

C$SetDevelopmentMode is used to enable expanded error information reporting (known as "development mode") for many of the C$ and P$ subprograms. (P$ subprograms are discussed in Appendix E, *Windows Printing*.) When development mode is enabled, more verbose error reporting is performed to assist the COBOL developer in implementing these subprogram calls. See also "C$ClearDevelopmentMode" on page F-7.

Calling Sequence

```
CALL "C$SETDEVELOPMENTMODE"
```

Development mode also may be set at program startup with the RM_DEVELOPMENT_MODE environment variable:

```
RM_DEVELOPMENT_MODE=[Y|y|N|n]
```

Specify Y or y to enable development mode. Specify N or n, or omit the variable, to disable development mode. All other values are undefined.

C$SetEnv

C$SetEnv is used to set or clear the values of environment variables.

Calling Sequence

```
CALL "C$SETENV" USING name, value [, return ]
```

name is an alphanumeric data item that contains the name of the environment variable to set or clear.

value is an alphanumeric data item that contains the value to which the environment variable is set. A value of SPACES indicates that the environment variable should be deleted.

return is a PICTURE 9(*n*) BINARY, where *n* can be a digit from 1 to 9. It is set to 0 if the call was successful and non-zero if it failed.

C$SetSyn

C$SetSyn is used to set the values of RM/COBOL synonyms in the Windows registry file.

Note This subprograms are supported only under Windows.

Calling Sequence

```
CALL "C$SETSYN" USING name, value, program
```

name is an alphanumeric data item that contains the name of the synonym to set or clear.

value is an alphanumeric data item that contains the value to which the synonym is set. A value of SPACES indicates that the synonym should be deleted.

program is an alphanumeric data item that indicates the name of the program whose synonym properties is being changed. A value of SPACES indicates to use the "Defaults" properties.

C$Show

C$Show is used to set the show state of the main RM/COBOL window.

Note This subprogram is supported only under Windows.

Calling Sequence

```
CALL "C$SHOW" USING flag
```

flag is a numeric data item that contains one of the values described below:

```
01 WIN-SHOW-STYLES.
   03 SW-HIDE               PIC 9(4) BINARY VALUE 0.
   03 SW-MINIMIZE           PIC 9(4) BINARY VALUE 6.
   03 SW-RESTORE            PIC 9(4) BINARY VALUE 9.
   03 SW-SHOW               PIC 9(4) BINARY VALUE 5.
   03 SW-SHOWMAXIMIZED      PIC 9(4) BINARY VALUE 3.
   03 SW-SHOWMINIMIZED      PIC 9(4) BINARY VALUE 2.
   03 SW-SHOWMINNOACTIVE    PIC 9(4) BINARY VALUE 7.
   03 SW-SHOWNA             PIC 9(4) BINARY VALUE 8.
   03 SW-SHOWNOACTIVATE     PIC 9(4) BINARY VALUE 4.
   03 SW-SHOWNORMAL         PIC 9(4) BINARY VALUE 1.
```

Value	Meaning
SW-HIDE	Hides the window and passes activation to another window.
SW-MINIMIZE	Minimizes the specified window and activates the top-level window in the system's list.
SW-RESTORE	Activates and displays a window. If the window is minimized or maximized, Windows restores it to its original size and position (same as SW_SHOWNORMAL).
SW-SHOW	Activates a window and displays it in its current size and position.
SW-SHOWMAXIMIZED	Activates a window and displays it as a maximized window.
SW-SHOWMINIMIZED	Activates a window and displays it as an icon.

Value	Meaning
SW-SHOWMINNOACTIVE	Displays a window as an icon. The window that is currently active remains active.
SW-SHOWNA	Displays a window in its current state. The window that is currently active remains active.
SW-SHOWNOACTIVATE	Displays a window in its mores recent size and position. The window that is currently active remains active.
SW-SHOWNORMAL	Activates and displays a window. If the window is minimized or maximized, Windows restores it to its original size and position (same as SW-RESTORE.

Examples

The following code fragment hides the main window:

```
CALL "C$SHOW" USING SW-HIDE.
```

The following code fragment shows the main window:

```
CALL "C$SHOW" USING SW-SHOW.
```

C$ShowArgs

C$ShowArgs displays the list of arguments that were used to call C$ShowArgs. This facility is useful during development of non-COBOL subprograms.

Note This subprogram is supported only under UNIX and performs no operation when called under Windows.

Calling Sequence

```
CALL "C$SHOWARGS" [USING argument [, argument [, …  ]]]
```

argument is any data item. C$ShowArgs will print its own name, the number of arguments, and the initial state flag. Then, for each argument, C$ShowArgs prints the address of the argument using hexadecimal notation, the size of the argument, the

numeric type of the argument, three or four character-strings indicating the type of the argument, and finally, the number of digits and the scale of the argument.

Note This subprogram is most useful when it is used to replace another subprogram temporarily, thereby allowing the actual arguments that are being passed to be inspected.

Example

```
Name="C$SHOWARGS", Args= 3, Initial=65535
   Arg # 1 Ptr=0041DBA8 Size=12 Type=16 ANS Digits=  0 Scale= 0
   Arg # 2 Ptr=0041DBB4 Size=10 Type= 3 NTC Digits= 10 Scale=-2
   Arg # 3 Ptr=0041DBBE Size=4  Type=11 NBS Digits=  8 Scale= 0
```

C$TBar

C$TBar is used to display a toolbar in the RM/COBOL window.

To use this subprogram, the runtime system must be able to locate the **rmbars.dll** file. The following example illustrates how to add this DLL to the Runtime Command line with the L Option:

```
runcobol program-name L=RMBARS.DLL
```

Other Runtime Command Options can be used (see Chapter 7, *Running*).

Note This subprogram is supported only under Windows.

Calling Sequence

```
CALL "C$TBAR" [USING buttonstr [, buttonstr …  ], exit-code ]
```

buttonstr is an alphanumeric data item that contains the button definition. The syntax is as follows:

```
buttonname["prompt"]=string
```

buttonname is the name of the icon stored in the filename specified by the Icon File property (see page 3-21).

prompt is an optional text string that is displayed if the status bar is on (see Status Bar property on page 3-27) and whenever the cursor is placed on the toolbar icon that is specified by *buttonname*.

string is an ASCII text string. However, it also can contain special characters for the Return, Tab, Escape, or Function keys. If the first character is a greater than character (>), then the characters that follow are executed as a command. The special characters are described in Table 3-2 on page 3-33. (These characters are interpreted by the COBOL ACCEPT statement, as described in Table 8-2 beginning on page 8-6.)

exit-code is a PICTURE 9(*n*) BINARY, where *n* can be a digit from 1 to 9.

Note Calling C$TBar with no arguments turns off the toolbar.

C$TBarEn

C$TBarEn is used to enable and disable buttons on the toolbar.

To use this subprogram, the runtime system must be able to locate the **rmbars.dll** file. The following example illustrates how to add this DLL to the Runtime Command line with the L Option:

```
runcobol program-name L=RMBARS.DLL
```

Other Runtime Command Options can be used (see Chapter 7, *Running*).

If the toolbar button bitmap contains three frames instead of the normal two, the third bitmap will be displayed while the button is disabled.

Note This subprogram is supported only under Windows.

Calling Sequence

```
CALL "C$TBAREN" USING buttonname, flag,
       buttonname, flag, …
```

buttonname is the name of the icon stored in the filename specified by the Icon File property (see page 3-21).

flag is a numeric data item with the value of 1 for enable and 0 for disable.

C$TBarSeq

C$TBarSeq is used to set the bitmap sequence to use for buttons on the toolbar.

To use this subprogram, the runtime system must be able to locate the **rmbars.dll** file. The following example illustrates how to add this DLL to the Runtime Command line with the L Option:

```
runcobol program-name L=RMBARS.DLL
```

Other Runtime Command Options can be used (see Chapter 7, *Running*).

Note This subprogram is supported only under Windows.

Calling Sequence

```
CALL "C$TBARSEQ" USING buttonname, seq,
       buttonname, seq, …
```

buttonname is the name of the icon stored in the filename specified by the Icon File property (see page 3-21).

seq is a numeric data item that contains a value of 0 through 9 indicating the sequence number to use for displaying the named button. See the “Toolbar Editor” section on page 3-37 for more information.

C$Title

C$Title is used to set the window title for the RM/COBOL window.

To use this subprogram, the runtime system must be able to locate the **c$title.dll** file. The following example illustrates how to add this DLL to the Runtime Command line with the L Option:

```
runcobol program-name L=C$TITLE.DLL
```

Other Runtime Command Options can be used (see Chapter 7, *Running*).

Note This subprogram is supported only under Windows.

Calling Sequence

```
CALL "C$TITLE" USING string
```

string is the text to be placed in the window title.

Note The Title Text property (see page 3-28) also can be used to set the text of the title for the RM/COBOL window.

C$WRU

C$WRU returns the program identification, line number, and intraline number of the CALL statement, which called the subprogram that contains the call to C$WRU.

Calling Sequence

```
CALL "C$WRU" USING program-name, prog-line,
      prog-intraline
```

program-name is a 30-character alphanumeric data item into which the program-id of the calling subprogram is stored. If the first subprogram of the run unit (that is, the main program) calls C$WRU, the value "RUNCOBOL" will be stored in PROGRAM-NAME, and zeroes are stored in *prog-line* and *prog-intraline*.

prog-line is a BINARY data item with the picture PIC 9(6) into which the line number containing the CALL statement is stored. If the program that contains the call to the subprogram that called "C$WRU" was compiled with the Q Compile Command Option (see Chapter 6, *Compiling*), the value stored in *prog-line* is the segment offset of the original CALL statement. Use the values from the Debug heading of the program listing to locate the statement.

prog-intraline is a BINARY data item with the picture PIC 9(2) into which the intraline number of the CALL statement is stored. See page 9-3 for a description of Debug line and intraline numbers. If the program that contains the call to the subprogram that called "C$WRU" was compiled with the Q Option, the value stored in *prog-intraline* is zero.

SYSTEM

SYSTEM allows an arbitrary operating system command to be executed.

Calling Sequence

```
CALL "SYSTEM" USING command-line [repaint-screen]
      [exit-code]
```

command-line is an alphanumeric data item that contains the command line to be passed to the operating system. Trailing spaces are stripped from *command-line* before the command is executed. To execute a command line that contains trailing spaces, place a NULL character after the last embedded space.

Note Under Windows, the command line is restricted to 130 characters. On most UNIX systems, the longest command line that can be executed is 4096 characters.

repaint-screen is an optional, one-byte, alphanumeric data item that controls whether the screen is redrawn after execution of the command. A value of Y or y causes the screen to be redrawn. A value of N or n does not redraw the screen. A blank or any other value defaults to the TERM-ATTR configuration record REDRAW-ON-CALL-SYSTEM value (see page 10-39).

Note This parameter is ignored under Windows.

exit-code is an optional numeric data item that contains the exit code of the command upon return from the operating system. *exit-code* must be declared as PIC S9(4) BINARY. The value returned in *exit-code* is dependent on the underlying operating system. A value of 0, however, indicates success and a non-zero value indicates an error.

If the argument count is incorrect or the arguments are of the wrong type, the run unit is stopped with the message “COBOL STOP RUN at line ? in SYSTEM ...”.

UNIX Considerations

A *command-line* that contains either a single NULL character or all blanks starts a new instance of the shell.

The command is executed with the system() library function call. For a null or all space *command-line*, the environment variable SHELL is used to locate the shell processor. To return to the calling COBOL program, type:

```
ctrl+d.
```

Windows Considerations

A *command-line* that contains either a single NULL character or all blanks starts a new instance of the command processor.

The *command-line* parameter may be used to specify either a DOS or Windows program. The execution of the calling COBOL program is suspended until the called program terminates. For a null or all space *command-line*, the environment variable COMSPEC is used to locate the command processor. To return to the calling COBOL program, type:

```
EXIT
```

The style of the window used for Windows programs is controlled with the SYSTEM Window Type property (see page 3-28). The SYSTEM Window Type property also can be set with the C$GUICFG non-COBOL subprogram as described on page F-16.

In order to execute a DOS internal command, it is necessary to specify completely the command processor on the command line. For example, to execute a **dir** command, enter the following:

```
C:\DOS\COMMAND.COM /C DIR
```

This example assumes that the command processor is located on drive C: in the directory DOS.

You can configure whether a DOS program runs in a full screen or in a window by modifying the MS-DOS Prompt Properties. This can be done by right-clicking the MS-DOS Prompt icon and selecting Properties from the pop-up menu.

Appendix G: Utilities

RM/COBOL provides a wide range of file conversion, management, and manipulation facilities. The majority of these utilities allow you to specify the required parameters either in the initial invocation command line or interactively during the course of execution.

This appendix describes the set of utilities provided for file conversion, management, and manipulation.

Organization

The utilities described in this appendix are as follows:

1. The RM/COBOL Conversion utilities provide an easy method of converting RM/COBOL (74) versions 1 and 2 indexed (**rmifca** and **rmifcb**), relative (**rmcrl1** and **rmcrl2**), and sequential (**rmcseq**) files to an RM/COBOL-compatible format.

2. The Combine Program utility (**rmpgmcom**) creates a program file by combining other program files and eliminating duplicate programs. It is used to create object program libraries.

3. The Map Program File utility (**rmmappgm**) produces a report describing the contents of an object program file created by the RM/COBOL compiler or the **rmpgmcom** utility.

4. The Map Indexed File utility (**rmmapinx**) produces a report describing the structure of an indexed file created by an RM/COBOL program or by the **rmdefinx** utility (described in the following item).

5. The Define Index File utility (**rmdefinx**) precreates an indexed file for use by RM/COBOL programs, or modifies some of the characteristics of an existing indexed file.

6. The Indexed File Recovery utility (**recover1**) is used to recover the data in an indexed file.

   The Indexed File Unload utility (**recover2**) is used to unload an indexed file to a sequential file. This utility is no longer needed to recover indexed files.

7. The Attach Configuration utility (**rmattach**), available only under Windows, is used to attach configuration files to **runcobol.exe**, **rmcobol.exe** and **recover1.exe**.

8. The Initialization File to Windows Registry Conversion utility (**ini2reg**), available only under Windows, converts an RM/COBOL for Windows initialization file and places its contents into the Windows registry database.

9. The RM/COBOL Configuration utility (**rmconfig**), available only under Windows, is used to modify the configuration options for one or more RM/COBOL programs.

Utilities Delivered on Media

The programs and files required to execute the utilities described in this appendix are provided with your RM/COBOL product. The actual number of files and programs depends on the specific version of the product you purchased and whether you purchased a development or a runtime system. The delivered media contains one or more README files that list the actual files and programs delivered. Please check these README files after you have installed the product to make sure that you have received all of the appropriate files and programs.

The utility programs and files may be placed in one directory. Be sure that the compiler and runtime system directory search sequences (see page 2-4 for UNIX and page 3-11 for Windows) include the directory in which these files are placed.

General Considerations

Files with an extension of **.cob** were created with the RM/COBOL compiler, and are executed with the RM/COBOL Runtime Command. Files with an extension of **.cbl** are RM/COBOL source files, which are used as examples for relative file conversion and as a copy file-driven, configurable index file conversion utility.

The programs **rmmapinx**, **rmmappgm**, **rmpgmcom**, and **recover1** generate reports that are written to a file named **PRINTER**. Under UNIX, the line printer spooler is used. Under Windows, the runtime system assigns this by default to the Windows default printer.

If you want to discard the report under UNIX, set an environment variable using the following commands:

```
PRINTER=/dev/null ; export PRINTER
```

If you want to discard the report under Windows, set the following synonym:

```
PRINTER=NUL
```

If you want the report to go to a disk file under UNIX, set an environment variable using the following commands:

```
PRINTER=filename ; export filename
```

If you want the report to go to a disk file under Windows, set the following synonym:

```
PRINTER=filename
```

If you want the report to go to the console under UNIX, set an environment variable using the following commands:

```
PRINTER=/dev/tty ; export PRINTER
```

If you want the report to go to the console under Windows, set the following synonym:

```
PRINTER=CON
```

Installing the Utility Programs

The RM/COBOL installation section (see the appropriate installation and system considerations chapter of this user's guide for your specific operating system) contains complete instructions on installing the utility programs. If you did not install the utilities when you installed RM/COBOL, refer to these instructions.

Where necessary, compile the utility programs with the RM/COBOL Compile Command, **rmcobol**.

Indexed File Conversion Utilities (rmifca and rmifcb)

The **rmifca** and **rmifcb** utilities convert an RM/COBOL (74) version 1 or version 2 indexed file to the RM/COBOL format.

rmifca and **rmifcb** require the following:

1. RM/COBOL compiler and runtime system.
2. Object file **rmifca.cob**.
3. Source file **rmifcb.cbl**.
4. RM/COBOL (74) version 1 or version 2 indexed file to be converted.
5. Available disk space for the creation of the new RM/COBOL indexed file. The new file size typically will be smaller than or equal to the original.

Indexed File Naming Conventions

RM/COBOL (74) version 1 and RM/COBOL maintain data and index information in a single file. No special index file naming conventions are required.

RM/COBOL (74) version 2 supports a dual-file format. In the dual-file format, both the data file and the index file (which contains both header and indexes) have the same name. The data file has the default filename extension, and the index file always has a filename extension of **.inx**. For example, if the data filename is **inxfl.dat**, the file that contains the header and indexes is named **inxfl.inx**. This requires that you make certain you include the **.inx** filename extension when specifying a version 2, dual-file indexed file format.

Using the Utility

Follow these steps to convert RM/COBOL (74) versions 1 and 2 indexed files to RM/COBOL format:

1. Execute **rmifca** using the following command:

   ```
   runcobol rmifca
   ```

   The program will prompt for the information required to convert the file.

2. In response to the first prompt, enter the name of the indexed file to be converted. If you are converting a version 2 indexed file, be sure to include the **.inx** filename extension as part of the filename.

   If you specify a version 2 dual-file indexed file, you will be requested to enter the filename of the data file portion of the indexed file.

3. The next prompts deal with the BLOCK and RECORD sizes. In order to answer correctly, you may need to refer to the RM/COBOL (74) source program in which the file is described.

   a. Describe the BLOCK CONTAINS clause. Enter the number of RECORDS or CHARACTERS in the block, and indicate whether the number you entered applies to RECORDS or CHARACTERS.

   b. Describe the RECORD CONTAINS clause. If the file you are converting is a version 2 indexed file, the maximum record length will be filled in. You need only specify the minimum record size if it is a variable-length record. If the file you are converting is a version 1 indexed file, you must specify both the minimum and maximum record sizes.

   c. Enter the name of the RM/COBOL indexed file to be created.

   Once all the information has been supplied, **rmifca** generates the copy files necessary to describe the conversion process to the actual conversion utility **rmifcb**.

4. Compile and execute **rmifcb**. The program displays what it is going to do and asks for confirmation to proceed. The program attempts to estimate processing time.

   rmifcb.cob can be renamed and saved for use as a standalone conversion program for versions 1 and 2 indexed files. If you are an application developer, this should ease the process of getting your users converted from a version 1 or version 2 system to the current RM/COBOL environment.

   The process described above applies only to copying data records from RM/COBOL (74) version 1 or 2 to RM/COBOL indexed files on an “as is” basis. However, since each data record is available during the execution of **rmifcb**, you may wish to customize a copy of **rmifcb** to provide data conversions, such as changing separate signs to combined signs on numeric USAGE display items. Comments in the source file **rmifcb.cbl** suggest where customized code may be placed.

Relative File Conversion Utility: Version 1.5 to RM/COBOL (rmcrl1)

The **rmcrl1** utility converts RM/COBOL (74) version 1.5 relative files to the RM/COBOL format.

Using the Utility

To convert a version 1.5 relative file to the RM/COBOL format, follow these steps:

1. Copy **rmcrl1.cbl** from the installation directory to a working directory.
2. Edit the source program, replacing—where indicated—the record size for the RM/COBOL (74) version 1.5 input and the RM/COBOL output relative files.
3. Enter the RM/COBOL Compile Command (**rmcobol**) to compile the program.
4. Under UNIX, set environment variables to assign file pathnames for the version 1.5 relative file to INPUT, and the RM/COBOL relative file to OUTPUT. For example:

   ```
   INPUT=/dir1/rel1.5 ; export INPUT

   OUTPUT=/dir2/rel85 ; export OUTPUT
   ```

   Under Windows, use synonyms to assign the file pathnames. Setting synonyms is described in Chapter 3, *Installation and System Considerations for Windows*.

   Note The source RM/COBOL (74) version 1 pathname and destination RM/COBOL pathname must specify different files, that is, the conversion cannot be made in place.
5. Enter the RM/COBOL Runtime Command (**runcobol**) to execute the program.

Relative File Conversion Utility: Version 2 to RM/COBOL (rmcrl2)

There are two source programs for converting version 2 relative files: **rmcrl2l.cbl** and **rmcrl2s.cbl**. These programs can be used to convert RM/COBOL (74) version 2 relative files to RM/COBOL format. **rmcrl2s.cbl** converts files with record sizes less than 512 bytes. **rmcrl2l.cbl** converts files with larger record sizes.

Using the Utility

To convert a version 2 relative file to RM/COBOL format, follow these steps:

1. Copy the appropriate source program from the installation directory to a working directory.
2. Edit the source program, replacing—where indicated—the record size for the RM/COBOL (74) version 2 input and the RM/COBOL output relative files.
3. Enter the RM/COBOL Compile Command (**rmcobol**) to compile the program.
4. Under UNIX, set environment variables to assign the file pathnames for the version 2 relative file to INPUT, and the RM/COBOL relative file to OUTPUT. For example:

   ```
   INPUT=/dir1/rel2.0 ; export INPUT

   OUTPUT=/dir2/rel85 ; export OUTPUT
   ```

   Under Windows, use synonyms to assign the file pathnames. Setting synonyms is described in Chapter 3 of this user's guide.

   Note The source RM/COBOL (74) version 2 pathname and destination RM/COBOL pathname must specify different files, that is, the conversion cannot be made in place.

5. Enter the RM/COBOL Runtime Command (**runcobol**) to execute the program.

Sequential File Conversion Utility (rmcseq)

Variable-length binary sequential files must be converted from RM/COBOL (74) version 2 format to RM/COBOL format. Line sequential and fixed-length binary sequential files do not require conversion. These files may be used directly by RM/COBOL programs. See the appropriate installation and system considerations chapter for your specific operating system to determine which of the sequential files are variable-length binary sequential files.

Using the Utility

1. Execute the **rmcseq.cob** program using the following command:

   ```
   runcobol rmcseq
   ```

2. Respond to the first prompt by entering an I to indicate an Intel (reversed byte) format, or an N (not reversed) to indicate all others. Check your hardware operations manual if you are unsure which response is appropriate.

3. Respond to the second prompt by entering the properly qualified pathname of the RM/COBOL (74) version 2 variable-length binary sequential file to be converted.

4. Respond to the third prompt by entering the pathname of the RM/COBOL variable-length binary sequential file to be produced.

5. The program should then execute, displaying a count of the records being converted. If conversion terminates without error, the following message appears:

   ```
   Convert file complete
   ```

   Other messages indicate an error in conversion, most likely caused by an attempt to convert a file that is not a variable-length binary sequential file.

   Note The source RM/COBOL (74) version 2 pathname and destination RM/COBOL pathname must specify different files, that is, the conversion cannot be made in place.

Combine Program Utility (rmpgmcom)

The **rmpgmcom** utility combines multiple RM/COBOL object files into a single program file library. RM/COBOL allows programs to be placed in the same file. This simplifies software distribution and provides a more consistent and logical representation of software. The **rmpgmcom** utility builds a Table of Contents (TOC) at the end of the output program file library. A Table of Contents speeds up **runcobol** library initialization while very slightly increasing the size of the library file.

The compiler allows several source programs to be contained in the same file. The program file generated has as many object files as the source file defines. **rmpgmcom**, on the other hand, allows source modules to be contained in separate files, and the contents of the resulting object files to be combined into one file.

rmpgmcom.cob is required to use this utility. This file is delivered in object form.

Using the Utility

The Combine Program utility is executed with this command:

```
runcobol rmpgmcom [ A= '[PRINTER,] [STRIP,] out-file,
        file-1 [ , file-2, … , file-n ] ' ]
```

PRINTER, if present, requests a copy of the report to be written to the printer specified with the synonym, PRINTER.

STRIP, if present, removes COBOL symbol table and debug line table information, produced by the compiler Y Option, from object files. This is useful to reduce the size of a program library after debugging is complete.

out-file is the name of the new program file being created. If a filename extension is not specified, **.cob** is used.

file-1, *file-2*, . . ., *file-n* are the names of the program files being combined to form *out-file*. For each name, if a filename extension is not specified, **.cob** is used. If the file does not exist with a filename extension of **.cob**, the name is used with no filename extension.

If the argument list is not specified, **rmpgmcom** prompts first for whether or not to copy the report to the PRINTER, second for the STRIP option, third for the output filename, and then for the input filenames. **rmpgmcom** adds the programs in each input file to the

output file, and then prompts for another input file. To terminate the program, press Enter without typing a name when prompted for an input file.

If the filenames are specified through the command line, the command line argument is limited to no more than 100 characters. Combining more than 100 characters of filenames requires direct operator input, use of input redirection, or multiple executions of the program.

As a precaution, if the output file exists before execution, **rmpgmcom** terminates, preventing accidental erasure of a good program file.

In most cases, an error does not terminate the program. If the program terminates abnormally, assume that the output file is not in a valid state and cannot be used to execute programs.

The same program name can occur in more than one input program file. If this is the case, **rmpgmcom** uses the first one encountered and ignores subsequent programs with the same names. This can be very useful when you want to replace one program in a program file with a new version. Instead of having to recreate the file, you could use commands similar to the following.

Note **rmpgmcom** can combine more than 500 programs, but only the first 500 are guaranteed to have unique names. You may want to limit your program libraries to no more than 500 programs for this reason.

For UNIX:

```
mv rmutil.lib, rmutil.bak
```

For Windows, use the Explorer or open a DOS box and use:

```
RENAME rmutil.lib rmutil.bak
```

For all operating systems:

```
runcobol rmpgmcom A='rmutil.lib, rmmappgm.cob, rmutil.bak'
```

rmutil.bak is the name of a program file containing multiple programs (including ***rmmappgm.cob***).

rmmappgm.cob is the name of the program file containing the program to be updated.

rmmappgm.cob is loaded into ***rmutil.lib***, after which the programs in ***rmutil.bak*** (which is the previous version of ***rmutil.lib***) are loaded into ***rmutil.lib***. The previous version of ***rmmappgm.cob*** in ***rmutil.bak*** is ignored.

Execution of Programs Within Libraries

To execute programs within the created library, the L Runtime Command Option is used. For example:

```
runcobol rmmappgm L=rmutil.lib
```

Refer to Chapter 7, *Running*, for additional information.

Examples

Here is sample input to **rmpgmcom**:

```
   Copy to PRINTER (y/n)?  Y
   Output File:  rmutil.lib
   Input File:  rmmappgm

The following programs are copied from rmmappgm.cob:
    MAP-PGM                1999/03/21  14:42:05

   Input File:  rmpgmcom

The following programs are copied from rmpgmcom.cob:
    PGM-COM                1999/03/21  14:37:15

   Input File:  rmmapinx

The following programs are copied from rmmapinx.cob:
    MAP-INX                1999/03/21  14:40:26

   Input File:  rmdefinx

The following programs are copied from rmdefinx.cob:
    DEF-INX                1999/03/21  14:39:36

   Input File:  (press ENTER)
```

Here is sample output from **rmpgmcom**.

```
The following programs are copied from rmmappgm.cob:
    MAP-PGM                1999/03/21  14:42:05

The following programs are copied from rmpgmcom.cob:
    PGM-COM                1999/03/21  14:37:15

The following programs are copied from rmmapinx.cob:
    MAP-INX                1999/03/21  14:40:26

The following programs are copied from rmdefinx.cob:
    DEF-INX                1999/03/21  14:39:36
```

The **rmpgmcom** utility allows for redirected input under UNIX. To redirect the input, follow these steps.

1. At the command line under UNIX, enter:

   ```
   ls *.cob > file.txt
   ```

   where *file.txt* is a valid file access name.

2. Edit *file.txt* using any text editor and enter Y (Yes) or N (No) as the first line of the file. (A response of Y requests a copy of the report to be written to the PRINTER.) Add the library name as the second line of the file.

3. At the command line prompt, enter:

   ```
   runcobol rmpgmcom < file.txt
   ```

Map Program File Utility (rmmappgm)

The **rmmappgm** utility reports information related to the object file created by the RM/COBOL compiler and the program library created by the **rmpgmcom** utility. This utility reports on all unnested programs contained in an object file and reports when a program library Table of Contents (TOC) is present. It also reports when a program is a demo version.

rmmappgm.cob is required to use the mapping utility. The file is delivered in object form.

Using the Utility

The Map Program File utility is executed with this command:

```
runcobol rmmappgm [A='file-name [,PRINTER]']
```

file-name is the name of the program file to be processed. If no filename extension is specified, **.cob** is used. If the file does not exist with a filename extension of **.cob**, the name is used with no filename extension.

PRINTER, if present, requests a copy of the report to be written to the printer specified with the synonym, PRINTER.

If the argument list is not specified, **rmmappgm** prompts first for the name of a file to be processed and then prompts for whether or not to copy the report to the printer. This continues after each report until you press Enter without typing a name.

The report generated by this program is always written to the screen and is also written to the printer only if the PRINTER option is specified. The information in the report is as follows:

PROGRAM NAME	Corresponds to the PROGRAM-ID value of the program.
SIZES	Indicates the size in bytes of the memory needed for the fixed procedure area, the data area, and the overlay area, as well as the total of these three.
# ARG	Indicates the number of arguments required by the program.
# FILE	Indicates the number of data files defined in the program, including any nested programs.
COMPILED	Indicates the date and time the program was compiled, the compiler options chosen, as well as the version of the compiler used and the operating system under which the program was compiled.
OBJ VERS	Indicates the object version of the program (see Appendix H, *Object Versions*, for details).

Examples

Here is sample input to **rmmappgm**.

```
Object File:  rmmappgm.cob
Copy to PRINTER (y/n)?  Y
Object File:  (press ENTER)
```

Here is a partial sample of output from **rmmappgm**.

```
                    ----------SIZES----------   #    #   --------------------COMPILED--------------------------OBJ
    PROGRAM NAME    PROCEDURE  DATA  OVLY  TOTAL ARG  FILE   DATE      TIME       VERSION        SYSTEM   OPTS    VERS
File:  rmmappgm.cob
RMMAPPGM                2170  1778     0   3948   1    2  1999/03/21 12:10:15  RM/COBOL 7.0n.00 Windows  E         7
```

Map Indexed File Utility (rmmapinx)

The **rmmapinx** utility reports information related to an indexed file.

Note In order to report information related to a Btrieve file, use the Btrieve File Manager (either the Windows interactive version, **wbmanage.exe**, or the command line version, **butil.exe**). Refer to the *Btrieve for Windows NT/Windows 95/Windows 98 Installation and Operation* manual for complete information about the utility.

Using the Utility

The Map Indexed File utility is executed with the following command:

```
runcobol rmmapinx [A='file-name [,DETAIL][,PRINTER]']
```

file-name is the name of the file to be mapped.

DETAIL, if present, requests a more detailed report.

PRINTER, if present, requests a copy of the report to be written to the printer specified with the synonym, PRINTER.

If the optional information is not specified, you are prompted for *file-name*, DETAIL, and PRINTER, as follows:

```
Indexed File:
Detail Information (y/n)?
Copy to PRINTER (y/n)?
```

Enter the name of the file to be used in response to the first prompt line. A response of Y to the second prompt requests detailed information (described in the "Detailed Information Report" section on page G-16) for the file. A response of N requests only the basic information (see the following paragraphs). When in prompt mode, the user is prompted again after each file report is processed. To exit the program when in prompt mode, press Enter without typing a name when prompted for a filename. A response of Y to the third prompt requests a copy of the report to be written to the printer.

Basic File Information Display

Basic file information is always reported for each existing file entered, without respect to the presence or absence of the DETAIL option.

- **File status.** If the file was created by the **rmdefinx** program (described on page G-19) and has never been opened for output, a file status line indicating this fact appears. Also, if this status is indicated, only the disk block size and data and key compression status (with compression characters) appear. Detail information, described in the next section, is reported if the detailed report is requested.

- **Record length.** Record length is reported in one of two formats. For fixed-length records, it is shown as a specific value:

  ```
  Records are fixed length = size
  ```

  size is the actual record size. If variable-length records are defined for the file, this is shown as a range of values:

  ```
  Records vary in length from min to max bytes
  ```

  min and *max* are the minimum and maximum record lengths.

- **Disk block size.** Disk block size is the number of bytes actually allocated to one block on disk.

- **User block size.** User block size is the number of records or bytes specified by the user in the FD statement used when creating this file.

- **Data compression status.** Data compression status may be either compressed or uncompressed. If compressed, the data space and zero characters also appear.

- **Key compression status.** Key compression status may be either compressed or uncompressed. If compressed, the key space character also appears.

- **Number of keys.** This is the actual number of keys (including the prime key) defined for the file.

- **Number of segments.** This is the total number of segments in all keys defined for the file. If the file has no split keys, the number of segments is equal to the number of keys.

- **Number of records.** This is the actual number of data records contained in the file.

- **Number of blocks.** This is the actual number of logical blocks allocated to the file.

- **Number of empty blocks.** This is the number of unused blocks allocated to the file.

- **Number of blocks required for a rewrite.** This is the maximum number of empty blocks required if a rewrite were to relocate the modified record in the file.
- **Key information.** See "Key Descriptor Information Display" on page G-17.
- **Last error.** This is the last error received when accessing the file. It includes the date and time the error occurred. Only errors with class of 30, or a class of 98 with a suberror greater than 2, are remembered.
- **Open For Modify Count.** This is a count, held in the file, of the number of times the file is currently open. If this count is not zero, and there are actually no current opens, it is an indication that the file may be corrupted because of an incomplete close operation.

Detailed Information Report

The following information is reported when the detailed report is requested, either by specifying DETAIL in the command line when invoking the utility, or by responding Y to the detailed report prompt.

- **File version information.** The file version number indicates any advanced features used in the file. The minimum read version number and the minimum write version number are used to prevent previous versions of RM/COBOL from reading or modifying files with features unavailable to them.
- **First unused empty block.** The first unused empty block will be displayed only for files with a version number of 2 or greater. It is the block number of an empty block that has never been used and that is followed only by other unused empty blocks.
- **File lock limit.** The largest address where a lock may be applied to this file is displayed only for files with a version number of 3 or greater. See the description of the LARGE-FILE-LOCK-LIMIT keyword on page 10-28 for more information.
- **Disk block increment.** Disk block increment is the difference in the disk addresses of consecutive blocks of the file. It is always greater than or equal to the disk block size.
- **Allocation increment.** Allocation increment is the number of disk blocks that are allocated when the file is first created and whenever the file increases in its physically allocated size.
- **Recoverability/Performance Strategy summary.** This is a summary of the recoverability and performance strategy options, either set by the runtime system when the file was created, or set when the file was created or modified by the **rmdefinx** utility (see page G-19).

Key Descriptor Information Display

If the file has been opened for output, the attributes of each key are reported one key segment per line. The information reported is as follows:

- **Key number.** The first key is labeled prime, with alternate keys numbered starting with 1.
- **Segment number.** The segment number within the key. The first segment of a key is number 1.
- **Starting position.** This is the position in the record where the key segment starts. The leftmost position in a record is position 1.
- **Segment length.** This is the number of bytes that the key segment occupies in the record.
- **Key length.** This is the total number of bytes that the entire key occupies in the record. It is the sum of the segment lengths of all of the segments of the key. This value is shown only on the final segment line of a split key since it applies to the entire key.
- **Tree height.** This is the maximum number of disk accesses that could be required to locate a record containing the key. Additional disk accesses may be required to read or modify the record. This value is shown only on the final segment line of a split key since it applies to the entire key.
- **Duplicates permitted.** This value is either yes or no. Yes indicates that the key allows duplicate key values to be present. This value is shown only on the final segment line of a split key since it applies to the entire key.

Additionally, a blank line is displayed between keys when any of the keys of the file is a split key. If the file has no split keys, there is one line per key with no intervening blank lines.

Examples

Here is sample input to **rmmapinx**. Each file listed is also described with RM/COBOL SELECT and FD statements.

```
Indexed File:  file1
Detail Information (y/n)?  y
Copy to PRINTER (y/n)?  Y
Indexed File:  (press ENTER)
```

Here is sample output from **rmmapinx**.

```
RM/COBOL Map Key Utility - 7.0 03-21-1999  12:59:17    Page   1
File Information:
  file1 is an Indexed File.
  Records are fixed length = 134 Bytes.
  Disk Block Size = 512 Bytes, User Block Size = not specified.
  Data Records are compressed, Keys are compressed.
    Data Block Space Character Value = 32.
    Data Block Zero Character Value = 48.
    Key Block Space Character Value = 32.
  File has 3 Keys and 6 Segments.
  File contains 1 Record and occupies 16 Blocks.
  There are 11 empty Blocks.
  12 empty Blocks may be needed for a rewrite.

The last error was 98,38, at 12:57 on 03-21-1999.
Open For Modify Count = 0.

Detail Information:
  File version number = 3.
  Minimum read version number = 3.
  Minimum write version number = 3.
  First unused empty block = 5.
  File Lock Limit = 64 GB.
  Disk Block Increment Size = 512 Bytes.
  Allocation Increment = 8 Blocks.
  Recoverability/Performance Strategy:
    Data are forced to the system only when necessary.
      Force Write Data Blocks = No.
      Force Write Index Blocks = No.
      Force to Disk = No.
      Force File Closed = No.

Key Information:
     Key   Segment  Starting  Segment   Key     Tree   Duplicates
  Number  Number   Position  Length   Length  Height  Permitted?
   Prime       1          1      30
   Prime       2         90       5       35       1         No
      1        1         31       3        3       1         No
      2        1         34      10
      2        2         84       6
      2        3         95      20       36       1         Yes
```

Define Indexed File Utility (rmdefinx)

The **rmdefinx** utility precreates an indexed file in order to alter the default characteristics assigned by RM/COBOL programs. The utility also can modify some of those characteristics on files created by RM/COBOL programs.

rmdefinx.cob is required to use the define indexed file utility. The file is delivered in object form.

Note 1 When using the **rmdefinx** utility on an indexed file larger than 16 bytes, rmdefinx must be executed with a configuration file with the following entry:

```
RUN-SEQ-FILES USE-LARGE-FILE-LOCK-LIMIT=YES
```

Note 2 In order to precreate a Btrieve file, use the Btrieve File Manager (either the Windows interactive version, **wbmanage.exe**, or the command line version, **butil.exe**). Refer to the *Btrieve for Windows NT/Windows 95/Windows 98 Installation and Operation* manual for complete information about the utility.

Using the Utility

The Define Indexed File utility is executed by issuing the following command:

```
runcobol rmdefinx [A='file-name']
```

file-name is the name of the file to be defined or altered.

You may omit the argument list. In this case, the program prompts for *file-name* in the following manner:

```
Indexed File:
```

The name of the file to be used is supplied in response to this prompt.

File Precreation

The following prompts are issued when a file is being precreated:

```
Disk Block Size (in bytes):
Disk Block Increment (in bytes):
Allocation Increment (in blocks):
```

These queries deal with the manner in which space is allocated and used in the file. Disk block size is the actual number of bytes used in each physical block. A physical block size is indicated by the disk block increment size. These two sizes should be identical. The number of blocks allocated each time more space is required in the file is controlled by the allocation increment.

The next prompt is as follows:

```
Data Compression (y/n)?
```

This controls the amount of space taken up by logical records in the file. If you want logical records to be stored without compression, enter N. Otherwise, enter Y, and then respond to the following two prompts:

```
Space Character Value:
Zero Character Value:
```

These control the manner in which data compression takes place. Respond with the decimal value of the characters to be interpreted by the compression algorithm as a space and a zero. For example, the ASCII space and zero have decimal values of 32 and 48, respectively; the EBCDIC space and zero have decimal values of 64 and 240, respectively.

The next two prompts are as follows:

```
Key Compression (y/n)?
Space Character Value:
```

These queries control key compression in a manner similar to data compression, except that only trailing spaces are compressed.

The next prompts are as follows:

```
Force Write Data Blocks (y/n)?
Force Write Index Blocks (y/n)?
Force to Disk (y/n)?
Force File Closed (y/n)?
```

These prompts determine recoverability/performance strategies for the file being processed. To select a strategy option, enter Y in response to the appropriate prompt. To omit a strategy option, enter N. See the discussion of data recoverability of indexed files in Chapter 8, *RM/COBOL Features*.

The next prompt is as follows:

```
Version number (0, 2, or 3)? 2
```

This prompt sets the version number of the file. Valid version numbers are shown in the following chart.

Feature	Version Number 0	Version Number 2	Version Number 3
Improved Empty Block List Algorithm		✔	✔
Use LARGE-FILE-LOCK-LIMIT			✔

The next prompt is as follows:

```
File Lock Limit (in GB)?
```

This prompt is shown only if the file version number has been set to 3. It allows you to specify the location of the largest lock to be placed on this file. For more information, see Chapter 10, *Configuration*, for descriptions of the LARGE-FILE-LOCK-LIMIT keyword (RUN-FILES-ATTR configuration record) and the DEFAULT-FILE-VERSION-NUMBER keyword (RUN-INDEX-FILES configuration record).

File Modification

When the file specified already exists, the utility allows you to change the allocation increment, described previously, and offers you the option to alter the key compression, the recoverability/performance strategy, the file version number, and the file lock limit.

The prompt to change the key compression is as follows:

```
Change key compression (y/n)?
```

If you enter Y, you are prompted for whether the key compression should be enabled and for the value of the key compression space character, as described on the previous page. If the key compression or the key compression space character is changed, the file is marked as needing recovery. After you run the Indexed File Recovery utility (**recover1**), described on page G-23, the indexed trees are built with the requested key compression. If the current key compression and key compression space character are unchanged, you are not forced to recover the index structure.

The prompt to change the recoverability or performance strategy is as follows:

```
Change Recoverability/Performance Strategy (y/n)?
```

If you enter Y, you are prompted for the four options discussed previously. If you enter N, the strategy is unchanged.

The prompt to change the file version number is as follows:

```
Change file version number (y/n)?
```

If you enter Y, you are prompted for the file version number discussed on page G-20. If you specify the file version number as 3, you are prompted for the file lock limit. If the version number is changed from 0 to another version, or changed from another version to 0, the file is marked as needing recovery, and the Indexed File Recovery utility (**recover1**) must be run before the file can be used. After you run the Indexed File Recovery utility (**recover1**), the empty block list is built with the correct algorithm. If the file version number is unchanged, you are not forced to recover the empty block list.

If you attempt to change the file version number to 0 of a file that contains split keys or duplicate prime keys, a message is displayed indicating that you cannot do so; files using these features cannot be converted to version number 0 files. Also, files with a version number of 3 may have grown too large to be changed back to version 0 or 2. For more information on indexed file version numbers, see Chapter 8.

After all questions have been answered, the following prompt appears:

```
OK (y/n)?
```

If you enter Y, the file is updated and the program either terminates (if a filename was specified on the command line) or prompts you for another filename.

Note The **rmdefinx** utility does not cause the file to "exist" in the COBOL sense. An OPEN OUTPUT (or OPEN I-O or EXTEND if SELECT OPTIONAL is used) must be successfully executed before other open modes become valid.

Example

Here is sample input to **rmdefinx**.

```
Indexed File: file1
New File.
Disk Block Size (in bytes): 1024
Disk Block Increment (in bytes): 1024
Allocation Increment (in blocks): 10
Data Compression (y/n)? n
Key Compression (y/n)? n
Define Recoverability/Performance Strategy
   Force Write Data Blocks (y/n)? y
   Force Write Index Blocks (y/n)? y
   Force to Disk (y/n)? y
   Force File Closed (y/n)? y
Set file version number
   Version number (0,2, or 3)? 3
   File Lock Limit (in GB)? 64
OK (y/n)? y
```

Indexed File Recovery Utility (recover1)

The **recover1** utility recovers data stored in an RM/COBOL indexed file. It is a standalone program; that is, it does not require use of the Runtime Command (**runcobol**) to be executed.

Note 1 In order to recover data stored in a Btrieve file, use the Btrieve File Manager (either the Windows interactive version, **wbmanage.exe**, or the command line version, **butil.exe**). Refer to the *Btrieve for Windows NT/Windows 95/Windows 98 Installation and Operation* manual for complete information about the utility.

Note 2 Unless specifically stated otherwise, the name **recover1** refers to both the UNIX (**recover1**) and Windows (**recover1.exe**) versions of the **recover1** program.

Note 3 If the output window of the Windows version of the **recover1** program disappears upon successful completion and you want that window to remain visible, set the Persistent property to TRUE for the **recover1.exe** program (see page 3-24 for details).

Use of the Recover1 Program

The Indexed File Recovery utility (**recover1**) is executed by issuing the following command:

```
recover1 file-1 file-2 [-i] [-k [file-3]] [-l [file-4]]
      [-m MB-of-memory] [-q] [-t] [-y] [-z]
```

file-1 is the filename of the indexed file to be recovered.

file-2 is the name of the file where **recover1** places any unrecoverable records found in the indexed file (see page G-25).

The *-i* option causes **recover1** to test only the file integrity and then stop. The file will not be modified in any way. Specifying *-i* causes both the *-t* and *-z* options to be ignored. If no problems are discovered, the return code is set to 0. If a problem is discovered, the return code is set to 1.

Note The integrity scan is a quick test of the file and is not comprehensive. Some problems, such as records with invalid duplicate keys, will not be detected. Files with no errors detected by the integrity scan may still receive “98” errors or other errors.

The *-k* option is used to indicate that the Key Information Block (KIB) should be assumed to be invalid. If no *file-3* is specified, the user will be prompted either for a

template file or for enough information to rebuild the KIB. If *file-3* is specified, it should be the name of a valid indexed file with the same format as the file being recovered. This file will be used as a template. The required KIB information is read from the KIB of the template. The template file can be a backup copy of the file being recovered, if the backup occurred before the file was damaged, or, it can be a file created by performing an OPEN OUTPUT with the proper FD. An OPEN OUTPUT must have been performed on the template file, but it need not contain any records. A template file must be specified if the KIB is corrupt and the file uses either an enumerated code set or an enumerated collating sequence.

The *-l* option is used to write information about errors encountered while recovering the file to the log file *file-4*. Only the first 100 errors will be logged. If *file-4* specifies a synonym name, the synonym will be resolved before opening the log file; this allows the use of the name PRINTER to send the log information to the print device. The default value of *file-4* is PRINTER.

The *–m* option specifies the number of megabytes of memory to allocate to the sort algorithm used in phase 4, build node blocks (see page G-25). Allocating more memory generally results in faster execution of **recover1** and causes fewer node blocks to be built. If this option is not specified, a suitable number will be computed. The minimum value is 0 which requests that a minimum amount of memory be used. The maximum value is 100. **Note** Specifying a number that is too large for your system may result in very poor system performance.

The *-t* option is used to indicate that unused space should be truncated, and returned to the operating system. **Note** Some versions of UNIX do not support the operating system call required to truncate a file.

The *-q* option causes **recover1** to perform its work without displaying information or asking the operator questions. If the file is marked as needing recovery, or has a non-zero Open For Modify Count (see “Basic File Information Display” on page G-15), then it will be recovered. Otherwise, no action occurs. This behavior can be modified by using the *-y* option.

The *-y* option causes **recover1** to assume that the operator wants to answer “y” to all possible questions and therefore does not stop to wait for a response. Using the “-y” option will cause a file to be recovered even if it is not marked for recovery.

The *-z* option is used to reset the Open For Modify Count to zero (see “Basic File Information Display” on page G-15), without performing a full recovery. If the file is marked as needing recovery, this option is ignored. **Note** Use the *-z* option with caution. Resetting the Open For Modify Count to zero without performing a full recovery may leave the file in a corrupted state.

If the **recover1** program is successful, the exit code is set to 0. If the **recover1** program is canceled by the operator, the exit code is set to 2. Otherwise, the exit code is set to 1.

The **recover1** program attempts to recover the indexed file in place; that is, the program rebuilds the internal file structure in the actual file being recovered. If necessary, the Key Information Block (KIB) is rebuilt and any corrupted data blocks are repaired. Corrupt data blocks may result in loss of some data records. Because of this feature, it is strongly recommended that you either backup the file or copy the indexed file to be recovered to some other directory or pathname as additional security. Any records that cannot be successfully reindexed into the file due to invalid duplicate key values, or invalid record sizes, are decompressed (if compression is selected for the file), converted to the native code set, and then written to *file-2*. **recover1** should be able to handle most kinds of indexed file corruption problems, but some fatal errors may still cause the recovery to fail. Any fatal error is displayed and causes the program to terminate. Broken hardware should be suspected in many of these cases.

file-2 can be in fixed- or variable-length format; this is set by **recover1** based on whether *file-1* is fixed- or variable-length format. Records placed in *file-2* were those undergoing change at the time of the system failure that required recovery or have invalid record sizes. Investigate any records appearing in *file-2* and make the appropriate corrections to *file-1*.

The **recover1** program's processing consists of up to four separate phases, which are run in the following order:

1. **Integrity Scan.** If the *-q* option or *-y* option is specified, the Integrity Scan phase is disregarded unless it is forced to occur by the specification of the *-i* option or *-l* option. This phase reads the entire file in a forward direction checking for simple errors, and produces a summary report showing the state of the file and an estimate of the number of records **recover1** can recover. The indexed file is not modified during this phase.

2. **Repair Blocks.** The Repair Blocks phase, which is always run, reads and writes the file in a backward direction repairing corrupt data blocks, converting non-data blocks to empty blocks, and rebuilding some internal file structures.

3. **Move Data Blocks.** The Move Data Blocks phase is run only when the truncate file option (*-t*) is specified. This phase reads and writes parts of the file moving high-numbered data blocks (near the end of the file) to lower-numbered available blocks to maximize the amount of space at the end of the file that can be truncated and returned to the operating system when **recover1** finishes.

4. **Build Node Blocks.** The Build Node Blocks phase, which is always run, reads data blocks and writes node blocks in the file in a forward direction rebuilding the entire node structure for each key of the file.

Note 1 After the Integrity Scan phase, if the Estimated Recoverable records value is zero or very low, and the number of corrupt data blocks is very close to the total number of data blocks found, the number of keys that allow duplicates may be incorrect, either because the KIB is corrupt or the user provided incorrect key information to **recover1**.

Note 2 After the Integrity Scan phase, if most of the blocks are invalid, the Disk Block Size or the Disk Block Increment may have been incorrectly specified or the KIB may be corrupt.

Note 3 During the Repair Blocks phase, a count of blocks which could be read but not written may be displayed. This count may indicate the presence of a hardware problem with your disk.

Recover1 Message File Processing Errors

During initialization, the **recover1** utility locates and reads its message file. If it cannot find its message file or the message file is corrupt, one of the following messages appears:

```
Unable to find the system message file
Unable to format the system message file
Unable to read the system message file
```

The **recover1** utility compares its version number and product code with those in the message file. If they do not match, one or both of the following messages appears:

```
Recover1:  Message file version mismatch, expected 7.0n.nn, found n.nn.nn
Recover1:  Message file product mismatch, expected XX, found YY
```

When any of the above messages appear, the **recover1** utility terminates with the following message:

```
Error invoking mismatched recover1 and message file.
```

The **recover1** utility message file may have the wrong name or be in the wrong directory. The **recover1** utility message file must have the name **rec.msg** (**REC.MSG** under UNIX). The **recover1** utility attempts to find the message file in the directory that contains the **recover1** executable file, the current directory, or through the PATH directory search sequence (see page 2-4 for UNIX or page 3-11 for Windows).

Note On some versions of UNIX, it is impossible to determine which directory contains the executable file when that directory is specified on the command line.

Example

An example run through the Indexed File Recovery utility is described in Figures G-1 through G-4. The recovery session is started in this example by the following command:

```
recover1 master.inx dropout1
```

Figure G-1 on page G-28 shows information about the file **master.inx**.

Under the name of the file to be recovered, a description of the state of the file is displayed. Any of the following messages may appear:

- This file has not been marked as needing recovery!
- The Open For Modify Count for this file is not zero: *count*
- File has been marked as corrupted due to a previous error.
- KIB is corrupt. Using template file: *file-3*
- KIB is corrupt. Enter a template filename (press Enter for manual entry).

If the KIB is corrupt, and a template filename is not entered, **recover1** will prompt the user for the required KIB information before continuing.

If more keys exist than can appear on this screen, as many as possible appear, after which you are asked if you want to see the remaining key descriptors. This continues until all keys are shown. You are then asked to verify that this is the file you want to recover. Entering N terminates the program. Entering Y continues the program.

Figure G-1 Indexed File Recovery Utility: File Recovery Verification

```
                Indexed File Recovery Utility
                  Recover1 Version 7.0n.00

Index File: master.inx

This file has not been marked as needing recovery!

Disk Block Size:        498     Minimum Record Length:    80
Disk Block Increment:   498     Maximum Record Length:    80
Number of Index Blocks: 170     Number of Records:       150

   Key Position Size  Remarks
 PRIME      1      8
    1       9      8
    2      17      8  duplicates allowed



Is this the file you wish to recover (y/n)?
```

Figure G-2 shows a summary of the information that is gathered during the file integrity scan. You are then asked if you would like to proceed with the recovery process. Entering N terminates the program. Entering Y continues the program.

The "Average record length" is computed by adding the length of all the records in the file and dividing by the number of records. The "Average data size" is computed by adding the size that the record actually occupies in the file and dividing by the number of records. This size allows you to determine how much your data can be compressed.

Figure G-2 Indexed File Recovery Utility: recover1 Summary

```
                Indexed File Recovery Utility
                  Recover1 Version 7.0n.00

Index File: master.inx
Drop  File: dropout1
This file has not been marked as needing recovery!

Disk Block Size:        498    Minimum Record Length:      80
Disk Block Increment:   498    Maximum Record Length:      80
Number of Index Blocks: 170    Number of Records:         150
Phase:  Integrity Scan         Estimated Recoverable:     150

             |   Total |   Total |   First |    Last |
Block Type   |   Found | Corrupt | Corrupt | Corrupt |
  KIB        |       1 |       0 |         |         |
  Data       |     102 |       0 |         |         |
  Node       |      61 |       0 |         |         |
  Empty      |       6 |       0 |         |         |
  Invalid    |       0 |       0 |         |         |
  Unreadable |       0 |       0 |         |         |

Average data size: 14, Average record length: 80

Do you wish to proceed with recovery (y/n)?
```

Figure G-3 shows the information that is displayed while **recover1** is rebuilding the node blocks for the prime key.

Figure G-3 Indexed File Recovery Utility: recover1 Statistics

```
                Indexed File Recovery Utility
                  Recover1 Version 7.0n.00

Index File: master.inx
Drop  File: dropout1
This file has not been marked as needing recovery!

Disk Block Size:          498     Minimum Record Length:   80
Disk Block Increment:     498     Maximum Record Length:   80
Number of Index Blocks:   170     Number of Records:      150
Phase:  Build Node Blocks         Estimated Recoverable:  150

Key being processed:                          PRIME
Records recovered:                            100
Records written to drop file:
Block being processed:                        13
Number of data blocks moved (for truncate):    5
```

Figure G-4 shows the information that is displayed after **recover1** terminates successfully. The two lines regarding truncation are shown only when the *-t* option is specified.

Figure G-4 Indexed File Recovery Utility: recover1 Finished Successfully

```
                Indexed File Recovery Utility
                  Recover1 Version 7.0n.00

Index File: master.inx
Drop  File: dropped
This file has not been marked as needing recovery!

Disk Block Size:          256     Minimum Record Length:  126
Disk Block Increment:     256     Maximum Record Length:  126
Number of Index Blocks:   120     Number of Records:      100
Phase:  Build Node Blocks         Estimated Recoverable:  100

Key being processed:              PRIME
Records recovered:                  100
Records written to drop file:
Block being processed:              120
Truncate option specified - number of data blocks moved:   4
Truncate action successful - new Number of Index Blocks: 112

Recovery successful.
```

In the example shown in Figure G-5, the KIB of the file has been corrupted, and key information must be entered for the file to be recovered. Key information can be obtained from the output of the Map Indexed File utility (see page G-14 for more information). Underlined characters have been entered by the user.

The recovery session is started by the following command:

```
recover1 master.inx dropout1 -k
```

Note Entering incorrect information about how many keys, or which keys, can have duplicate values may cause unpredictable results.

Figure G-5 Indexed File Recovery Utility: Entering Key Information

```
                  Indexed File Recovery Utility
                    Recover1 Version 7.0n.00

Index File: master.inx

Last error was 98,38 at 9:29 on 03-21-1999

Are any of the keys in this file segmented (split) (y/n)? y
Key #: PRIME Segment #: 2  Starting Position? 10    Length? 5
             Another Segment (y/n)? n
             Total Key Length =  13  Duplicates Permitted (y/n)? n
Another Key (y/n)? n
```

Figure G-6 shows an example of entering the remainder of the KIB information. Underlined characters have been entered by the user.

Figure G-6 Indexed File Recovery Utility: Entering KIB Information

```
                          Indexed File Recovery Utility
                            Recover1 Version 7.0n.00

Index File: master.inx


Last error was 98,38 at 9:29 on 03-21-1999

Minimum Record Length (in bytes)? 80

Maximum Record Length (in bytes)? 80

Disk Block Size (in bytes)? 498

Data Compression (y/n)? y  Space Character Value? 32  Zero Character Value? 48

Key Compression (y/n)? y   Space Character Value? 32

File Version Number (0, 2, or 3)? 2

Disk Block Increment (in bytes)? 498

Allocation Increment (in blocks)? 8

Force Write Data Blocks (y/n)? n  Force Write Index Blocks (y/n)? n

Force to Disk (y/n)? n            Force File Closed (y/n)? n

Code Set (1=none/2=ASCII/3=EBCDIC)? 1

Collating Sequence (1=none/2=ASCII/3=EBCDIC)? 1


Is this information correct (y/n)? y
```

After the key and KIB information has been successfully entered, the recovery process proceeds the same as before, beginning with , as illustrated in Figure G-1 on page G-28. If a template file had been specified on the command line or a template filename had been entered when prompted, the screens prompting for the key and KIB information would not have been displayed. A template file must be specified if the KIB is corrupt and the file uses either an enumerated code set or an enumerated collating sequence.

Recover1 Program Error Messages

Error *status* initializing file manager

recover1 was unable to initialize the RM/COBOL file management system for the reason indicated by *status*. The usual cause for this error is that a buffer pool has been configured that is too large to be allocated. See the BUFFER-POOL-SIZE keyword of the RUN-FILES-ATTR configuration record on page 10-26 for instructions on changing the buffer pool size.

Truncate option not supported

recover1 detected that the truncated function was not supported on the system when the user requested file truncation. Truncation of the file is not possible.

recovery terminating - no records recoverable!

recover1 detected corruption in the indexed file and no records could be recovered. In this case, **recover1** terminates at the end of the integrity scan to protect the user from erroneously deleting all the records from the file. This error may indicate that the block size, the block size increment, or the number of keys that allow duplicates has been incorrectly specified or the KIB may be corrupt.

Error *status* on template file

recover 1 detected an error in the KIB of the template file specified by the user. The user may enter another template file, may enter the KIB information manually, or may enter a Ctrl-C to terminate **recover 1**.

Cannot write near end of file - check "ulimit"

recover1 detected that blocks near the end of the file can be read but not written, but other blocks of the file may be both read and written. This error may indicate that the operating system file size limit (ulimit) may be smaller than the size of the file. Correctly set the file size limit or use an account with sufficient privileges and run **recover1** again.

Standalone Use of the Recover2 Program

The **recover2** utility program can be used to unload an indexed file to a sequential file. The **recover2** program is no longer needed to recover indexed files. It is invoked by entering the command:

```
runcobol recover2 K [A='file-1[,[file-2][,option]']
```

file-1 is the filename of the indexed file to be unloaded. **recover2** does not use the directory search sequence to locate *file-1*.

file-2 is the filename of the sequential file into which **recover2** unloads the indexed file records.

option can be either SUB or NOSUB, depending on whether or not you want **recover2** to trust the overhead information in the file. NOSUB indicates that the overhead information in the indexed file (record size, block size, and so forth) is correct and can be used to unload the file. SUB indicates that the overhead information may not be correct and needs to be verified and possibly altered. The overhead information appears and you are given the opportunity to alter the information before processing of the file begins. You must enter the value for the "Number of Keys that allow Duplicates".

file-1, *file-2* and *option* can be omitted, and **recover2** prompts you for a value.

For example, entering the command:

```
runcobol recover2 K A='file-1, option'
```

causes **recover2** to prompt you for the *file-2* filename. Entering the command:

```
runcobol recover2 K A='file-1, file-2'
```

causes **recover2** to prompt you for the option to use.

recover2 also produces a log duplicating the overhead information appearing on the screen to the printer specified with the synonym, PRINTER.

If an error occurs, **recover2** displays a message, then continues to attempt to recover the file. The exit code is set to 1.

If no errors occur, the recovery is successful and the exit code is set to 0.

Figure G-7 shows the main screen associated with the data unload program (**recover2**). In the first attempt, the NOSUB Option is specified and all of the fields shown are filled in by the program. If the file cannot be unloaded with the NOSUB Option, an error message appears and a second attempt is made with the SUB Option specified, causing **recover2** to prompt you for the values by first displaying what is in the file. To select the displayed value, press Enter or Tab. Otherwise, type a new value and press Enter.

Note When using the SUB Option, the value for the number of keys that allow duplicates must be entered by the user since there is no default.

Figure G-7 Indexed File Recovery Utility: recover2 Main Screen

```
         Copy all data records to dropped record file

Index File: master.inx
 Drop File: drop
    Option: nosub

     Disk Block Size: 498            Maximum Record Length: 80
Disk Block Increment: 498            Minimum Record Length: 80
                      Number of Keys that allow Duplicates: 1
Data Record Compression (y/n)? Y
        SPACE Character Value: 32
         ZERO Character Value: 48
Records Written to Drop File:
       Block being Processed: 8
```

Figure G-8 shows the OK prompt you see during the second attempt. Responding N to this prompt causes the program to restart the prompts for file information. Responding Y indicates that secondary data recovery should start.

Figure G-8 Indexed File Recovery Utility: Secondary Recovery

```
         Copy all data records to dropped record file

Index File: master.inx
 Drop File: drop
    Option: sub

     Disk Block Size: 498            Maximum Record Length: 80
Disk Block Increment: 498            Minimum Record Length: 80
                      Number of Keys that allow Duplicates: 1
Data Record Compression (y/n)? Y
        SPACE Character Value: 32
         ZERO Character Value: 48
Record Written to Drop File:
      Block being Processed:
OK (y/n)?
```

Recover2 Program Error Messages

File: *index-filename* **- Open Error** *status***.**

recover2 was unable to open the indexed file for the reason indicated by *status*. The execution of **recover2** terminates.

File: *index-filename* **- Input Error** *status***.**

recover2 encountered the error indicated by *status* while reading the indexed file. If the NOSUB Option was chosen, execution terminates. If the SUB Option was chosen, the operator is given the option to continue execution.

File: *index-filename* **- Premature end of file encountered.**

recover2 encountered the end of file in an unexpected place while reading the indexed file, and **recover2** may reasonably recover. If the SUB Option was chosen, the operator may be given the option to continue. Otherwise, execution terminates.

File: *index-filename* **- File has never been opened for output.**

The indexed file has never been opened for output and therefore cannot contain any data records.

File: *index-filename* **- may not be an Indexed file.**

The overhead structures in the indexed file are not consistent. If the NOSUB Option was chosen, execution terminates. If the SUB Option was chosen, the operator may continue execution. Values that appear for block size and record size should be carefully verified.

File: *index-filename* **- Block Size is too big for recover2 program.**

The block size specified is larger than 65280 bytes, which is the largest block size supported by **recover2**. Execution terminates.

File: *index-filename* **- Invalid compressed data in block/record** *block number/record-label***.**

recover2 has encountered a compressed data record that is inconsistent with the version of **recover2** being executed or with the compressed data record length. The indicated record and subsequent records in the block are not written to the unload file. Processing continues with the next block.

File: *index-filename* **- Record length mismatch.**

The minimum record size is greater than the maximum record size or the block size is too small for the worst-case record size (due to data compression). It is checked when the NOSUB Option is chosen. Execution terminates.

File: *index-filename* **- Bad block overhead in block** *block number***.**

recover2 has encountered a data block with inconsistent overhead structures. No records from the block are written to the unload file. Processing continues with the next block.

File: *index-filename* **- Bad record overhead after block/record** *block number/record label***.**

recover2 has encountered a data record with inconsistent overhead structures. Any records in the block subsequent to the indicated record are not written to the unload file. Processing continues with the next block.

File: *index-filename* **- Record size {< minimum | > maximum} for block/record** *block number/record label***.**

recover2 has encountered a data record that does not conform to the constraints of minimum or maximum record length but is otherwise consistent. The indicated record is written to the unload file. Processing continues with the next record.

File: *unload-filename* **- Record Size is too big for recovery program.**

The maximum record length specified is too large for **recover2**. The maximum record length is 65280 bytes. Execution terminates.

File: *unload-filename* **Error:** *status***.**

The indicated error was encountered during an I/O operation on the unload file. Execution terminates.

Attach Configuration Utility (rmattach)

The Attach Configuration utility (**rmattach**) attaches a configuration file (described in Chapter 10) to an RM/COBOL command processor **.exe** file and creates a new command processor file. The following processors can be configured in this manner:

- runtime system (**runcobol.exe**)
- compiler (**rmcobol.exe**)
- Indexed File Recovery utility (**recover1.exe**)

Note The **rmattach** utility will work only with the Windows version of RM/COBOL.

Using the Utility

The **rmattach** utility is executed with this command:

```
rmattach input-exe-file output-exe-file config-file
```

input-exe-file is the name of the command processor file to be configured. This file will not be modified.

Note The RUNPATH directory search sequence is not used to open this file. If *input-exe-file* is not in the current directory, the entire pathname must be entered.

output-exe-file is the name of the newly configured **.exe** file. If a file with the same name already exists, it is overwritten. *output-exe-file* must not have the same name as that specified for *input-exe-file*. *output-exe-file* should have a filename extension of **.exe**.

config-file is the name of a line sequential file containing the desired configuration records (see Chapter 10). If a configuration file is already attached to *input-exe-file*, it will be replaced by the contents of *config-file*.

rmattach does no syntax checking of the configuration file. The **.exe** file will diagnose errors during its initialization.

Here is an example of an **rmattach** command:

```
rmattach runcobol.exe runcfg.exe setting.cfg
```

Initialization File to Windows Registry Conversion Utility (ini2reg)

The Initialization File to Windows Registry Conversion utility (**ini2reg**) converts an RM/COBOL Windows initialization file (**.ini**) and places its contents into the Windows registry database.

Previous versions of RM/COBOL stored program configuration information for the compiler, runtime, and Indexed File Recovery utility (**recover1.exe**) programs in **.ini** files. Beginning with version 6.5, RM/COBOL uses the Windows registry database to store this information. With this utility, earlier **.ini** files can be converted and current initialization information can be distributed to users via a **.reg** file that can be exported from the Windows registry database.

Note This utility is available only under Windows.

Using the Utility

The **ini2reg** utility is executed by clicking on the INI to Registry icon or typing the command:

```
ini2reg [-q] [file-name]
```

By default, the **ini2reg** utility program converts text in the initialization file from the OEM character set to the ANSI character set. If the initialization file already used an ANSI character set, use the *-q* option to disable this conversion.

file-name is the name of the initialization file to be merged into the Windows registry database. If no file is specified, an Open File dialog box appears in order to browse the file system for the proper file. *file-name* must be specified with a proper path. This utility does not search the PATH or RUNPATH environment variables.

RM/COBOL Configuration Utility (rmconfig)

The RM/COBOL Configuration utility (**rmconfig**) provides a way to modify the configuration options for one or more COBOL programs. These options are specific to the RM/COBOL system running under Windows.

A modified version of the **rmconfig** property sheet can be displayed for a single COBOL program by right-clicking the program icon, Registry Configuration, and choosing Properties.

Note This utility is available only under Windows.

Using the Utility

The **rmconfig** utility is executed by clicking on the Registry Configuration icon or typing the command:

```
rmconfig [-r|-c|-1] [file]
```

-r indicates that you will be configuring properties to be used while running programs.

-c indicates that you will be configuring properties to be used while compiling programs.

-1 indicates that you will be configuring properties to be used while recovering data files with **recover1.exe** (see page G-23).

file is the name of the file that you wish to configure.

Figure G-9 shows the **rmconfig.exe** tab of the Properties dialog box. The Select File tab allows the specification of configuration options for a certain COBOL program (Individual File option) or for all programs (Default Properties option). Changes made on the other Properties tabs will affect the configuration of the program or programs selected here. See Chapter 3, *Installation and System Considerations for Microsoft Windows*, for descriptions of the other Properties tabs.

Figure G-9 Select File Tab



Appendix H: Object Versions

This appendix lists the new object features that are incompatible with earlier releases of RM/COBOL-8X and RM/COBOL.

Level Numbers

The object version level number in a RM/COBOL object file identifies the earliest release of the RM/COBOL product that supports the features required by the program. The set of features available in the first release of the product, RM/COBOL-8X, has been assigned object version 1. When new features have been added in subsequent releases of RM/COBOL, these have been assigned successive object version numbers. The RM/COBOL compiler marks each object file with the object version number of the latest features actually used in the source program.

Every release of the RM/COBOL runtime system supports features up to some object version level. Object files with a higher object version level number cannot be run. When a program is named in the Runtime Command or in a CALL statement, the runtime system searches for an object file containing a program with the specified name. If during this search, the runtime system finds an object program that has an object version level number which exceeds that accepted by the runtime system, that object program is not considered valid and the runtime system continues its search. If no valid program with the specified name is found, the ON EXCEPTION phrase of the CALL statement is taken or the Runtime Command fails.

The RM/COBOL compiler has an object version level option to control the object version level number placed in the object file. When the option is specified, any language features used in the source program requiring a higher object version cause a source diagnostic, and the program is not compiled. The object version level number placed in the resulting object file is no higher than the value specified in the compiler option. If the object version level option is not specified, the default value is the highest value accepted by the compiler, thus allowing all features supported by the compiler. Since the compiler marks the object program with the value of the latest feature actually used in the source program, the resulting object program may still be executable on earlier releases of the runtime system.

Table H-1 enumerates past RM/COBOL product releases and the highest object version level number they accept.

Table H-1 Object Version Numbers by Product

Product	Platform	Releases	Object Level Number
RM/COBOL-8X	DOS	1.*nn*	1
RM/COBOL	DOS	2.*nn*	2
	UNIX	2.0*n*	2
RM/COBOL	AS/400		3
RM/COBOL	DOS	4.*nn*	4
	UNIX	4.0*n*	4
RM/COBOL	DOS	5.*nn*	5
	UNIX	5.*nn*	5
RM/COBOL	DOS	5.2*n*	6
	UNIX	5.2*n*	6
RM/COBOL	UNIX	6.*nn*	7
	Windows	6.*nn*	7
RM/COBOL	UNIX	7.*nn*	8
	Windows	7.*nn*	8

In most cases, the object version is of no concern to the user. However, when compiling programs intended for distribution to other users, the object version may be of concern. If these other users do not have the current release of the runtime system, Compile Command Option Z (see page 6-14) should be specified to restrict the object version level. The object version level number specified to the compiler should be the highest value that does not exceed the level accepted by any of the runtime systems used by the intended recipients. When the object version level number is limited by use of Option Z, the compiler suppresses any optimizations and diagnoses all source language features not supported by earlier runtime systems.

The features associated with each object version are described in the following sections.

Object Version 1

The RM/COBOL-8X compiler and runtime system versions 1.*nn* support features in object version 1. These product releases implement the high subset of ANSI COBOL 1974.

If the object version level number is limited to 1 by use of Compile Command Option Z, the resulting object program is executable on any released RM/COBOL-8X or RM/COBOL runtime system.

Object Version 2

The RM/COBOL compiler and runtime system versions 2.*nn* support object version 2. These product releases implement the intermediate subset of ANSI COBOL 1985. The RM/COBOL version 2.*nn* runtime systems support the language features of both object version 1 and object version 2.

Several new language features were added in object version 2 that are not supported by previous versions. Unless the object version is limited to 1 by Compile Command Option Z, programs with the following features will not execute on runtime systems with a version number less than 2:

1. A source program with a simple INSPECT statement.

   A simple INSPECT statement is one with single-character control operands and only a single CHARACTERS, ALL, LEADING or FIRST phrase per TALLYING or REPLACING phrase. A simple INSPECT statement may have both a TALLYING and REPLACING phrase and both a BEFORE and AFTER INITIAL phrase.

   The RM/COBOL version 2.*nn* and later compilers generate optimized code for simple INSPECT statements. The optimized code is not supported by earlier runtime systems. If the Compile Command options specify object version 1, the previous unoptimized code is generated for a simple INSPECT statement.

2. A source program with a NUMERIC class condition which has an unsigned numeric display operand.

   The RM/COBOL version 2.*nn* and later compilers generate optimized code for a NUMERIC class condition the operand of which is an unsigned numeric display data item. The optimized code is not supported by earlier runtime systems. If the Compile Command options specify object version 1, the previous unoptimized code is generated for such a class condition.

3. In COBOL-85 compatibility mode, FILE STATUS clauses imply that ANSI COBOL 1985 I-O status values are expected. RM/COBOL-8X version 1.*nn* runtime systems never produce ANSI COBOL 1985 I-O status values.

   If the Compile Command options specify object version 1 and do not specify ANSI COBOL 1974 compatibility mode, FILE STATUS clauses are diagnosed as an object version incompatibility and are ignored.

4. The following RM/COBOL new language features require new runtime system support for their implementation. If the Compile Command options specify object version 1, these language features are diagnosed as an object version incompatibility and are compiled:

    a. Reference modification

    b. The PADDING CHARACTER clause

    c. The RECORD DELIMITER clause

    d. The VALUE clause with or subordinate to OCCURS clauses

    e. A class-name, ALPHABETIC-LOWER, or ALPHABETIC-UPPER class condition

    f. A CD FOR I-O referenced in a DISABLE, ENABLE, RECEIVE or SEND statement

    g. An ACCEPT . . . FROM DAY-OF-WEEK phrase

    h. A CALL . . . USING phrase which references a subscripted identifier

    i. A DISPLAY . . . WITH NO ADVANCING phrase

    j. An INSPECT . . . CONVERTING phrase

    k. A MERGE . . . GIVING phrase which specifies two or more files

    l. An OPEN EXTEND phrase which references a relative or indexed organization file

    m. The PURGE statement

    n. A SEND . . . REPLACING LINE phrase

    o. A SORT . . . WITH DUPLICATES IN ORDER phrase

    p. A SORT . . . GIVING phrase which specifies two or more files

Note Several important language features added in the version 2.0*n* releases of RM/COBOL do not generate object version 2 code for their implementation. Examples of such features are EVALUATE, INITIALIZE and the NOT conditional phrases (NOT AT END, NOT ON SIZE ERROR, and so forth). These new language features may be used whether or not the object version is restricted to object version 1 without affecting the object version of the resulting object program.

Object Version 3

The RM/COBOL compiler and runtime system versions 3.*nn* support object version 3. These product releases implement the high subset of ANSI COBOL 1985. The RM/COBOL version 3.*nn* runtime systems support the language features of object versions 1, 2, and 3.

Two language features were added in object version 3 that are not supported by the earlier versions. These are as follows:

1. The EXTERNAL clause in file-description-entries and Working-Storage Section record-description entries.

2. Nested programs, including the PROGRAM IS COMMON clause, the GLOBAL file description entry clause, the GLOBAL data description entry clause and the GLOBAL phrase of the USE statement.

Note Programs with either of these two features will not execute on runtime version 1.*nn* or 2.*nn* systems. Since these features required new runtime system support, you cannot compile them if the object version level is restricted to 1 or 2 with Compile Command Option Z. If the object version level is restricted to 1 or 2, the RM/COBOL compiler diagnoses these features as an object version incompatibility.

The new language feature CALL . . . USING BY CONTENT does not generate new object code. Programs using this feature can be compiled when the object version level is restricted to 1 or 2 on Compile Command Option Z.

When compiling a sequence of programs not separated by END PROGRAM headers, you must restrict the object version level to 1 or 2. Versions 3.00 and later of the RM/COBOL compiler interpret such a sequence as nested programs.

Object Version 4

The RM/COBOL compiler and runtime system versions 4.*nn* support object version 4. These product releases extend the high subset of ANSI COBOL 1985 with the X/Open Screen Section. The RM/COBOL version 4.*nn* runtime systems support the language features of object versions 1 through 4.

Four language features were added in object version 4 that are not supported by the earlier versions. These are as follows:

1. ACCEPT or DISPLAY statements that reference screen-names defined in the new Screen Section of the Data Division.

2. ACCEPT statements that specify the FROM ESCAPE KEY or the FROM EXCEPTION STATUS phrase.

3. CALL PROGRAM statement.

4. DELETE FILE statement.

Note Programs with any of these four features will not execute on runtime version 3.*nn* or earlier systems. Since these features required new runtime system support, you cannot compile them if the object version level is restricted to 3 or less with Compile Command Option Z. If the object version level is restricted to 3 or less, the RM/COBOL compiler diagnoses these features as an object version incompatibility.

Object Version 5

The RM/COBOL compiler and runtime system versions 5.*nn* support object version 5. The RM/COBOL version 5.*nn* runtime systems support the language features of object versions 1 through 5.

Two language features were added in object version 5 that are not supported by the earlier versions. These are as follows:

1. A READ statement that specifies the PREVIOUS phrase for a relative or indexed organization file.

2. A START statement that specifies a KEY IS LESS, a KEY IS NOT GREATER, or a KEY IS LESS OR EQUAL relation.

Note Programs with either of these two features will not execute on runtime version 4.*nn* or earlier systems. Since these features required new runtime system support, you cannot compile them if the object version level is restricted to 4 or less with Compile Command Option Z. If the object version level is restricted to 4 or less, the RM/COBOL compiler diagnoses these features as an object version incompatibility.

Object Version 6

The RM/COBOL compiler and runtime system versions 5.2*n* support object version 6. The RM/COBOL version 5.2*n* runtime systems support the language features of object versions 1 through 6.

Two language features were added in object version 6 that are not supported by earlier versions. These are as follows:

1. An ACCEPT statement that specifies the TIME phrase.

2. A START statement that specifies an identifier in the SIZE phrase. Even though the SIZE phrase is supported only by the 5.2*n* compiler, a literal specified in the SIZE phrase of the START statement is supported by all RM/COBOL runtime system.

Note Programs with either of these two features will not execute on runtime version 5.1*n* or earlier systems. Since these features require new runtime system support, you cannot compile them if the object version level is restricted to 5 or less with Compile Command Option Z. If the object version level is restricted to 5 or less, the RM/COBOL compiler diagnoses these features as an object version incompatibility.

In addition, performance enhancements for certain existing language features require runtime systems that support object version 6. Most programs compiled with the version 5.2*n* compiler result in object files that require object version 6 support unless the object version is restricted to 5 or less. The performance enhancements requiring object version 6 are the following:

1. Adding a literal value in the range –128 to +127 to an integer binary data item that is within the first 65280 bytes of the program local data area. The addition can be the result of an ADD statement, an INSPECT statement TALLYING phrase, a PERFORM statement VARYING or AFTER phrase, a SEARCH statement VARYING phrase or an UNSTRING statement TALLYING phrase.

2. Subtracting a literal value in the range –127 to +128 from an integer binary data item that is within the first 65280 bytes of the program local data area. The subtraction can be the result of a SUBTRACT statement or a PERFORM statement VARYING or AFTER phrase.

3. PERFORM statement with the TIMES phrase when the local data area for the program, including compiler-generated temporary data items, is less than 65280 bytes in length.

4. Subscripted operands 255 characters or less in length that are elements of tables within the first 65280 bytes of the program local data area that are specified in

INITIALIZE, MOVE, READ, RELEASE, RETURN, REWRITE, SET or WRITE statements.

5. Operands, subscripted or not, 255 characters or less in length that are within the first 65280 bytes of the program local data area specified in ACCEPT, CALL, CALL PROGRAM, CANCEL, DISABLE, DISPLAY, ENABLE, INITIALIZE, INSPECT, MOVE, READ, RECEIVE, RELEASE, RETURN, REWRITE, SEND, SET, START, STOP, STRING, UNSTRING and WRITE statements or in class or relation conditions.

6. Nonnumeric relations where the subject and object operands are different length data items, neither operand is subscripted or reference modified other than by literals, both operands are 255 characters or less in length, and both operands are within the first 65280 bytes of the program local data area.

7. GO TO statements in the fixed permanent segments of a program that generates between 32512 and 65280 bytes of object code for the fixed permanent segments.

Note The program local data area is the area of storage reserved for File Section, Working-Storage, Communication, and Screen Section data items not described with the external attribute. Linkage Section data items and data items described with the EXTERNAL clause are not part of the program local data area.

Object Version 7

The RM/COBOL compiler and runtime system versions 6.*nn* support object version 7. In addition, runtime system version 6.*nn* supports the language features of object versions 1 through 7.

New language features were added in object version 7 that are not supported by earlier versions. These are as follows:

1. A compiler configuration option allows for computational sign representations that are compatible with COBOL-74 data types.

2. Thirty digits of precision are available for numeric data items.

3. The compiler and runtime system provide support for the START statement to specify the FIRST or LAST KEY phrase. For example, START *file-name* KEY IS FIRST *key-name*.

4. The compiler and runtime system provide support for duplicate prime record keys (WITH DUPLICATES may be specified for the RECORD KEY phrase).

5. The compiler and runtime system provide support for split keys. The RECORD KEY phrase and the ALTERNATE RECORD KEY phrase may define split keys.

6. The compiler and runtime system provide support for multiple record locks in the same file. The LOCK MODE clause of the file control entry may now specify the LOCK ON MULTIPLE RECORDS phrase.

Note Programs that use any of these features will not execute on runtime versions 5.*n* or earlier systems. Since these features require new runtime system support, you cannot compile them if the object version level is restricted to 6 or less with Compile Command Option Z. If the object version level is restricted to 6 or less, the RM/COBOL compiler diagnoses these features as an object version incompatibility.

Object Version 8

The RM/COBOL compiler and runtime system versions 7.*nn* support object version 8. In addition, runtime system version 7.*nn* supports the language features of object versions 1 through 8.

New language features were added in object version 8 that are not supported by earlier versions. These are as follows:

1. BINARY, COMPUTATIONAL-4 and COMP-4 usage data items allocated as other than two- four-, eight-, or sixteen-bytes as a result of the BINARY-ALLOCATION keyword specification in the COMPILER-OPTIONS configuration record or the binary allocation override specification in the source. If a binary data item is allocated as sixteen bytes because of these new features, object version 7 will be required and generated since it was the first object version that supported sixteen-byte binary.

2. Pointer data items (USAGE POINTER), the figurative constant NULL (NULLS), the ADDRESS special register, and Formats 5 and 6 of the SET statement for manipulating pointer data items.

3. The GIVING or RETURNING phrase in the Procedure Division header or in a CALL statement.

4. The CENTURY-DATE, CENTURY-DAY, DATE-AND-TIME, or DAY-AND-TIME options in the ACCEPT statement.

5. The OMITTED option for an argument in the USING phrase of a CALL statement.

6. A source program that refers to linkage records (01 or 77 level data items defined in the Linkage Section) in the USING phrase of a CALL statement or with reference modification.

   The RM/COBOL version 7.00 and later compilers generate code to reference the data item on which the linkage record is based, that is, the actual argument passed by the calling program or the area of memory referenced by a SET ADDRESS OF statement. This new code is not supported by earlier runtime systems. If the Compile Command options specify object version 7 or lower, then the previous code is generated that uses the description of the data item in the linkage section of the called program.

7. A source program may now use more than 64K of name space (unique spellings of user-defined words), but object versions less than 8 support a maximum of 64K of name space for the object symbol table. If the Compile Command Option Y is specified to place the symbol table in the object file for debugging purposes and more than 64K of name space has been used, object version 8 is required and will be generated regardless of the maximum object version setting specified in the Compile Command Option Z. The compiler generates a diagnostic message in this event.

Note 1 Programs that use any of these features will not execute on runtime versions 6.*n* or earlier systems. Since these features require new runtime system support, you cannot compile them if the object version level is restricted to 7 or less with Compile Command Option Z. If the object version level is restricted to 7 or less, the RM/COBOL compiler diagnoses these features as an object version incompatibility.

Note 2 Several important language features added in the version 7.0 releases of RM/COBOL do not generate object version 8 code for their implementation. These include level-number 78 constant-name declarations, constant-name references, the DATE-COMPILED option in the ACCEPT statement, in-line comments, a numeric literal specified in the VALUE clause for a numeric edited data item, and the COUNT, COUNT-MAX, COUNT-MIN, LENGTH, and PROGRAM-ID special registers. A binary allocation override that specifies two-, four-, or eight-byte allocation may be used for any object version. A binary allocation override that specifies sixteen-byte allocation may be used for object version 7.

Appendix I: Extension, Obsolete, and Subset Language Elements

RM/COBOL supports the extension, obsolete, and subset language elements discussed in this appendix. Each language element is only briefly described in order to identify it. For further information on each language element, refer to the *RM/COBOL Language Reference Manual*.

The extension language elements are RM/COBOL extensions to the American National Standard COBOL X3.23-1985. Extensions such as the ACCEPT and DISPLAY screen control syntax simplify the use of COBOL in an interactive environment. Other extensions relax some of the rules of COBOL to simplify program writing.

The obsolete language elements are language features declared obsolete in ANSI COBOL 1985. The standard has declared certain features as obsolete to indicate that they will be removed in the next full revision of COBOL. The features declared obsolete are ones, such as the ALTER statement, that have been identified as contributing to poor programming practices. Obsolete features should be avoided in new programs and removed from existing programs when they are revised.

The subset language elements are language features that are required only when more than the minimum COBOL language is implemented. Above minimum COBOL, there are two additional subsets defined by the standard: intermediate and high. In addition, RM/COBOL supports two standard optional modules: segmentation and communication. Each of these optional modules is further divided into a level 1 and level 2 subset, where the level 2 subset includes the level 1 subset.

Compile Command Option F (see page 6-15) contains a flagging option to cause flagging of the occurrence of any of the items in the following lists. Each of the lists is preceded by an explanation of the flagging message produced for items on that list.

Extension Elements

The warning message:

```
W   69:   FIPS NONCONFORMING NONSTANDARD
```

is produced for each of the following language elements if they appear in a source program compiled with the F=EXTENSION Compile Command Option (see page 6-15). Each item on the list is an RM/COBOL extension to the American National Standard COBOL X3.23-1985 language features and may, therefore, not be available in other COBOL implementations.

Many extensions noted for RM/COBOL-8X do not appear below. These extensions have not been deleted, but have been incorporated as standard features in the American National Standard COBOL X3.23-1985.

The extensions are as follows:

1. More than seven subscripts.
2. In-line comments (*>*comment-entry*).
3. *integer-1* + *integer-2* as a subscript (literal subscript with relative offset) or zero used for relative offset in a subscript.
4. Numeric literals with more than 18 digits.
5. Numeric data items with more than 18 digits of precision.
6. Nonnumeric literals greater than 160 characters in length.
7. Text-names and library-names specified as nonnumeric literals.
8. COPY statement within a copied file.
9. User-defined word ending in a hyphen.
10. Reserved words used as system-names (the ASSIGN clause in the file control entry, the VALUE OF clause in the file description entry, and the ENTER statement).
11. Use of an index-name in subscripting a table other than the one with which it is associated.
12. Apostrophe used as a delimiter for nonnumeric literals.
13. ALL [ALL] . . . *literal* form of a figurative constant.

14. Procedure-name that is the same as a data-name or index-name.
15. NULL or NULLS figurative constants.
16. Hexadecimal literal.
17. ADDRESS special register.
18. COUNT, COUNT-MAX, and COUNT-MIN special registers.
19. LENGTH special register.
20. PROGRAM-ID special register.
21. constant-name reference (a constant-name is defined in a level-number 78 data description entry).
22. RETURN-CODE special register.
23. ID abbreviation for IDENTIFICATION.
24. Identification Division optional paragraphs out of order.
25. Program-name specified as a nonnumeric literal.
26. REMARKS paragraph in the Identification Division.
27. OBJECT-COMPUTER paragraph optional clauses out of order.
28. ALPHABET keyword missing in the SPECIAL-NAMES paragraph when an alphabet-name appears.
29. Repeated character in an ALPHABET literal.
30. ALPHABET literal THRU phrase on ALSO phrase.
31. ALPHABET literal ALSO phrase on THRU phrase.
32. SYMBOLIC CHARACTERS clause specified as SYMBOLIC CHARACTER, that is, CHARACTER used as a synonym for CHARACTERS.
33. CURRENCY SIGN literal specified as a figurative constant.
34. ASSIGN TO clause with data-name specified for file-access-name.
35. CODE-SET clause in the file control entry.
36. COLLATING SEQUENCE clause in the file control entry.
37. ORGANIZATION clause that specifies LINE or BINARY.

38. RESERVE clause that specifies NO or ALTERNATE.

39. RECORD KEY clause that specifies the DUPLICATES phrase.

40. RECORD KEY clause that specifies the split-key-name option.

41. ALTERNATE RECORD KEY clause that specifies that split-key-name option.

42. LOCK MODE clause in the file control entry.

43. Optional word IS in POSITION phrase of MULTIPLE FILE TAPE clause.

44. SCREEN SECTION in the Data Division.

45. CODE-SET clause that refers to an alphabet-name defined with the literal phrase.

46. CODE-SET clause specified for a relative or indexed file.

47. LINAGE clause integer operand with a positive sign explicitly specified.

48. Qualification of the data-name in the RECORD IS VARYING DEPENDING ON clause.

49. Level-number with three or more digits.

50. Level-number 78 data description entry.

51. DEPENDING phrase specified in OCCURS clause that omits [TO *integer-2*].

52. More than 30 characters in a PICTURE character-string.

53. PICTURE character-string that ends in a comma or period and is not immediately followed by a period space separator.

54. REDEFINES of last name on same level, even though it is also a REDEFINES.

55. REDEFINES not first clause in a data description entry.

56. SYNCHRONIZED clause specified with USAGE INDEX in a data description entry.

57. USAGE COMP-1, COMP-3, COMP-4, COMP-6, COMPUTATIONAL-1, COMPUTATIONAL-3, COMPUTATIONAL-4, and COMPUTATIONAL-6.

58. USAGE POINTER.

59. USAGE clause that specifies a binary allocation override (*integer-3*).

60. VALUE clause in a data description entry that specifies the WHEN SET TO FALSE phrase.

61. VALUE clause in a data item data description entry in the File Section or Linkage Section or in other than the first record description entry subordinate to a communication description entry in the Communication Section that is included in the resultant source program as the result of a COPY statement.

62. VALUE clause in a data item data description entry in an external record in the Working-Storage Section record that is included in the source program as the result of a COPY statement.

63. VALUE clause that specifies a numeric literal for a numeric edited data item.

64. Procedure Division header that specifies the GIVING or RETURNING phrase.

65. END PROGRAM specified without a program-name.

66. END PROGRAM header that specifies a nonnumeric literal for the program-name.

67. Segment-numbers greater than 99.

68. Optional word THEN used as a statement connective.

69. Both operands of a relation being literals.

70. An index-name as one operand in a relation and an arithmetic expression as the other operand.

71. Pointer data item used in a relation condition.

72. Literal specified in a class condition.

73. Literal specified in a sign condition.

74. Nondisplay data item specified in a NUMERIC class condition.

75. ACCEPT . . . FROM CONSOLE when CONSOLE not defined as a *mnemonic-name* in the SPECIAL-NAMES paragraph.

76. ACCEPT . . . FROM SYSIN when SYSIN not defined as a *mnemonic-name* in the SPECIAL-NAMES paragraph.

77. ACCEPT … FROM CENTURY-DATE.

78. ACCEPT … FROM CENTURY-DAY.

79. ACCEPT … FROM DATE-AND-TIME.

80. ACCEPT … FROM DATE-COMPILED.

81. ACCEPT … FROM DAY-AND-TIME.

82. ACCEPT . . . FROM ESCAPE KEY statement.

83. ACCEPT . . . FROM EXCEPTION STATUS statement.

84. ACCEPT operand series.

85. ACCEPT statement that specifies a screen-name.

86. ACCEPT with screen control (LINE, POSITION, SIZE, CURSOR, CONTROL, ERASE, TAB, UNIT, PROMPT, UPDATE, ECHO, BLINK, REVERSE, HIGH, LOW, OFF, CONVERT, NO BEEP, ON EXCEPTION, NOT ON EXCEPTION, END-ACCEPT, BEFORE TIME).

87. CALL PROGRAM statement.

88. CALL . . . USING *literal*.

89. CALL … USING pointer data item.

90. CALL … USING OMITTED.

91. CALL … GIVING/RETURNING phrase.

92. CLOSE statement that specifies the NO REWIND phrase with either the REEL or UNIT phrase.

93. DELETE FILE statement.

94. DISABLE statement without INPUT, OUTPUT or I-O phrase.

95. DISPLAY . . . UPON CONSOLE when CONSOLE is not defined as a *mnemonic-name* in the SPECIAL-NAMES paragraph.

96. DISPLAY . . . UPON SYSOUT when SYSOUT not defined as a *mnemonic-name* in the SPECIAL-NAMES paragraph.

97. DISPLAY statement that specifies a screen-name.

98. DISPLAY with screen control (LINE, POSITION, SIZE, CONTROL, ERASE, UNIT, BLINK, REVERSE, HIGH, LOW, CONVERT, BEEP).

99. ENABLE statement without INPUT, OUTPUT or I-O phrase.

100. ENTER statement not ended by a period.

101. EVALUATE statement that specifies an index-name or index data item as a selection subject or selection object.

102. GOBACK statement.

103. IF statement that specifies END-IF and NEXT SENTENCE.

104. INSPECT . . . TALLYING . . . FOR FIRST phrase.

105. INSPECT statement that refers to an ALL *literal* as a control operand.

106. INSPECT statement that refers to a group data item as a control operand.

107. MOVE CORRESPONDING statement with a receiving operand series.

108. OPEN EXCLUSIVE phrase.

109. OPEN EXTEND statement that refers to a file described with the LINAGE clause.

110. OPEN . . . WITH LOCK phrase.

111. PERFORM *integer-1* TIMES statement where *integer-1* is zero or signed.

112. In-line PERFORM VARYING statement with AFTER phrases.

113. READ . . . PREVIOUS phrase.

114. READ statement that specifies the WITH NO LOCK or WITH LOCK phrase.

115. RELEASE . . . FROM *literal*.

116. REWRITE . . . FROM *literal*.

117. SEARCH statement that specifies END-SEARCH and NEXT SENTENCE.

118. SEND . . . FROM *literal*.

119. SET statement (Format 1) that specifies more than one TO phrase.

120. SET statement (Format 2) that specifies more than one UP/DOWN BY phrase.

121. SET {*condition-name*} . . . TO FALSE statement.

122. SET statement that specifies more than one instance of the TO TRUE phrase.

123. SET statement (Formats 5 and 6) that refers to a pointer data item.

124. START statement with LESS THAN, LESS THAN OR EQUAL, or equivalent relations.

125. START statement that specifies the SIZE phrase.

126. START statement in which the FIRST or LAST option is specified in the KEY phrase.

127. STOP statement that specifies an identifier instead of the *literal* phrase.

128. STOP RUN statement with RETURN-CODE specified.

129. UNLOCK statement.

130. WRITE . . . FROM *literal*.

131. WRITE . . . ADVANCING TO LINE phrase.

Obsolete Elements

The warning message:

```
W   71:   FIPS OBSOLETE
```

is produced for each of the following language elements if they appear in a source program compiled with the F=OBSOLETE Compile Command Option (see page 6-15). Each item on the list is identified in the American National Standard COBOL X3.23-1985 as being an obsolete language element which will be deleted from the next full revision of the COBOL standard.

1. ALL *literal*, where *literal* has a length greater than 1 if associated with a numeric or numeric edited data item.

2. AUTHOR, INSTALLATION, DATE-WRITTEN, DATE-COMPILED and SECURITY paragraphs.

3. MEMORY SIZE clause.

4. RERUN clause.

5. MULTIPLE FILE TAPE clause.

6. LABEL RECORDS clause.

7. VALUE OF clause.

8. DATA RECORDS clause.

9. ALTER statement.

10. KEY phrase of the DISABLE statement.

11. KEY phrase of the ENABLE statement.

12. ENTER statement.

13. GO TO statement with omitted *procedure-name-1*.

14. REVERSED phrase of the OPEN statement.

15. STOP *literal* phrase.

16. Segment-numbers and the SEGMENT-LIMIT clause.

Subset Elements

The warning message:

```
W   70:   FIPS NONCONFORMING STANDARD
```

is produced for each of the following language elements if they appear in a source program compiled with the appropriate F Compile Command Option (see page 6-15). The keyword which causes the language element to be flagged is shown in parentheses after each element description. Note that HIGH elements will be flagged if F=INTERMEDIATE or F=HIGH is specified, COM2 elements will be flagged if F=COM1 or F=COM2 is specified, and SEG2 elements will be flagged if F=SEG1 or F=SEG2 is specified.

If obsolete element flagging is also enabled, any obsolete element from the following list will only be flagged as obsolete even when the other keyword is also specified in the F Compile Command Option. That is, obsolete flagging takes precedence over subset flagging.

1. Segment-number (SEG1, OBSOLETE).

2. Noncontiguous segments with same segment-number (SEG2, OBSOLETE).

3. Symbolic-character (HIGH).

4. ALL literal figurative constant (HIGH).

5. LINAGE-COUNTER special register (HIGH).

6. Qualification (HIGH).

7. More than three subscripts (HIGH).

8. Reference modification (HIGH).

9. Continuation of a COBOL word, numeric literal or PICTURE character-string (HIGH).

10. IDENTIFICATION DIVISION header of a contained program (HIGH).

11. END PROGRAM header (HIGH).
12. COMMON clause in PROGRAM-ID paragraph (HIGH).
13. INITIAL clause in PROGRAM-ID paragraph (HIGH).
14. DATE-COMPILED paragraph (HIGH, OBSOLETE).
15. COPY statement (INTERMEDIATE).
16. COPY . . . OF/IN *library-name* (HIGH).
17. COPY . . . REPLACING phrase (HIGH).
18. REPLACE statement (HIGH).
19. SEGMENT-LIMIT clause (SEG2, OBSOLETE).
20. ALPHABET clause literal phrase (HIGH).
21. SYMBOLIC CHARACTERS clause (HIGH).
22. OPTIONAL phrase in file control entry (HIGH).
23. ACCESS MODE RANDOM clause (INTERMEDIATE).
24. ACCESS MODE DYNAMIC clause (HIGH).
25. RELATIVE KEY phrase (INTERMEDIATE).
26. ALTERNATE RECORD KEY clause (HIGH).
27. ORGANIZATION RELATIVE clause (INTERMEDIATE).
28. ORGANIZATION INDEXED clause (INTERMEDIATE).
29. PADDING CHARACTER clause (HIGH).
30. RECORD DELIMITER clause (HIGH).
31. RECORD KEY clause (INTERMEDIATE).
32. RESERVE AREA clause (HIGH).
33. MULTIPLE FILE TAPE clause (HIGH, OBSOLETE).
34. SAME RECORD AREA clause (HIGH).
35. SAME SORT/SORT-MERGE AREA clause INTERMEDIATE).
36. SD level indicator (INTERMEDIATE).

37. BLOCK CONTAINS *integer-1* TO *integer-2* RECORDS/CHARACTERS (HIGH).

38. LINAGE clause (HIGH).

39. RECORD VARYING IN SIZE clause (HIGH).

40. VALUE OF clause which specifies a data-name (HIGH, OBSOLETE).

41. COMMUNICATION SECTION header (COM1).

42. CD level indicator (COM1).

43. INITIAL clause in a CD entry (COM2).

44. SYMBOLIC SUB-QUEUE-1, SUB-QUEUE-2 and SUB-QUEUE-3 clauses in a CD entry (COM2).

45. Data-name series in a CD entry (COM2).

46. DESTINATION TABLE clause in a CD entry (COM2).

47. Level-number 66 data description entry (HIGH).

48. Level-number 88 data description entry (HIGH).

49. EXTERNAL clause (HIGH).

50. GLOBAL clause (HIGH).

51. OCCURS clause ASCENDING/DESCENDING KEY phrase (HIGH).

52. OCCURS clause *integer-1* TO *integer-2* TIMES DEPENDING ON phrase (HIGH).

53. REDEFINES clauses nested (HIGH).

54. REDEFINES clause that refers to a table item (HIGH).

55. RENAMES clause (HIGH).

56. Procedure Division header USING phrase with more than five operands (HIGH).

57. Condition-name condition (HIGH).

58. Sign condition (HIGH).

59. Logical operators AND, OR, NOT (HIGH).

60. Arithmetic expression operators + – * / ** (HIGH).

61. ACCEPT statement FROM phrase (HIGH).
62. ACCEPT MESSAGE COUNT statement (COM1).
63. ADD statement CORRESPONDING phrase (HIGH).
64. ALTER statement procedure-name series (HIGH, OBSOLETE).
65. CALL statement with *identifier-1* (HIGH).
66. CALL statement USING phrase with more than five operands (HIGH).
67. CALL statement USING BY CONTENT or BY REFERENCE phrase (HIGH).
68. CALL statement ON OVERFLOW phrase (HIGH).
69. CALL statement ON EXCEPTION phrase (HIGH).
70. CALL statement NOT ON EXCEPTION phrase (HIGH).
71. CANCEL statement (HIGH).
72. CLOSE statement FOR REMOVAL phrase (HIGH).
73. CLOSE statement WITH NO REWIND phrase (HIGH).
74. CLOSE statement WITH LOCK phrase (HIGH).
75. COMPUTE statement (HIGH).
76. DELETE statement (INTERMEDIATE).
77. DISABLE statement (COM2).
78. DISPLAY statement UPON phrase (HIGH).
79. DISPLAY statement WITH NO ADVANCING phrase (HIGH).
80. DIVIDE statement REMAINDER phrase (HIGH).
81. ENABLE statement (COM2).
82. EVALUATE statement (HIGH).
83. GO TO statement with omitted procedure-name (HIGH, (OBSOLETE).
84. IF statement that contains a conditional statement (HIGH).
85. INITIALIZE statement (HIGH).
86. INSPECT statement with multicharacter data item (HIGH).

87. INSPECT statement BEFORE/AFTER phrase series (HIGH).
88. INSPECT statement TALLYING phrase series (HIGH).
89. INSPECT statement REPLACING phrase series (HIGH).
90. INSPECT statement CONVERTING phrase (HIGH).
91. MERGE statement (INTERMEDIATE).
92. MOVE statement CORRESPONDING phrase (HIGH).
93. MOVE statement de-editing of numeric edited items (HIGH).
94. OPEN statement WITH NO REWIND phrase (HIGH).
95. OPEN statement REVERSED phrase (HIGH, OBSOLETE).
96. OPEN statement EXTEND phrase (HIGH).
97. PERFORM statement TEST BEFORE/AFTER phrase (HIGH).
98. PERFORM statement VARYING phrase (HIGH).
99. PURGE statement (COM2).
100. READ statement NEXT phrase (HIGH).
101. READ statement KEY phrase (HIGH).
102. READ statement INVALID KEY phrase (INTERMEDIATE).
103. READ statement NOT INVALID KEY phrase (INTERMEDIATE).
104. RECEIVE statement (COM1).
105. RECEIVE statement SEGMENT phrase (COM2).
106. RELEASE statement (INTERMEDIATE).
107. RETURN statement (INTERMEDIATE).
108. REWRITE statement INVALID KEY phrase (INTERMEDIATE).
109. REWRITE statement NOT INVALID KEY phrase (INTERMEDIATE).
110. SEARCH statement (HIGH).
111. SEND statement (COM1).
112. SEND statement Format 1 (COM2).

113. SEND statement WITH identifier phrase (COM2).

114. SEND statement WITH ESI phrase (COM2).

115. SEND statement BEFORE/AFTER ADVANCING *mnemonic-name* phrase (COM2).

116. SEND statement REPLACING LINE phrase (COM2).

117. SET statement *condition-name* TO TRUE (HIGH).

118. SORT statement (INTERMEDIATE).

119. START statement (HIGH).

120. STRING statement (HIGH).

121. SUBTRACT statement CORRESPONDING phrase (HIGH).

122. UNSTRING statement (HIGH).

123. USE statement GLOBAL phrase (HIGH).

124. USE statement ON file-name series (HIGH).

125. USE statement ON EXTEND (HIGH).

126. WRITE statement BEFORE/AFTER ADVANCING *mnemonic-name* phrase (HIGH).

127. WRITE statement AT END-OF-PAGE/EOP phrase (HIGH).

128. WRITE statement NOT AT END-OF-PAGE/EOP phrase (HIGH).

129. WRITE statement INVALID KEY phrase (INTERMEDIATE).

130. WRITE statement NOT INVALID KEY phrase (INTERMEDIATE).

Appendix J: Code-Set Translation Tables

The following tables describe the translation between ASCII and EBCDIC character sets. The ASCII to EBCDIC translation is identical to that described by IBM in the document, *Systems Network Architecture Format and Protocol Reference Manual: Architecture Logic* (SC30-3112-0). The EBCDIC to ASCII translation is the inverse of the ASCII to EBCDIC mapping, with the addition that EBCDIC characters with no ASCII equivalent are assigned values in the range X‘80’ to X‘FF’.

Character abbreviations are defined in Table J-3 beginning on page J-15.

Table J-1 ASCII to EBCDIC Conversion

ASCII Code (Decimal)	ASCII Code (Hexadecimal)	U.S. Character	EBCDIC Code (Hexadecimal)	U.S. Character
0	00	NUL	00	NUL
1	01	SOH	01	SOH
2	02	STX	02	STX
3	03	ETX	03	ETX
4	04	EOT	37	EOT
5	05	ENQ	2D	ENQ
6	06	ACK	2E	ACK
7	07	BEL	2F	BEL
8	08	BS	16	BS
9	09	HT	05	HT
10	0A	LF	25	LF
11	0B	VT	0B	VT
12	0C	FF	0C	FF
13	0D	CR	0D	CR
14	0E	SO	0E	SO
15	0F	SI	0F	SI
16	10	DLE	10	DLE
17	11	DC1	14	ENP

Table J-1 ASCII to EBCDIC Conversion *(Cont.)*

ASCII Code (Decimal)	ASCII Code (Hexadecimal)	U.S. Character	EBCDIC Code (Hexadecimal)	U.S. Character
18	12	DC2	24	INP
19	13	DC3	04	SEL
20	14	DC4	15	NL
21	15	NAK	3D	NAK
22	16	SYN	32	SYN
23	17	ETB	26	ETB
24	18	CAN	18	CAN
25	19	EM	19	EM
26	1A	SUB	3F	SUB
27	1B	ESC	27	ESC
28	1C	FS	1C	IFS
29	1D	GS	1D	IGS
30	1E	RS	1E	IRS
31	1F	US	1F	IUS
32	20	Space	40	Space
33	21	!	4F	|
34	22	”	7F	”
35	23	#	7B	#
36	24	$	5B	$
37	25	%	6C	%
38	26	&	50	&
39	27	’	7D	’
40	28	(	4D	(
41	29	)	5D	)
42	2A	*	5C	*
43	2B	+	4E	+
44	2C	,	6B	,
45	2D	-	60	-
46	2E	.	4B	.
47	2F	/	61	/

Table J-1 ASCII to EBCDIC Conversion *(Cont.)*

ASCII Code (Decimal)	ASCII Code (Hexadecimal)	U.S. Character	EBCDIC Code (Hexadecimal)	U.S. Character
48	30	0	F0	0
49	31	1	F1	1
50	32	2	F2	2
51	33	3	F3	3
52	34	4	F4	4
53	35	5	F5	5
54	36	6	F6	6
55	37	7	F7	7
56	38	8	F8	8
57	39	9	F9	9
58	3A	:	7A	:
59	3B	;	5E	;
60	3C	<	4C	<
61	3D	=	7E	=
62	3E	>	6E	>
63	3F	?	6F	?
64	40	@	7C	@
65	41	A	C1	A
66	42	B	C2	B
67	43	C	C3	C
68	44	D	C4	D
69	45	E	C5	E
70	46	F	C6	F
71	47	G	C7	G
72	48	H	C8	H
73	49	I	C9	I
74	4A	J	D1	J
75	4B	K	D2	K
76	4C	L	D3	L
77	4D	M	D4	M

Table J-1 ASCII to EBCDIC Conversion *(Cont.)*

ASCII Code (Decimal)	ASCII Code (Hexadecimal)	U.S. Character	EBCDIC Code (Hexadecimal)	U.S. Character
78	4E	N	D5	N
79	4F	O	D6	O
80	50	P	D7	P
81	51	Q	D8	Q
82	52	R	D9	R
83	53	S	E2	S
84	54	T	E3	T
85	55	U	E4	U
86	56	V	E5	V
87	57	W	E6	W
88	58	X	E7	X
89	59	Y	E8	Y
90	5A	Z	E9	Z
91	5B	[	4A	¢
92	5C	\	E0	\
93	5D	]	5A	!
94	5E	^	5F	¬
95	5F	_	6D	_
96	60	‘	79	‘
97	61	a	81	a
98	62	b	82	b
99	63	c	83	c
100	64	d	84	d
101	65	e	85	e
102	66	f	86	f
103	67	g	87	g
104	68	h	88	h
105	69	I	89	i
106	6A	j	91	j
107	6B	k	92	k

Table J-1 ASCII to EBCDIC Conversion *(Cont.)*

ASCII Code (Decimal)	ASCII Code (Hexadecimal)	U.S. Character	EBCDIC Code (Hexadecimal)	U.S. Character
108	6C	l	93	l
109	6D	m	94	m
110	6E	n	95	n
111	6F	o	96	o
112	70	p	97	p
113	71	q	98	q
114	72	r	99	r
115	73	s	A2	s
116	74	t	A3	t
117	75	u	A4	u
118	76	v	A5	v
119	77	w	A6	w
120	78	x	A7	x
121	79	y	A8	y
122	7A	z	A9	z
123	7B	{	C0	{
124	7C	|	6A	|
125	7D	}	D0	}
126	7E	~	A1	~
127	7F	DEL	07	DEL

Table J-2 EBCDIC to ASCII Conversion

EBCDIC Code (Decimal)	EBCDIC Code (Hexadecimal)	U.S. Character	ASCII Code (Hexadecimal)	U.S. Character
0	00	NUL	00	NUL
1	01	SOH	01	SOH
2	02	STX	02	STX
3	03	ETX	03	ETX
4	04	SEL	13	DC3
5	05	HT	09	HT
6	06		80	
7	07	DEL	7F	DEL
8	08		81	
9	09		82	
10	0A		83	
11	0B	VT	0B	VT
12	0C	FF	0C	FF
13	0D	CR	0D	CR
14	0E	SO	0E	SO
15	0F	SI	0F	SI
16	10	DLE	10	DLE
17	11		84	
18	12		85	
19	13		86	
20	14	ENP	11	DC1
21	15	NL	14	DC4
22	16	BS	08	BS
23	17		87	
24	18	CAN	18	CAN
25	19	EM	19	EM
26	1A		88	
27	1B		89	
28	1C	IFS	1C	FS
29	1D	IGS	1D	GS

Table J-2 EBCDIC to ASCII Conversion *(Cont.)*

EBCDIC Code (Decimal)	EBCDIC Code (Hexadecimal)	U.S. Character	ASCII Code (Hexadecimal)	U.S. Character
30	1E	IRS	1E	RS
31	1F	IUS	1F	US
32	20		8A	
33	21		8B	
34	22		8C	
35	23	8D		
36	24	INP	12	DC2
37	25	LF	0A	LF
38	26	ETB	17	ETB
39	27	ESC	1B	ESC
40	28		8E	
41	29		8F	
42	2A		90	
43	2B		91	
44	2C		92	
45	2D	ENQ	05	ENQ
46	2E	ACK	06	ACK
47	2F	BEL	07	BEL
48	30		93	
49	31		94	
50	32	SYN	16	SYN
51	33		95	
52	34		96	
53	35		97	
54	36		98	
55	37	EOT	04	EOT
56	38		99	
57	39		9A	
58	3A		9B	
59	3B		9C	

Table J-2 EBCDIC to ASCII Conversion *(Cont.)*

EBCDIC Code (Decimal)	EBCDIC Code (Hexadecimal)	U.S. Character	ASCII Code (Hexadecimal)	U.S. Character
60	3C		9D	
61	3D	NAK	15	NAK
62	3E		9E	
63	3F	SUB	1A	SUB
64	40	Space	20	Space
65	41		9F	
66	42		A0	
67	43		A1	
68	44		A2	
69	45		A3	
70	46		A4	
71	47		A5	
72	48		A6	
73	49		A7	
74	4A	¢	5B	[
75	4B	.	2E	.
76	4C	<	3C	<
77	4D	(	28	(
78	4E	+	2B	+
79	4F	|	21	!
80	50	&	26	&
81	51		A8	
82	52		A9	
83	53		AA	
84	54		AB	
85	55		AC	
86	56		AD	
87	57		AE	
88	58		AF	
89	59		B0	

Table J-2 EBCDIC to ASCII Conversion *(Cont.)*

EBCDIC Code (Decimal)	EBCDIC Code (Hexadecimal)	U.S. Character	ASCII Code (Hexadecimal)	U.S. Character
90	5A	!	5D	]
91	5B	$	24	$
92	5C	*	2A	*
93	5D	)	29	)
94	5E	;	3B	;
95	5F	¬	5E	^
96	60	-	2D	-
97	61	/	2F	/
98	62		B1	
99	63		B2	
100	64		B3	
101	65		B4	
102	66		B5	
103	67		B6	
104	68		B7	
105	69		B8	
106	6A		7C	
107	6B	,	2C	,
108	6C	%	25	%
109	6D	_	5F	_
110	6E	>	3E	>
111	6F	?	3F	?
112	70		B9	
113	71		BA	
114	72		BB	
115	73		BC	
116	74		BD	
117	75		BE	
118	76		BF	
119	77		C0	

Table J-2 EBCDIC to ASCII Conversion *(Cont.)*

EBCDIC Code (Decimal)	EBCDIC Code (Hexadecimal)	U.S. Character	ASCII Code (Hexadecimal)	U.S. Character
120	78		C1	
121	79	‘	60	‘
122	7A	:	3A	:
123	7B	#	23	#
124	7C	@	40	@
125	7D	’	27	’
126	7E	=	3D	=
127	7F	”	22	”
128	80		C2	
129	81	a	61	a
130	82	b	62	b
131	83	c	63	c
132	84	d	64	d
133	85	e	65	e
134	86	f	66	f
135	87	g	67	g
136	88	h	68	h
137	89	i	69	i
138	8A		C3	
139	8B		C4	
140	8C		C5	
141	8D		C6	
142	8E		C7	
143	8F		C8	
144	90		C9	
145	91	j	6A	j
146	92	k	6B	k
147	93	l	6C	l
148	94	m	6D	m
149	95	n	6E	n

Table J-2 EBCDIC to ASCII Conversion *(Cont.)*

EBCDIC Code (Decimal)	EBCDIC Code (Hexadecimal)	U.S. Character	ASCII Code (Hexadecimal)	U.S. Character
150	96	o	6F	o
151	97	p	70	p
152	98	q	71	q
153	99	r	72	r
154	9A		CA	
155	9B		CB	
156	9C		CC	
157	9D		CD	
158	9E		CE	
159	9F		CF	
160	A0		D0	
161	A1	~	7E	~
162	A2	s	73	s
163	A3	t	74	t
164	A4	u	75	u
165	A5	v	76	v
166	A6	w	77	w
167	A7	x	78	x
168	A8	y	79	y
169	A9	z	7A	z
170	AA		D1	
171	AB		D2	
172	AC		D3	
173	AD		D4	
174	AE		D5	
175	AF		D6	
176	B0		D7	
177	B1		D8	
178	B2		D9	
179	B3		DA	

Table J-2 EBCDIC to ASCII Conversion *(Cont.)*

EBCDIC Code (Decimal)	EBCDIC Code (Hexadecimal)	U.S. Character	ASCII Code (Hexadecimal)	U.S. Character
180	B4		DB	
181	B5		DC	
182	B6		DD	
183	B7		DE	
184	B8		DF	
185	B9		E0	
186	BA		E1	
187	BB		E2	
188	BC		E3	
189	BD		E4	
190	BE		E5	
191	BF		E6	
192	C0	{	7B	{
193	C1	A	41	A
194	C2	B	42	B
195	C3	C	43	C
196	C4	D	44	D
197	C5	E	45	E
198	C6	F	46	F
199	C7	G	47	G
200	C8	H	48	H
201	C9	I	49	I
202	CA		E7	
203	CB		E8	
204	CC		E9	
205	CD		EA	
206	CE		EB	
207	CF		EC	
208	D0	}	7D	}
209	D1	J	4A	J

Table J-2 EBCDIC to ASCII Conversion *(Cont.)*

EBCDIC Code (Decimal)	EBCDIC Code (Hexadecimal)	U.S. Character	ASCII Code (Hexadecimal)	U.S. Character
210	D2	K	4B	K
211	D3	L	4C	L
212	D4	M	4D	M
213	D5	N	4E	N
214	D6	O	4F	O
215	D7	P	50	P
216	D8	Q	51	Q
217	D9	R	52	R
218	DA		ED	
219	DB		EE	
220	DC		EF	
221	DD		F0	
222	DE		F1	
223	DF		F2	
224	E0	\	5C	\
225	E1		F3	
226	E2	S	53	S
227	E3	T	54	T
228	E4	U	55	U
229	E5	V	56	V
230	E6	W	57	W
231	E7	X	58	X
232	E8	Y	59	Y
233	E9	Z	5A	Z
234	EA		F4	
235	EB		F5	
236	EC		F6	
237	ED		F7	
238	EE		F8	
239	EF		F9	

Table J-2 EBCDIC to ASCII Conversion *(Cont.)*

EBCDIC Code (Decimal)	EBCDIC Code (Hexadecimal)	U.S. Character	ASCII Code (Hexadecimal)	U.S. Character
240	F0	0	30	0
241	F1	1	31	1
242	F2	2	32	2
243	F3	3	33	3
244	F4	4	34	4
245	F5	5	35	5
246	F6	6	36	6
247	F7	7	37	7
248	F8	8	38	8
249	F9	9	39	9
250	FA		FA	
251	FB		FB	
252	FC		FC	
253	FD		FD	
254	FE		FE	
255	FF		FF	

Character abbreviations are defined in Table J-3.

Table J-3 Character Abbreviations

Abbreviation	Meaning
ACK	Acknowledgment
BEL	Bell
BS	Backspace
CAN	Cancel
CR	Carriage Return
DC1	Device Control 1
DC2	Device Control 2
DC3	Device Control 3
DC4	Device Control 4
DEL	Delete
DLE	Data Link Escape
EM	End of Medium
ENP	Enable Presentation
ENQ	Enquiry
EOT	End of Transmission
ESC	Escape
ETB	End of Transmission Block
ETX	End of Text
FF	Form Feed
FS	File Separator
GS	Group Separator
HT	Horizontal Tab
IFS	Interchange File Separator
IGS	Interchange Group Separator
INP	Inhibit Presentation
IRS	Interchange Record Separator
IUS	Interchange Unit Separator
LF	Line Feed
NAK	Negative Acknowledgment

Table J-3 Character Abbreviations *(Cont.)*

Abbreviation	Meaning
NL	New Line
NUL	Null
RS	Record Separator
SEL	Select
SI	Shift In
SO	Shift Out
SOH	Start of Heading
STX	Start of Text
SUB	Substitute
SYN	Synchronous Idle
US	Unit Separator
VT	Vertical Tab

Index

2

2 Compile Command Option, 6-14, 6-16, 10-15

7

7 Compile Command Option, 6-14, 10-9, F-22

A

A (Address Stop) Command, Debug option, 9-20
A Compile Command Option, 6-9, 6-22, 9-1, 9-9, 10-12
A Runtime Command Option, 7-5
ACCEPT and DISPLAY statements, operating-system specific information, 8-1–8-21. *See also* ACCEPT statement, Terminal I-O; DISPLAY statement
  cursor types, 2-9, 3-43
  defined keys, 8-2
    edit keys
      backspace, 8-3
      delete character, 8-3
      erase entire, 8-4
      erase remainder, 8-4
      insert character, 8-4
      left arrow, 8-3
      right arrow, 8-3
  initial contents of a screen field, 8-1
  keys that generate field termination codes, 8-5
  redirection of input and output, 2-22, 8-1
    standard error, 2-25
    standard input, 2-22
    standard output, 2-24–2-25, 6-18
  terminal attributes, 2-9
  terminal interfaces, 2-9
ACCEPT FROM EXCEPTION STATUS statement, 8-30
ACCEPT MESSAGE COUNT statement, 8-65
ACCEPT statement, Terminal I-O. *See also* ACCEPT and DISPLAY statements, operating-system specific information; DISPLAY statement
  BEFORE TIME phrase, 8-21
    CHARACTER-TIMEOUT keyword, TERM-ATTR configuration record, 10-36
  configuration
    ACCEPT-FIELD-FROM-SCREEN keyword, RUN-ATTR record, 8-1, 10-23
    ACCEPT-INTENSITY keyword, RUN-ATTR record, 10-23
    ACCEPT-PROMPT-CHAR keyword, RUN-ATTR record, 10-24
    ACCEPT-SUPPRESS-CONVERSION keyword, COMPILER-OPTIONS record, 10-6
    B keyword, RUN-OPTION record, 10-33
    BCOLOR keyword, TERM-ATTR record, 10-36, 10-40
    BEEP keyword, RUN-ATTR record, 10-24
    BLINK keyword, RUN-ATTR record, 10-24
    CHARACTER-TIMEOUT keyword, TERM-ATTR record, 10-36
    COLUMNS keyword, TERM-ATTR record, 10-37
    FCOLOR keyword, TERM-ATTR record, 10-39, 10-40
    M keyword, RUN-OPTION record, 10-34
    REDRAW-ON-CALL-SYSTEM keyword, TERM-ATTR record, 10-39
    REVERSE keyword, RUN-ATTR record, 10-25
    ROWS keyword, TERM-ATTR record, 10-39

ACCEPT statement, Terminal I-O
configuration *(Cont.)*
RUN-OPTION record, 10-33
SCREEN-CONTENT-OPTIMIZE keyword, TERM-ATTR record, 10-40
SUPPRESS-NULLS keyword, TERM-ATTR record, 10-40
TAB keyword, RUN-ATTR record, 10-26
TERM-INPUT record, 10-41
TERM-INTERFACE record, 10-49
TERM-UNIT record, 10-49
examples, default configuration files, 10-51
UNDERLINE keyword, RUN-ATTR record, 10-26
USE-COLOR keyword, TERM-ATTR record, 10-40
CONTROL phrase, 8-11
BCOLOR keyword, 2-21, 3-31, 8-12, 8-24, 10-40
valid color names, 8-13
FCOLOR keyword, 2-21, 3-31, 8-12, 8-24, 10-40
valid color names, 8-13
GRAPHICS keyword, 2-21, 3-41, 8-13, 8-17
MASK keyword, xlii, 8-2, 8-3, 8-14
PROMPT keyword, xlvii, 8-18
REPAINT-SCREEN keyword, 8-18, D-23
SCREEN-COLUMNS keyword, 8-18
TAB keyword, 8-17
CONVERT phrase, 2-23, 2-25
CURSOR phrase, 2-23, 8-17
ECHO phrase, 2-23
ERASE phrase, 8-19
HIGH phrase, 8-17, 8-19
LOW phrase, 8-17, 8-19
OFF phrase, 8-17, 8-20
ON EXCEPTION phrase, 2-22–2-24, 8-5, 8-21
PROMPT phrase, 8-1, 8-3, 8-17
REVERSE phrase, 8-20
SECURE phrase, 8-17, 8-20
ACCEPT statement, Terminal I-O *(Cont.)*
SIZE phrase, 2-23, 2-25, 8-17, 8-20
TAB phrase, 8-17
TIME phrase. *See* BEFORE TIME phrase
UPDATE phrase, 8-1
ACCEPT-FIELD-FROM-SCREEN keyword, RUN-ATTR configuration record, 8-1, 10-23
ACCEPT-INTENSITY keyword, RUN-ATTR configuration record, 10-23
ACCEPT-PROMPT-CHAR keyword, RUN-ATTR configuration record, 10-24
ACCEPT-SUPPRESS-CONVERSION keyword, COMPILER-OPTIONS configuration record, 10-6
ACTION keyword, TERM-INPUT configuration record, 10-41
ADVANCING phrase
SEND statement, 8-69
WRITE statement (sequential I-O), 8-45
Allocation map listing, 6-18, 6-22, 10-12
ALLOCATION-INCREMENT keyword, RUN-INDEX-FILES configuration record, 10-31
ALLOCATION-MAP value, LISTING-ATTRIBUTES keyword, 6-22, 10-12
ALLOW-EXTENDED-CHARS-IN-FILENAMES keyword, RUN-FILES-ATTR configuration record, 10-26
Alphabet-name, user-defined word type, 6-22
analysis program. *See* Instrumentation
ANSI insertion mode
field editing, 10-45
RESET-ANSI-INSERTION value, 10-46
SET-ANSI-INSERTION value, 10-47
TOGGLE-ANSI-INSERTION value, 10-48
Argument passing, 7-5
ASCII, translation, J-1–J-5
character abbreviations, J-15
ATOMIC-TRANSFER-SIZE keyword, RUN-INDEX-FILES configuration record, 10-31
Attach Configuration utility (rmattach), xlv, 10-2, G-39
AUTO-LINE-FEED keyword, PRINT-ATTR configuration record, 10-21

B

B (Breakpoint) Command, Debug option, 9-21
B Compile Command Option, 6-8, 10-15
B keyword, RUN-OPTION configuration record, 10-33
B Runtime Command Option, 7-4, 8-20, 10-33
Backspace key, 8-3
BACKSPACE value, ACTION keyword, 10-41, 10-45
BCOLOR keyword
  CONTROL phrase, ACCEPT and DISPLAY statements, 2-21, 3-31, 8-12, 8-24, 10-40
  TERM-ATTR configuration record, 10-36
BEEP keyword
  CONTROL phrase, DISPLAY statement, 8-24
  RUN-ATTR configuration record, 10-24
BEEP phrase
  ACCEPT and DISPLAY statements, 10-24
  DISPLAY statement, 8-23
BEFORE TIME phrase, ACCEPT statement, 8-21
  CHARACTER-TIMEOUT keyword, TERM-ATTR configuration record, 10-36
BELL phrase. *See* BEEP phrase
Binary allocation, 10-6, 10-9, C-18, C-21
Binary sequential files
  configuring, 10-15, 10-35
  record delimiting technique, 6-8, 8-42
BINARY-ALLOCATION keyword, COMPILER-OPTIONS configuration record, 10-6, C-18, C-21, F-6
BINARY-ALLOCATION-SIGNED keyword, COMPILER-OPTIONS configuration record, 10-9, C-18
BLINK keyword
  CONTROL phrase, DISPLAY statement, 8-24
  RUN-ATTR configuration record, 10-24
BLINK phrase
  ACCEPT and DISPLAY statements, 10-24
  DISPLAY statement, 8-23
Blinking attribute, 2-20, 8-23
BLOCK CONTAINS clause, file description entry, xlvii, 8-42, 8-48, 8-53, 8-56
Block size, 10-26
  indexed files, xlvii, 8-53, 8-56
  relative files, 8-48
  sequential files, 8-42
BLOCK-SIZE keyword
  RUN-FILES-ATTR configuration record, 10-26
  RUN-INDEX-FILES configuration record, 10-31
  RUN-REL-FILES configuration record, 10-34
  RUN-SEQ-FILES configuration record, 10-34
Boolean, 2-10, 2-12, 2-19–2-20, 3-17
Bourne Shell script, xlvii, D-1
BPS keyword, TERM-UNIT configuration record, 10-49
Btrieve MicroKernel Database Engine (MKDE). *See* Btrieve, system considerations for
Btrieve, system considerations for, xliv, 4-1
  C$BTRV subprogram, xxviii, F-3
  components
    Btrieve MicroKernel Database Engine (MKDE), 4-4, 4-5
    configuration and installation, 4-7
    limitations with RM/COBOL indexed files, 4-19
    types of
      client-based, 4-4
      server-based, 4-4
    Btrieve requester for Windows NT/Windows 95/Windows 98, 4-4, 4-5
    NetWare, 4-4
    RM/COBOL development system, 4-4, 4-5
    RM/COBOL runtime system, 4-4, 4-5
    RM/COBOL-to-Btrieve Adapter (rmbtrv32) program, xliv, 4-1, 4-4, 4-5, 4-7, 10-20
  dynamic link libraries, 4-5, 4-18
  file management system, RM/COBOL, 4-6
  files
    split keys, 4-7
    system considerations, 4-7
    versus RM/COBOL indexed file performance, 4-8

Btrieve, system considerations for *(Cont.)*
limitations with RM/COBOL indexed files, 4-19
local area networks (LANs), 4-1, 4-4, 4-9
software, required, 3-2, 4-4
starting, 4-18
Buffer pool, 6-43, 8-40, 8-49, 8-54, 8-60, 10-26
Buffer size, with ACCEPT and DISPLAY statements, 2-23, 7-4, 8-20
BUFFER-POOL-SIZE keyword, RUN-FILES-ATTR configuration record, 6-43, 8-40, 8-60, 10-26, A-7, A-28, G-34

C

C (Clear) Command, Debug option, 9-22
C (or assembly) language subprograms, D-5, D-12, D-19–D-20
initial entry flag, D-14
C Compile Command Option, 6-9, 6-20, 10-13
C entry points for COBOL functions
RmForget(int y1, int x1, int y2, int x2), D-23
RmRefreshCwd(), D-23
RmRepaintScreen(), D-23
C Runtime Command Option, 7-3, 10-1, A-38
C$BitMap subprogram, F-3
C$BTRV subprogram, xxviii, F-3
C$CARG subprogram, 10-8, F-5
C$Century subprogram, xlvi, F-7
C$ClearDevelopmentMode subprogram, xxvii, F-7
C$Delay subprogram, xxvii, F-8
C$FORGET subprogram, D-23, F-8
C$GetEnv subprogram, xxvii, F-9
C$GetLastFileName subprogram, xxvii, F-10
C$GetLastFileOp subprogram, xxvii, F-10
C$GetRMInfo subprogram, xxvii, F-11
C$GetSyn subprogram, xxvii, F-13
C$GetSysInfo subprogram, xxvii, F-14
C$GUICFG subprogram, xliv, 3-19–3-28, F-16
C$MBar subprogram, 3-22, 3-34, 3-42, F-17
C$MemoryAllocate subprogram, xxvii, F-18
C$MemoryDeallocate subprogram, xxvii, F-19
C$NARG subprogram, F-19
C$OSLockInfo subprogram, F-20
C$PlaySound subprogram, xxvii, E-44, F-21
C$RBMenu subprogram, xliv, 3-36, 3-43, F-22
C$RERR subprogram, xlvi, F-22
C$SBar subprogram, 3-27, 3-42, F-25
C$SCRD subprogram, 10-8, F-26
C$SCWR subprogram, F-27
C$SetDevelopmentMode subprogram, xxviii, F-33
C$SetEnv subprogram, xxvii, F-34
C$SetSyn subprogram, xxvii, F-34, F-35
C$ShowArgs subprogram, xxviii, F-36
C$TBar subprogram, 3-22, 3-32, 3-43, F-37
C$TBarEn subprogram, xliv, F-38
C$TBarSeq subprogram, xliv, 3-37, F-39
C$Title subprogram, 3-28, 3-43, F-39
C$WRU subprogram, F-40
CALL "SYSTEM", 3-45, 6-44, 7-8, D-20, F-41. *See* also SYSTEM subprogram
CALL statement, 8-33–8-38, 10-8
external objects, 8-36
initial entry flag, D-14
linking C (or assembly) language subprograms into the runtime system, D-12
printing from Windows, E-9
subprogram loading, 8-34
Called program summary, 6-18, 6-27
Calling non-COBOL programs from RM/COBOL programs, D-12
CCD. *See* Communications Descriptor
Cd-name, user-defined word type, 6-24
Character sequence specifications, 10-42
CHARACTERS clause, 8-43, 8-49, 8-53
CHARACTER-TIMEOUT keyword
BEFORE TIME phrase, ACCEPT statement, 8-21
TERM-ATTR configuration record, 10-36
CHARACTER-WIDTH keyword, TERM-UNIT configuration record, 10-50
Class-name, user-defined word type, 6-22
CLOSE statement
REEL and UNIT phrases (sequential I-O), 8-45
WITH NO REWIND phrase (sequential I-O), 8-45

COBOL-74 keyword, COMPILER-OPTIONS configuration record, 10-9
Cobol-CGI, 1-3
Cobol-RPC, 1-3
Cobol-WOW, 1-3
CODE keyword, TERM-INPUT configuration record, 10-41
CodeBridge, xxvi, 1-2, F-4. *See also* CodeBridge documentation
CODE-SET clause, 8-37, 8-44, 8-49, 8-54
Code-set translation tables, J-1
  character abbreviations, J-15
CodeWatch, xxvi, 1-2, 3-4, 6-13. *See also* CodeWatch documentation
COLLATING SEQUENCE clause, 8-37, 8-54, 8-55
Color terminal support, 8-24
  TERM-ATTR configuration record
    BCOLOR keyword, 10-36
    FCOLOR keyword, 10-39
    USE-COLOR keyword, 10-40
  with ACCEPT and DISPLAY statements, 2-21, 3-31, 8-11–8-13
  with pop-up windows, 2-21, 8-24
COLUMN and COL phrases. *See* POSITION phrase
COLUMNS keyword
  PRINT-ATTR configuration record, 10-21
  TERM-ATTR configuration record, 10-37
Combine Program utility (rmpgmcom), 3-4, 6-3, 6-13, 10-11, 10-16, G-9
Combined sign
  leading, C-10
  trailing, C-9
Comma, EDIT-COMMA keyword, 10-24
Commands
  compile, 6-3
  debug, 9-2
  runtime, 7-1
Commit File function, 10-27
Communications descriptor (CCD), 8-68
COMP. *See* COMPUTATIONAL
Compatibility between RM/COBOL (74) 2.*n* and RM/COBOL-85, 6-14, 6-16
Compatibility with earlier version of RM/COBOL, object versions, H-1
Compilation. *See also* Compile Command; Compiler
  Compile Command, 6-3
  libraries, 6-3
  listings, 6-18
  process, 6-1
  system files
    listing, 6-2, 6-18, 10-19, 10-20
    object, 6-2
    source, 6-2
Compile Command, 6-3
  error marker and diagnostics, 6-31
  error recovery, 6-32
  error threading, 6-33
  format of, 6-4
  invoking, 6-1
  messages
    banner, 6-33
    compiler configuration errors, 6-35, 6-42
    compiler exit codes, 6-44
    compiler status, 6-34
  options, 6-5
    allocation map (A), 6-9, 6-22, 9-1, 9-9, 10-12
    alternate usage of COMP data items (U), 6-7, 10-10
    and the negation character ~, 6-5
    ANSI COBOL 1974 or 1985 semantics (7), 6-14, 10-9, F-22
    binary sequential files (B), 6-8, 10-15
    compiler configuration (G), 6-6, 10-1, A-38
    compiler configuration supplement (H), 6-6, 10-1, A-38
    compiler memory (W), 6-7, 10-16
    create smaller COBOL object files (Q), 6-13, 9-1, 11-3, A-2, F-11, F-40
    cross reference map (X), 6-11, 6-28, 10-13
    language element flagging (F), 6-15, 10-12, I-2, I-8, I-9

Compile Command
options *(Cont.)*
line sequential files (V), 6-8, 6-16, 10-15
listing file on disk (L), 6-9, 6-18, 6-33, 10-13, 10-14, 11-1
output the debug line table (Y), 6-13, 9-1, 9-5, 9-6, 10-11, G-9, H-10
output the symbol table (Y), xxxiii, 6-13, 9-1, 9-5, 9-6, 10-11, 10-16, G-9, H-10
print listing (P), 6-10, 6-18, 6-33, 6-41, 10-13
RM/COBOL 2.*n* programs (2), 6-14, 6-16, 10-15
separate sign in the absence of a SIGN clause (S), 6-7, 6-16, 10-15, C-7, C-9
sequentially numbered listing (R), 6-10, 10-15
specified in configuration files, 6-5
specified on the compile command line, 6-5
specify object file pathname (O), 6-12, 10-14
specify the RM/COBOL object version (Z), 6-14, H-2
suppress automatic conversion in certain ACCEPT and DISPLAY statements (M), 2-23, 6-11, 10-6
suppress banner message and terminal error listing (K), 6-7, 6-18, 10-13
suppress copied text (C), 6-9, 6-20, 10-13
suppress object program (N), 6-11
suppress source program listing (E), 6-9, 6-20, 10-13
with debugging mode (D), 6-15, 10-11
write a copy of the listing to a standard output device (T), 6-11, 6-18, 6-33, 6-41, 10-13
samples of valid and invalid, 6-17
types of options
compiler configuration, 6-6
data item, 6-7
file type, 6-8
listing, 6-8
object program, 6-11
source program, 6-15
Compiler. *See also* Compile Command; Compilation
banner message, Compile Command, 6-33
configuration errors, 6-35, 6-42
configuration options, Compile Command, 6-6
error marker and diagnostic format, 6-31
error recovery messages, 6-32
error threading facility, 6-33
exit codes, 6-44
initialization errors, 6-43
input/output errors, 6-35
overlay file, 2-5, 3-12
status messages, 6-34
syntax errors, 6-31
Compiler configuration options, Compile Command, 6-6
COMPILER-OPTIONS configuration record, 10-6
ACCEPT-SUPPRESS-CONVERSION keyword, 10-6
BINARY-ALLOCATION keyword, 10-6, C-18, C-21, F-6
BINARY-ALLOCATION-SIGNED keyword, 10-9, C-18
COBOL-74 keyword, 10-9
COMPUTATIONAL-AS-BINARY keyword, 10-9
COMPUTATIONAL-TYPE keyword, 10-10, C-12, C-13
COMPUTATIONAL-VERSION keyword, 10-10, C-13, C-17
DEBUG keyword, 10-11
DEBUG-TABLE-OUTPUT keyword, xxxiii, 10-11
DERESERVE keyword, 10-12
FLAGGING keyword, 10-12
LISTING-ATTRIBUTES keyword, 6-22, 6-28, 10-12
LISTING-DATE-FORMAT keyword, 10-13
LISTING-DATE-SEPARATOR keyword, 10-14
LISTING-PATHNAME keyword, 10-14

COMPILER-OPTIONS configuration record *(Cont.)*
LISTING-TIME-SEPARATOR keyword, 10-14
OBJECT-PATHNAME keyword, 10-14
OBJECT-VERSION keyword, 10-14
RESEQUENCE-LINE-NUMBERS keyword, 10-14
RMCOBOL-2 keyword, 10-15
SEPARATE-SIGN keyword, 10-15
SEQUENTIAL-FILE-TYPE keyword, 10-15
SUPPRESS-NUMERIC-OPTIMIZATION keyword, 10-15
SYMBOL-TABLE-OUTPUT keyword, 10-16
WORKSPACE-SIZE keyword, 10-16
Compressed files, UNIX installation, 2-2
Compression. *See* DATA-COMPRESSION keyword; KEY-COMPRESSION keyword
COMPUTATIONAL data format, 6-16
type option, Compile Command, 6-7
COMPUTATIONAL-1 data format, 6-16
COMPUTATIONAL-3 data format, 6-16
COMPUTATIONAL-AS-BINARY keyword, COMPILER-OPTIONS configuration record, 10-9
COMPUTATIONAL-TYPE keyword, COMPILER-OPTIONS configuration record, 10-10, C-12, C-13
COMPUTATIONAL-VERSION keyword, COMPILER-OPTIONS configuration record, 10-10, C-13, C-17
Condition-name, user-defined word type, 6-24
config.sys BUFFERS command, 8-60
config.sys FILES command, 8-60
Configuration errors, 6-35, 6-42, 10-3, A-1, A-37
Configuration file options, 6-5
negating, 6-5
Configuration file structure, 10-1
termcap default configuration example, 10-51
terminfo default configuration example, 10-54
Windows default configuration example, 10-57
with the Compile Command options, 6-5
Configuration files
ini2reg utility, xliii, 3-4, 3-16, G-40
recover1.ini, 3-16
rmcobol.ini, 3-16
runcobol.ini, 3-16
Configuration records, 6-5, 10-3
attached configuration file, xlv, 10-2, G-39
built-in configuration file, xlv, 10-2, D-5
COMPILER-OPTIONS, 10-6
DEFINE-DEVICE, 10-16
errors, 10-3
EXTENSION-NAMES, 10-19
EXTERNAL-ACCESS-METHOD, xlvii, 4-9, 10-20
list of, 10-3
PRINT-ATTR, 10-20
RUN-ATTR, 10-23
RUN-FILES-ATTR, xlii, 10-26
RUN-INDEX-FILES, 4-16, 10-31
RUN-OPTION, 10-33
RUN-REL-FILES, xlii, 10-34
RUN-SEQ-FILES, xlii, 10-34
RUN-SORT, 10-36
TERM-ATTR, 10-36
TERM-INPUT, 10-41
TERM-INTERFACE, 10-49
TERM-UNIT, 10-49
Constant-name, user-defined word type, 6-27
Control characters, DEFINE-CONTROL-CHARACTERS keyword, 10-50
CONTROL phrase
ACCEPT and DISPLAY statements, 8-11
BCOLOR keyword, 8-12
DISPLAY statement, 8-24, 8-26
FCOLOR keyword, 8-12
GRAPHICS keyword, 8-13, 8-17
MASK keyword, 8-2, 8-3, 8-14
PASS-THRU keyword, 8-17
PROMPT keyword, 8-18
REPAINT-SCREEN keyword, 8-18
SCREEN-COLUMNS keyword, 8-18
TAB keyword, 8-17
terminfo strings, 2-21

CONTROL-BREAK value, ACTION keyword, 10-41, 10-45
Conventions and symbols, xxxvii
Conversion. *See* ACCEPT-SUPPRESS-CONVERSION keyword; CONVERT phrase
CONVERT phrase, ACCEPT and DISPLAY statements, 2-23, 2-25
Copy file, default extension, 10-19
Copy files, printing from Windows
  DEVCAPS.CPY, E-39, E-44, E-45
  list of, E-44
  LOGFONT.CPY, E-29, E-44, E-47
  PRINTDLG.CPY, E-17, E-18, E-38, E-44, E-52
  PRINTINF.CPY, E-41, E-44, E-62
  TXTMTRIC.CPY, E-26, E-44, E-65
  WINDEFS.CPY, E-7, E-8, E-23, E-31, E-44, E-69
COPY keyword, EXTENSION-NAMES configuration record, 10-19
COPY statement, 8-31
  listing, 6-9, 6-20
CREATE-FILES keyword, EXTERNAL-ACCESS-METHOD configuration record, 10-20
Creating pop-up windows, 8-22
Cross reference listing, 6-18, 6-28, 10-13
CROSS-REFERENCE value, LISTING-ATTRIBUTES keyword, 6-28, 10-13
CURRENCY SIGN clause, 10-25, C-2, I-3
Currency symbol, EDIT-CURRENCY-SYMBOL keyword, 10-24, 10-25. *See also* Dollar sign
CURSOR phrase, ACCEPT statement, 2-23, 8-17
Cursor positioning, 2-9, 3-43
Cursor types, 2-9, 3-43
customiz utility, xlvii, 10-2, D-1, D-6
Customizing RM/COBOL for UNIX, D-1
  C entry points for COBOL functions, D-23
  installing the customized product, D-11
  Makefile, xlvii, D-1, D-5, D-6, D-9
  relinking the same product, D-5
  terminal interfaces, 2-9
  using
    customiz utility, xlvii, D-1
      C language subprograms (MCBA and Flexgen), D-4
      Enterprise CodeBench, 1-3, D-4
      examples, D-6
      Pop-Up Window Manager, D-3
      RM/InfoExpress, 1-3, 10-20, D-2
      RM/plusDB, 10-20, D-3
      terminfo or termcap terminal interfaces, D-2
      VanGui Interface Builder, 1-3, D-5
    other customizations
      adding a Message Control System (MCS), 8-65, D-5
      adding C (or assembly) language subprograms, D-5, D-12
        accessing C subprograms, D-18
        C subprogram examples, D-20
        calling sequence, D-12
        debugging C (or assembly) language subprograms, D-20
        preparing C (or assembly) subprograms, D-19
        restrictions to C (or assembly) language subprograms, D-19
      built-in configuration file, xlv, 10-2, D-5

D

D (Display) Command, Debug option, 9-23
D Compile Command Option, 6-15, 10-11
D Runtime Command Option, 7-3, 9-1
Data address development, 9-6
Data characters, 10-37
Data compression, 8-63
Data item options, Compile Command, 6-7

DATA keyword, TERM-INPUT configuration record, 10-42
DATA-CHARACTERS keyword, TERM-ATTR configuration record, 10-37
DATA-COMPRESSION keyword, RUN-INDEX-FILES configuration record, 10-31
Data-name, user-defined word type, 6-24
Date
  listing format configuration, 10-13
  listing separator configuration, 10-14
DBCS characters, xlii, 8-15, 10-37
DBCS-CHARACTERS keyword, TERM-ATTR configuration record, xlii, 10-37
Debug
  command summary, 9-2
  commands
    clear breakpoints (C), 9-22
    clear data traps (U), 9-40
    display set breakpoints (B), 9-21
    display the value of a data item (D), 9-23. *See also* Data address development
    end a Debug session (E), 9-27
    modify the value of a specified data item (M), 9-28
    resume program execution at a specified location (R), 9-34, A-2
    set a breakpoint and clear once satisfied (A), 9-20
    set a breakpoint and do not clear once satisfied (B), 9-21
    specify a screen line for Debug displays (L), 9-28
    step through individual statements (S), 9-35
    stop program execution (Q), 9-33
    trap a data item when its value changes (T), 9-36
  data address development, 9-6
    address-size format, 9-9
    alias format, 9-11
    identifier format, 9-6
  debug references
    in the data item, 9-5
    in the program area, 9-5
Debug *(Cont.)*
  error messages, 9-13
  general concepts, 9-2
    breakpoints, 9-3
    data types, 9-4
    debug values, 9-4
    execution counts, 9-3
    intraline numbers, 9-3, F-11, F-40
    line numbers, 9-3
    statements, 9-2
    stepping, 9-3
    traps, 9-3
  invoking, 9-1
  output debugging information (Y Compile Command Option), xxxiii, 6-13, G-9
  regaining control, 9-11
  screen positions, 9-5
DEBUG keyword, COMPILER-OPTIONS configuration record, 10-11
Debugging, symbolic
  configuration, 10-16
  Y Compile Command Option, xxxiii, 6-13, G-9
DEBUG-TABLE-OUTPUT keyword, COMPILER-OPTIONS configuration record, xxxiii, 10-11
Decimal point, EDIT-DECIMAL keyword, 10-25
DEFAULT-FILE-VERSION-NUMBER keyword, RUN-INDEX-FILES configuration record, 10-31
DEFAULT-TYPE keyword, RUN-SEQ-FILES configuration record, 10-35
Define Indexed File utility (rmdefinx), 3-4, 8-50, 8-56, 8-64, 8-65, A-31, G-19
DEFINE-CONTROL-CHARACTERS keyword, TERM-UNIT configuration record, 10-50
DEFINE-DEVICE configuration record, 10-16
  DEVICE keyword, 10-16
  ESCAPE-SEQUENCES keyword, 3-25, 10-17, E-38
  PATH keyword, 10-17
  PIPE keyword, 10-17
  RAW keyword, 3-26, 10-17, E-43
  Windows printers, 10-18

Delete Character key, 8-3
DELETE-CHARACTER value, ACTION keyword, 10-41, 10-45
DERESERVE keyword, COMPILER-OPTIONS configuration record, 10-12
DESTINATION TABLE OCCURS clause, 8-69
DEVICE keyword, DEFINE-DEVICE configuration record, 10-16
Device support, 8-46
  named pipe, 8-47
  printer, 8-46
  tape, 8-47
DEVICE-SLEWING-RESERVE keyword, RUN-SEQ-FILES configuration record, 10-35
Diagnostic undermark, 6-31
Directory search sequences
  compiler, 6-4, 6-10, 6-12, 6-35, 6-41, 8-32
    NetWare search paths, 3-13
    under UNIX, 2-4
    under Windows, 3-11
  recover1 utility, G-26
  runtime, 8-35
    NetWare search paths, 3-13
    under UNIX, 2-4
    under Windows, 3-11
  synonyms, setting properties, 3-11, 3-29
  using Btrieve files, 4-11
DISABLE statement, 8-65, 8-69
DISABLE-COMMIT-FILE keyword, RUN-FILES-ATTR configuration record, 10-27
DISPLAY statement. *See also* ACCEPT and DISPLAY statements, operating-system specific information; ACCEPT statement, Terminal I-O
  BEEP phrase, 8-23
  BLINK phrase, 8-23
  configuration
    B keyword, RUN-OPTION record, 10-33
    BCOLOR keyword, TERM-ATTR record, 10-36, 10-40
    BEEP keyword, RUN-ATTR record, 10-24
DISPLAY statement
  configuration *(Cont.)*
    BLINK keyword, RUN-ATTR record, 10-24
    COLUMNS keyword, TERM-ATTR record, 10-37
    DISPLAY-INTENSITY keyword, RUN-ATTR record, 10-24
    FCOLOR keyword, TERM-ATTR record, 10-39, 10-40
    K keyword, RUN-OPTION record, 10-33
    M keyword, RUN-OPTION record, 10-34
    PASS-THRU-ESCAPE keyword, TERM-ATTR record, 10-39
    REDRAW-ON-CALL-SYSTEM keyword, TERM-ATTR record, 10-39
    REVERSE keyword, RUN-ATTR record, 10-25
    ROWS keyword, TERM-ATTR record, 10-39
    SCREEN-CONTENT-OPTIMIZE keyword, TERM-ATTR record, 10-40
    SUPPRESS-NULLS keyword, TERM-ATTR record, 10-40
    TERM-INPUT record, 10-41
    TERM-INTERFACE record, 10-49
    TERM-UNIT record, 10-49
      examples, default configuration files, 10-51
    UNDERLINE keyword, RUN-ATTR record, 10-26
    USE-COLOR keyword, TERM-ATTR record, 10-40
  CONTROL phrase, 8-11, 8-24
    BCOLOR keyword, 2-21, 3-31, 8-12, 8-24, 10-40
      valid color names, 8-13
    BEEP keyword, 8-24
    BLINK keyword, 8-24
    ERASE keyword, 8-24
    FCOLOR keyword, 2-21, 3-31, 8-12, 8-24, 10-40
      valid color names, 8-13

DISPLAY statement
CONTROL phrase *(Cont.)*
GRAPHICS keyword, 2-21, 3-41, 8-13, 8-17
HIGH keyword, 8-24
LOW keyword, 8-24
MASK keyword, xlii, 8-14
NO BEEP keyword, 8-24
NO BLINK keyword, 8-24
NO ERASE keyword, 8-24
NO REVERSE keyword, 8-24
PASS-THRU keyword, 8-17
REPAINT-SCREEN keyword, 8-18, D-23
REVERSE keyword, 8-24
SCREEN-COLUMNS keyword, 8-18
CONVERT phrase, 2-23, 2-25
ERASE phrase, 8-19, 8-24
HIGH phrase, 8-17, 8-19, 8-25
LINE phrase, 8-25
LOW phrase, 8-17, 8-19, 8-25
pop-up windows, creating, 8-22
POSITION phrase, 8-25
REVERSE phrase, 8-20, 8-25
SIZE phrase, 2-23, 2-25, 8-17, 8-20
UNIT phrase, 8-26
DISPLAY-INTENSITY keyword, RUN-ATTR configuration record, 10-24
DLL. *See* Dynamic link libraries
Dollar sign, EDIT-DOLLAR keyword, 10-25. *See also* Currency symbol
Double-byte character set characters, xlii, 8-15, 10-37
DUPLICATES phrase, RECORD KEY clause, H-8
Dynamic link libraries, 3-12, 8-35
16-bit and 32-bit implementations, xliii
Btrieve requester for Windows, 4-5
RM/COBOL-to-Btrieve Adapter (rmbtrv32) program, 4-18

E

E (End) Command, Debug option, 9-27
E Compile Command Option, 6-9, 6-20, 10-13
EBCDIC code-name, translation, J-5–J-14
character abbreviations, J-15
ECHO phrase, ACCEPT statement, 2-23
Edit keys
backspace, 8-3
delete character, 8-3
erase entire, 8-4
erase remainder, 8-4
insert character, 8-4
left arrow, 8-3
masked input processing, 8-3
right arrow, 8-3
EDIT-COMMA keyword, RUN-ATTR configuration record, 10-24
EDIT-CURRENCY-SYMBOL keyword, RUN-ATTR configuration record, 10-24
EDIT-DECIMAL keyword, RUN-ATTR configuration record, 10-25
EDIT-DOLLAR keyword, RUN-ATTR configuration record, 10-25
ENABLE statement, 8-65, 8-69
ENABLE-LOGGING keyword, RUN-OPTION configuration record, 10-33
ENABLE-OLD-DOS-FILENAME-HANDLING keyword, RUN-FILES-ATTR configuration record, 10-27
Enhancements to RM/COBOL
version 6.5, xliii
version 6.6, xli
version 7, xxv
Enterprise CodeBench, 1-3, D-4
Environment variables
for NetWare search paths, 3-13
HOME, 2-3
PATH, 2-4, 3-12, 6-35, 6-41, 8-36, G-26
resolution of program names, xlvii
RMPATH, 2-4, 3-11–3-13, 3-30, 8-32
RUNPATH, 2-4, 3-11–3-13, 3-30, 4-10, 8-35
TERM, 2-11, 8-18
TERMCAP, 2-10
TERMINFO, 2-11

Erase Entire key, 8-4
ERASE EOL and ERASE EOS. *See* ERASE phrase
ERASE keyword, CONTROL phrase, DISPLAY statement, 8-24
ERASE phrase
  ACCEPT and DISPLAY statements, 8-19
  DISPLAY statement, 8-24
Erase Remainder key, 8-4
ERASE-ENTIRE value, ACTION keyword, 10-41, 10-46
ERASE-REMAINDER value, ACTION keyword, 10-41, 10-46
Error classes, 6-32
Error messages. *See* Messages
ERROR-MESSAGE-DESTINATION keyword, RUN-ATTR configuration record, 2-25
ERROR-ONLY-LIST value, LISTING-ATTRIBUTES keyword, 10-13
Escape. *See* SCREEN-ESCAPE value
Escape sequences, RM/COBOL-specific, 3-25, 10-17, E-43, E-85
  raw mode-byte I/O, E-43, E-85
ESCAPE-SEQUENCES keyword, DEFINE-DEVICE configuration record, 3-25, 10-17, E-38
ESCAPE-TO-COMMAND value, ACTION keyword, 10-41, 10-46
ESCAPE-TO-OS value, ACTION keyword, 10-41, 10-46
Exception codes, keys used, 8-5
EXCEPTION keyword, TERM-INPUT configuration record, 10-42
Exit codes
  compiler, 6-44
  program, 7-8, 8-33
EXPANDED-PATH-SEARCH keyword, RUN-FILES-ATTR configuration record, 2-3, 3-10, 10-27
EXTEND phrase, 6-16
EXTENSION-NAMES configuration record, 10-19. *See also* Extensions
  COPY keyword, 10-19
  LISTING keyword, 10-19
  OBJECT keyword, 10-19
  SOURCE keyword, 10-19
Extensions
  configuring, 10-19
  defaults, 1-4, 3-10, 6-2, 7-1, 8-32, 10-19
  resolution of program names, xlvii
  Windows 95 and Windows NT, xliii
EXTERNAL clause, 8-36
External objects
  data records, 8-37
  file connectors, 8-37
  indexes, 8-38
EXTERNAL-ACCESS-METHOD configuration record, xlvii, 4-9, 10-20
  CREATE-FILES keyword, 10-20
  NAME keyword, 10-20
  OPTIONS keyword, 10-20

F

F Compile Command Option, 6-15, 10-12, I-2, I-8, I-9
FATAL-RECORD-LOCK-TIMEOUT keyword, RUN-FILES-ATTR configuration record, 10-27
FCOLOR keyword
  CONTROL phrase, ACCEPT and DISPLAY statements, 2-21, 3-31, 8-12, 8-24, 10-40
  TERM-ATTR configuration record, 10-39
Features. *See* Enhancements to RM/COBOL
Field editing actions, 10-45
Field termination codes, 8-5
FIELD-HOME value, ACTION keyword, 10-41, 10-46
File access names, 2-5, 3-13
  locating RM/COBOL files
    under UNIX, 2-3
    under Windows, 3-10, 3-29
  printer support, 2-7
  tape support, 2-7

File allocation, in indexed files, 8-56
File buffering, 6-43, 8-40, 8-49, 8-54, 8-60, 10-26
File control entry
  CODE-SET clause, 8-37, 8-49, 8-54
  COLLATING SEQUENCE clause, 8-37, 8-55
  RECORD KEY clause, H-8
File description entry
  BLOCK CONTAINS clause, 8-42, 8-48, 8-53
  CODE-SET clause, 8-37, 8-44, 8-49, 8-54
  LINAGE clause, 8-43
  RECORD clause, 8-42, 8-48, 8-52
File lock facility, 2-8
File lock limit, xlii, 10-28, G-16
File management system, RM/COBOL, 4-6
File naming conventions, RM/COBOL, 1-4, 10-19
File organization
  indexed, 8-50
  relative, 8-47
  sequential, 8-41
File performance, indexed files, 8-59
File sharing, 8-38
FILE STATUS clause, file control entry, 10-27, 10-30
File status data item
  indexed file, 8-55
  relative file, 8-50
  sequential file, 8-44
File type options, Compile Command, 6-8
File types and structure, 8-40
  indexed files, 8-50
    and Btrieve, 4-1, 4-4, 4-8
    BLOCK CONTAINS clause, 8-53, 8-62, 10-31, G-15, G-20
    block sizes, xlvii, 8-56
    CODE-SET clause, 8-54
    COLLATING SEQUENCE clause, 8-55
    data compression, 8-50, 8-63, 10-31, 10-32, G-15, G-20
    data recoverability, 8-51, 8-63, 10-32, G-16, G-20
File types and structure
  indexed files *(Cont.)*
    file allocation increment, 8-56, 10-31, G-16, G-20
    file size estimation, 8-56
    file version number, 8-56, 10-31, G-16, G-22
    RECORD clause, 8-52
    RESERVE clause, 8-54
    WITH NO LOCK phrase, 8-55
  relative files, 8-47
    BLOCK CONTAINS clause, 8-48
    CODE-SET clause, 8-49
    RECORD clause, 8-48
    RESERVE clause, 8-49
    WITH NO LOCK phrase, 8-49
  sequential files, 8-41
    ADVANCING *mnemonic-name* phrase, 8-45
    ADVANCING ZERO LINES phrase, 8-45
    binary sequential, 6-8, 8-42, 10-15, 10-35
    BLOCK CONTAINS clause, 8-42
    CODE-SET clause, 8-44
    device support, 8-46
    LINAGE clause, 8-43
    line sequential, 6-8, 8-41, 10-15, 10-35
    printer support, 8-46
    RECORD clause, 8-42
    REEL and UNIT phrases, 8-45
    RESERVE clause, 8-44
    REVERSED phrase, 8-44
    tape support, 8-47
    WITH NO LOCK phrase, 8-44
    WITH NO REWIND phrase, 8-45
File version number, in indexed files, xlii, 8-56, 8-64, 10-31, G-16, G-22
FILE-CONTROL-PARAGRAPH
  indexed file control entry, 8-54
  relative file control entry, 8-49
  sequential file control entry, 8-44
FILE-HANDLE-LIMIT keyword, RUN-FILES-ATTR configuration record, 10-27

FILE-LOCK-LIMIT keyword, RUN-FILES-ATTR configuration record, 10-28
Filename extension. *See* Extensions
File-name, user-defined word type, 6-24
FILE-PROCESS-COUNT keyword, RUN-FILES-ATTR configuration record, 10-28
Files
  copy, 10-19
  libraries, 6-3, 7-2
  listing, 6-2, 6-3, 6-18, 10-19
  locating of, 2-3, 3-10
  object, 6-2, 6-3, 7-1, 10-19
  source, 6-2, 6-3, 10-19
FILL character, 3-27
FLAGGING keyword, COMPILER-OPTIONS configuration record, 10-12
FORCE-CLOSED keyword, RUN-INDEX-FILES configuration record, 8-51, 10-31
FORCE-DATA keyword, RUN-INDEX-FILES configuration record, 8-52, 10-32
FORCE-DISK keyword, RUN-INDEX-FILES configuration record, 8-52, 10-32
FORCE-INDEX keyword, RUN-INDEX-FILES configuration record, 8-52, 10-32
FORCE-USER-MODE keyword, RUN-FILES-ATTR configuration record, 3-45, 10-28
FORM-FEED-AVAILABLE keyword, PRINT-ATTR configuration record, 10-21
FROM phrase, SEND statement, 8-69
FROM/UPON CONSOLE phrase, ACCEPT and DISPLAY statements, 2-22–2-25
Function key mapping, 2-9

G

G Compile Command Option, 6-6, 10-1, A-38
Generic exception keys, 10-48
Generic key name, field termination codes, 8-5
GRAPHICS keyword, CONTROL phrase, ACCEPT and DISPLAY statements, 2-21, 3-41, 8-13, 8-17
GUI keyword, TERM-INTERFACE configuration record, 10-49

H

H Compile Command Option, 6-6, 10-1, A-38
HIGH keyword, CONTROL phrase, DISPLAY statement, 8-24
HIGH phrase
  ACCEPT and DISPLAY statements, 8-17, 8-19
  DISPLAY statement, 8-25
High-intensity attribute, 2-20, 8-12, 8-25
HIGHLIGHT phrase. *See* HIGH phrase
Home. *See* SCREEN-HOME value
HOME environment variable, file locations, 2-3

I

I Runtime Command Option, 7-3, 11-1
Indexed File Conversion utilities (rmifca and rmifcb), G-4
Indexed file performance, 8-59
  altering size of indexed file blocks, 8-62
  controlling length of record keys, 8-62
  correct data recovery strategy, 8-63
  in-memory buffering, 8-60
  using key and data compression, 8-63
  using RM/COBOL facilities, 8-64
  with Btrieve, 4-1, 4-4, 4-8
Indexed File Recovery utility (recover1), xlii, xlvi, 2-5, 3-4, 3-12, 3-16, 3-18, 8-51, 8-64, 8-65, 10-31, A-13, A-31, G-23
  recover2, xlii, G-35
  recovery, xlii
Indexed File Unload utility (recover2). *See* Indexed File Recovery utility (recover1)
Indexed files, 8-40, 8-50. *See also* File types and structure
  and Btrieve, 4-1, 4-4, 4-8
  block sizes, xlvii, 8-56
Index-name, user-defined word type, 6-26
ini2reg utility, xliii, 3-4, 3-16, G-40
INITIAL clause, PROGRAM-ID paragraph, 8-34
Initial contents of a screen field, 8-1
Initial entry flag, D-14

Initialization File to Windows Registry Conversion utility (ini2reg), xliii, 3-4, 3-16, G-40
Input sequence specification, 10-44
Input/output control
  redirection of, 2-22, 8-1, 10-25
  standard error device, 2-25, 6-7, 10-25
  standard input device, 2-22, 10-25
  standard output device, 2-24–2-25, 6-11, 6-18, 6-33, 6-41, 10-13, 10-25, 10-39
Insert Character key, 8-4
INSERT-CHARACTER value, ACTION keyword, 10-41, 10-46
Insertion mode
  ANSI, 10-45
  RM, 10-45
  single-character, 10-45
Installation
  UNIX, 2-1–2-3
    system considerations, 2-3–2-25. *See also* Configuration records
    system requirements, 2-1
    system verification, 5-1
  Windows, 3-1–3-7
    registering the runtime, 3-5
    system considerations, xliv, 3-7–3-45. *See also* Configuration records
    system removal, 3-7
    system requirements, 3-1
    system verification, 5-3
Installing the utility programs, G-3
Instrumentation
  data analysis, 11-4
    ANALYSIS program, 11-4
      listing files processed by, 11-5
    suppression of, 11-7
  data collected, 11-2
    method of, 11-3
    sample data structure, 11-2
  invocation of, 11-1
Interactive Debugger. *See* Debug
INTERMEDIATE-FILES keyword, RUN-SORT configuration record, 10-36
Internal data formats
  nonnumeric data items, C-2
  numeric computational data items, C-5
    signed numeric COMPUTATIONAL, C-13
    signed numeric COMPUTATIONAL-1, C-14
    signed numeric COMPUTATIONAL-3, C-16
    signed numeric COMPUTATIONAL-4, C-21
    unsigned numeric COMPUTATIONAL, C-11
    unsigned numeric COMPUTATIONAL-3, C-15
    unsigned numeric COMPUTATIONAL-4, C-18
    unsigned numeric COMPUTATIONAL-6, C-24
  numeric DISPLAY data items, C-5
    signed numeric DISPLAY (LEADING SEPARATE), C-8
    signed numeric DISPLAY (LEADING), C-10
    signed numeric DISPLAY (TRAILING SEPARATE), C-7
    signed numeric DISPLAY (TRAILING), C-9
    unsigned numeric DISPLAY (NSU), C-6
Internal subprogram library, F-1

K

K Compile Command Option, 6-7, 6-18, 10-13
K keyword, RUN-OPTION configuration record, 10-33
K Runtime Command Option, 7-3, 10-33, A-41–A-42
KEEP-FLOPPY-OPEN keyword, RUN-FILES-ATTR configuration record, 10-28
Key compression, 8-63, 10-32
KEY phrase
  DISABLE statement, 8-69
  ENABLE statement, 8-69
KEY-COMPRESSION keyword, RUN-INDEX-FILES configuration record, 10-32
Keys
  cursor types, 2-9, 3-43
  defined, 8-2
  edit, 8-3
  generate field termination codes, 8-5

L

L (Line Display) Command, Debug option, 9-28
L Compile Command Option, 6-9, 6-18, 6-33, 10-13, 10-14, 11-1
L Runtime Command Option, 7-2, 7-6, 8-34, A-40, G-11
Language elements
  extensions, I-2
  obsolete, I-8
  subset, I-9
LANs. *See* Local area networks
LARGE-FILE-LOCK-LIMIT keyword, RUN-FILES-ATTR configuration record, xlii, 10-28, G-16
Left Arrow key, 8-3
LEFT-ARROW value, ACTION keyword, 10-41, 10-46
Libraries, 6-3, 7-2
  internal subprogram, F-1
Library files, 6-3, 7-2
  Table of Contents (TOC)
    rmmappgm utility, 3-4, G-12
    rmpgmcom utility, 3-4, 6-3, G-9
Library initialization, G-9
Limits and ranges
  RM/COBOL, B-1
  RM/COBOL indexed files and Btrieve MicroKernel Database Engine, 4-19
LINAGE clause, 8-43
LINAGE-COUNTER special-register, 10-8
LINAGE-INITIAL-FORM-POSITION keyword, PRINT-ATTR configuration record, 8-43, 10-21
LINAGE-PAGES-PER-PHYSICAL-PAGE keyword, PRINT-ATTR configuration record, 8-43, 10-22
Line draw characters, 2-20, 3-41, 8-13, 8-28
LINE phrase, DISPLAY statement, 8-25
Line sequential files
  configuring, 10-15, 10-35
  record delimiting technique, 6-8, 8-41
LINES keyword, PRINT-ATTR configuration record, 10-22
Listing, 6-18
  allocation map, 6-22, 10-12
    alphabet-names, symbolic-characters, mnemonic-names and class-names, 6-22
    as used by Debug, 9-10
    constant-names, 6-27
    data-names, condition-names, file-names and cd-names, 6-24
    index-names, 6-26
    split-key-names, 6-23
  called program summary, 6-27
  configuration, 10-12
  copy level indicator, 6-20
  cross reference listing, 6-28, 10-13
  error marker and diagnostics, 6-31
  error recovery, 6-32
  error threading, 6-33
  program listing, 6-19
    listing header, 6-19
    listing subheader, 6-19
  summary listing, 6-29
  summary of sections, 6-18
Listing file, 6-2, 6-3, 6-18
  configuration, 10-13
  default extension, 10-19
LISTING keyword, EXTENSION-NAMES configuration record, 10-19
Listing options, Compile Command, 6-8
LISTING-ATTRIBUTES keyword, COMPILER-OPTIONS configuration record, 6-22, 6-28, 10-12
LISTING-DATE-FORMAT keyword, COMPILER-OPTIONS configuration record, 10-13
LISTING-DATE-SEPARATOR keyword, COMPILER-OPTIONS configuration record, 10-14
LISTING-FILE value, LISTING-ATTRIBUTES keyword, 10-13
LISTING-PATHNAME keyword, COMPILER-OPTIONS configuration record, 10-14

LISTING-TIME-SEPARATOR keyword, COMPILER-OPTIONS configuration record, 10-14
Local area networks (LANs), 4-1, 4-4, 4-9, D-2
Locating RM/COBOL files
  directory search sequences
    under UNIX, 2-4
    under Windows, 3-11
  file access names
    under UNIX, 2-5
    under Windows, 3-13, 3-29
  file locations within operating system pathnames
    under UNIX, 2-3, 10-27
    under Windows, 3-10, 10-27
  NetWare search paths, 3-13
  Windows systems print jobs, 3-15
LOG-PATH keyword, RUN-OPTION configuration record, 10-33
LOW keyword, CONTROL phrase, DISPLAY statement, 8-24
LOW phrase
  ACCEPT and DISPLAY statements, 8-17, 8-19
  DISPLAY statement, 8-25
Low-intensity attribute, 2-20, 8-12, 8-25
LOWLIGHT. *See* LOW phrase

M

M (Modify) Command, Debug option, 9-28
M Compile Command Option, 2-23, 6-11, 10-6
M keyword, RUN-OPTION configuration record, 10-34
M Runtime Command Option, 2-25, 7-4, 10-34
Makefile. *See* Customizing RM/COBOL for UNIX
Map Indexed File utility (rmmapinx), xlvi, 3-4, 8-61, G-14
Map Program File utility (rmmappgm), 3-4, G-12
MASK keyword, CONTROL phrase, ACCEPT and DISPLAY statements, xlii, 8-2, 8-3, 8-14
Masked input processing, xlii, 8-2, 8-14, 8-16
MCS. *See* Message Control System
Memory available for a run unit, 2-7, 3-41
MEMORY-SIZE keyword, RUN-SORT configuration record, 10-36
Message Control System (MCS), 8-65, D-5
Message file processing errors, A-39
Message files, 3-12
Messages. *See also* Runtime messages
  compiler
    banner, Compile Command, 6-33
    configuration errors, 6-35, 6-42
    error marker and diagnostic format, 6-31
    error recovery, 6-32
    error threading facility, 6-33
    exit codes, 6-44
    initialization errors, 6-43
    input/output errors, 6-35
    status, 6-34
    syntax errors, 6-31
  debug errors, 9-13
  program exit codes, 7-8, 8-33
  recover1, G-26, G-34
  redirection of input and output, 2-22
  runtime errors, 7-7, A-1
Microsoft Windows
  32-bit implementation, xliii
  CALL "SYSTEM", 3-45, 6-44, 7-8, D-20, F-41
  configuration
    creating a shortcut, 3-7
    filename extension associations, 3-9
    prompting for a filename, 3-9
  Control menu, 3-43
    Copy option, 3-44
    Copy table option, 3-44
    icon, 3-42
    Paste option, 3-24, 3-44
    Properties option, 3-44
  default configuration example, 10-57
  file sharing, 8-38
  ini2reg utility, xliii, 3-4, 3-16, G-40
  initialization files, 3-16

Microsoft Windows *(Cont.)*
installation and system requirements, xliv, 3-1–3-7
registering the runtime, 3-5
line draw characters, portable, 3-41
locating RM/COBOL files
directory search sequences, 3-11
file access names, 3-13, 3-29
file locations within operating system pathnames, 3-10, 10-27
NetWare search paths, 3-13
Windows system print jobs, 3-15
memory available for a COBOL run unit, 3-41
NetWare, 3-10, 4-4
performance, 3-45
printing, xxvi, 3-15, 3-25, 3-26, 10-18, E-1
properties, setting, 3-17, 3-44
Color, 3-31
Menu Bar, 3-26, 3-34, 3-42, F-17
Miscellaneous, 3-19
Auto Paste, 3-20, 3-24, F-16
Auto Scale, 3-20, 3-27, F-16
Command Line Options, 3-20
Enable Close, 3-20, F-16
Enable Properties Dialog, 3-21, F-16
Font, 3-21
Full OEM To ANSI Conversions, 3-21, F-16
Icon File, 3-21, 3-32, F-33–F-39
Load Registry On CALL, 3-22, 3-30
Load Registry On RETURN, 3-22, 3-30
Logo Bitmap, 3-22
Logo Bitmap File, 3-23
Main Window Type, 3-23
Mark Alphanumeric, 3-23, 3-44, F-16
Offset X, 3-23
Offset Y, 3-24
Panels Controls 3D, 3-24
Panels Static Controls Border property, 3-24
Paste Termination, 3-24, F-16
Persistent, 3-24, F-16, G-23
Printer Dialog Always, 3-15, 3-25
Microsoft Windows
properties, setting
Miscellaneous *(Cont.)*
Printer Dialog Never, 3-25
Printer Enable Escape Sequences, 3-26
Printer Enable Raw Mode, 3-26
Remove Trailing Blanks, 3-26
Scroll Buffer Size, 3-26
Show Return Code Dialog, 3-27, 3-44
Show Through Borders, 3-27
Sizing Priority, 3-27
Status Bar, 3-27, F-38
Status Bar Text, 3-27, F-25
SYSTEM Window Type, xliv, 3-28, F-42
Title Text, 3-28, 3-43, F-39, F-40
Toolbar, 3-21, 3-28
Update Timeout, 3-28
Use Windows Colors, 3-29, 8-12
Pop-up Menu, xliv, 3-36, 3-43, F-22
Properties dialog box, illustrated, 3-17
selecting a file to configure, 3-17
Synonyms, 3-29
Toolbar, 3-26, 3-32, 3-43, F-37
recover1.ini file, 3-16
registry file, xliii, 3-16, 3-22, 3-30, F-16
rmcobol.ini file, 3-16
rmconfig utility, xliii, 3-4, 3-16, G-41
runcobol.ini file, 3-16
runtime system screen
cursor types, 3-43
described, 3-42
system considerations, 3-7–3-45
SYSTEM subprogram, 3-45
Toolbar editor, 3-21, 3-37, F-39
use with pop-up windows, 8-21
Mnemonic-name, user-defined word type, 6-22
MOVE-ATTR keyword, TERM-UNIT configuration record, 10-50
MULTIPLE phrase, LOCK MODE clause, file control entry, 2-8, H-9
Multiple record locks, 2-8, H-9

N

N Compile Command Option, 6-11
NAME keyword, EXTERNAL-ACCESS-METHOD configuration record, 10-20
Named pipe support, 8-47
NetWare, 3-10, 4-4
  search paths, 3-13
  system requirements, 3-1–3-2
Network file access, 2-8
NO BEEP keyword
  CONTROL phrase, DISPLAY statement, 8-24
  RUN-ATTR configuration record, 10-24
NO BLINK keyword
  CONTROL phrase, DISPLAY statement, 8-24
  RUN-ATTR configuration record, 10-24
NO ERASE keyword, CONTROL phrase, DISPLAY statement, 8-24
NO REVERSE keyword
  CONTROL phrase, DISPLAY statement, 8-24
  RUN-ATTR configuration record, 10-25
Nonnumeric data items, C-2
NO-TERMINAL-DISPLAY value, LISTING-ATTRIBUTES keyword, 10-13
Number of files a run unit can open, 2-8
Number of region locks, 2-8
Numeric computational data items, C-5
Numeric DISPLAY data items, C-5

O

O Compile Command Option, 6-12, 10-14
Object file, 6-2, 6-3, 7-1
  default extension, 10-19
OBJECT keyword, EXTENSION-NAMES configuration record, 10-19
Object program options, Compile Command, 6-11
Object versions, G-13, H-1–H-10
OBJECT-PATHNAME keyword, COMPILER-OPTIONS configuration record, 10-14
Objects, external, 8-36
OBJECT-VERSION keyword, COMPILER-OPTIONS configuration record, 10-14
OFF phrase, ACCEPT statement, 8-17, 8-20
ON EXCEPTION phrase
  ACCEPT statement, 2-22–2-24, 8-5, 8-21
  CALL statement, 8-35
ON OVERFLOW phrase, CALL statement, 8-35
Online services, xxxix
OPEN OUTPUT
  block sizes in indexed files, xlvii, 8-56
  sequential files in a shared environment, 8-38
OPEN statement
  REVERSED phrase (sequential I-O), 8-44
  WITH LOCK phrase, 8-38
OPTIONS keyword, EXTERNAL-ACCESS-METHOD configuration record, 10-20
Organization of this guide, xxxiv
Overlay file, compiler, 2-5, 3-12

P

P Compile Command Option, 6-10, 6-18, 6-33, 6-41, 10-13
P$ChangeDeviceModes subprogram, E-37, E-44
P$ClearDialog subprogram, E-15
P$ClearFont subprogram, E-24, E-29
P$DisplayDialog subprogram, 3-15, E-16
P$DrawBitmap subprogram, E-7, E-19
P$DrawBox subprogram, E-20, E-22, E-23
P$DrawLine subprogram, E-20, E-23
P$EnableDialog subprogram, 3-15, 3-25, E-16
P$EnableEscapeSequences subprogram, E-38
P$GetDeviceCapabilities subprogram, E-39, E-44
P$GetDialog subprogram, E-17, E-44
P$GetHandle subprogram, E-41
P$GetPosition subprogram, E-21, E-28
P$GetPrinterInfo subprogram, E-41, E-44
P$GetTextExtent subprogram, E-25
P$GetTextMetrics subprogram, E-25, E-29, E-44
P$GetTextPosition subprogram, E-28
P$LineTo subprogram, E-21, E-23
P$MoveTo subprogram, E-22
P$SetBoxShade subprogram, E-22, E-34
P$SetDefaultAlignment subprogram, E-28
P$SetDefaultMode subprogram, E-7, E-8, E-35

P$SetDefaultUnits subprogram, E-8, E-36
P$SetDialog subprogram, E-18, E-44
P$SetFont subprogram, E-6, E-24, E-29, E-44
P$SetHandle subprogram, E-41, E-43
P$SetLeftMargin subprogram, E-36
P$SetLineExtendMode subprogram, E-31
P$SetPen subprogram, E-23
P$SetPitch subprogram, E-31
P$SetPosition subprogram, E-23, E-33
P$SetRawMode subprogram, E-43
P$SetTabStops subprogram, E-32
P$SetTextColor subprogram, E-32
P$SetTextPosition subprogram, E-33
P$SetTopMargin subprogram, E-37
P$TextOut subprogram, E-32, E-34
PADDING CHARACTER clause, 8-37
PARITY keyword, TERM-UNIT configuration record, 10-50
PASS-THRU keyword, CONTROL phrase, DISPLAY statement, 8-17
PASS-THRU-ESCAPE keyword, TERM-ATTR configuration record, 8-17, 10-39
PATH environment variable, 2-5, 3-12, 6-35, 6-41, 8-36, G-26
PATH keyword
  DEFINE-DEVICE configuration record, 10-17
  TERM-UNIT configuration record, 10-50
Pathname, 2-3, 3-10
Performance, improved, 3-45
PICTURE character-string, window control block, 8-27
PIF. *See* Program information file
PIPE keyword, DEFINE-DEVICE configuration record, 10-17
Piping, 2-22, 8-1
  named pipe support, 8-47
Pop-Up Window Manager. *See* Pop-up windows
Pop-up windows, 8-22
  color terminal support, 8-24
  control block, 8-24, 8-27
    binary allocation, 10-8
    defining the border, 8-28
    defining the location, 8-28
    defining the location of the title, 8-29
    defining the size, 8-28
    defining the title, 8-30
    identifying, 8-28
    initializing, 8-29
  creating, 8-22
    BEEP phrase, DISPLAY statement, 8-23
    BLINK phrase, DISPLAY statement, 8-23
    CONTROL phrase, DISPLAY statement, 8-24
    ERASE phrase, DISPLAY statement, 8-24
    HIGH phrase, DISPLAY statement, 8-25
    LINE phrase, DISPLAY statement, 8-25
    LOW phrase, DISPLAY statement, 8-25
    POSITION phrase, DISPLAY statement, 8-25
    REVERSE phrase, DISPLAY statement, 8-25
    UNIT phrase, DISPLAY statement, 8-26
  customiz utility, under UNIX, D-3
  installing with the customiz utility, xlvii
  operation status, 8-30
  removing, 8-26
    CONTROL phrase, DISPLAY statement, 8-26
    UNIT phrase, DISPLAY statement, 8-26
  sample program, 7-6
  system verification, 5-2, 5-3
  use with the Windows operating system, 8-21, D-3
POSITION phrase, DISPLAY statement, 8-25
PRECEDENCE keyword, TERM-INPUT configuration record, 10-42

PRINT-ATTR configuration record, 10-20
AUTO-LINE-FEED keyword, 10-21
COLUMNS keyword, 10-21
FORM-FEED-AVAILABLE keyword, 10-21
LINAGE-INITIAL-FORM-POSITION keyword, 8-43, 10-21
LINAGE-PAGES-PER-PHYSICAL-PAGE keyword, 8-43, 10-22
LINES keyword, 10-22
TOP-OF-FORM-AT-CLOSE keyword, 10-23
WRAP-COLUMN keyword, 10-23
WRAP-MODE keyword, 10-23
Printer
DEFINE-DEVICE configuration record, 10-17
file access names, 2-7
support on sequential files, 8-46
PRINTER? printer device, 10-19, 3-15, E-4, E-16, E-41, E-43
Printing, from Windows, xxvi, 3-15, 3-25, 3-26, 10-18, E-1
copy files, E-44
escape sequences, RM/COBOL-specific, E-43, E-85
raw mode-byte I/O, E-43, E-85
examples, code fragments
change a font while printing, E-77
change the orientation of the page, E-75
change the orientation of the paper, E-79
change the pitch of a font, E-79
change the print resolution, E-75
draw a box around text, E-73
draw a box using relative positioning, E-73
draw a ruler, E-74
draw a shaded box with colors, E-73
list of, E-71
open and write to separate printers, E-80
print a watermark, E-73
print a word in boldface type, E-78
print a word in italics, E-78
print a word underlined, E-78
print bitmap files, E-77
Printing, from Windows
examples, code fragments *(Cont.)*
print multiple copies, E-13, E-75
print multiple text outputs on the same line, E-78
print text at the corners of a page, E-82
print text at the top of a page, E-81
set alignment of text, E-84
set text position, E-84
set the point size for a specific font, E-83
set the printer device, display the Windows Print dialog box, and check the return code value, E-76
P$ subprogram functions, E-1–E-9
bypass printer drivers and enable printing with escape sequences, E-85
change the current printer, E-43
change the orientation of the paper, E-37
change the paper source, E-37
clear all font description values and return them to their default (unset) state, E-24
clear values of the Windows Print dialog box to their default (unset) state, E-15
compute the printable area of the page to be printed, E-39
concatenate lines while printing, E-31
display Windows Print dialog box automatically when predefined printer device (PRINTER?) is next opened, E-16
draw a line starting at the current position, E-21
draw boxes, E-20
draw boxes around text, E-25
draw lines, E-20
enable a set of RM/COBOL-specific escape sequences, E-38
enable printing with RM/COBOL-specific escape sequences and bypass printer drivers, E-43
font, returning to normal, E-6
generate columns of text, E-36

Printing, from Windows
P$ subprogram functions*(Cont.)*
invoke standard Windows Print dialog box, E-16
list of, E-2–E-4
omitting P$ subprogram arguments, OMITTED keyword, CALL statement, E-9
print a bitmap file, E-19
print multiple copies, E-13, E-75
print partial reports, E-14
reposition the line-draw pen without drawing a line, E-22
reset the printer, E-37
retrieve characteristics of the current font, E-25
retrieve device capabilities of printer, E-39
retrieve ending position of the last print operation, E-21
retrieve ending position the last print operation adjusted to the top or bottom of the current font, E-28
retrieve handle to the current printer, E-41
retrieve values from Windows Print dialog box, E-17
set (change) fonts while printing to a Windows printer, E-29
set (initialize) values in Windows Print dialog box, E-18
set a left margin (offset from left side of paper) for the subsequent COBOL WRITE statement, E-36
set a new position for the next print operation adjusted from the top or bottom of the current font, E-33
set a position for the next print operation, E-23
set color and density of the color used in P$DrawBox, E-22
set color for text output, E-32
set default alignment used in text positioning, E-28
Printing, from Windows
P$ subprogram functions*(Cont.)*
set default mode used in positioning and sizing parameters, E-35
set default unit of measurement in positioning and sizing parameters, E-36
set new values in DEVMODE structure, E-37
set normal, compressed, or expanded font pitch, E-31
set output text on the printer while bypassing COBOL WRITE statement, E-34
set raw mode output when the next printer is opened, E-43
set style, width, and color of pen tool for a box or line, E-23
set tab stop increments, E-32
set top margin for subsequent pages, E-37
specify detailed printer information, E-41
using, E-6
common arguments, E-7
overview, E-4
Printer Dialog Always property, 3-25
Printer Dialog Never property, 3-25
Printer Enable Escape Sequences property, 3-26
Printer Enable Raw Mode property, 3-26
Windows system print jobs, 3-15
PRINT-LISTING value, LISTING-ATTRIBUTES keyword, 10-13
Program exit codes, 7-8
Program information file, 3-45
Program listing, 6-19
Program names, resolution of, xlvii, 8-34
Program, internal, F-1
Prompt character, xlvii
PROMPT keyword, CONTROL phrase, ACCEPT statement, xlvii, 8-18
PROMPT phrase, ACCEPT statement, 8-1, 8-3, 8-17
Properties, setting. *See* Microsoft Windows
PURGE statement, 8-65

Q

Q (Quit) Command, Debug option, 9-33
Q Compile Command Option, 6-13, 9-1, 11-3, A-2, F-11, F-40

R

R (Resume) Command, Debug option, 9-34, A-2
R Compile Command Option, 6-10, 10-15
RAW keyword, DEFINE-DEVICE configuration record, 3-26, 10-17, E-43
READ statement
  WITH NO LOCK phrase (indexed I-O), 8-55
  WITH NO LOCK phrase (relative I-O), 8-49
  WITH NO LOCK phrase (sequential I-O), 8-44
RECEIVE statement, 8-65
RECORD clause, 8-42, 8-48, 8-52
Record delimiting techniques
  binary sequential, 6-8, 8-42
  configuring, 10-15, 10-34
  line sequential, 6-8, 8-41
RECORD KEY clause, file control entry, DUPLICATES phrase, H-8
Record locking, 2-8, H-9
  time-out settings, 10-27, 10-30
Redirection of input and output control, 2-22, 6-18, 8-1, 10-25
REDRAW-ON-CALL-SYSTEM keyword, TERM-ATTR configuration record, 10-39, D-20
REEL phrase, CLOSE statement (sequential I-O), 8-45
Region lock facility, H-9
  under UNIX, 2-8
Registering the runtime, 3-5
Registration, xxxix
Registry file, xliii, 3-16
  C$GUICFG subprogram, F-16
  Initialization File to Windows Registry Conversion utility (ini2reg), xliii, 3-4, 3-16, G-40
  Load Registry On CALL property, 3-22, 3-30
  Load Registry On RETURN property, 3-22, 3-30
  RM/COBOL Configuration utility (rmconfig), xliii, 3-4, 3-16, G-41
Relative File Conversion utility
  rmcrl1, G-6
  rmcrl2, G-7
Relative files, 8-40, 8-47. *See also* File types and structure
Relativity, 1-3
Removing pop-up windows, 8-26
Renaming executables, 1-4
REPAINT-SCREEN keyword, CONTROL phrase, ACCEPT and DISPLAY statements, 8-18, D-23
REPAINT-SCREEN value, ACTION keyword, 10-41, 10-46
REPLACING LINE phrase, SEND statement, 8-69
RESEQUENCE-LINE-NUMBERS keyword, COMPILER-OPTIONS configuration record, 10-14
RESERVE clause, 8-44, 8-49, 8-54
Reserved words, dereserve, 6-16, 10-12
RESET-ANSI-INSERTION value, ACTION keyword, 10-41, 10-46
Resolution of program names, xlvii, 8-34
RESOLVE-LEADING-NAME keyword, RUN-FILES-ATTR configuration record, 2-6, 3-15, 10-29
RESOLVE-SUBSEQUENT-NAMES keyword, RUN-FILES-ATTR configuration record, 2-6, 3-15, 10-30
RETURN-CODE special register, 7-8, 8-33
Reverse attribute, 2-20

REVERSE keyword
CONTROL phrase, DISPLAY statement, 8-24
RUN-ATTR configuration record, 10-25
REVERSE phrase
ACCEPT and DISPLAY statements, 8-20, 10-25
DISPLAY statement, 8-25
REVERSED phrase, OPEN statement (sequential I-O), 8-44
REVERSE-VIDEO phrase. *See* REVERSE phrase
Right Arrow key, 8-3
RIGHT-ARROW value, ACTION keyword, 10-41, 10-47
RM insertion mode
field editing, 10-45
SET-RM-INSERTION value, 10-47
RM/COBOL
add-on packages, 1-3
Btrieve, 3-2, 4-1
CodeBridge, xxvi, 1-2, F-4
code-set translation tables, J-1
CodeWatch, xxvi, 1-2, 3-4, 6-13
compiler, 1-1, 6-1
configuration, 10-1
debugging, 9-1
extension, obsolete, and subset language elements, I-1
features, xxv, xli–xlvii, 8-1–8-22
ACCEPT and DISPLAY statements, operating-system specific information, 8-1–8-21
CALL statement, 8-33
file buffering, 8-40, 8-49, 8-54
file sharing, 8-38
file types and structure, 8-40
indexed file performance, 8-59
message control system (MCS), 8-65
pop-up windows, 8-21
STOP RUN numeric statement and RETURN-CODE special register, 8-33
temporary files, 8-59, 10-19
RM/COBOL *(Cont.)*
file naming conventions, 1-4
for UNIX
customizing, 10-2, D-1
installation and system requirements, 2-1–2-3
system considerations, 2-3–2-25
for Windows
installation and system requirements, xliv, 3-1–3-7
registering the runtime, 3-5
system considerations, 3-7–3-45
instrumentation, 11-1
internal data formats, C-1
internal libraries and utility programs, 1-2
limits and ranges, 4-19, B-1
local area networks (LANs), 4-1, 4-4, 4-9
NetWare, 3-1–3-2, 3-10, 3-13, 4-4
object versions, H-1
P$ subprograms, xxvi, E-1
printing from Windows, xxvi, E-1
renaming executables, 1-4
runtime messages, A-1
runtime system, 1-1, 7-1
software, 1-1
subprogram library, F-1
system verification, 5-1
RM/COBOL and ANSI COBOL, 6-7
RM/COBOL Configuration utility (rmconfig), xliii, 3-4, 3-16, G-41
RM/COBOL indexed files and Btrieve MicroKernel Database Engine limitations, 4-19
automatic creation of variable-length record files, 4-23
current record position limitations, 4-19
effect on input/output errors, 4-24
effect on RM/COBOL applications, 4-22
file position indicator limitations, 4-20
key placement, 4-23
Permission Error detection limitations, 4-21

RM/COBOL indexed files and Btrieve MicroKernel Database Engine limitations *(Cont.)*
support for Btrieve internal data formats, 4-24
support for RM/COBOL internal data formats, 4-23
using existing Btrieve files with RM/COBOL, 4-21
variable-length records, 4-7, 4-15, 4-23
verification of maximum record and block length, 4-23
RM/COBOL Open File Manager, 10-20, D-2
RM/COBOL-to-Btrieve Adapter (rmbtrv32) program. *See also* Btrieve
Btrieve MicroKernel Database Engine (MKDE), 4-4, 4-5
Btrieve software requirements, 3-2
COBOL application programs, 4-5
concepts, 4-1
configuration options, 4-9, 10-20
EXTERNAL-ACCESS-METHOD record
B rmbtrv32 MKDE page size, 4-10
C create, 4-10
D duplicates, 4-11
I initial display, 4-12
L lock, 4-13
M mode, 4-14
O owner, 4-15
P rmbtrv32 page size, 4-8, 4-15, 4-23
T diagnostic trace filename, 4-15
RUN-INDEX-FILES record
BLOCK-SIZE, 4-16
DATA-COMPRESSION, 4-16
dynamic link libraries, 4-5, 4-18
enhancements, xliv
file management system, RM/COBOL, 4-6
indexed files, 4-1, 4-5
RUNPATH environment variable, 4-10
starting, 4-18
system considerations for Btrieve files, 4-7
RM/InfoExpress, xlvii, 1-3, 10-20, D-2
RM/Panels, 1-3
Load Registry On CALL property, 3-22
Load Registry On RETURN property, 3-22
pop-up menus, 3-36
three-dimensional controls, 3-24
RM/plusDB, 10-20, D-3
rmattach utility, xlv, 10-2, G-39
rmbtrv32 program. *See* RM/COBOL-to-Btrieve Adapter (rmbtrv32) program; Btrieve
rmcobol (Compile Command), 6-1, 6-3
RMCOBOL-2 keyword, COMPILER-OPTIONS configuration record, 10-15
rmconfig utility, xliii, 3-4, 3-16, G-41
rmdefinx utility, 3-4, 8-50, 8-56, 8-64, 8-65, A-31, G-19
rmmapinx utility, xlvi, 3-4, 8-61, G-14
rmmappgm utility, 3-4, G-12
RMPATH environment variable, 2-4, 3-11–3-13, 3-30, 8-32
rmpgmcom utility, 3-4, 6-3, 6-13, 10-11, 10-16, G-9
ROWS keyword, TERM-ATTR configuration record, 3-26, 10-39
RUN-ATTR configuration record, 10-23
ACCEPT-FIELD-FROM-SCREEN keyword, 8-1, 10-23
ACCEPT-INTENSITY keyword, 10-23
ACCEPT-PROMPT-CHAR keyword, 10-24
BEEP keyword, 10-24
BLINK keyword, 10-24
DISPLAY-INTENSITY keyword, 10-24
EDIT-COMMA keyword, 10-24
EDIT-CURRENCY-SYMBOL keyword, 10-24
EDIT-DECIMAL keyword, 10-25
EDIT-DOLLAR keyword, 10-25
ERROR-MESSAGE-DESTINATION keyword, 2-25
REVERSE keyword, 10-25
SCROLL-SCREEN-AT-TERMINATION keyword, 10-25
TAB keyword, 10-26
UNDERLINE keyword, 10-26

runcobol (Runtime Command), 7-1
RUN-FILES-ATTR configuration record, xlii, 10-26
ALLOW-EXTENDED-CHARS-IN-FILENAMES keyword, 10-26
BLOCK-SIZE keyword, 10-26
BUFFER-POOL-SIZE keyword, 6-43, 8-40, 8-60, 10-26, A-7, A-28, G-34
DISABLE-COMMIT-FILE keyword, 10-27
ENABLE-OLD-DOS-FILENAME-HANDLING keyword, 10-27
EXPANDED-PATH-SEARCH keyword, 2-3, 3-10, 10-27
FATAL-RECORD-LOCK-TIMEOUT keyword, 10-27
FILE-HANDLE-LIMIT keyword, 10-27
FILE-LOCK-LIMIT keyword, 10-28
FILE-PROCESS-COUNT keyword, 10-28
FORCE-USER-MODE keyword, 3-45, 10-28
KEEP-FLOPPY-OPEN keyword, 10-28
LARGE-FILE-LOCK-LIMIT keyword, xlii, 10-28, G-16
RESOLVE-LEADING-NAME keyword, 2-6, 3-15, 10-29
RESOLVE-SUBSEQUENT-NAMES keyword, 2-6, 3-15, 10-30
USE-PROCEDURE-RECORD-LOCK-TIMEOUT keyword, 10-30
RUN-INDEX-FILES configuration record, 4-16, 10-31
ALLOCATION-INCREMENT keyword, 10-31
ATOMIC-TRANSFER-SIZE keyword, 10-31
BLOCK-SIZE keyword, 10-31
DATA-COMPRESSION keyword, 10-31
DEFAULT-FILE-VERSION-NUMBER keyword, 10-31
FORCE-CLOSED keyword, 8-51, 10-31
FORCE-DATA keyword, 8-52, 10-32
FORCE-DISK keyword, 8-52, 10-32
FORCE-INDEX keyword, 8-52, 10-32
KEY-COMPRESSION keyword, 10-32
RUN-OPTION configuration record, 10-33
B keyword, 10-33
ENABLE-LOGGING keyword, 10-33
K keyword, 10-33
LOG-PATH keyword, 10-33
M keyword, 10-34
RUNPATH environment variable, 2-4, 3-11–3-13, 3-30, 4-10, 8-35
RUN-REL-FILES configuration record, xlii, 10-34
BLOCK-SIZE keyword, 10-34
USE-LARGE-FILE-LOCK-LIMIT keyword, xlii, 10-34
RUN-SEQ-FILES configuration record, xlii, 10-34
BLOCK-SIZE keyword, 10-34
DEFAULT-TYPE keyword, 10-35
DEVICE-SLEWING-RESERVE keyword, 10-35
TAB-STOPS keyword, 10-35
USE-LARGE-FILE-LOCK-LIMIT keyword, xlii, 10-35
RUN-SORT configuration record, 10-36
INTERMEDIATE-FILES keyword, 10-36
MEMORY-SIZE keyword, 10-36
Runtime Command, 7-1
input/output control redirection, under UNIX, 2-22
invoking, 7-1
messages
diagnostic, 7-7
execution, 7-7
program exit codes, 7-8
options, 7-2
banner and STOP RUN message suppression (K), 7-3, 10-33, A-41–A-42
configuration file (C), 7-3, 10-1, A-38
instrumentation (I), 7-3, 11-1
invoke Interactive Debugger (D), 7-3, 9-1
level 2 semantics for Format 1 ACCEPT and DISPLAY statements (M), 2-25, 7-4, 10-34

Runtime Command
options *(Cont.)*
maximum size for ACCEPT and DISPLAY buffers (B), 7-4, 8-20, 10-33
memory to be used for a sort operation (T), 7-4, A-7, A-36
object or non-COBOL program libraries (L), 7-2, 7-6, 8-34, A-40, G-11
pass an argument to the main program (A), 7-5
supplemental runtime configuration file (X), 7-3, 10-1, A-38
switch set and reset (S), 7-4, 11-7
samples of valid and invalid, 7-6
types of options
configuration, 7-3
debug and test, 7-3
environment, 7-4
program, 7-5
Runtime messages
error message format, A-1
error message types, 7-7, A-1
COBOL normal termination, A-1, A-42
configuration, A-1, A-37
data reference, A-1, A-3
input/output, A-1, A-11
internal error, A-1, A-36
message control, A-1, A-37
operator-requested termination, A-1, A-3
procedure, A-1, A-6
runcobol initialization messages, A-1, A-39
initialization errors, A-39
main program loading errors, A-40
message file processing errors, A-39
option processing errors, A-40
registration error messages, A-41
runcobol banner message, A-41
runcobol usage message, A-41
sort-merge, A-1, A-36
traceback, A-1, A-3

S

S (Step) Command, Debug option, 9-35
S Compile Command Option, 6-7, 6-16, 10-15, C-7, C-9
S Runtime Command Option, 7-4, 11-7
Scan suppression, 6-32
Screen field, initial contents, 8-1
Screen width, 8-18
SCREEN-COLUMNS keyword, CONTROL phrase, ACCEPT and DISPLAY statements, 8-18
SCREEN-CONTENT-OPTIMIZE keyword, TERM-ATTR configuration record, 10-39
SCREEN-ESCAPE value, ACTION keyword, 10-41, 10-47
SCREEN-HOME value, ACTION keyword, 10-41, 10-47
SCREEN-PREVIOUS-FIELD value, ACTION keyword, 10-41, 10-47
SCREEN-TERMINATE value, ACTION keyword, 10-41, 10-47
SCROLL-SCREEN-AT-TERMINATION keyword, RUN-ATTR configuration record, 10-25
SECURE phrase, ACCEPT statement, 8-17, 8-20. *See also* OFF phrase
Segmentation, 6-1
SELECT clause, use of, 3-14
SEND statement, 8-65, 8-69
Separate sign
compiler option, 6-7
configuration, 10-15
leading, C-8
trailing, C-7
SEPARATE-SIGN keyword, COMPILER-OPTIONS configuration record, 10-15
Sequential File Conversion utility (rmcseq), G-8
Sequential files, 8-40, 8-41. *See also* File types and structures
SEQUENTIAL-FILE-TYPE keyword, COMPILER-OPTIONS configuration record, 10-15

SET-ANSI-INSERTION value, ACTION keyword, 10-41, 10-47
SET-RM-INSERTION value, ACTION keyword, 10-41, 10-47
Shared environments, 8-38
Sign, operational
  compiler option, 6-7
  configuration, 10-15
  leading combined, C-10
  leading separate, C-8
  trailing combined, C-9
  trailing separate, C-7
Signed COMPUTATIONAL, C-13
Signed COMPUTATIONAL-1, C-14
Signed numeric COMPUTATIONAL-3, C-16
Signed numeric COMPUTATIONAL-4, C-21
Signed numeric DISPLAY (LEADING SEPARATE), C-8
Signed numeric DISPLAY (LEADING), C-10
Signed numeric DISPLAY (TRAILING SEPARATE), C-7
Signed numeric DISPLAY (TRAILING), C-9
SIZE phrase
  ACCEPT and DISPLAY statements, 2-23, 2-25, 8-17, 8-20
  START statement (relative and indexed I-O), H-7
Sort files, temporary, 8-59
SORT statement
  configuring, 10-36
  errors, A-36
  memory, 7-4, 10-36
Sort-merge facility, temporary files, 8-59
Source file, 6-2, 6-3
  default extension, 10-19
SOURCE keyword, EXTENSION-NAMES configuration record, 10-19
Source listing, 6-19
Source program options, Compile Command, 6-15
Special-registers
  LINAGE-COUNTER, 10-8
  RETURN-CODE, 7-8, 8-33
Split keys, 4-7, 6-23
Split-key-name, user-defined word type, 6-23
Standard error device, 2-25, 6-7, 10-25
Standard input device, 2-22, 10-25
Standard output device, 2-24–2-25, 6-11, 6-18, 6-33, 6-41, 10-13, 10-25, 10-39
STOP literal statement, 2-25, 7-7
STOP RUN numeric statement, 8-33
STOP-BITS keyword, TERM-UNIT configuration record, 10-51
STRIP option (rmpgmcom utility), 6-13, 10-11, 10-16, G-9
Subprogram libraries, xxvii, F-1
Subprogram loading, 8-34, D-13
  resolution of program names, xlvii
Summary listing, 6-29
Support services, technical, xxxix
SUPPRESS-COPY-FILES value, LISTING-ATTRIBUTES keyword, 10-13
SUPPRESS-NULLS keyword, TERM-ATTR configuration record, 10-40
SUPPRESS-NUMERIC-OPTIMIZATION keyword, COMPILER-OPTIONS configuration record, 10-15
Switches, 7-4
Symbolic-character, user-defined word type, 6-22
Symbols and conventions, xxxvii
SYMBOL-TABLE-OUTPUT keyword, COMPILER-OPTIONS configuration record, 10-16
Synonyms
  entries in file access names, 2-5, 3-13
  in directory search sequences, use of, 3-11
  properties, setting, 3-11, 3-29
Syntax errors, 6-31
System files. *See* Files
SYSTEM subprogram, 3-45, 6-44, 7-8, D-20, F-41
System verification
  under UNIX, 5-1
  under Windows, 5-3

T

T (Trap) Command, Debug option, 9-36
T Compile Command Option, 6-11, 6-18, 6-33, 6-41, 10-13
T Runtime Command Option, 7-4, A-7, A-36
TAB keyword
  CONTROL phrase, ACCEPT statement, 8-17
  RUN-ATTR configuration record, 10-26
TAB phrase, ACCEPT statement, 8-17
Tab stops
  configuring, 10-35
  source files (BDS), 6-2
Table of Contents (TOC)
  rmmappgm utility, G-12
  rmpgmcom utility, G-9
TAB-STOPS keyword, RUN-SEQ-FILES configuration record, 10-35
Tape
  DEFINE-DEVICE configuration record, 10-17
  file access names, 2-7
  support on sequential files, 8-47
Technical support services, xxxix
TEMP, locating temporary files, 8-59
Temporary files, locating, 8-59
TERM environment variable, 2-11, 8-18
TERM-ATTR configuration record, 10-36
  BCOLOR keyword, 10-36
  CHARACTER-TIMEOUT keyword, 8-21, 10-36
  COLUMNS keyword, 10-37
  DATA-CHARACTERS keyword, 10-37
  DBCS-CHARACTERS keyword, xlii, 10-37
  FCOLOR keyword, 10-39
  PASS-THRU-ESCAPE keyword, 8-17, 10-39
  REDRAW-ON-CALL-SYSTEM keyword, 10-39, D-20
  ROWS keyword, 3-26, 10-39
  SCREEN-CONTENT-OPTIMIZE keyword, 10-39
  SUPPRESS-NULLS keyword, 10-40
  USE-COLOR keyword, 10-40
Termcap, 8-2
  database, 2-10–2-22
  default configuration, 10-51
    changing, D-2
  terminal input and output, 2-9
TERMCAP environment variable, 2-10
TERMCAP keyword, TERM-INTERFACE configuration record, 10-49
Terminal attributes, 2-9
  configuring, 10-36
Terminal input and output
  cursor types, 2-9
  terminal attributes, 2-9
  terminal interfaces, 2-9
Terminal interfaces, 2-9, D-2
TERMINAL-LISTING value, LISTING-ATTRIBUTES keyword, 10-13
Terminate. *See* SCREEN-TERMINATE value
Terminfo, 8-2
  database, 2-10–2-22
  default configuration, 10-54
    changing, D-2
  terminal input and output, 2-9
TERMINFO environment variable, 2-11
TERMINFO keyword, TERM-INTERFACE configuration record, 10-49
TERM-INPUT configuration record, 10-41
  ACTION keyword, 10-41
    field editing actions
      BACKSPACE value, 10-45
      CONTROL-BREAK value, 10-45
      DELETE-CHARACTER value, 10-45
      ERASE-ENTIRE value, 10-46
      ERASE-REMAINDER value, 10-46
      ESCAPE-TO-COMMAND value, 10-46
      ESCAPE-TO-OS value, 10-46
      FIELD-HOME value, 10-46
      INSERT-CHARACTER value, 10-46
      LEFT-ARROW value, 10-46
      REPAINT-SCREEN value, 10-46
      RESET-ANSI-INSERTION value, 10-46
      RIGHT-ARROW value, 10-47

TERM-INPUT configuration record
ACTION keyword
field editing actions *(Cont.)*
SCREEN-ESCAPE value, 10-47
SCREEN-HOME value, 10-47
SCREEN-PREVIOUS-FIELD value, 10-47
SCREEN-TERMINATE value, 10-47
SET-ANSI-INSERTION value, 10-47
SET-RM-INSERTION value, 10-47
TOGGLE-ANSI-INSERTION value, 10-48
character sequence specifications, 10-42
CODE keyword, 10-41
DATA keyword, 10-42
EXCEPTION keyword, 10-42
field editing actions, 10-45
input sequence specification, 10-44
PRECEDENCE keyword, 10-42
TERM-INTERFACE configuration record, 10-49
GUI keyword, 10-49
TERMCAP keyword, 10-49
TERMINFO keyword, 10-49
WINDOWS keyword, 10-49
TERM-UNIT configuration record, 10-49
BPS keyword, 10-49
CHARACTER-WIDTH keyword, 10-50
DEFINE-CONTROL-CHARACTERS keyword, 10-50
MOVE-ATTR keyword, 10-50
PARITY keyword, 10-50
PATH keyword, 10-50
STOP-BITS keyword, 10-51
TYPE keyword, 10-51
UNIT keyword, 10-51
Tilde (~)
file locations, 2-3, 10-27
negation character, Compile Command line, 6-4
setting menu bar properties, 3-35
setting pop-up menu properties, 3-36
Time, listing separator configuration, 10-14
Time-out, BEFORE TIME phrase, ACCEPT statement, 8-21, 10-36
TMP, locating temporary files, 8-59
TOGGLE-ANSI-INSERTION value, ACTION keyword, 10-41, 10-48
TOP-OF-FORM-AT-CLOSE keyword, PRINT-ATTR configuration record, 10-23
TYPE keyword, TERM-UNIT configuration record, 10-51

U

U (Untrap) Command, Debug option, 9-40
U Compile Command Option, 6-7, 10-10
UNC. *See* Universal naming convention
Underline attribute, 2-20
UNDERLINE keyword, RUN-ATTR configuration record, 10-26
UNIT keyword, TERM-UNIT configuration record, 10-51
UNIT phrase
CLOSE statement (sequential I-O files), 8-45
DISPLAY statement, 8-26
Universal naming convention (UNC), 3-10
UNIX
customizing RM/COBOL, D-1
input/output control redirection, 2-22
installation and system requirements, 2-1–2-3
locating RM/COBOL files
directory search sequences, 2-4
file access names, 2-5
file locations within operating system pathnames, 2-3
memory available for a COBOL run unit, 2-7
network file access, 2-8
number of files, 2-8
number of region locks, 2-8
pathnames, 2-3
system considerations, 2-3–2-25
terminal input and output
cursor types, 2-9
terminal attributes, 2-9
terminal interfaces, 2-9
Unsigned numeric COMPUTATIONAL, C-11

Unsigned numeric COMPUTATIONAL-3, C-15
Unsigned numeric COMPUTATIONAL-4, C-18
Unsigned numeric COMPUTATIONAL-6, C-24
Unsigned numeric DISPLAY (NSU), C-6
UPDATE phrase, ACCEPT statement, 8-1
UPON/FROM CONSOLE phrase, ACCEPT and DISPLAY statements, 2-22–2-25
USAGE clause, 10-10, C-5
  data description entry, 10-8
USE-COLOR keyword, TERM-ATTR configuration record, 10-40
USE-LARGE-FILE-LOCK-LIMIT keyword
  RUN-REL-FILES configuration record, xlii, 10-34
USE-LARGE-FILE-LOCK-LIMIT keyword, RUN-SEQ-FILES configuration record, xlii, 10-35
USE-PROCEDURE-RECORD-LOCK-TIMEOUT keyword, RUN-FILES-ATTR configuration record, 10-30
User-defined words, 6-22
Utilities
  Attach Configuration (rmattach), xlv, 10-2, G-39
  Combine Program (rmpgmcom), 3-4, 6-3, 6-13, 10-11, 10-16, G-9
  Define Indexed File (rmdefinx), 3-4, 8-50, 8-56, 8-64, 8-65, A-31, G-19
  delivered media, G-2
  Indexed File Conversion (rmifca and rmifcb), G-4
  Indexed File Recovery (recover1), xlii, xlvi, 2-5, 3-4, 3-12, 3-16, 3-18, 8-51, 8-64, 8-65, 10-31, A-13, A-31, G-23
    recover2, xlii, G-35
    recovery, xlii
  Initialization File to Windows Registry Conversion (ini2reg), xliii, 3-4, 3-16, G-40
  installation, 2-2, G-3
  Map Indexed File (rmmapinx), xlvi, 3-4, 8-61, G-14
  Map Program File (rmmappgm), 3-4, G-12
Utilities *(Cont.)*
  Relative File Conversion
    rmcrl1, G-6
    rmcrl2, G-7
  RM/COBOL Configuration (rmconfig), xliii, 3-4, 3-16, G-41
  Sequential File Conversion (rmcseq), G-8

V

V Compile Command Option, 6-8, 6-16, 10-15
VanGui Interface Builder, 1-3, D-5
Variable-length records, 4-7, 4-15, 4-23
Verification procedures
  for UNIX, 5-1
  for Windows, 5-3
Version number, file, xlii, 8-56, 8-64, 10-31, G-16, G-22
Video display attributes, 2-9

W

W Compile Command Option, 6-7, 10-16
WANs. *See* Wide Area Networks (WANs)
WCB-BORDER-CHAR parameter, 8-28
WCB-BORDER-SWITCH parameter, 8-28
WCB-BORDER-TYPE parameter, 8-28
WCB-FILL-SWITCH parameter, 8-29
WCB-HANDLE parameter, 8-28
WCB-LOCATION-REFERENCE parameter, 8-28
WCB-NUM-COLS parameter, 8-28
WCB-NUM-ROWS parameter, 8-28
WCB-TITLE parameter, 8-29
WCB-TITLE-JUSTIFICATION parameter, 8-29
WCB-TITLE-LENGTH parameter, 8-29
WCB-TITLE-LOCATION parameter, 8-29
Web site, xxxix
Wide area networks (WANs), D-2
WINDOW-CREATE keyword, pop-up windows CONTROL phrase, 8-22
WINDOW-REMOVE keyword, pop-up windows CONTROL phrase, 8-26

Windows. *See* Microsoft Windows; Pop-up windows; Printing, from Windows
WINDOWS keyword, TERM-INTERFACE configuration record, 10-49
WITH DUPLICATES phrase, RECORD KEY clause, H-8
WITH LOCK phrase, OPEN statement (relative and indexed I-O), 8-38, 8-64
WITH NO LOCK phrase, READ statement, 8-44, 8-49, 8-55
WITH NO REWIND phrase, CLOSE statement (sequential I-O), 8-44
WITH phrase, SEND statement, 8-69
WORKSPACE-SIZE keyword, COMPILER-OPTIONS configuration record, 10-16
WRAP-COLUMN keyword, PRINT-ATTR configuration record, 10-23
WRAP-MODE keyword, PRINT-ATTR configuration record, 10-23
WRITE statement
  ADVANCING *mnemonic-name* phrase (sequential I-O), 8-45
  ADVANCING ZERO LINES phrase (sequential I-O), 8-45

X

X Compile Command Option, 6-11, 6-28, 10-13
X Runtime Command Option, 7-3, 10-1, A-38

Y

Y Compile Command Option, xxxiii, 6-13, 9-1, 9-5, 9-6, 10-11, 10-16, G-9, H-10
Year 2000 subprogram, xlvi, F-7

Z

Z Compile Command Option, 6-14, H-2
Zoned sign
  leading, C-10
  trailing, C-9

Liant Software Corporation
License Agreement

THIS LICENSE AGREEMENT SETS FORTH THE TERMS AND CONDITIONS OF THE LICENSE AND THE LIMITED WARRANTY FOR THE SOFTWARE ON THE ENCLOSED MAGNETIC AND/OR CD-ROM MEDIA. CAREFULLY READ THE FOLLOWING LICENSE AGREEMENT BEFORE BREAKING THE SEAL ON ANY OF THE MEDIA. BY BREAKING THE SEAL YOU ACCEPT THE TERMS OF THIS AGREEMENT. IF YOU DO NOT ACCEPT THE TERMS OF THIS AGREEMENT, DO NOT OPEN ANY OF THE MEDIA; PROMPTLY RETURN THE ENTIRE PACKAGE TO YOUR DEALER FOR A FULL REFUND.

DEFINITIONS

The following definitions apply to the terms as they appear in this agreement.

- Liant means Liant Software Corporation, a Delaware corporation.
- You and Your refer to any person or entity that acquires or uses this Package.
- Package means the Software, user's manual(s), and other items accompanying this agreement.
- Software refers to the computer program contained in this Package, together with all codes, techniques, software tools, formats, designs, concepts, methods, and ideas associated with that computer program. The term also includes all copies of any part of the Software, as well as the user manual(s), other printed materials, and any "online" or electronic documentation, contained in this Package.
- Media means magnetic disks, tape, and/or CD-ROM containing the Software.
- LAN means a local area network of computers interconnected to each other or to a hub or concentrator by metallic or fiber-optic circuits. Computers or networks connected over public common carrier circuits or over a public switched-circuit network, are not considered to be a single LAN.
- Usage Level means the number of simultaneous uses of the Software on a single computer or LAN, permitted under this agreement as indicated on the Media.

PERMITTED USES

Liant grants You a non-exclusive license to use the Software in this Package according to the terms set forth below.

You may:

- Install the Software on one computer at a time.
- Make one backup copy of the Software, which automatically becomes the property of Liant and is subject to this agreement.
- Operate the Software on one computer or LAN at a time.
- In the case of LAN installations, operate the Software on as many computers on a single LAN as is permitted by the Software's Usage Level.
- In the case of a multiuser computer, operate the Software to service up to the number of concurrent program executions permitted by the Software's Usage Level.

PROHIBITED USES

You may not:

- Allow the Software to become available to any person or entity other than Your employees. You may, however, after written notification to Liant, transfer all (but no lesser portion) of the Software to another person or entity who is not otherwise prohibited by this agreement to use the Software, provided such person or entity agrees in writing to be subject to all terms of this agreement.
- Modify the Software or merge it with another program, except for Your personal use on a single computer. The program resulting from any modification or merger of the Software is subject to this agreement.
- Reverse engineer, disassemble, decompile, or make any attempt to discover the source code to the Software.
- Translate or create derivative works based on the Software.
- Remove, obscure, or alter any notice of the patent, copyright, or other proprietary rights related to the Software.
- Sub-license, sell, lend, rent, or lease any portion of the Software, directly or indirectly.
- Copy any portion of the Software, except to make a backup copy, as described above under Permitted Uses.
- Transfer the Software or any direct, modified or merged product thereof to any person or entity in violation of the United States Export Administration Act.
- Operate the Software on more than one computer or LAN at a time, except as described above under Permitted Uses.

The Software involves valuable proprietary rights of Liant and others. There is no transfer to You of any title to or ownership of the Software or any patent, copyright, trade secret, trade name, trademark, and other proprietary rights related to the Software, regardless of the form that original or other copies exist in. You may not violate these rights, and You must take all appropriate steps to protect Liant's rights. Liant may at any time replace, modify, alter, improve, enhance, or change the Software without prior notice.

Both the license and Your right to use the Software terminate automatically if You violate any part of this agreement. In the event of termination, You must immediately destroy all copies of the Software or return them to Liant.

LIMITED WARRANTY

For a period of ninety (90) days from the date You received the Software, Liant warrants that, upon delivery by Liant and acceptance by You, the media on which the Software is distributed will be materially free from defects in materials and workmanship and that the Software will substantially conform to the specifications established by Liant. This warranty gives You specific legal rights, and You may also have other rights that vary from state to state.

If any of the Software fails to comply with the warranties set forth above, Liant will replace the Media or, at Liant's option, make a reasonable effort to correct the program errors. You must, however, return all copies of the Software, along with a copy of Your paid invoice, to an authorized Liant dealer within ninety (90) days of the date You received the Software. If Liant is unable to correct defective Media or program errors, Liant will refund all or a fair portion of the price You paid for this Package, at Liant's option. The refund will fully satisfy Your claims for Software or Media failure. Any replacement software will be warranted for the rest of the original 90-day warranty period or for thirty (30) days from the date You received the replacement, whichever is longer.

Liant WILL NOT BE LIABLE FOR ANY:

- BUG, ERROR, OMISSION, DEFECT, DEFICIENCY, OR NONCONFORMITY IN ANY SOFTWARE.
- IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE.
- IMPLIED WARRANTY RELATING TO COURSE OF PERFORMANCE, COURSE OF DEALING, OR USAGE OF TRADE OR ANY OTHER IMPLIED WARRANTY OF ANY TYPE WHATSOEVER.
- CLAIM OF INFRINGEMENT.
- CLAIM IN TORT, WHETHER OR NOT ARISING IN WHOLE OR IN PART FROM Liant's FAULT, NEGLIGENCE, STRICT LIABILITY, OR PRODUCT LIABILITY.
- CLAIM FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, OR CONSEQUENTIAL DAMAGES, COVER, OR LOSS OF DATA, REVENUE, CUSTOMERS, GOODWILL OR USE.

Any written or oral information or advice given by Liant dealers, distributors, agents, or employees will in no way increase or modify the scope of this warranty. Nor may You rely on any such written or oral communication.

GENERAL

Under this agreement, Liant is not responsible for maintaining or helping You to use the Software.

This agreement constitutes the entire agreement and supersedes any prior agreement between Liant and You concerning this Package. Liant is not bound by any provision of any purchase order, receipt, acceptance, confirmation, correspondence, or otherwise. This agreement cannot be amended, modified, or waived, unless the change is written, specifically identified as an amendment and signed by an authorized Liant representative and You.

U.S. GOVERNMENT RESTRICTED RIGHTS

The Software and accompanying documentation are provided with RESTRICTED RIGHTS. Use, duplication, or disclosure by the Government is subject to restrictions as set forth in subparagraph (c)(1)(ii) of the Rights in Technical Data and Computer Software clause at 48 DFARS 252.227-7013, or in subparagraph (c)(1) and (2) of the Commercial Computer Software–Restricted Rights clause at 48 CFR 52.27-19, as applicable. The contractor/manufacturer is Liant Software Corporation, 8911 Capital of Texas Highway North, Suite 4300, Austin, Texas 78759-7267.

LIANT

Retooling Enterprise Systems

Part No. 301563
Printed in USA 0192 Rev 0499